

SECTION 09642 – WOOD GYMNASIUM FLOORING

PART 1 - GENERAL

1.1 DESCRIPTION

A. Related work specified under other sections.

1. CONCRETE SUBFLOORS - SECTION 03_ _ _

a. Slab depression is:

SportBond Plus - 7/16" Rezill DIN or Multiflex Pads

3/8" flooring - 1-7/8"

1/2" flooring - 2"

11/16" flooring - 2-3/8"

SportBond Plus - 3/4" Neo-Shok or Rezill R6 Pads

3/8" flooring - 2-1/8"

1/2" flooring - 2-1/4"

11/16" flooring - 2-3/8"

b. The general contractor shall furnish and install the concrete subfloor depressing the slab sufficiently to accommodate the floor system. The slab shall be steel troweled and finished smooth to a tolerance of 1/8" in any 10' radius by the general contractor. High spots shall be ground level, and low spots filled in with approved leveling compound by the general contractor to the full approval of the installer (Flooring Contractor).

2. MEMBRANE WATERPROOFING - SECTION 07_ _ _

a. Concrete subfloors on or below grade shall be adequately waterproofed beneath the slab and at the perimeter walls and on earth side of below grade walls by general contractor using suitable type membrane.

3. THRESHOLDS - SECTION 08_ _ _

4. GAME STANDARD INSERTS - SECTION 11_ _ _

1.2 REFERENCES

A. MFMA - Maple Flooring Manufacturers Association

B. DIN - Performance Standard DIN 18032 Part 2.

1.3 QUALITY ASSURANCE

A. Manufacturer

1. Manufacturer of resilient flooring shall be a firm specializing in manufacturing products specified in this section.
2. Manufacturer of flooring and subfloor components must be ISO 9001:2000 Certified to assure quality control of materials provided.
3. Basis of design shall be "SportBond Plus" sports floor system as provided by **Connor Sports Flooring, www.connorfloor.com, (800-833-7144)**.
4. Materials other than those listed must be approved 10 days prior by written addendum. Materials from non-approved manufacturers will not be accepted.

B. Installer (Flooring Contractor)

1. The complete installation of the flooring system, as described in the scope of these specifications, shall be carried out by an experienced installer (Flooring Contractor), and the work shall be performed in accordance with most recent installation instructions of the manufacturer.
2. Installer (Flooring Contractor) shall be liable for all matters related to installation for a period of one year after the floor has been substantially installed and completed.

C. Performance Testing

1. Flooring system shall have been independently tested and evaluated for Athletic Performance according to the International Standard DIN 18032, Part 2.
2. Flooring system shall have been independently tested and evaluated for Engineering Performance according to the Structural Testing and Engineering Measures (STEM).

1.4 SUBMITTALS

A. Specification - Submit Connor SportBond specification sheets.

- B. Sample** - Submit one sample of specified system, if requested by architect.
- C. Maintenance Literature** - Upon completion of floor installation, send to owner, attendants or individuals in charge and responsible for the upkeep of the building a CARE CARD. This card spells out care and maintenance instructions including temperature and humidity ranges for areas where flooring is installed.

1.5 WORKING CONDITIONS

- A. The wood flooring specified herein shall not be installed until all masonry, painting, plaster, tile, marble and terrazzo work is completed, and overhead mechanical trades and painters have finished in the wood floor areas. The building shall be enclosed and weathertite.
- B. The concrete subfloor shall be determined dry by industry standard testing procedures, free of foreign materials and turned over to the installer (Flooring Contractor) broom clean. Moderate room temperature of 65 degrees or more shall be maintained a week preceding and throughout the duration of the work. Humidity conditions within the building shall approximate the humidity conditions that will prevail when the building is occupied.
- C. Permanent heat, light and ventilation shall be installed and operating during and after installation, maintaining a temperature range compatible with the expected low and high moisture content of the flooring, the moisture content range is determined by the flooring contractor based on the facility's mechanical controls and/or geographical location.
- D. Flooring must be stored in a dry, well-ventilated area, not in contact with masonry, to acclimate to building conditions and shall be installed at moisture content compatible with the normally expected environmental range of temperature and relative humidity achieved while the facility is occupied.
- E. General Contractor shall lock floor area after floor is finished to allow proper curing time. If general contractor or owner requires use of gym after proper curing time, he shall protect the floor by covering with non-marring kraft paper or red rosin paper with taped joints until acceptance by owner of complete gymnasium floor.
- F. Working conditions as described above shall be followed. Variations and substitutions shall be submitted for approval to the architect who shall advise Connor of the same.

1.6 HUMIDITY CONTROL

- A. Since all wood flooring will expand and contract as relative humidity varies, it is important to minimize extremes between low and high. Hardwood flooring is manufactured at moisture content most compatible with a 35%-50% relative humidity range. Geographical regions and available mechanicals determine the typical range of temperature and humidity for each facility. Maintaining a 15% fluctuation between highest and lowest average indoor relative humidity provides limited shrinkage and growth. Facility managers should make use of available HVAC systems to prevent excessive tightening and shrinkage of flooring.

1.7 WARRANTY

- A. Connor warrants that the materials it has supplied will be free from manufacturing defects for a period of one year. The foregoing warranty is in lieu of and excludes all other warranties not expressly set forth herein, whether express or implied in operation of law or otherwise, including, but not limited to, any implied warranties of merchantability or fitness. This warranty is expressly limited to the flooring materials (goods) supplied by Connor. This warranty does not cover floor damage caused (wholly or in part) by fire, winds, floods, moisture, other unfavorable atmospheric conditions or chemical action, nor does it apply to damage caused by ordinary wear, misuse, abuse, negligent or intentional misconduct, aging, faulty building construction, concrete slab separation, faulty or unsuitable subsurface or site preparation, settlement of the building walls or faulty or unprofessional installation of Connor flooring systems.
- B. Connor shall not be liable for incidental or consequential losses, damages or expenses directly or indirectly arising from the sale, handling or use of the materials (goods) or from any other cause relating thereto, and their liability hereunder in any case is expressly limited to the replacement of materials (goods) not complying with this agreement, or at their elections, to the repayment of, or crediting buyer with, an amount equal to the purchase price of such materials (goods), whether such claims are for breach of warranty or negligence. Any claim shall be deemed waived by buyer unless submitted to Connor in writing within 30 days from the date buyer discovered, or should have discovered, any claimed breach.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Vapor Barrier** - 6-mil polyethylene.
- B. Resilient Pads**
 - 1. Connor Rezill DIN 7/16" X 2" X 2" pads.

2. Optional Pads – (specify above or delete)
 - a. Connor MultiFlex 7/16" X 1" X 2-3/4" polyurethane pads.
 - b. Connor NeoShok 3/4" thick, hemispherical, two stage, polyurethane Red 70 durometer (gymnasium) or Blue 60 durometer (multipurpose) or Black 50 durometer (aerobic/dance) pads.
 - c. Connor Rezill R6 3/4" X 2" X 2" pads.
- C. Subfloor** - 2 layers of 15/32" APA rated sheathing, Exposure 1.
- D. Flooring** (Connor SportBond Maple)
 1. 3/8" X 7/8" X 9-5/8" Second & Better Grade, Square Edge, Kiln Dried, Edge Grain, Northern Hard Maple Flooring, graded in accordance with MFMA standards, as manufactured by Connor Sports Flooring, Amasa, MI. Mills option: 1-1/8" flooring strips can be supplied in lieu of standard 7/8" wide flooring strips.
 2. Options - (specify above or delete)
 - a. Sizes – 1/2" X 7/8" X 9" or 11/16" X 7/8" X 9"
 - b. Grades – Third & Better Grade
 3. Treating (specify or delete) - Flooring shall be treated with WOODLIFE-3 preservative.
- E. Fasteners**
 1. Flooring Adhesive - SportBond single component elastomeric polyurethane.
 2. Subfloor Adhesive - PL 400 construction adhesive or equal.
 3. Subfloor Fasteners – 1" coated staples or equivalent.
- F. Finish Materials** - Connor oil modified polyurethane seal and finish or equal.
- G. Game Lines** - Game line paint shall be compatible with finish.
- H. Wall Base** - 3" X 4", heavy duty, molded, vented cove base with pre-molded outside corners.
- I. Protective Floor Cover** (specify or delete) – Provide Connor "Court Cover" protective floor cover. 3' x 6' tiles, 100% Invista type 6,6 nylon, available in standard colors (Mauve, Paradise).

PART 3 - EXECUTION

3.1 EXECUTION

- A. Inspect concrete slab for proper tolerance and dryness. Report any discrepancies to general contractor and architect in writing.
- B. Concrete slab shall be broom cleaned by general contractor.
- C. Installer (Flooring Contractor) shall document all working conditions provided in General Specifications prior to commencement of installation.

3.2 INSTALLATION

A. Subfloor

1. Cover concrete with poly, sealing and lapping joints a minimum of 6".
2. Install lower layer of subfloor perpendicular to long dimension of room spacing all edges 1/4" and breaking joints 4'. Provide 1-1/2" expansion voids at perimeter and at all vertical obstructions. The underside of first layer shall have 32 resilient pads attached per sheet. Space pads nominally 13" on center along 8' edge and 14" center along 4' edge, with outer pads spaced 3" on center from plywood edge. Install solid blocking at doorways and under bleachers in the stacked position.
3. The second layer of subfloor shall be laid at a 45-degree angle over the first layer, 1/4" spacing at all edges and breaking joints 4'. Apply ribbons of PL 400 adhesive in box-X pattern to underside of subfloor. Attach second layer of subfloor with fasteners 12" on center in both directions.

B. Maple Flooring

1. Install Connor SportBond maple flooring into freshly applied SportBond adhesive in a continuous end-to-end pattern.
 - a. Optional pattern (specify or delete) - Connor SportBond maple flooring shall be installed in an alternating SportBond Square parquet pattern.
2. Flooring shall be laid with fine hairline cracks to allow for intermediate expansion, in accordance with local humidity conditions.

3.3 FINISHING

A. Maple Flooring

1. Machine sand with course, medium, and fine paper to a smooth, even and uniform surface.
2. Remove sanding dust from entire surface by tack or vacuum.
3. Inspect entire area of floor to insure that surface is acceptable for finishing, clean and completely free from sanding dust.
4. Apply two (2) coats of approved seal and two (2) coats of approved finish per manufacture's instructions.

5. Buff and clean floor between coats.
6. Games Lines: Apply game lines as indicated on drawings, between seal and first coat of finish.

3.4 BASE INSTALLATION

- A. Install vent cove base to walls with base cement or screws. Use pre-molded outside corners and mitered inside corners.

3.5 CLEANING

- A. Remove excess and waste materials from the area of work.

END OF SECTION 09642

November 26, 2007
SportBondPlus 240
Master Rev C