



1423 Lincolnway East, Goshen, IN 46526
P.O. Box 577, Goshen, IN 46527-0577
(574) 534-2716 FAX
(574) 533-7100

March 31, 2004

To Whom It May Concern:

This is to address the Oliver Technologies System as applied to Commodore Corporation homes. This review is based on the RADCO test report RAD-3236.

Use of the Oliver Technologies Inc. All Steel Foundation Brace System is acceptable for transverse bracing in Wind Zone I on Commodore Corporation homes, pending full compliance with the limitations of the Oliver Technologies' Installation instructions and based on the following limitations:

- Soil Type - per test.
- Maximum Roof Overhang - 16"
- Maximum Sidewall Height - 96"
- Maximum Roof Pitch - 4:12
- Maximum Rail Spacing - per RADCO tests
- Maximum Pier Height - 48"
- Minimum Main Rail Spacing - 99.5"

The certification for this application is for the above for wind resistance to Wind Zone I. All other applications of the Commodore Corporations Installation Instruction Manual must be complied with.

Should anyone have any questions regarding the above, please do not hesitate to contact the undersigned.

Sincerely,

Nasser Tahmassebi

Nasser Tahmassebi
Senior Vice President
Engineering & Production

NT/smc

FEDERAL MANUFACTURED
HOUSING CONSTRUCTION
& SAFETY STANDARDS

APR 1 8 2004

APPROVED

CAUTION

The home manufacturer cannot be responsible for any damage or injury resulting directly or indirectly from installation of accessories, nor any modifications or additions to the home subsequent to shipment from the factory. All alterations or additions must be in compliance with the Federal Manufactured Housing Construction and Safety Standards and will be at the risk of the installer and/or homeowner.

Local building officials should be consulted prior to making any alterations or additions to the home to insure compliance with all applicable codes and requirements.

5.6.7 Alternate tie down systems. Commodore Corporation will accept and approve any proprietary tie down system provided that it complies with the following conditions:

1. System must be listed by a nationally recognized third party agency.
2. System must be approved by a professional engineer.
3. System must be installed in accordance to the Manufactures installation instructions.

Some of the systems, which have been approved for use by Commodore, include:

Vector Dynamics, Oliver Technologies Inc., Tiedown Engineering Xi2, as well as any other company complying with the conditions listed above. It is important to insure that any tie down system being used has been rated for the wind load application in which the home is sited.

5.6.8 Alternate concrete slab anchors. In lieu of auger-type ground anchors described in this manual, anchors which are designed to be imbedded in concrete are acceptable substitutes. Such anchors must be appropriately rated for design loads and installed according to manufacturers installation instructions.

5.7 Site built structures.

5.7.1 Installation of on-site structures. It is considered acceptable to construct an on-site attachment to the home such as a garage, carport, porch or other similar structure provided that the home has been sited on a permanent foundation according to the following limitations:

1. The home was ordered with the appropriate structural package to accommodate the extra loading imposed by the attached structure. To confirm that this option has been built into the home, there will be a label present in the home that will indicate, "home has been designed for attachment."
2. If the home was not ordered with the appropriate optional structure package, then the attached structure must be self-supporting, provided with adequate support for all it's live and dead loads.

All site work including proper fire separation and foundation systems for add-on structures must comply with all state and local codes.