


Pedestal Adapter 9000 Brackets



Tip: When 25"D pedestals are used on a 30"D work-surface, you must specify a pedestal adapter package for each pedestal specified.

STANDARD INCLUDES

Pair of brackets: Black paint only



REQUIRED TO SPECIFY

Style number

SPECIFICATION INFORMATION

Style Number	U.S. Price
9U239	\$50

Rails



STANDARD INCLUDES

Package of two or four rails: Black paint only

REQUIRED TO SPECIFY

Style number

SPECIFICATION INFORMATION

Width	Style Number	U.S. Price
<i>For Use with Drawers (Package of Two)</i>		
15"	RXADRL15	\$16

Dividers



STANDARD INCLUDES

Package of two dividers: Black only


REQUIRED TO SPECIFY

Style number

SPECIFICATION INFORMATION


Dimensions	Style Number	U.S. Price
<i>For Use in 6"H Drawers</i>		
15"	RXADV1506	\$26
<i>For Use in 12"H Drawers</i>		
15"	RXADV1212	\$26

Product Details




Flush-front pull full-width and integral with the drawer.

Optional full-width wood pulls attach to integral pull with double-sided tape. Wood pull ships separately from pedestal for field installation.



Pencil tray to hold small office supplies is included with each box/box/file pedestal.


Label holders are available from Customer Service Parts. Label holder fits inside the integral pull.




Locks are available factory- or field-installed. Factory-installed locks are standard and available keyed random only. Optional field-installed locks are available with consecutive, specific, and random keying options. Master-keyed locks are also available. Field-installed lock cylinders must be specified separately.

Individual drawer locks are available on file/file pedestals for applications where you want to limit access to each drawer. Pedestals include a security shield above each drawer to prevent unauthorized access. Individual locking drawers are only available with field-installed locks. Consecutive, specific, and random keying options are available. Master-keyed locks are also available. Field-installed lock cylinders must be specified separately.


Connections



Panel supported worksurfaces can support pedestals. Use an end panel to provide sufficient support for the work surface.




Recessed back panels require that pedestals be 5" less deep than the work surface.




25"D pedestals when attached to 30"D unit assemblies with recessed back panel will require a pedestal adapter bracket to be specified. A pedestal adapter bracket can only be used in this application.

Note: When specifying a 30"D unit assembly with one/two pedestals and recessed back panel, adapter brackets are included.



Fixed pedestals can be attached two in a row on 45"W, 60"W, 65"W, 70"W, or 75"W worksurfaces, or three in a row on 70"W, 75"W, or 90"W worksurfaces.

Exception: 90"W panel supported work surface ships with a center support. If the work surface is to be attached to two 45"W panels, the center support will block attachment of the third pedestal.



Field installed accessories are available, (i.e. pencil trays, media trays, stationery trays, dividers, and rails).

Wiring & Cabling



Front grommets should not be specified over pedestals..

Pedestals do not reach to the floor, which allows access to receptacles in the panel base. Pedestals can be used to conceal access to power on the floor.

Surface Materials

Pedestal, steel drawer fronts, and integral pulls

- Paint

Pedestal, steel drawer fronts, and integral pulls

- Open-pore finishes
- Customized stain (option)


Lock

- 9201 Polished Chrome
- 9250 Ember Chrome (option)


Drawer bodies, drawer suspensions, rails, dividers, and glides

- Black

Application Topics



Full-height pedestal



3/4-height pedestal

26 1/4" H worksurfaces do not allow enough space for a full-height pedestal or back panel. Use 3/4-height pedestals or raise the worksurface.

45" W modular return or 45"W modular worksurface package will accommodate pedestals.

45" W modular bridge does not accommodate pedestals.

60" W modular bridge will accommodate three pedestals.

Shipping

Pedestals are normally shipped in heavy-duty, recyclable stretch wrap to reduce the amount of corrugated board needed.