

MULTIPLE NOMINATION HISTORIC DISTRICT SUMMARY FORM

MRA/THEMATIC NOMINATION TITLE: Eastside Multiple Resource Area

HISTORIC DISTRICT NAME: Emery-Price Historic District

OWNER OF PROPERTY: Multiple ownership

(On Continuation Sheets list all properties by address which are included within the district and provide the names and addresses of their owners.)

DESCRIPTION: See continuation sheets

Condition		Check one	Check one
<input checked="" type="checkbox"/> excellent	<input checked="" type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved date _____
<input checked="" type="checkbox"/> fair	<input type="checkbox"/> unexposed		

Describe the present and original (if known) physical appearance

(Use Continuation Sheets)

SIGNIFICANCE

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/humanitarian
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> transportation
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics government	<input checked="" type="checkbox"/> other (specify: <u>Black History</u>)
		<input type="checkbox"/> invention		

Specific dates Ca. 1840-1935 **Builder/Architect** N/A

Statement of Significance (in one paragraph)

(Use Continuation Sheets)

GEOGRAPHICAL DATA

Acreage of nominated property Approx. 19 acres

Quadrangle name Covington, KY

Quadrangle scale 1:24,000

UTM References

A	<u>16</u>	<u>715500</u>	<u>4328680</u>	B	<u>16</u>	<u>715695</u>	<u>4328710</u>
	Zone	Easting	Northing		Zone	Easting	Northing
C	<u>16</u>	<u>715830</u>	<u>4328490</u>	D	<u>16</u>	<u>715585</u>	<u>4328345</u>
E	<u>16</u>	<u>715770</u>	<u>4328330</u>	F			
G				H			

Verbal boundary description and justification

(Use Continuation Sheets)

DISTRICT MAPS ATTACHED:

1. District Boundary Map Showing Contributing & Noncontributing Properties.
2. District Map Showing Location & Direction of Numbered Photographs.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

For NPS use only
received 2/9/87
date entered

Emery-Price Hist. Dist. (Eastside MRA)
Continuation sheet Covington, Kenton Co., KY Item number 7

Page 1

Emery-Price Historic District

Description

The Emery-Price Historic District contains 134 structures along or part of 13 blocks in downtown Covington, Kentucky. The district is composed primarily of pre-1900 residential structures constructed in the late Greek Revival, Queen Anne, Italianate, Second Empire and Colonial Revival designs. Within the district are 104 contributing and 30 non-contributing buildings. While some commercial encroachment has occurred on the northern edges of the district the area remains primarily residential in character.

The area encompassed by the district is composed of flat terrain with the streets divided into a standard north/south and east/west grid. The land averages approximately 50' to 55' above the level of the Licking and Ohio Rivers. To the north of the district is the Licking-Riverside Historic District (NR, 1975). To the west is the main commercial area of the city and the Downtown Commercial Historic District (NR, 1983). To the east is the floodwall of the Licking River and the modern Price Housing Projects. On the south of the district is a continuation of older architecture on rectangular blocks in the proposed Helentown District.

The Emery-Price Historic District is bounded on the north by Eighth Street, on the west by rear lot lines of properties facing Scott Street and Madison Avenue, on the south by Lynn, Robbins and Eleventh streets and on the east by Greenup Street and an irregular line at the rear of properties along Greenup Street, Robbins Street and Lynn Street.

East/West Streets

E. 8th Street

Overview: E. 8th Street in the district contains four contributing buildings.

Detailed Description: The south side of the 100 block of E. 8th Street forms the northern boundary of the district. On this block is a one-story brick Italianate residence and three two-story brick duplexes (Photo 10). One duplex is a late Greek Revival style and the other two are Second Empire designs with slate mansard roofs. All properties on this block are contributing and have not been significantly altered.

E. 9th Street

Overview: E. 9th Street in the district contains 14 contributing and 4 non-contributing buildings.

United States Department of the Interior
National Park ServiceNational Register of Historic Places
Inventory—Nomination Form

Emery-Price Hist. Dist. (Eastside MRA)

Continuation sheet Covington, Kenton Co., KY Item number 7

Page 2

For NPS use only

received

2/9/87

date entered

Detailed Description: E. 9th Street is a narrow east/west street and parts of two blocks between Madison Avenue and Greenup Street are in the district. Adjacent to the district boundary is the 9th Street Methodist Church which is located in the Downtown Commercial District. This church was constructed in 1860 and has been an important black church since 1880. Although already a part of the adjacent district the church has important connections with the Emery-Price area. On the south side of the block between Madison and Scott are six buildings, two of which are non-contributing due to alterations. The remaining buildings are brick late Greek Revival dwellings constructed before 1869. On the north side of the 100 block are several vacant lots, four pre-1869 brick residences and the First Colored Baptist Church. The Baptist Church was constructed in 1916 and designed by architect Randolph Craig in a simple vernacular Gothic design. On the south side of the block are three two-story Italianate brick homes constructed before 1869 and a two-story Greek Revival home (Photo 18). The Italianate house at 111 E. 9th Street displays excellent sheet metal hood molding and cornice brackets. Also in the block are three frame houses, two of which are non-contributing due to alterations.

E. 10th Street


Overview: E. 10th Street in the district contains 19 contributing and 6 non-contributing buildings.

Detailed Description: Parts of three blocks of E. 10th Street are included between Madison Avenue and Prospect Avenue. In the block between Madison Avenue and Scott Street are two brick Colonial Revival residences located at 10 and 14 E. 10th and a Mission style apartment building constructed ca. 1910 4-6 E. 10th. These structures are some of the few early 20th century dwellings in the district. Also on the block is a two-story Greek Revival dwelling and two contributive but altered residences. In the 100 block is one of the district's few modern intrusions, the 1975 general fire station. Although the building occupies half of the block it has extensive site planning and landscaping which mitigates its modern design. Adjacent to the fire station's parking area is a three-story brick rowhouse built between 1877 and 1886 in the Second Empire style (Photo 19). This rowhouse has four separate units and is a major contributive element in the district.

On the north side of the 100 block are eight brick and frame residences all of which are contributing. Four are simple Queen Anne and Greek Revival designs while the other four have Italianate detailing. At 144 E. 10th is a corner store constructed after 1877 in the Italianate style. The storefront has been enclosed with brick but the cast iron pilasters remain visible. In the 200 block of E. 10th only four structures are included including a fine Greek Revival duplex at 215-217 (Photo 12). Beyond these structures are numerous vacant lots and altered frame buildings.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form



Emery-Price Hist. Dist. (Eastside MRA)

Continuation sheet Covington, Kenton Co., KY Item number 7

Page 3

E. Robbins Street

Overview: E. Robbins Street in the district contains 9 contributing and 2 non-contributing buildings.

Detailed Description: East Robbins is another east/west street running between Madison and Prospect Avenues. Parts of three blocks are included in the district. On the north side of the street in the block between Madison and Scott are two matching ca. 1880 Italianate brick residences, a pre-1869 Greek Revival dwelling and Colonial Revival design building (Photo 6). In the 100 block only two buildings, both Italianate residences, face Robbins Street. In the 200 block the north side of the street is included which contains two altered frame dwellings and three pre-1869 Greek Revival residences (Photo 11).

Lynn Street

Overview: Lynn Street in the district contains 5 contributing and 4 non-contributing buildings.

Detailed Description: Lynn Street is a block long east/west street which runs between Scott and Greenup Streets. Lynn Street contains seven residences, three of which are non-contributing, and two important black churches. At 127 Lynn is the Lane Chapel Methodist Church built in 1925. Across the street is the St. James Methodist Church which was built in 1947 and is non-contributing. At 121 Lynn is a notable one-story frame dwelling with excellent rusticated wood frame siding and it is one of the few structures in the Eastside area with this type of exterior treatment. The residences on the street are mainly Italianate designs although several have been altered.

E. 11th Street

Overview: E. 11th Street in the district contains 4 contributing buildings.

Detailed Description: The southern boundary of the district is defined by the north side of E. 11th Street. Approximately half the block is included between Scott and Greenup Streets to include four contributing structures. At 118 E. 11th is a fine two-story brick Queen Anne with a corner tower. At 114 and 118 are two pre-1877 brick residences with Italianate and Greek Revival detailing. At the corner of Eleventh and Greenup is a two-story brick corner store (Photo 9). Although the storefront has been altered the original cast iron pilasters remain. On this block are also several vacant lots.

North/South Streets

Scott Street

Overview: Scott Street in the district contains 33 contributing and 9

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Emery-Price Hist. Dist. (Eastside MRA)

Continuation sheet Covington, Kenton Co., KY Item number 7

For NPS use only
received 2/19/87
date entered

Page 4

non-contributing buildings.

Detailed Description: Scott Street is a major north/south street in Covington and one of the most significant in the district. The wide north/south streets such as Scott generally contain larger and more prominent homes than those streets running east/west. Within the boundaries of the district are all or parts of four blocks of Scott Street. In the 800 block are several altered structures on the east side of the street which have been converted into commercial use (Photo 16). At 810-28 Scott is Emery Row, a three-story brick eleven unit rowhouse constructed in the Queen Anne style (Photo 17). Built ca. 1880, the building is attributed to architect S. Hannaford. This rowhouse is the largest in the district and one of the most significant in the Eastside area. It features extended bay windows, square towers and arched windows on the top floor. Over the windows is stone jack arching and each floor is divided by belt coursing. On the west side of the 800 block are seven pre-1900 structures which form an impressive grouping of styles. Only two are non-contributing due to brick additions on the main facade (Photo 1). The buildings at 809 and 811 Scott are substantial three story, brick Second Empire designs. At 825 Scott is a modern two-story intrusion.

On the west side of the 900 block between 9th and 10th Streets are two Italianate and two Queen Anne structures (Photo 2). The Italianate design at 913 Scott was originally a commercial building and it retains much of its cast iron storefront. On the east side of the 900 block are two Queen Anne rowhouses, one altered structure and the Colonial design Health Department Clinic whose facade was added to an older structure in 1929. The east side of the 1000 block of Scott contains a modern fire station. On the west side are two contributing Italianate residences and a three-story Queen Anne rowhouse at 1013-1019 (Photo 7).

After crossing E. Robbins on Scott Street is the Covington Arts Center built in 1905 (Photo 20). This building, originally the public library, is an excellent example of the Neo-Classical style with a rusticated limestone exterior and was constructed by the Andrew Carnegie foundation (NR 1972). The building was designed by architects Boll and Taylor of Cincinnati and displays an large pediment supported by Ionic columns on the main facade. Over the doorway is an elliptical pediment supported by brackets. Other details include quoining, a prominent cornice with modillion blocks and statuary in the gable field. At 1023 Scott is a good example of a ca. 1900 Colonial Revival townhouse featuring Doric porch columns and a Palladian window in the gable of the main facade. Two vacant lots and an Italianate residence are also located on the west side of the block. South of Lynn Street are modern structures which are excluded from the district.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

For NPS use only
received 2/19/87
date entered

Emery-Price Hist. Dist. (Eastside MRA)

Continuation sheet Covington, Kenton Co., KY Item number 7

Page 5

Greenup Street

Overview: Greenup Street in the district contains 16 contributing and 5 non-contributing buildings.

Detailed Description: Greenup Street is another major north/south thoroughfare in Covington and parts of five blocks lie within the district boundaries. On the west side of the 800 block is a Queen Anne corner store with much of its storefront intact and Italianate residence both of which were built between 1894 and 1909. At 811-13 is the Mildred Flats apartment building constructed ca. 1900 (Photo 14). On the east side of this block is the Robinson Business College, formerly the Lincoln-Grant Public School (Photo 15). This school was the center for black education during much of the 20th century. Constructed in 1932, it was the major black high school in Covington until it was desegregated in 1965. The three-story brick school is a combination of restrained Classical and Art Deco elements. It is one of the few examples of Art Deco detailing in the Eastside area.

Between 9th and 10th Streets on the west side are two altered buildings in the 900 block (Photo 3). On the east side are seven pre-1900 buildings, two of which are altered (Photo 8). On the west side of the 1000 block are three large vacant lots and at 1013 is a Italianate store. This store has a bricked in storefront but the original stone columns remain. On the east side of the block is a fine row of five Queen Anne and Italianate design residences and stores with one intrusion (Photo 4). Past Robbins on the west is a large three-story ca. 1880 commercial building.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

For NPS use only

received

NOV 1 1987

date entered

Continuation sheet Emery-Price Hist. Dist. (Eastside MRA)
Covington, Kenton Co., KY Item number 8

Page 1

Emery-Price Historic District

Significance

The Emery-Price Historic District is a significant collection of pre-1900 architecture located near downtown Covington, Kentucky. The district is significant through its architecture and also as a center for Covington's black population since 1900. The majority of properties were built between ca. 1840 and 1900 in late Greek Revival, Italianate and Queen Anne designs. The district has been primarily a middle and working class neighborhood adjacent to the commercial area of Covington.

Much of the Emery-Price district was settled after 1840 by German and Irish immigrants. One block south of the district at 12th and Greenup German residents built St. Joseph's Church (now demolished) which was a center for German residents for much of the 19th century. By 1880 most lots in the Emery-Price area had been settled with one to two-story brick and frame homes.

By the late 19th century the Emery-Price area became one of the centers for Covington's small black population. One of the first black schools was located on Robbins Street near Madison (now demolished) and the district was home to many of the city's black professionals. The 9th Street Methodist Church adjacent to the district served a black congregation beginning in 1880. One of the major leaders of the black community was the Reverend Jacob Price who was a successful merchant, minister and community leader. He helped establish several churches in the neighborhood and promoted black education. The Jacob Price Homes which are located on the eastern edge of the district are named in his honor. The Lincoln-Grant School was the major black school of the 20th century in Covington and still stands on Greenup Street.

While some demolition and alterations to structures has occurred within the district most properties display their original architectural detailing. Within the district are fine examples of Victorian architecture including the notable Queen Anne Emery Row rowhouse on Scott Boulevard. The district continues to be an important center for Covington's black population and the area is a center for city directed rehabilitation efforts.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Emery-Price Hist. Dist. (Eastside MRA)

Continuation sheet Covington, Kenton Co., KY

Item number 10

Page 1

For NPS use only

received


date entered

Emery-Price Verbal Boundary Description and Justification

The boundary of the Emery-Price Historic District is as follows:

Beginning on the southeast corner of Greenup and E. 11th St., thence westwardly following the north right-of-way line of E. 11th St. 175' to a point, thence northward 75', thence westward 15' to a point, thence north 75' to a point across Lynn St. to the north right-of-way line of Lynn, thence westwardly 150' to the northeast intersection of Lynn and Scott Blvd., thence 50' northwardly along the eastern right-of-way of Scott to a point, thence 150' westwardly across Scott to the southwest boundary of 1033 Scott, thence 175' northwardly to a point across E. Robbins on the north right-of-way of E. Robbins, thence westwardly 75' to the first alley west of Scott, thence 200' along the east right-of-way of the alley to a point across E. 10th St., thence 100' westwardly across the alley along the north right-of-way of E. 10th St. to a point, thence northwardly 50' to a point, thence 40' eastwardly to a point, thence 35' northwardly to the first alley north of E. 10th St., thence 25' along the south right-of-way, thence 25' northwardly across the alley to a point, thence 10' westwardly to a point, thence northwardly 50' to the south right-of-way of E. 9th St., thence 160' eastwardly to a point, thence 275' across E. 9th St., across E. Saratoga to the south right-of-way of E. 8th St., thence 450' to the southwest corner of Greenup and E. 8th St., thence 125' southwardly across E. Saratoga to the southern right-of-way, thence 225' across Greenup to a point, thence 175' to the north right-of-way of E. 9th St. to a point, thence eastwardly 50' to a point, thence southwardly 125' across E. 10th St. to the south right-of-way, thence eastwardly 100' to the east property line of 223 E. 10th St., thence 75' southwardly to a point, thence 25' eastwardly to a point, thence 75' southwardly to the north right-of-way of E. Robbins, thence 350' westwardly across Greenup St. to a point, thence 175' southwardly across E. Robbins to a point, thence 75' eastwardly across the northern boundary of 1035 Greenup to the west right-of-way of Greenup, thence 200' southwardly across Lynn to the point of beginning.

The Emery-Price Historic District is bounded on the north by the Licking Riverside Historic District and the Downtown Commercial Historic District. On the west the district is bounded by the Downtown Commercial Historic District and modern intrusions along Madison Avenue. On the south the district is bounded by the proposed Helentown Historic District and modern intrusions. To the east the boundary line is drawn to exclude altered non-contributing properties and the intrusive Jacob Price housing project. This boundary is drawn to include the majority of properties associated with the areas of significance of the Emery-Price district.



Emery-Price Historic District
 (Eastside MRA, Covington, Kenton Co)
 Quad: Covington, KY 1:24,000
 UTM References

- A. 16/715500/4328680
- B. 16/715695/4328710
- C. 16/715830/4328490
- D. 16/715585/4328345
- E. 16/715770/4328330

(NEWPORT) 4162 III SW
 DE COURSEY 2.5 MI.
 KENTON 14 MI.


NOV 14

EMERY-PRICE HISTORIC DISTRICT




EASTSIDE MULTIPLE RESOURCE AREA
COVINGTON, KENTUCKY

MAP KEY



VACANT - NON-CONTRIBUTING



PRE-1935 STRUCTURE
ALTERED - NON-CONTRIBUTING



POST-1935 STRUCTURE
NON-CONTRIBUTING



ALL OTHER PROPERTIES ARE CONTRIBUTING
THOSE MARKED WITH AN "A" ARE ALTERED BUT CONTRIBUTING

SCALE- 1" = 100'

NORTH ARROW AS MARKED

Licking River

34
41



PROSPECT


GREENUP AV.

E. 11TH ST.

40

E. ROBBINS

JACOB PRICE HOMES
THE CITY OF CINCINNATI MUNICIPAL HOUSING
COMMISSION (COLORADO)



Eastside MRA
Emery-Price Historic District

GARRARD ST.

GREENUP

31

Copyright 1954 by The Southern Map Co.









R.E. PRICE
I.I. PRICE

NOV 1 194



22

23



MADISON AV.


SCOTT (BLVD)

GREENUP

Eastside MRA
Emery-Price Historic
District




39



E. 11TH ST. MARKET SPACE


NOV 1 4



Eastside MRA
Emery-Price Historic
District




L i c k i n g R i v e r



Eastside MRA
Emery-Price Historic
District

Copyright 1924 by the Sanborn Map Co



22

SCOTT (BLVD)

24

GREENUP

Eastside MRA
Emery-Price Historic
District



107 14

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form



Continuation sheet

Item number

Page

Multiple Resource Area
Thematic Group

dnr-11

Name Eastside Multiple Resource Area

State Kenton County, KENTUCKY

Nomination/Type of Review

Date/Signature

1. Austinburg Historic District

Substantive Review

Keeper

Attest

A. Schlagel 2/18/87

2. Emery-Price Historic District

Substantive Review

Keeper

Attest

A. Schlagel 2/18/87

3. Helentown Historic District

Substantive Review

Keeper

Attest

A. Schlagel 2/18/87

4. West Fifteenth Street Historic District

Substantive Review

Keeper

Attest

A. Schlagel 2/18/87

5.

Keeper

Attest

6.

Keeper

Attest

7.

Keeper

Attest

8.

Keeper

Attest

9.

Keeper

Attest

10.

Keeper

Attest

86003484

NATIONAL REGISTER OF HISTORIC PLACES
EVALUATION/RETURN SHEET

Emery--Price Historic District (Eastside MRA)
Kenton County
KENTUCKY

NOV 14 1986

Substantive Review

Working No. _____

Fed. Reg. Date: _____

Date Due: 12/1/86 - 12/29/86

Action: ACCEPT

RETURN 12-29-86

REJECT

Federal Agency: _____

- resubmission
- nomination by person or local government
- owner objection
- appeal

Substantive Review: sample request appeal NR decision

Reviewer's comments:

Please review count as disc in cover -
Also, please clarify difference between
Kenton County Library which is not clear
as either in this district or in Helentown -
listed on NR for 1983 or in 1972 - as
in cover form listed in in form

Recom./Criteria Return

Reviewer A Schlage

Discipline Arch Hist

Date 12/29/86

see continuation sheet

Nomination returned for: technical corrections cited below and modify count as appropriate
 substantive reasons discussed below - In other works - are there 2 library buildings

1. Name

2. Location

3. Classification

Category	Ownership	Status	Present Use
	Public Acquisition	Accessible	

4. Owner of Property

5. Location of Legal Description

6. Representation in Existing Surveys

Has this property been determined eligible? yes no

7. Description

Condition	Check one	Check one
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> original site
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input type="checkbox"/> moved date _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed	
	<input type="checkbox"/> unaltered	
	<input type="checkbox"/> altered	

Describe the present and original (if known) physical appearance

- summary paragraph
- completeness
- clarity
- alterations/integrity
- dates
- boundary selection

8. Significance

Period _____ Areas of Significance—Check and justify below

Specific dates _____ Builder/Architect _____

Statement of Significance (in one paragraph)

- summary paragraph
- completeness
- clarity
- applicable criteria
- justification of areas checked
- relating significance to the resource
- context
- relationship of integrity to significance
- justification of exception
- other

Emery-Price Historic District (Statewide HRA)
 Kenton County
 KENTUCKY

9. Major Bibliographical References

10. Geographical Data

Acreage of nominated property _____

Quadrangle name _____

UTM References _____

Verbal boundary description and justification _____

11. Form Prepared By

12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

____ national ____ state ____ local

State Historic Preservation Officer signature _____

title _____ date _____

13. Other

- Maps
- Photographs
- Other

Questions concerning this nomination may be directed to _____

Signed Amy Schlaepf Date 12/29/86 Phone: _____

116
136
PROBLEM DESCRIPTION SHEET

State Name KY County Name Kenton

Resource Name Emery-Price Historic District

Data Collector's Surname MHW Today's Date 18/Nov/86

Federal Register List 1/1 Cert. Date 1/1

Reference No. 0600 3484

Describe Problem:

Check
County
Issue

① Building count is inaccurate; row houses have been counted as single, rather than individual, buildings (eg Item 7, p. 2^(E. 10²⁵¹), #1; p. 3 Sect. 91). I have counted an additional 19 c. buildings, bringing the total to 135. Also, Kenton Co. library appears (from address and name) to be in this H.D., not in Helentown, as stated in cover. On the other hand, the 1983 date for NR listing does not agree with the 1972 LI date of the library at 1028 Scott. I have counted it here on basis of address. There are no libraries pending in Kenton county (1 bldg has been subtracted from c. bldgs) not used as lib today -> Very good catch - What is the story

② UTHs have been re-ordered to start in NE corner of district and proceed clockwise.

Changes made by Thompson 1/21/87

here?
diff date of constr
diff listing date -
2 diff bldgs?

Team Leader _____ Date 1/1 N R Staff _____ Date 1/1

Problem Team _____ Date 1/1

NATIONAL REGISTER OF HISTORIC PLACES
EVALUATION/RETURN SHEET

Emery--Price Historic District (Eastside MRA)
Kenton County
KENTUCKY

Substantive Review

Working No. 11/14/86
Fed. Reg. Date: 2/2/88
Date Due: 3/26/87
Action: ACCEPT 2-18-87
 RETURN
 REJECT
Federal Agency: _____

- resubmission
- nomination by person or local government
- owner objection
- appeal

Substantive Review: sample request appeal NR decision

Reviewer's comments: *Corey context problems resolved*
Property signed as example of neighborhood of 19th-20th Wm
accord to committee (discuss staff) Schloess Miller 2/87
Acceptance
Recom./Criteria _____
Reviewer _____
Discipline 2/18/87
Date _____
see continuation sheet

Nomination returned for: _____ technical corrections cited below
_____ substantive reasons discussed below

1. Name _____

2. Location _____

3. Classification
Category _____ Ownership _____ Status _____ Present Use _____
Public Acquisition Accessible

4. Owner of Property _____

5. Location of Legal Description _____

6. Representation in Existing Surveys
Has this property been determined eligible? yes no

7. Description
Condition: excellent good fair
 deteriorated ruins unexposed
Check one: unaltered altered
Check one: original site moved date _____

Describe the present and original (if known) physical appearance
 summary paragraph
 completeness
 clarity
 alterations/integrity
 dates
 boundary selection

8. Significance

Period Areas of Significance—Check and justify below

Specific dates Builder/Architect
Statement of Significance (*in one paragraph*)

- summary paragraph
- completeness
- clarity
- applicable criteria
- justification of areas checked
- relating significance to the resource
- context
- relationship of integrity to significance
- justification of exception
- other

9. Major Bibliographical References

10. Geographical Data

Acreage of nominated property _____
Quadrangle name _____
UTM References _____

Verbal boundary description and justification

11. Form Prepared By

12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

____ national ____ state ____ local

State Historic Preservation Officer signature

title date

13. Other

- Maps
- Photographs
- Other

Questions concerning this nomination may be directed to _____

Signed _____ Date _____ Phone: _____



















COVINGTON LIQUOR
DISPENSARY

COVINGTON LIQUOR
DISPENSARY

ONE WAY

Coca-Cola

ICE
KEES

1900



RENTAL

NO STANDING
OR PARKING
EXCEPT
AS SHOWN













HEAL BARBERS

LANVIN FR. BLDG.

481 3637

ONE WAY



SCOTT







Carnegie
Arts Center

Please refer to the map in the
Multiple Property Cover Sheet
for this property

Multiple Property Cover Sheet Reference Number: 64000217