## NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY

RECEIVED

NOV 0 5 1979

DATE ENTERED

JAN 1 0 1980

SEEI	NSTRUCTIONS IN HOW TO TYPE ALL ENTRIES O			S
1 NAME	New Amsterdam TH			
	sew romaneration 1	Contract		
HISTORIC	m mi	1 1 1 0	1	
	m Theater, Rooftop The	ater and Aerial Ga	ardens	
AND/OR COMMON	- Decil diago. Non Amaton	Jam Thooton Doofts	n Thouton	
ine New Amsterdar	m Building: New Amster	dam Ineater, Rooft	op meater	
2 LOCATION	1			
STREET & NUMBER				
214 West 42nd St	treet	13 (da. 21)	NOT FOR PUBLICATION	
CITY, TOWN			CONGRESSIONAL DISTR	IICT
New York City		VICINITY OF	20	see EndopOds
STATE New York		CODE 037	county New York	O61
3 CLASSIFIC	ATION			
CATEGORY	OWNERSHIP	STATUS	PRES	ENT USE
DISTRICT	PUBLIC	X OCCUPIED	AGRICULTURE	MUSEUM
$\frac{X}{X}$ BUILDING(S)	X_PRIVATE	_UNOCCUPIED	XCOMMERCIAL	
STRUCTURE	BOTH	WORK IN PROGRESS	EDUCATIONAL	PARK
SITE	PUBLIC ACQUISITION	ACCESSIBLE	ZENTERTAINMENT	PRIVATE RESIDENC
OBJECT	_IN PROCESS	XYES: RESTRICTED		
_055201			GOVERNMENT	SCIENTIFIC
	BEING CONSIDERED	YES: UNRESTRICTED	INDUSTRIAL	TRANSPORTATION
		NO	MILITARY	OTHER:
4 OWNER O	F PROPERTY			
NAME				
Antour Er	nterprises; Mark I. Fi	nkelstein, Principa	11	
	10 1 0			
CITY, TOWN	42nd Street		STATE	
New York	City	VICINITY OF	New York 1	0037
			New Tork 1	0037
5 LOCATION	NOF LEGAL DESCR	APTION		
COURTHOUSE,				
REGISTRY OF DEEDS,	ETC. Surrogate's Court	t		
STREET & NUMBER				
	31 Chambers Stree	et		
CITY, TOWN			STATE	
	New York City		New York 1	0037
6 REPRESEN	TATION IN EXIST	ING SURVEYS		
A STATE OF THE PARTY OF THE PAR				
TÎTLE	e Continuation She	<b>~</b> +		
	e Continuation she	ec		
DATE		FEDERAL	STATECOUNTYLOCAL	
DEPOSITORY FOR	1 3000		LUCAL	•
SURVEY RECORDS				
CITY, TOWN			STATE	

X GOOD

\_FAIR

#### CONDITION

\_\_EXCELLENT \_\_\_DETERIORATED RUINS UNEXPOSED

**CHECK ONE** 

\_UNALTERED X ALTERED

CHECK ONE

X ORIGINAL SITE MOVED DATE.

BOVAD FRAD BAR

#### DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The New Amsterdam Building is located at 214 West 42nd Street, on the south side of the block bounded by Seventh and Eighth Avenues. It was designed in 1903 by Henry B. Herts and Hugh Tallant as a performance showplace for the renowned theatrical production team of Marc Klaw and Abraham Erlanger. Klaw and Erlanger went to the considerable expense of over \$1,500,000 to build the New Amsterdam, excluding the cost of the land. The New Amsterdam Building houses the main theater, whose access is gained through the lobby of an elevenstory office tower, which is surmounted by a second theater on its roof. These features combine to make the New Amsterdam an ingeniously versatile building and an early example of the multiple-use planning concept as applied to the design of theater buildings. The main theater was opened to the public on October 26, 1903, with Klaw and Erlanger's sumptuous production of Shakespeare's A Midsummer Night's Dream, starring Nathaniel C. Goodwin. Klaw and Erlanger allowed Herts and Tallant an unusual degree of financial and aesthetic freedom in the design of the New Amsterdam. This enabled the architects to pursue a far-reaching artistic program for the building's interior and 42nd Street facade. The work of over twelve American and European sculptors, painters and craftsmen, working primarily in the then-emerging Art Nouveau idiom, gives the New Amsterdam its elegant and distinctive atmosphere.

The New Amsterdam office tower, which fronts on 42nd Street, is 150 feet high and approximately 20 feet wide. The tower is composed of six floors devoted to office use above an arched theater entrance of three stories. The facade of the building is of grey limestone, and is topped by a steep red tile roof. A large central dormer bears the standing figures which represent Drama and Music; the roof is topped by a cheneau of wrought bronze. The seventh floor level has three large windows, with tympana decorated with terra cotta panels designed by Grendellis and Ricci. These panels depict trios of cupids symbolizing Song, Declamation and Dance. 1

In its original appearance, the theater entrance had a pair of double doors framed by a low segmental arched opening, flanked by two rusticated stone piers. These doors and transoms featured panels of elaborately leaded glass. A large, curved glass panel bearing the name of the theater was located above the door. This entrance configuration was altered c. 1937, when the New Amsterdam was converted from a legitimate theater to use as a motion picture theater. At this time, the original doors and their transoms of leaded glass were removed; above the location of the original doors, a two-story high arch with levels of windows remains. The windows have a bronze framework which is decorated with realistically modelled flower and vine forms. These windows were originally flanked by pairs of Moureale Sicilian marble columns, veined in gray and white and trimmed with ornamental bronze belts. The bronze capitals, the design of which was based on the Composite order, were the work of Enid Yandell. 2 Between the volutes were heads representing the four ages of drama, and long bronze pendants extended down the column shafts. These columns supported a high-arched entablature with a modillion cornice. A large keystone, carved by Grendellis and Ricci, was draped with a garland of oak, laurel and ivy. Centered above the cornice was a cluster of sculpted figures which were the work of George Gray Barnard. The central

UNITED STATES DEPARTMENT OF THE INTERIOR HERITAGE CONSERVATION AND RECREATION SERVICE

#### FOR HCRS USE ONLY

RECEIVED NOV 0 5 1979

DATE ENTERED

JAN 1 0, 1980

### NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

New Amsterdam Theater, Rooftop Theater and Aerial Gardens New York County

**CONTINUATION SHEET** 

ITEM NUMBER 6 PAGE 1

- 1. WPA Files, Artists and Writers Project
  Department of Records and Information Services Federal
  Municipal Archives, New York, New York
- 2. "42nd Street Theatre and the City" Exhibition, Fall 1977, text and booklet by Josephine Dakin, Megan Lawrence and Ray Ring for The Graduate Center, City University of New York
  33 West 42nd Street, New York, New York
  Local
- 3. "Inside 42nd Street"

  Exhibition, Summer, 1978, text and booklet by May Callas, sponsored by the 42nd Street Redevelopment Corporation at the W.R. Grace and Co. Gallery
  1114 Avenue of the Americas, New York, New York
- 4. American Institute of Architects Guide to New York City
  Norval White, Elliot Willensky
  Collier Macmillan Publishers, 1978
  New York, New York
- 5. Survey of the Times Square Area
  New York City Landmarks Preservation Commission
  305 Broadway, New York, New York, 1978

#### NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY	1			
RECEIVED	inv 05	1979		
DATE ENTERED		1019	80	

CONTINUATION SHEET 1

ITEM NUMBER 7 PAGE 2

figure was a woman personifying Drama, holding a mirror in one hand and a mask in the other. Above her head was a draped baldachin representing the stage; from the baldachin, extending down the slope of the arch were garlands of fruit and flowers, and musical instruments. To the left of the central figure was Pierrot, representing musical comedy. The skillfully executed and highly ornamental allegorical scenes, set against a classically-derived facade, communicated a sense of theatrical intrigue.

The original entrance doors of the New Amsterdam opened directly into a small vestibule containing relief panels by St. John Issing. The theme of the panels was folklore; the floor of this area was laid with sage green square antique cathedral tiles. When the New Amsterdam Theater began to show movies (c. 1937), this vestibule was altered to its present appearance. It is now open to the air, and an exterior ticket booth was added on the western side of the entrance.

The lobby walls, finished in beige terra cotta, form an enframement for a series of display panels, ticket windows and elevator doors. The walls have foliated marble panels between pilasters of modelled terra cotta by Grendellis and Ricci from designs by Neumark of Bremen. Along the upper portion of each of the walls is a series of twelve relief panels by the sculptor R. Hilton Perry. The panels on the east wall depict five scenes from Shakespeare: Macbeth and the Witches; the Battle of Bosworth Field; Hamlet and his father's ghost; Rosalind watching Orlando in the Forest of Arden; and Titania and Bottom from A Midsummer Night's On the west wall are five panels from Richard Wagner's dramatic operas: Aldrich's advent in the lair of the Rhine maidens; Siegfried's battle with the Dragon; the awakening of Brunnhilde by Siegfried's kiss; the death of Siegfried; and the fulfillment of the curse. The panel over the entrance depicts a scene from Faust. Over the auditorium doors is a panel representing Greek drama. The lobby was originally lit by a series of plaster and leaded glass chandeliers, suspended from a coffered ceiling. These chandeliers have been replaced by unobtrusive, modern fixtures. The lighting served to cast highlights on the panels, which are ivory colored and in high relief.

Beyond the lobby is a small foyer which originally featured a ceiling of stained glass and represented "A Song of Flowers." The side walls bore panels by R. Hilton Perry depicting the New Amsterdam of the 17th century and the New York of the 19th century. These have been obliterated by a refreshment stand and vending machines. Surmounting the lobby doors is an elaborate plaster relief panel by the architect, Hugh Tallant. It occupies a semicircular space above the door enframement, and has "Progress" as its theme.

This foyer adjoins the promenade foyer, which extends across the full width of the auditorium. At the rear of the auditorium, on either end of the promenade foyer, are stairways ascending to the balconies and descending to the men's and

### NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

FOR NPS USE ONLY
RECEIVED NOV 0 5 1979
DATE ENTERED JAN 1 0 1980

CONTINUATION SHEET 2

**ITEM NUMBER** 7

PAGE 3

women's lounges. The stairs are of Cremo marble from Maryland, and have thick railings of cast terracotta in a green faience glaze. These railings, designed by Bassoe, are textured with a sandblast finish. The theme of the railings is naturalistic: they are molded with masses of flowers and vines, with small animals passing through them. The newel posts were inspired by characters from Shakespearian comedies, such as As You Like It, A Midsummer Night's Dream, and The Tempest. The resurgent images of such designs enhance the whimsical and fantastic atmosphere of the interior. At the southern end of the promenade foyer, over the exit doors to 41st Street, is the "Sylvan Panel," a naturalistic relief sculpture by St. John Issing.


The general reception room and lounge is visible through a wide arch between the stairways at the rear of the promenade. This room is extensively panelled and is decorated in gold and green. At either end are lunettes with murals by George Peixotto of "Inspiration" and "Creation." In the center of the rear wall is a large fireplace of Caen stone and Irish marble, carved in realistic floral patterns. Above the fireplace, in framed niches, are the busts of Shakespeare, Virgil and Homer. The panels lining the lower walls originally contained 38 heads by Strunz representing famous "Lovers of Historical Drama." The walls have built-in seating which originally was covered with needlepoint cushions and backs. The reception room is still illuminated by soft and indirect cove lighting. Originally, each side of the entry to this room was flanked by a marble fountain, surmounted by a tablet of rich green and turquoise mosaic.

From the south end of the reception room, a stairway leads down to the ladies' retiring room. Now modernized and simplified, its original decor was derived from the rose--colors were shades of tea rose, walls had carvings in low relief of roses with intertwined stems and leaves. The all-encompassing theme was carried to the ceiling, which was treated as a single, large rose, whose petals bore painted representations of the five senses, as well as representations of Jupiter, Eros and Ganymede.

At the north end of the promenade foyer, downstairs, is the men's lounge. Placed between the men's and ladies' lounges is the New Amsterdam Room, or the Smoking Room. The room is sunken by about three feet below grade, and is reached by two separate stairs leading from each of the lounges. The New Amsterdam Room is a rectangular space, with an oval colonnade supporting a segmental dome. The columns are of Caen stone, with unornamented round shafts surmounted by an undulating, ribbon-like column capital configuration. The walls are panelled in brown Flemish oak and lined with upholstered seating. The floor is of brown Welsh quarry tile. The innermost corner of the room contains a Caen stone fireplace and gray washed bricks, with a hood decorated in sinuous Art Nouveau inscriptions by Henry Mercer. Eight allegorical panels by George Peixotto line the dome.

### NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

3



CONTINUATION SHEET

ITEM NUMBER

PAGE

7

4

Upper portions of the Flemish oak-panelled outer walls feature murals by Edward Simmons and R. W. Finn; there are 16 in all. Seven of the scenes are as follows: Eric the Icelander discovering Vineland; Henry Hudson entering the North River; Stuyvesant reaching his post; the British fleet taking New Amsterdam; the Dutch recapture of New Amsterdam; Bradford setting up his press; and the British army sailing from New York.

To the right of the Grand Promenade is the oval-shaped auditorium of the New Amsterdam, framed by seven wood-panelled arches. The auditorium is 86 feet wide by 90 feet long, measured from stage apron to the wall of the General Reception Room. The distance between its arched dome and the orchestra floor below measures 80 feet. The effect of the height of the dome is accentuated by the proscenium arch, which is 40 feet wide and 36 feet high. An elliptical arch rises from the stage and extends to the ring of the dome, thereby framing the upper part of a 45 foot by 18 foot mural, located over the proscenium. Two smaller arches rise inside this arch to form the frame of the proscenium and the lower part of the frame of the mural. The mural was designed by Robert Blum, and executed by A. B. Wenzel following Mr. Blum's death. Its theme is the Drama, and it bears personifications of Poetry, Truth, Love, Melancholy, Death and Chivalry. Two additional murals depicting Virtue and Courage flank the central mural. The proscenium is also embellished by sixteen figures of peacocks and vines in a dark green tint, all modelled by St. John Issing.

The delicate color scheme of the New Amsterdam Theater's interior, included in a critical commentary in The New York Times, 1903, is still applicable today:

It is a silvery green ground with tender pinks, mauves, lilacs, red and gold produced by flowers either woven into the green stuffs of carpets, fauteuils, and curtains,...or molded on the walls. The result is a subdued yet gay effect like a meadow in Springtime sowed with daisies, violets, and flowers of slightly stronger hues. There is a sense of fragility, a Botticelli feeling of flowers, and something delicate one may call virginal, as if it were an assembly place for children and maidens.<sup>3</sup>

The color scheme is further enhanced by the lighting, which highlights the ornamented surfaces. Only reflected light is used in the lobby, the light source positioned behind coves and cornices. Dispersed throughout the auditorium promenade and stairways were bronze heads (since removed) bearing small electrical lights in their crowns, thus providing gentle illumination.

## NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

OR NPS USE ONLY				
RECEIVED NOV	5 1979		ALCON.	
GECEIAED MAA				
		10		

CONTINUATION SHEET

ITEM NUMBER 7

PAGE

The stage, which measures 100 feet by 60 feet, is equipped with a remarkable range of technical facilities. The area below it was excavated to a depth of two stories, to accommodate a series of bridges which are raised and lowered by means of twelve electric motors. The entire stage can be lowered to a total depth of 33 feet. A large capacity elevator, used for raising and lowering sets to below-stage storage rooms, in addition to two elevators leading to dressing rooms and a large carpentry shop, are located at stage level. The dressing rooms for both the New Amsterdam auditorium and the Rooftop Theater are on the 41st Street side of the building, and have a combined capacity of 500 persons. 4


In addition to the stage's superb technical facilities, the auditorium features an early use of cantilevered balcony construction. The proscenium opening is clearly visible from the rear seats, without columns to obstruct the view to the stage. The second balcony is set back from the line of the first. In front of it, an additional pair of boxes was cantilevered from the auditorium wall (These have been removed) The upper balcony is suspended from the ceiling with tension rods. The theater also features double-wall construction, with fifteen-foot wide interior fire galleries between the auditorium walls and the outer walls of the building to facilitate exit in case of fire. The auditorium originally featured twelve oval-shaped boxes which were projected in two staggered pairs from the arches in the side walls immediately flanking the stage. The upper area of each arch was filled with a grille of polychromed floral tracery. The furnishings and ornamentation of each box represented a different flower. As such, these were referred to by name, such as the buttercup box, the violet box, etc., instead of by number. Each of the boxes was additionally ornamented on the front with a decorative motif corresponding to the box's individual floral theme. The removal of these boxes represents one of the few major alterations to this theater since its opening.

Above the auditorium is the Rooftop Theater, reached by the two elevators in the lobby, which, like the others which service the office tower, are of cast metal, with a floral and vine motif in the Art Nouveau style. Unlike the rooftop theaters of previously constructed urban theaters, the New Amsterdam's was permanently roofed and had a fully equipped stage and outdoor "Aerial Gardens." The Rooftop Theater was designed as a supper club, and opened on June 6, 1904 with a musical vaudeville production entitled A Little of Everything, starring Fay Templeton. It was furnished with tables and serviced by a large kitchen in the building.

The Rooftop Theater was positioned above the auditorium of the New Amsterdam. To comply with building codes forbidding construction above a theater stage, the roof theater's length was curtailed--its rear stage wall is an upward extension from the proscenium wall below. The proscenium is framed to bear the tremendous weight with a 10-ton plate girder, which was the largest built to

## NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

5



CONTINUATION SHEET

**ITEM NUMBER** 

PAGE

7

6

date in New York. It measures 90 feet in length and 14 feet in depth. The Rooftop Theater originally had no balcony, but was encircled by a ring of boxes with a promenade behind.<sup>6</sup>

Florenz Ziegfeld was a part owner of the New Amsterdam, with Klaw and Erlanger. From 1913 until 1927, when he constructed his own theater, Ziegfeld produced the Ziegfeld Follies at the New Amsterdam. The atmosphere was elegant and the technical facilities afforded by the New Amsterdam stage allowed the creative genius of stage designer Joseph Urban to flourish.

In 1915, Ziegfeld commissioned Urban to convert the Rooftop Theater into a nightclub to house the Midnight Frolic. It thus acquired a moveable stage, glass balconies and cross lighting to create rainbow effects. In 1922, the Rooftop Theater's supper tables were replaced by seats and it became a broadcasting studio for the Columbia Broadcasting System. The following year, the Rooftop Theater was converted to the 700-seat Dresden. It has since been used for radio, most recently for television productions, and as a studio rehearsal hall for Broadway shows, among them: Death of a Salesman, A View from the Bridge, and My Fair Lady. The theater, nonetheless, has retained its proscenium arch, whose motif matches that of the main auditorium. The theater acquired a central balcony at some point coincident with its conversion to use as a movie theater. The ornamentation of the theater's side boxes provides important stylistic links to the auditorium below, as their panels bear polychromed Art Nouveau motifs.

By the time the economic depression of the 1930's occurred, Ziegfeld had built his own theater, and Klaw had relinquished ties with Erlanger to become a partner with Dillingham in the management of other theaters in New York. In 1936, the New Amsterdam was acquired by the Dry Dock Savings Bank at a foreclosure auction. The New Amsterdam main theater was in legitimate use until 1937, when Alfin Enterprises converted it to use as a motion picture theater. Such economic consequences have affected the lobby areas and lower exterior facade in the conversion of the theaters to other uses. However, with the exception of the removal of the balconies and the repeated remodelling of the Rooftop Theater seating, the design of the interior and the upper facade have remained intact. The integrity of the architectural program—the massing and interrelation of forms and passages—together with the artistic works which enliven every aspect of the New Amsterdam and the exceptional technical features of the theaters, attest to the genius of the architects Henry B. Herts and Hugh Tallant.

## NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

RECEIVED NOV 0 5 1979 AN 1 0 1980

CONTINUATION SHEET

ITEM NUMBER 7

PAGE 7

#### NOTES TO ITEM 7

- 1. William Bates, The New Amsterdam, November 1, 1903.
- 2. Andrew Craig Morrison, "Theaters of 42nd Street," (graduate research paper), 1968.
- 3. Charles DeKay, New York Times, November 1, 1903, p. 21.
- 4. William Bates, The New Amsterdam, November 1, 1903.
- 5. Iron and bronze ornament by the Winslow Bros. Co.
- 6. New York Commercial Advertiser, July 11, 1903, reported that:

  more than 2,000 tons of steel have been utilized in the building.

  The unusually elaborate system of construction employed in this building is well exemplified by one fact--that the main girder supporting the roof theater is the largest single piece of ironwork ever put into any building in the world.

PERIOD

#### AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW

PREHISTORIC	_ARCHEOLOGY-PREHISTORIC	COMMUNITY PLANNING	_LANDSCAPE ARCHITECTURE	RELIGION
1400-1499	_ARCHEOLOGY-HISTORIC	CONSERVATION	_LAW	SCIENCE
1500-1599	AGRICULTURE	ECONOMICS	LITERATURE	XSCULPTURE
1600-1699	X_ARCHITECTURE	_EDUCATION	MILITARY	_SOCIAL/HUMANITARIAN
1700-1799	XART	X_ENGINEERING	X_music	XTHEATER
1800-1899	COMMERCE	EXPLORATION/SETTLEMENT	PHILOSOPHY	TRANSPORTATION
-X1900-	X_COMMUNICATIONS	INDUSTRY	POLITICS/GOVERNMENT	OTHER (SPECIFY)
		INVENTION	almos Lamber	

SPECIFIC DATES

1903

BUILDER/ARCHITECT

Henry B. Herts Hugh Tallant

MACHEST BEING THE

#### STATEMENT OF SIGNIFICANCE

The New Amsterdam Building, constructed in 1903 by Henry B. Herts and Hugh Tallant, consists of an eleven-story office tower and main auditorium behind it, surmounted by a smaller but equally complete theater on its roof. It is of major significance to the history of architecture and the fine arts, as it is a superb example of the rare use of the Art Nouveau style as applied to architecture in New York. The building is also architecturally noteworthy for its skeleton steel construction and the architects' use of cantilevers for balconies in the theaters. As a theater complex encompassing a main auditorium and the smaller Rooftop Theater, the New Amsterdam is widely considered integral to Broadway entertainment history. It has played host to many important New York State productions, and has launched the careers of many figures who went on to attain national fame. Furthermore, the idea of clustering together a ground floor auditorium, an office tower, and a roof theater in one complex is unique from a planning point of view, considering its year of construction. As such, the New Amsterdam represents an early example of mixed use concept as applied to theater construction.

The New Amsterdam represented a departure for the architects, and was described by one reviewer as an "experiment...a break from historic styles..." The architects, then both in their 30's, had already established a reputation through the design of the Lyceum and the Liberty Theaters, and went on to design the Brooklyn Academy of Music in 1908. In contrast to their other works, the New Amsterdam was designed for multiple-use with its eleven-story office tower and two theaters. Another striking feature is the use of the then-emerging Art Nouveau style throughout the interior of the building. Derived from forms in nature, Art Nouveau treatment is characterized by the use of flowing lines and sensitive color treatment through the use of secondary tones. This style was to have considerable impact on the history of 20th-century architecture and decorative arts. The interior displays the work of muralists, ceramicists, and sculptors whose creations are rich in allegorical meaning. The art follows the contours of the interior's construction lines. A sense of discovery was created by offsetting the architectural mass with an elaborate treatment of surfaces. A contemporary reviewer observed that Herts and Tallant insisted upon:

The truthful expression in design of structural requirement, the conformity of the raiment to the skeleton, the demands that all ornament shall form an integral and even necessary part of the design adopted...new constructural methods and new practical requirements cry out for a new artistic expression.

9 MAJOR BIBLIOGRAI	PHICAL REFERENCES	SIGNIFICANOS
"Individualism in Archi	itecture." Architectural Ro	ecord, June-January, 1904.
"The New Theaters of Ne	ew York." Architectural Rec	cord, June-January, 1904.
Bates, William. The New	Amsterdam, November 1, 190	03. (see continuation sheet)
10 GEOGRAPHICAL DA	<b>NTA</b>	UTM NOT VERIFIED
ACREAGE OF NOMINATED PROPERTY	less than 1 acre	
QUADRANGLE NAME Centra	al Park	QUADRANGLE SCALE 1:24,000
A 1 18 5 8 5 4 100	45 1 1 93 0 B ZONE	E EASTING NORTHING
ELI LILI	LILII FL	لسليليا لسليلا
G	LILLI HLL	
VERBAL BOUNDARY DESCRIPT	TION	
		on the south side of West 42nd Street (see continuation sheet) PPING STATE OR COUNTY BOUNDARIES
STATE None	CODE COUNTY	CODE
STATE	CODE COUNTY	CODE
	Contact: Elizabe Divisionio, Research Associate	eth Spencer-Ralph, 518-474-0479 on for Historic Preservation
organization New York Lai	ndmarks Conservancy	March 1979
STREET & NUMBER		TELEPHONE
17 Battery l	Place	212-425-4085
CITY OR TOWN New York		STATE New York 10004
12 STATE HISTORIC P	RESERVATION OFFIC	ER CERTIFICATION
	ATED SIGNIFICANCE OF THIS PROPER	
NATIONAL X	STATE	LOCAL
hereby nominate this property for in criteria and procedures set forth by the STATE HISTORIC PRESERVATION OFFICE	nclusion in the National Register and control of the National Park Service.	ric Preservation Act of 1966 (Public Law 89-665), I sertify that it has been evaluated according to the
	3110 11ebel vacion 1 <b>4</b> e1	d ServicesDATE 10/29/79
fairl &	ROPERTY IS IN FLUDED IN THE NATH	ONAL REGISTER  DATE 140-80
ATTEST: LUA J. Debt	REGISTER	DATE JOH IN 1950
CHIEF OF REGISTRATION		

## NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

	Superior St		
ov 05	1979		
	JAN	101	agn
		nv 0 5 1979	

CONTINUATION SHEET 1

ITEM NUMBER 8

PAGE 2

The effect is both lush and playful, and, most importantly, each vista looking toward the stage is framed by an ornamental form in the Art Nouveau style. In this way, the separate elements of the interior interact to produce a cohesiveness that transcends the individuality of the separate works. One such area, exemplary of the collaboration of many artisans, is the Smoking Room, or the Amsterdam Room, with its murals by George Peixotto, Henry Mercer, Edward Simmons, and R. W. Finn. A polychromed smoke grille believed to be the work of Hugh Tallant is in the central dome area. A reviewer, writing in the Architectural Record in 1904, noted the attention to detail evident in the New Amsterdam:

The architects have made a careful, laborious and intelligent attempt to design a building that is finished in every detail, and its excellence of much of this detail, particularly in the Smoking Room, and other subordinate rooms of the theater...(is) the best achievement of the architects. These gentlemen stand for a very high standard, and their work is never merely bizarre and crude.

In addition to its artistic features, the New Amsterdam's technical aspects won it high regard as the "best constructed and most handsomely decorated theater in the world," and as "the brightest among all of 42nd Street's treasures."

Both theaters and the office structure are of skeleton steel construction throughout. The use of such a method of construction, whereby the building is supported by steel instead of masonry supports, had previously been confined to applications in office buildings. It has the distinct advantage of providing a maximum amount of usable interior space and it permits a clear and unobstructed view from each seat and box in the house. Both the main auditorium and the Rooftop Theater have balconies on the suspension and cantilever principle, which eliminates all support posts in the line of sight. A contemporary journal noted that:

This is the first instance that this has been accomplished without the use of girders crossing from one side of the theater to the other.

The New Amsterdam was included in the 1926 edition of  $\underline{\text{The American Spirit in}}$  Architecture for this noteworthy feature.

The abandonment of the horseshoe gallery in favor of the gallery stretching from side to side has made necessary the development of the proscenium boxes. These are often combined with the proscenium arch into one composition. In the New Amsterdam Theater, New York, the curving forms necessary in a large theater are treated

## NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

OR NPS USE					
RECEIVED	NOV	05	1979		
DATE ENTERS				1980	

CONTINUATION SHEET 2

ITEM NUMBER 8

PAGE 3

in a manner delightfully playful, free and original.8

The positioning of the Rooftop Theater directly above the main auditorium was another technical achievement of the New Amsterdam. The Rooftop Theater, which has an orchestra, originally had only its two balconies and twelve boxes, a large rear promenade, and an open air garden situated directly over the stage house of the main theater. Herts and Tallant named the upper roof area the "Aerial Gardens" for the fine view of New York afforded when the New Amsterdam was among the taller buildings on 42nd Street. This was the first time that a theater complete in every detail had ever been superimposed upon a similar structure. A 1903 source reported that:

Employed in the main theater and in the stage house, there are approximately 270,000 separate pieces of steel which occupy about one-fifth the space ordinarily allotted to masonry and wood. There are approximately 2,000 tons of wrought steel in the buildings, 57 cantilevers, and 38 counterweighted electric elevator machines back of the curtain line. The magnitude of this undertaking can be appreciated, perhaps, from the statement that 7,500 architects and engineers' plans were required for the guidance of the artisans in building.

The fact that both theaters are surrounded by exterior fire escapes, in addition to twelve-foot wide galleries and staircases, completely isolated by fire walls, gave the patron an added sense of security. In addition, the office and theater structures were treated with a patented process to make them totally fireproof.

The original heating and ventilation system devised by Herts and Tallant for the New Amsterdam (although replaced by modern air conditioning system with aluminum ducts) is of as much interest today as it was at the time of its completion. The theater, whose cubic volume measures approximately 400,000 cubic feet, excluding the space represented by the Smoking Room, the separate retiring rooms, general waiting room, grand foyer, vestibule and lobby, was heated by indirect radiation distributed by four-foot and ten-foot blower fans located in the sub-basement. Air for ventilation of the theater was brought in through louvers in the porte cochere on 41st Street, then drawn by a 10-foot blower fan through silk filters in the main air chamber, and finally, was forced over a heater which contained 4,300 square feet of radiating surface. The air was then moistened to natural humidity and forced into the main plenum chamber under the main auditorium. It was admitted to the auditorium through special openings in the floor beneath the seats. The 10-foot fan was designed to completely change the air of the auditorium in approximately 10 minutes. All dirt and dust was expelled by

## NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

OR NPS USE	DNLY			
RECEIVED				
DATE ENTEREL	NOA O	5 1979 <sub>N</sub>	10	Joon

CONTINUATION SHEET 3

ITEM NUMBER 8

PAGE 4

72 degree exhaust disc fans installed in the exhaust chamber over the theater. Uniform temperature was maintained by automatically-controlled temperature regulators.

At the time of its construction, the stage of the New Amsterdam Theater auditorium represented the most complete assemblage of stage mechanisms of any theater in the world. A multitude of mechanical devices was provided in such a manner as to avoid any interference with the performers. This innovation is best exemplified by the two-story stage elevator mechanism which, although not currently in use, is still preserved intact. It raised and lowered the sets, and was equipped with an efficient trap door which instantly closed when scenery was lowered onto the stage. These facilities allowed Klaw and Erlanger to mount beautiful scenic productions in what one reviewer claimed was "by all odds the handsomest theater in this country to-day." 10

For 30 years subsequent to its 1903 opening, the New Amsterdam Theater was regarded as the premier musical-comedy theater in New York. Prior to the arrival of Florenz Ziegfeld at the New Amsterdam in 1913, the theater's productions included: George M. Cohan's Forty-five Minutes from Broadway, with Fay Templeton and Victor Moore; Richard III, starring Richard Mansfield; the 1907 premier of Lehar's The Merry Widow; the 1911 production of The Pink Lady, with Hope Dawn. In 1914, Irving Berlin's first musical, entitled Watch Your Step, starring Vernon and Irene Castle, was staged at the New Amsterdam. Ziegfeld came to the New Amsterdam in 1913, and presented the Ziegfeld Follies revues from that year until 1920, from 1922 to 1925, and, lastly, in 1927. During this period, his business offices were housed in the office tower of the New Amsterdam. Ziegfeld's productions were famous for the array of beautiful and original scenery, costumes and stage effects, as well as for the combined talents of leading composers, writers, performers and glamorous "Ziegfeld Girls."

In 1913, the dancer Ann Pennington first appeared in the Follies, where she gained fame as the originator of the Black Bottom Dance. The famous comedienne Fanny Brice, who was discovered by Ziegfeld in 1909, starred in the New Amsterdam Follies of 1916, 1917, 1920, and 1923. In 1914, Ina Claire saluted the opening of transcontinental telephone service in the United States with the song "Hello, Frisco, Hello," and soon rose to fame as a comedienne. Another star to make his debut in the Follies was Ed Wynn, in 1914. In the following year, W. C. Fields made his debut in the Follies. 1915 marked the year when Ziegfeld staged a show in the New Amsterdam Rooftop Theater. The show was originally called Danse de Follies, and was later renamed the Midnight Frolic. Working within the existing sumptuous setting provided by the Rooftop Theater and its Aerial Gardens, Ziegfeld created a legendary and exotic nightclub. Many performers featured in the Follies appeared in Midnight Frolic performances the same evening. Ziegfeld used the Rooftop Theater as a testing ground for new talent;

## NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

FOR NPS USE ON					
RECEIVED		5 1070			
	OA A	5 1979			
DATE ENTERED		JAI	VIL	) 1980	

CONTINUATION SHEET

ITEM NUMBER 8

PAGE 5

it was there that Eddie Cantor, Norma Jeires and Will Rogers began their entertainment careers. Some highlights of the Rooftop Theater entertainments were Fanny Brice's first presentations of the "Rose of Washington Square" and "Secondhand Rose." Eddie Cantor and Will Rogers also attained prominence there.

Ziegfeld introduced Marilyn Miller, who became famous as a dancer and actress, in P. G. Wodehouse's 1920 production of Sally. In 1921, Ed Wynn starred in the revue Ed Wynn's Carnival. Marilyn Miller went on to star in Sunny in 1925 and Rosalie in 1928, playing opposite Jack Donahue, the comedian and actor in both productions. Among other landmark productions which increased the New Amsterdam Theater's fame were: Whoopee, starring Eddie Cantor and Ruth Etting, and George Tyler's 1927 revival of Trelawney of the Wells, with John Drew, Pauline Lord, Helen Gahagan, Estelle Winwood, and Peggy Wood.

The year 1931 saw the revue entitled The Band Wagon, with Fred and Adele Astaire inthei last appearance together, and Frank Morgan, Helen Broderick and Tilly Losch. Also in 1931, the Players Club revival of J. M. Barrie's The Admirable Crichton featured Walter Hampden, Fay Bainter and Estelle Winwood. The following year, Mary Boland starred in Irving Berlin's Face the Music. In the same year, Eva Le Gallienne's Civic Repertory staged productions of The Cherry Orchard with Nazimova, and Alice in Wonderland.

Fay Templeton starred in the 1933 production of Jerome Kern's Roberta, which also starred Bob Hope. The following year Revenge with Music was featured, with Libby Holmen. Bert Lahr, Eugene and Willie Howard, and Rudy Vallee starred in George Waite's Scandals of 1936. Walter Huston portrayed Othello in 1937. This marked the last legitimate theater production of the New Amsterdam.

In the summer of 1937, the New Amsterdam's auditorium was used for the showing of movies. Ironically, the first movie offering was a version of A Midsummer Night's Dream, the very play the theater featured at its 1903 opening.

The New Amsterdam Building is well represented in published sources. In 1908, five years after its opening, New York Plaisancz, a journal devoted to reviewing entertainment sites in New York City, featured the New Amsterdam in its first issue, noting its excellent decor and exceptional atmosphere. A model of the facade of the theater/office complex is said to have been featured in the St. Louis Exposition of 1904. As previously noted, the use of cantilevers and the effect of their usage on the morphology of theaters, earned the New Amsterdam mention in the 1926 edition of The American Spirit in Architecture, published by the Yale University Press as a photographic survey and series of essays on architecture. More recently, the New Amsterdam Building was included in the 1978 exhibition entitled "Inside 42nd Street," held by the Cultural Council Foundation at the

Form No. 10-300a (Hev. 10-74)

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

#### NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

RECEIVED NOV 0 5 1979

DATE ENTERED

JAN 1 0 1980

CONTINUATION SHEET 5

ITEM NUMBER

8

PAGE 6

G. W. Grace Building. At this writing, the Theater Historical Society is honoring the New Amsterdam by devoting its special Annual edition to the historical significance of the New Amsterdam Theater and its Rooftop Theater.

## NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

6

RECEIVED NOV 0 5 1979
DATE ENTERED JAN 1 0 1980

CONTINUATION SHEET

ITEM NUMBER

PAGE

8

7

#### NOTES TO ITEM 8

- 1. "The New Theaters of New York," Architectural Record, June-January, 1904, p. 56.
- 2. Maurice Rheims, author of The Flowering of Art Nouveau, (Harry N. Abrams, Inc., New York) states that:
  Art Nouveau...sought unusual, original effects, and was colorful, consistent, harmonious, and functional, prefiguring the shape of things to come--the Bauhaus, Surrealism, and abstract art.
- 3. "Individualism in Architecture," Architectural Record, June-January, 1904, p. 68.
- 4. "The New Theaters of New York," Architectural Record, June-January, 1904, p. 57.
- 5. William Bates, The New Amsterdam, November 1, 1903.
- 6. J. Dakin, M. Lawrence, R. Ring, 42nd Street Theatre and the City, The Graduate Center, City University of New York, 1977, p. 8.
- 7. William Bates, The New Amsterdam, November 1, 1903.
- 8. Talbot Faulkner Hamlin, The American Spirit in Architecture, (Yale University Press, New Haven), 1926, p. 301.
- 9. November 8, 1908 review from the Erlanger Collection Scrapbooks, Lincoln Center for the Performing Arts Theater Collection Library.
- 10. Ibid.
- 11. Joel Lobenthal, 'Miracle on 42nd St.: The New Amsterdam Theater," 1976, pp. 20-36.
- 12. April 26, 1939 entry in WPA Files, collection of the Department of Records and Information Services, Municipal Archives of the City of New York.

FHR-8-300A (11/78)

UNITED STATES DEPARTMENT OF THE INTERIOR HERITAGE CONSERVATION AND RECREATION SERVICE

# FOR HCRS USE ONLY RECEIVED NOV 0 5 1979 DATE ENTERED. JAN | 0 1980

2

## NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

The New Amsterdam Theater, Rooftop Theater and Aerial Gardens New York County

**CONTINUATION SHEET** 

ITEM NUMBER 9 PAGE

Dakin, J.; Lawrence, M.; and Ring, R. 42nd Street Theatre and the City. New York: City University of New York, 1977.

Hamlin, Talbot Faulkner. The American Spirit in Architecture.

New Haven: Yale University Press, 1926.

Form No. 10-300a (Hev. 10-74)

UNITED STATES DEPARTMENT OF THE INTERIOR
NATIONAL PARK SERVICE

## NATIONAL REGISTER OF HISTORIC PLACES INVENTORY -- NOMINATION FORM

1

RECEIVED NOV 0 5 1979
DATE ENTERED JAN 1 0 1980

CONTINUATION SHEET

ITEM NUMBER

10 PAGE

2

on the block bounded by Seventh Avenue to the east and Eighth Avenue to the west. Access to the building is gained through a rectangular lobby with elevators that run to the offices and Rooftop Theater above. The New Amsterdam Theater is on the ground floor, beyond this lobby. It occupies a rectangular space almost one half a block in width reaching to 41st Street. The Rooftop Theater, located on the seventh floor, was built on top of the New Amsterdam Theater's roof.





Property New ansterdan Theater	20maccu
State 74 Month Working Number 1-5-79 2665	80002664
TECHNICAL  Photos Maps	CONTROL
itt in 1903, this is one of the most famous of N. y:s theaters. the building is ing turally for its lavish beauxants interior, and for its innovative design (a la h seven stories of office space, and crowned with a smaller theater & roof garden its engineering design (sheleton steel construction, cantilevered balconies, fire h whicate stage machinery). The theater was also used for performances by many	at the top for level) accept all , and its wealth Patrick Ar of the leading 1/2/80
ues in american entertaument - Horenz Ziegfield, dring Berlin ARCHITE age M. Cohan, Fanny Bince, Ed Wynn, W.C. Fields, Will Rogers, Eddie cantor, etc. the the interior.	CTURAL HISTORIAN ere have been only minor changes
	ARCHEOLOGIST
	OTHER
	HAER
	Inventory Review
Interiors are entable for Art Nouveau I Polyle decoration— an unusual use of that style for an architectural purpose—	REVIEW UNIT CHIEF  Accept  L. Boeke  1/10/80
	BRANCH CHIEF
	KEEPER
National Register Write-up Send-back	Entered <u>JAN 1 0 19</u> 8



The New Amsterdam Building Nov 05 1979 New York, New York Co. Mark Sick, 1976

New Mark 6, 7 Mercer St., N.Y., N.Y. 10013
View of 42nd St. facade. Note 7th floor
windows, with tympana decorated with
terracotta panels designed by Grendellis
and Ricci.
Photograph # 1

JAN 1 0 1980



The New Amsterdam Building New York, New York County cholo: Armen Kachaturian, 1977 10 East 23rd St., N.Y., N.Y. 10010 View facing towards the 42nd St. entry of the main lobby. Note art nouveau elevator doors and modeled terracotta panels by Grendellis and Ricci. The east wall friezes depict five scenes from Shakespeare by R. Hilton Perry.

neg:

Photograph # 2




The New Amsterdam Buildi New York, New York County

Armen Kachaturian, 1977

10 East 23rd St., N.Y., N.Y. 10010

Detail of lobby scene by R. Hilton Perry of Titania and Bottom from A Midsummer Night's Dream, the first production of the New Amsterdam Theater.

Photograph # 3



JAN 1 0 1980

The New Amsterdam Theater
New York, New York County

Armen Kachaturian, 1977

10 East 23rd St., N.Y., N.Y. 10010 Detail view of one of ground floor lobby elevator doors. Photograph # 4

NOV 0 5 1979



The New Amsterdam Theater
New York, New York Conty

Armen Kachaturian, 1977

10 East 23rd St., N.Y., N.Y. 10010

"Progress" plaster relief panel by
architect Hugh Tallant above doors
between lobby and foyer.

Photograph # 5

JAN 1 0 1980



NAT'LREG

The New Amsterdam Building Nov 0 5 1979

New York, New York County Nov 0 5 1979

photo: Armen Kachaturian. 1977

Lunette mural of "Creation" in the general reception room, by George Peixotto.

Photograph # 6

JAN 1 0 1980



JAN 1 0 1980

The New Amsterdam Building Nov 0 5 1979
New York, New York County

Photo: Armen Kachaturian, 1977

Newel post and naturalistic stair railing, designed by Bassoe, are of cast terracotta in a green faience glaze and sandblast finish.

Photograph # 7



The New Amsterdam Building New York, New York Court New 05 1979.

New York, New York Court New 05 1979.

Armen Kachaturian, 1977

10 East 23rd St., N.Y., N.Y. 10010

Detail of naturalistic stair railing, designed by Bassoe, is of cast terracotta in a green faience glaze and sandblast finish.

Photograph # 8



NAT'LREG

The New Amsterdam Building Nov 05 1979
New York, New York


Armen Kachaturian, 1977
10 East 23rd St., N.Y., N.Y. 10010
The Smoking Room: Caen stone columns form an oval colonnade, supporting a segmental dome.

Photogragh # 9



The New Amsterdam Bulldin New York, New York County Armen Kachaturian, 1977

Nec. 10 East 23rd St., N.Y., N.Y. 10010 The Smoking Room: Eight allegorical panels by George Peixotto line the oval dome. Photograph # 10



The New Amsterdam Building HEATER
New York, New York

1190

The Smoking Room: detail, smoke grille.

Photograph # 11



9

The New Amsterdam Building THE ALER New York, New York Os 1979 New York, New York Os 1979 10 East 23rd St., N.Y., N.Y. 10010 Promenade foyer, south end: above the exit doors to 41st St., the "Sylvan Panel" by St. John Issing. Photograph # 12



JAN 1 0 1980

The New Amsterdam Building
New York, New York
Armen Kachaturian, 1977

10 East 23rd St., N.Y., N.Y. 10010 Interior of the New Amsterdam Theater: view looking into dome and back to balconies. Photograph # 13



JAN 1 0 1980

The New Amsterdam Building New York, New York County
Mark Sick 1076

photo: Mark Sick, 1976

10013 Mark 6, 7 Mercer St., N.Y., N.Y. Proscenium and stage of the Rooftop Theater. NOV 0.5 1979 Photograph # 14




6

The New Amsterdam Theater
New York, New York

Photo: Armen Kachaturian, 1977

10 East 23rd St., N.Y., N.Y. 10010
Rooftop Theater: ornament framing
the proscenium.
Photograph # 15

NOV 0.5 1979



MAT'L RES

IAN 1 0 1980

The New Amsterdam Building 1979

New York, New York County

photo: Armen Kachaturian, 1977

10 East 23rd St., N.Y., N.Y. 10010 Rooftop Theater: proscenium detail

Photograph # 16



The New Amsterdam Building
New York, New York Country 00 0 5 1979
Mark Sick, 1976
Mark 6 7 Mary

Mark 6, 7 Mercer St., N.Y., N.Y. 10013 Rooftop Theater, view from stage toward entry; note original boxes to the left, above entry, with art nouveau panels.

Photograph # 17





# JAN 1 0 1980

The New Amsterdam Building
New York, New York

New York, New York

CENTRAL PARK QUADRANGLE UNITED STATES NEW YORK-NEW JERSEY DEPARTMENT OF THE INTERIOR 7.5 MINUTE SERIES (TOPOGRAPHIC)
SW/4 HARLEM 15' QUADRANGLE GEOLOGICAL SURVEY 74°00′ 40°52′30″ YONKERS (CITY HALL) 4.7 MI.

1 591 55' 14 MI. TO INTERSTATE 287 PALISADES, N.Y. 11 MI. 17 MI. TO INTERSTATE 287 6265 IV NW 57'30" 588 0.5 MI. TO INTERCHANGE I (YONKERS) 2 190 000 FEET (N. J.) | 586 GARDEN STATE | PKWY. 7 MI. 73°52′30″ 40°52′30″ 4525000m.N. Tubby Hoo 740 000 FEET Park 230 000 FEET PALISADES PARK RIDGEFIELD CLIFFSIDE PARK Hunts Point Rikers Island RIKERS ISLAND CHANNEL Bowery) LA GUARDIA ALBPORT 200 000 FEET (N.Y.) NEW AMSTERDAM THEATER, NY County
214 West 42 Not Sheet )
EASTING Zone 18 North Beach 585 400 NORTHING 4611930 CENTRAL PARK QUAD: Jackson Heights Long Island City 700 000 FEET 57'30" 592 2 210 000 FEET (N. J.) 593 VERRAZANO-NARROWS BRIDGE 14 MI. 73°52′30″ Mapped, edited, and published by the Geological Survey SCALE 1:24 000 Revised in cooperation with New York ROAD CLASSIFICATION Department of Transportation Control by USGS, USC&GS, and New Jersey Geodetic Survey 1 .5 0 CONTOUR INTERVAL 10 FEET Interstate Route U.S. Route State Route T-5089, T-5264, †-5278, T-5448, T-5449, T-5451, T-5452, T-5453, T-5458, DATUM IS MEAN SEA LEVEL RECEIVED and T-5778. Topography by photogrammetric methods from aerial photographs DEPTH CURVES AND SOUNDINGS IN FEET—DATUM IS MEAN LOW WATER SHORELINE SHOWN REPRESENTS THE APPROXIMATE LINE OF MEAN HIGH WATER THE MEAN RANGE OF TIDE IS APPROXIMATELY

4 FEET IN THE HUDSON RIVER AND 5.7 FEET IN THE EAST RIVER NEW YORK taken 1954 and planetable surveys 1956 Revised from aerial photographs taken 1966. Field checked 1966 CENTRAL PARK, N. Y. - N. J. UITM GRID AND 1966 MAGNETIC NORTH DECLINATION AT CENTER OF SHEET Selected hydrographic data compiled from USC&GS Charts 226, 274, 745, SW/4 HARLEM 15' QUADRANGLE QUADRANGLE LOCATION ~746, and 747 (1966). This information is not intended for navigational purposes THIS MAP COMPLIES WITH NATIONAL MAP ACCURACY STANDARDS N4045-W7352.5/7.5 REGISTER FOR SALE BY U.S. GEOLOGICAL SURVEY, WASHINGTON, D. C. 20242 Polyconic projection. 1927 North American datum 1966 10,000-foot grids based on New York coordinate system, Long Island zone, A FOLDER DESCRIBING TOPOGRAPHIC MAPS AND SYMBOLS IS AVAILABLE ON REQUEST and New Jersey coordinate system AMS 6265 IV SW-SERIES V821 1000-meter Universal Transverse Mercator grid ticks, zone 18, shown in blue Red tint indicates areas in which only landmark buildings are shown

#### ENTRIES IN THE NATIONAL REGISTER

### STATE NEW YORK

## Date Entered JAN 10 1980

Flower, Roswell P., Memorial Library

Bloomingburgh Reformed Protestant Dutch Church

Williams, Johann, Farm

Ansonia Hotel

New Amsterdam Theater

Gifford-Walker Farm

Brooklyn Borough Hall

Mann, Andrew, Inn

Brandreth Pill Factory

## Location

Watertown Jefferson County

Bloomingburgh Sullivan County

Niagara Falls Niagara County

New York New York County

New York New York County

North Bergen Genesee County

Brooklyn Kings County

Unadilla Otsego County

Ossining Westchester County

### Also Notified

Honorable Daniel P. Moynihan

Honorable Jacob, K. Javits
Honorable Robert C. McEwen
Honorable Matthew F. McHugh
Honorable John J. La Falce
Honorable Ted Weiss

Honorable Barber B. Conable, Jr.

Honorable Frederick W. Richmond

Monorable James M. Hanley Honorable Richard L. Ottinger

State Historic Preservation Officer Mr. Orin Lehman Commissioner Parks and Recreation Agency Building #1. Empire State Plaza Albany, New York 12238

/ers/bjr

IR