city, town

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

For NPS use only

received date entered

9 1984 7 1984

Type all entries—complete	이 강하는 (이 15.0 개기에 전 목) 보고 있는 경기를 받는다고 있는데 되었다. 그 그리고 있는데 그리고 있다면 되었다.	gister Forms		
1. Name				
historic Mecca Templ	e (City Center of	Music & Dra	ma)	
and or common City Ce	enter 55th Street D	ance Theate	r	
2. Location				
street & number 131 Wes	± 55th Street			not for publication
city, town New Yor	·k	vicinity of		
state New Yor		county	New York	code 061
3. Classifica	tion			
Category district building(s) structure site object being NA	work quisition	ccupied k in progress	Present Use agriculture commercial educationalX entertainment government industrial military	museum park private residence religious scientific transportation other:
4. Owner of	Property			
	ice Theater Foundat	ion	N.Y.C. Department Bess Meyerson, Co	of Cultural Affairs mmissioner
street & number 130 West	56th Street		830 Fifth Avenue New York, N.Y. 10	021
city, town New York		vicinity of	state	N.Y. 10019
5. Location	of Legal Des	scriptio	n	
courthouse, registry of deeds	, etc. New York Co	unty Regist	er's Office	
street & number	31 Chambers	Street		
city, town	New York		state	N.Y. 10002
6. Represent	tation in Ex	isting S	Surveys	
Landmarks Preser title Commission (LP-1		has this prop	perty been determined elig	(2/24/81) lible? _X_yes no
date April 12, 1983			federal state	county X local
depository for survey records	Landmarks Preser	vation Comm	ission 20 Vesey S	treet,
city, town New York		~	state	N.Y. 10007

7. Description

Condition X excellent	deteriorated	Check one unaltered	Check one original site		
good fair	ruins unexposed	_X_ altered	moved date	N/A	
MA CONTRACTOR OF THE PARTY OF T					

Describe the present and original (if known) physical appearance

Mecca Temple (City Center of Music and Drama) occupies a mid-block site between Seventh Avenue and the Avenue of the Americas (Sixth Avenue). Filling its entire lot, the building goes through the block with its main theater entrance on West 55th Street and entrances to the stage area and upper floors on West 56th Street. As the location of its public entrance, the West 55th Street facade (photo No. 1) is faced with limestone and highlighted by ornate terra-cotta door and window enframements while the broad dome of the theater as well as the brick side walls rise slightly above its neighbors. The section of the building facing West 56th Street (photo No. 2) is comprised of a twelve-story brick tower which is also higher than neighboring buildings so that the upper portions of its side facades are also exposed.

The West 55th Street portion of the building houses the theater and consists of a massive sandstone cube crowned by a green-glazed tile dome. The top of the sandstone front facade steps up toward the center, echoing the rise of the dome behind it and is articulated by a cornice of heavy dentils suggesting crenellation. Its chamfered upper corners ease the transition between cube and dome. Most of the upper portion of this facade is plain, being sparsely pierced by slit-like lancet windows. In addition a large, shallow pointed arch is articulated across the entire front of plain stone. Within this huge arch is an "alfiz" entrance enframement of terra cotta and polychromed, glazed tile surrounding a series of doors.

An arcade of nine horseshoe arches containing doorways spans the base of the giant facade arch. These arches have voussoirs of glazed ochre tile and are supported by thin coupled and engaged columns of polished pink- and gray-veined granite. Their capitals are of polychromed, glazed terra cotta. The tympana within the arches contain polychrome tiles and some carry the motif of the scimitar and crescent, one of the "jewels" of the order. Hanging from the arches in front of each doorway is an elegant metal light fixture with horseshoe arch and star design (photo No. 4). A polychromed, glazed terra cotta frieze of abstract foliate forms in blue, green and ochre on a white ground fills the spandrels above the arches up to a molding on the mezzanine level.

The center five of these horseshoe arches are grouped with five pairs of pointed arch windows on the mezzanine level within an alfiz. This rectangular molding is composed of ochre-glazed terra cotta pilasters on a blue field and supports a muqarnas cornice, also of glazed, polychromed terra cotta (photo No. 5). Each pair of windows on the mezzanine level is joined by an engaged colonnette, clad in another design variation of the polychromed glazed terra cotta. The colorful frieze motif of the first floor is carried around these windows as well and fills the entire wall space within the alfiz.

The organization of the interior spaces is reflected in the arrangement of the openings of the first floor. The five center arches contain doorways which lead to the main floor lobby of the theater. The two horseshoe arches on each side of the alfiz open onto staircases leading to the mezzanine and first balcony levels. The two larger horseshoe-arched entrances which flank the giant facade arch have similar decorative schemes to the others but are clearly distinguished from them (photo No. 3). These doorways lead to the two stair towers which descend to the banqueting hall below the theater and rise up to the second balcony of the theater.

United States Department of the InteriorNational Park Service

National Register of Historic Places Inventory—Nomination Form

Mecca Temple (City Center of Music & Drama)

Continuation sheet New York County, N.Y. Item number 7

For NPS use only received date entered

Page 2

The West 56th Street facade is very different, reflecting the function of this part of the building. The predominant material is yellow brick rendered in a more restrained manner. The ground floor, a high basement faced with the same tawny ashlar sandstone as the West 55th Street facade, contains five arches - two pairs varying in height and width and a central arch, forming an ABCBA pattern. The extreme arches (A) are the broadest and like the central arch (C), provide access to the rear of the stage. The two narrower arches (B), each fanlit and flanked by large lanterns, serve as the building's pedestrian entrances.

Above this, an eleven-story tower was built to house offices and the Shriners' lodge rooms. These have an interior arrangement prescribed by the Shriners which renders conventional exterior fenestration unnecessary.' To deal with this problem the architect filled the space with successive layers of bricks, corresponding to the rhythm of the ground floor arches (ABCBA) to create a central, vertical element terminating in a pedimented temple front. The six piers within this central element are made of bricks angled out from the bond in the same position in every course for six stories. While the third story pediments, balconies, and moldings are sandstone, all the cartouches, capitals, and coping above are a buff-colored terra cotta. The exposed side facades of this tower are even more severe, with a few plain window openings piercing the brick walls.

The interior of the theater section includes an entrance-ticket lobby (photo No. 6) which is entered by the doors in the central five horseshoe arches on West 55th Street. Shiney, gold metallic doors enframed by colorful glazed tile in a foliate motif lead from this lobby to the foyer of the theater (photo No. 7). The theater itself seats 3,000 in an orchestra level and two balconies (photo No. 9). The interior is decorated in an elaborate scheme of Moorish-inspired designs, including lancet windows and multi-pointed stars (photo Nos. 10 & 11). Elaborate chandeliers hang from three-dimensional ceiling plasterwork and highlight the large proscenium arch (photo No. 8). The pitch of the floor for the orchestralevel seating has recently been changed to improve sight lines and the rear wall of the auditorium rebuilt at orchestra level.

8. Significance

Period prehistoric 1400–1499 1500–1599 1600–1699 1700–1799 1800–1899X 1900–	Areas of Significance—C — archeology-prehistoric — archeology-historic — agriculture — X architecture — art — commerce — communications	check and justify below community planning conservation economics education engineering exploration/settlemen industry invention	landscape architecture law literature military music t philosophy politics/government	religion science sculpture social/ humanitarian theater transportation other (specify)
Specific dates	1922-24	Builder/Architect H	arry P. Knowles	

Statement of Significance (in one paragraph)

The Mecca Temple (City Center of Music and Drama) is architecturally significant as a distinctive intact example of fraternal architecture in New York City. Designed by Harry P. Knowles in 1922 for the fraternal order the Shriners, this building was meant to express the rich heritage of the group. The building displays Moorish-inspired designs such as an elaborate alfiz filled with polychromatic glazed terra cotta, horseshoe arches, and the scimitar and crescent motif, all of which relate the structure to the group's Islamic sources. In addition, these historicizing elements are arranged on the facade in a functionally expressive manner and relate clearly to the various uses of the building. In 1943 the building became the home of the City Center of Music and Drama. Today, with its design intact, it continues to operate as a theater for dance under the auspices of the 55th Street Dance Theater Foundation.

The Ancient Order of Nobles of the Mystic Shrine (The Shriners) is a nineteenth-century offshoot of the Order of Freemasons. Present-day Masons see themselves as spiritual heirs of the craftsmen who engineered and built the major monuments of the ancient and medieval worlds, associating themselves with the philanthropic, democratic and charitable principles these early builders espoused.

The Shriners, who must also be Masons, attached themselves to a more exotic heritage, the Order of the Mystic Shrine founded at Mecca in 698 AD. By mid-nineteenth century its original purpose, to assist local governments in suppressing crime and maintaining law and order, had evolved into fraternal benevolence. In this country, the Shriners were founded in 1872 by the actor William Jermyn Florence and the surgeon Dr. Walter Millard Fleming. These men had each attained a high level within the Masons and were interested in establishing a "playground for Masons," or a place for comradery and entertainments for those who had reached an equally high stage. Florence had previously observed Shrine meetings in France, Algeria and Egypt and had attained a copy of this ritual. With Fleming, he made certain modifications of the ritual to bring it into conformity with democratic standards, while retaining certain Near Eastern emblems, such as the tassled scarlet cap and the crescent moon crossed with the scimitar. Fleming, Florence and a group of Masons held the first formal meeting of the new Mecca Temple in New York in September 1872 and groups soon formed in other U.S. cities as

Theater has always been an important part of Shriner activity, with its roots going back to one of the original goals of the founder -- entertainment for Masons. Other theatrical associations have been in the group's recruitment activities, its numerous entertainer-members and

9. Major Bibliographical References

see continuation sheet

10. Geograph	ical Data			0.1
Acreage of nominated property Quadrangle name Central UTM References	less than 1 a Park Quad	cre	Quad	drangle scale 1:24,000
	5 1 2 8 4 0 orthing	B	ne Easting	Northing
C		D F H		
Verbal boundary description The nominated prope Lot 15 as outlined	rty occupies	Borough of ed map, wi	Manhattan th a scale	, Tax Map Block 1008 of 1"=120'.
List all states and counties	for properties overl	apping state o	r county bounda	aries NA
state	code	county		code
state	code	county		code
street & number Agency B1		Ρ.	telephone	7 1983 518-474-0479
city or town Albany	orio Bros	arvatio	state NY	r Certification
The evaluated significance of thi national As the designated State Historic 665), I hereby nominate this prop	s property within the s	state is: X local or the National I	listoric Preservati	on Act of 1966 (Public Law 89–
according to the criteria and pro-	cedures set forth by th	e National Park	Service.	e in this seem evaluates
title Deputy Commission	ner for Histor	ric Preser	vation da	ate 8/2/84
For NPS use only I hereby certify that this produces the second of the s)	ne National Regi Entered in National Reg	he	ate 9-7-84
Keeper of the National Regis	0	01.30 J 00 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0		
Attest:			da	ite
Chief of Registration				

NPS Form 10-900-4 342)

United States Department of the Interior **National Park Service**

National Register of Historic Places Inventory—Nomination Form

received

Mecca Temple (City Center of Music & Drama) New York County, NY

data entered

Continuation sheet

Item number

2 Page

the general fantasy of the order's exotic trappings. Theater or theaterrelated activities have long been used by the Shriners to raise money for their philanthropic activities, from early relief for flood victims to the present Shriners' Hospitals which are located throughout the country.

In their early years in New York, Shriners held their meetings and evenings of entertainment and relaxation at Masonic Headquarters at Sixth Avenue and 23rd Street (demolished). This hall quickly proved too small for their growing numbers and they relocated, first to Carnegie Hall and then to the 71st Regiment Armory building. In 1921 the Shriners voted to build their own building, including a large hall which could be rented out for conventions, performances and films and which would thus The lots they bought on West 55th and 56th Streets be income-producing. were in an area of stables and garages with yet unimproved streets, but the Shriners hoped that their presence in the area would attract apartment houses and office buildings with a consequent increase in land value.

The architect chosen for the new buildings was Harry Percy Knowles (1871-1923), who was himself a Master Mason and a Noble of the Mystic Shrine. Except for the fact that Knowles was born in Canada, little is presently known of his education or professional background until he came to New York City in 1891. By 1899 he was head draftsman for the prestigious architectural firm of N. LeBrun & Sons. Knowles had his own firm by 1904 and his designs include the seventeen-story Masonic Building at 46 West 23rd Street in Manhattan (1909) as well as important additions to the Shriners' Hospital in Utica (1922). Mecca Temple was Knowles's last work before he died in January 1923. His design was posthumously supervised by the firm of Clinton & Russell.

At Mecca Temple Knowles was faced with a threefold challenge: an irregularly shaped site; the juxtaposition of an access to spaces vastly varying in size and function; and the expression of the Shriners' historic associations on the facade. He used the site to good advantage, placing the auditorium within the broader West 55th Street frontage and reserving the narrower 56th Street lot for the twelve-story tower (lodge and club rooms) and entrance and access to the mid-site stage area. The banquet hall, located below the auditorium, was accessible both from the auditorium lobby and the wide street entrance westernmost on 55th Street. The lodge and club rooms, identical in function, were housed in the tower, which also contained offices on its upper floors. These spaces, which were used much more frequently and at different times than the auditorium or banquet hall, shared the West 55th Street entrance. The carying functions necessitated a structural steel framing system which was notable at that time for its scope and complexity.1

1"Structural Steel Framing of Mecca Temple, N.Y." American Architect, 127 (Feb. 25, 1925), 173-180.

United States Department of the Interior National Park Service

For NPS use only

National Register of Historic Places Inventory—Nomination Form

date entered

Continuation sheet

Mecca Temple (City Center of Music & Drama)

New York County, NY Item number 8

Page 3

The West 55th Street facade serves to announce the Shriners' ancient and treasured "heritage empreinté." No specific prototype was used for this domed temple. Knowles drew upon a more general academic historicism of Islamic architectural motifs, including the Alhambra, Egyptian mosques and Templar church facades. The arcade of horseshoe arches, the schematicized naturalistic forms in the attached columns and capitals, the colorful glazed tiles (from the New York Architectural Terra Cotta Company in Long Island City), the pilasters and friezes of the "alfiz" itself, the lancet windows, and the contrast of the decoration with the tawny ashlar facing all evoke Islamic sources.

The West 55th Street facade has been called "Saracenic," "Moorish-Baroque, " and "delightfully absurd."2 The Shriners preferred "modified Arabian."3 Knowles, aware of his clients' wish to proclaim historic antecedents, created a totally appropriate design. This building is one of the best in a little documented building category: architecture of fraternal orders. Although there are other American fraternal groups such as the Odd Fellows and the Knights of Columbus with their own distinctive architecture and design motifs, the Masons and Shriners are perhaps the best known of these groups in this country. They trace their roots to the Middle East (the Masons to Egypt and Greece, the Shriners to Mecca in present-day Saudi Arabia) and have an historic affinity with the building trades. Thus their buildings are important for their associative value and great emphasis was given to specific design motifs such as the pointed-arch openings, the scimitar and crescent and the five-pointed star, as well as to the colors used (red, yellow and green being a combination considered evocative of the Middle East). While other Shrine temples employed these motifs as well, the Mecca Temple is a particularly successful example, combining historically evocative elements with modern function.

The 1930s brought financial difficulties to this large hall. The bank foreclosed on the property in 1937 and for two years an individual, Irving Verschleiser, attempted to run the building as Mecca Temple Casino, Inc. but was financially unsuccessful. In 1942 the city foreclosed for taxes and the building was put up for public auction. The City of New York bought the property and in 1943, a private, non-profit corporation, the City Center of Music and Drama, was formed under the auspices of Mayor Fiorello LaGuardia, City Council President Newbold Morris, and Morton Baum. This was the first instance in this country of local government subsidizing the arts for the purpose of making them accessible to all people. Originally, the theater was meant to provide a permanent house for a free concert series which had been started during the Depression. However,

2"Saracenic" - H. Greene, "The Planning of Fraternal Buildings,"

<u>Architectural Forum</u>, 45 (Sept. 1926) 144; "Moresco-Baroque" - J.C. Waddell,
"The Mecca Temple-Dance: 10-Looks: 3, <u>Playbill</u>, Oct. 1976; "delightfully
absurd" - Norval White and Elliot Willensky, <u>AIA Guide to NYC</u> (New York:
Macmillan Publishing Co., Inc. 1978), p. 173.

3The Meccan, (October 1923), 5.

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

For NPS use only

received

date entered

Mecca Temple (City Center of Music & Drama)
Continuation sheet New York County, NY Item number 8

Page 4


before long the center became an umbrella for various resident companies, including the newly formed New York City Opera, the New York City Symphony and the Ballet Society (which later became the New York City Ballet). City Center's first managing director, Harry Friedgut, stressed the center's role as a great municipal theater creating programs of extraordinary interest and variety, which, unlike commercial theater, would not be dependent upon the whims of public taste. He tried to provide inexpensive tickets and he worked to create interest in the theater by offering discounts to various groups. Throughout the 1940s and 1950s City Center hosted many innovative and well-received productions. By the mid-1960s, however, the New York City Ballet and the New York City Opera had moved their homes to the new Lincoln Center. Other dance and theatrical groups filled their places at the City Center both as resident and visiting companies. Finally, in 1976 the City Center management withdrew its support of the resident companies as well as of the theater itself. Efforts to save the house for dance coalesced under the newly formed 55th Street Dance Theater Foundation in 1976. The Joffrey, Alvin Ailey, Elliot Feld Ballet Companies and the American Ballet Theater were the founding companies of this group, but performing seasons have been shared with numerous other dance companies as well. A major renovation of the theater interior was recently undertaken which improved the house's long criticized sight lines. Currently dance of many varieties thrives at City Center.

2

United States Department of the InteriorNational Park Service

National Register of Historic Places Inventory—Nomination Form

Mecca Temple (City Center of Music and Drama Continuation sheet New York County, N.Y. Item number



Page

Corbett, Harvey Wiley. "Architecture of Fraternal Buildings," Architectural Forum, 45 (September 1926), pp. 129-136

Foreman, Robert L. "The City Center." Unpublished Compilation of magazine articles tracing the history of the building from 1921-44, prepared for the 55th Street Dance Theater Foundation, 1981.

Greene, Herbert. "The Planning of Fraternal Buildings," Architectural Forum, 45 (September 1929), pp. 141-144.

Guarnera, Leonard, Masonic Historian: correspondence, research file. Landmarks Preservation Commission.

New York. Landmarks Preservation Commission. Research file: Mecca Temple.

Saunders, George M. A Short History of the Shrine. Chicago, 1972.

Ueland, Alexander. William Jermyn Florence, Shriner and Humanitarian. Boston: Christopher Publishing House, 1958.

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

Mecca Temple (City Center of Music and Drama) Continuation sheet New York County, N.Y. Item number

For NPS use only received date entered

2

Page

11

Form Researched & Prepared by:

Virginia Kurshan Landmarks Preservation Commission 20 Vesey Street New York, N.Y. 10007

(212) 566-7577



WASO Form - 177 ("R" June 1984)

UNITED STATES DEPARTMENT OF THE INTERIOR NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES EVALUATION/RETURN SHEET

New York County					
NEW YORK			Working No	AUG 9 1984	
			Fed. Reg. Date:		
			Date Due: 9	16/84 - 9/23/84	
			Action: AC	CCEPT 9-3-84	
resubmission		Entered in	the R	TURN	
nomination by person of	or local government	National R		JECT	
owner objection			Federal Agency:		
appeal					
] sample	☐ appeal	☐ NR dec	ision	
Reviewer's comments:			* Total (1)		
			Recom./Criteria_		
			Date		
			see continu	ation sheet	
Nomination returned for: _	technical corrections cited bel				
	substantive reasons discussed	below			
1. Name					
2. Location				e de la companya de l	
3. Classification					
Category	Ownership	Status	Present U	se	
	Public Acquisition	Accessible			
4. Owner of Property					
5. Location of Legal Descri	ption	local	67670		
6. Representation in Existing	ng Surveys				
Has this property been dete	rmined eligible?	□ no			
7. Description			97,66	913	
Condition	. (1) : (1)	eck one	Check one		
= excellent	deteriorated	unaltered	origin origin	al site	
good [ruins	altered	☐ move	d date	
☐ fair [unexposed				
Describe the present and or	iginal (if known) physical appearan	се			
summary paragraph					
completeness					
clarity					
alterations/integrity					
dates		en en en en en en en entrepheten (de la fill de la communication en en en			
boundary selection					
Dodingal y selection	teach hadrates as the hausine	or only from months one	an according?		
	AND THE RESERVE AND THE PARTY PROPERTY OF THE PARTY AND TH	CONTRACTOR OF SECURE ASSESSMENT OF SECURE ASSESSMEN			

8. Significance	
Period Areas of Significance—Check and justify below	
Specific dates Builder/Architect Statement of Significance (in one paragraph)	
summary paragraph completeness	Meesaa Temple New York County NEW YORK
☐ clarity ☐ applicable criteria ☐ justification of areas checked	
☐ relating significance to the resource ☐ context ☐ relationship of integrity to significance	
☐ justification of exception ☐ other	
9. Major Bibliographical References	
10. Geographical Data	
Acreage of nominated property Quadrangle name	
UTM References	All all and a second
Verbal boundary description and justification	
11. Form Prepared By	
12. State Historic Preservation Officer Certification The evaluated significance of this property within the state is:	The same of the sa
nationalstatelocal	76 (se
State Historic Preservation Officer signature	
title date	
13. Other	
☐ Maps ☐ Photographs ☐ Other	
Questions concerning this nomination may be directed to	
Signed Date	_ Phone:



New York County, New York

Photo by : Sachner, 1978
Neg. at: New York Landmarks
Preservation Commission

55th Street facade



New York County, New York

Phot by: Carl Forster, 1982 Neg. at: New York Landmarks Preservation Commission

56th Street facade



New York County, New York


Photo by: Carl Forster, 1982
Neg. at: New York Landmarks
Preservation Commission

Detail, main entrance doors on 55th Street



4. MECCA TEMPLE (CITY CENTER OF MUSIC AND DRAMA)
New York County, New York

Photo by: Forster, 1983
Neg. at: New York Landmarks
Preservation Commission
55th Street facade detail
Tympanum over entrance



New York County, New York

Photo by: Forster, 1982
Neg. at: New York Landmarks
Preservation Commission

55th Street facade detail Mezzanine windows



New York County, New York

Photo by: Forster, 1982
Neg. at: New York Landmarks
Preservation Commission

Ticket lobby

ENTER NG LIST RDS

7. MECCA TEMPLE(CITY CENTER OF MUSIC AND DRAMA)
New York County, New York

Photo by: Forster, 1982
Neg. at: New York Landmarks
Preservation Commission

Interior door to auditorium



New York County, New York

Photo by: Forster, 1982
Neg. at: New York Landmarks
Preservation Commission


Interior of theater, view of stage



New York County, New York

Photo by: Forster, 1982 Neg. at: New York Landmarks Preservation Commission

Interior of the theater, view from the stage



10. MECCA TEMPLE (CITY CENTER OF MUSIC AND DRAMA)
New York County, New York

Photoby: Forster, 1982
Neg. at: New York Landmarks
Preservation Commission

Theater interior detail



11. MECCA TEMPLE (CITY CENTER OF MUSIC AND DRAMA)
New York County, New York

Photo by: Forster, 1982 Neg. at: New York Landmarks Preservation Commission

Theater interior detail



New York County, New York

Photo by: Forster, 1982

Neg at: New York Landmarks
Preservation Commission

Mezzanine lobby, view towards 55th St.

Red tint indicates areas in which only landmark buildings are shown

the National or State reservations shown on this map