United States Department of the InteriorNational Park Service

National Register of Historic Places Inventory—Nomination Form

See instructions in How to Complete National Register Forms
Type all entries—complete applicable sections

For NPS use only

received AUG 2 7 1984

date entered

SEP 2 7 1984

Type all entries—complete applicable	e sections	to substitute of	S Delign Trans
1. Name		e (5.33)	
historic Merestead/Former	Sloane Estate)		
and/or common		ilea il	
2. Location			
street & number Byram Lake Ro	pad ,	_	not for publication
city, town Mount Kisco	/ ic vicinity of	. 75	
state New York co	ode 036 county	Westchester	code 119
3. Classification	di di		
Category Ownership district public building(s) private structure both site	Status occupied unoccupied work in progress Accessible x yes: restricted yes: unrestricted no	Present Use agriculture = commercial educational entertainment government industrial military	museum park rpivate residence religious scientific transportation other:
4. Owner of Prope	erty	n es la radica	
name Dr. & Mrs. Robert L. I	Patterson		
street & number Byram Lake	e Road		137.2
city, town Mount Kis	co vicinity of	state	New York
5. Location of Leg	gal Description	on	
courthouse, registry of deeds, etc. Wes	stchester County Offi	ce of Land Records	
street & number	18 Martine Avenue	720 - 33 125	
city, town Wh	nite Plains	state	New York
6. Representation	n in Existing	Surveys	
title None	has this pro	perty been determined elig	gible?yes _X_ no
date		federal state	e county local
depository for survey records			
city, town		state	

7. Description

Condition excellent	deteriorated	Check one X unaltered	Check one _x_ original site
_x good	ruins unexposed	altered	moved date NA

Describe the present and original (if known) physical appearance

Merestead, the country estate of William Sloane, includes a large neo-Georgian mansion completed in 1907, a nineteenth-century farm complex modified at approximately the same date, and 136 acres of open fields, gardens, and woodlands. Approximately nine acres at the northwest corner of the estate property was sold off during the mid-twentieth century. The estate is located in a rural area of northern Westchester County on Bryam Lake Road east of the village of Mount Kisco, New York. There are ten contributing historic components which constitute the historic Merestead estate complex. The estate buildings and entire original estate lands have remained virtually unchanged since the early twentieth century and the property contains no non-contributing structures.

The following building descriptions are keyed numerically to the map of the estate attached to this nomination.

1. Mansion, 1906-1907

The mansion is the centerpiece of the estate. It was designed in the neo-Georgian style by the noted architectural firm of Delano and Aldrich and was completed in 1907.

The two and one-half story mansion is essentially rectangular in plan with open porches projecting from the north and south ends and a one and one-half story service wing extending east from the northern portion of the main east facade. The walls are constructed of red brick laid in Flemish bond with marble watertable, belt course, window sills, and keystones. The hipped roof is covered with slate.

The west or garden facade is symmetrically composed of nine bays with a central entrance articulated with engaged Tuscan Doric columns and an entablature surmounted by a broken pediment. Full length openings with French doors and transoms flank the entrance at the first floor. These are headed bybrick jack arches with keystones and equipped with panelled shutters. The second story has nine identical six-over-six windows with jack-arched headers and louvred window blinds. The corners of the facade are detailed with brick quoins. A broad cornice with modillions terminates the second story. Five Georgian style dormers project from the hip roof: each has round-arched, double-hung windows. Four brick chimneys rise above the roofline of this elevation.

The main east facade faces a courtyard and incorporates a round-arched entrance and a columned porch located at the center of a five bay portion of this elevation. This portion is flanked by a slightly projecting one bay pavilion at the left end and the one and one-half story service wing at the right. Fenestration and detailing is similar to that described for the garden facade with the exception of four small first floor windows which flank the entrance. Four dormers occur at this elevation. A large brick chimney rises above the intersection of the service wing and main portion of the mansion.

The north and south ends of the mansion each include polygonal porches supported by Tuscan Doric columns and crowned by balustrades.

The first floor interior of the mansion is organized around a center entrance hall with extensions at the east side leading to the library at the south end

United States Department of the Interior **National Park Service**

National Register of Historic Places Inventory—Nomination Form

date entered

Continuation sheet

Merestead/Former Sloane Estate, Mt. Kisco, Westchester Co., NY Item number

Page 2

and the pantry and staircase at the north end. A formal dining room and living room are symmetrically placed at the north and south sides of the entrance hall along the west front of the mansion. At the second story, a transverse hallway leads to the bedrooms at each side with the stairhall occurring at the north end. The service wing includes kitchen and laundry facilities at the first floor and living quarters for the servants at the second floor.

The formal spaces of the interior are detailed in a manner consistent with the neo-Georgian style of the exterior. Walls include panelled wainscots, molded panels and entablatures, as well as elaborate cornices with modillions. Doorways are framed by fluted pilasters and entablatures in the hallways. The doors themselves are mahogany with panelled designs. Fireplaces are individually designed and detailed and usually include marble surrounds and elaborate wooden mantels and overmantels. A variety of electric candle sconces and chandeliers provide lighting in the major interior spaces.

The house's exterior and interior retains a high level of integrity and remains remarkably unchanged since its original construction.

2. Garden House, circa 1907

A single story frame garden pavilion with a hipped roof is located a short distance south of the mansion at the opposite side of the croquet court. Surrounded by gardens and a small rectangular pool, it has engaged columns and a paneled wainscot.

3. Garage Building, circa 1907

A small, one-story, three-car garage with brick exterior and slate-covered gable roof is located next to the main house's service wing.

4. Carriage House, circa 1907

South of the mansion on the south side of Byram Lake Road stands a single story carriage house. The structure consists of a rectangular block with two flanking, projecting pavilions at the main (north) facade. The building is sheathed in stucco and covered by a hipped, slate roof which has several dormers, a chimney, and a rooftop octagonal cupola with a dome. Door openings are located at the center of the north facade beneath a large semi-circular fanlight which projects above the eaves of the roof. Fenestration consists of six-over-six windows and semicircular lunettes framed within blind arcades.

5. Garage, circa 1907

A modest, three-bay, hipped roof garage is located immediately west of the carriage house. It includes three segmentally arched openings at the main facade, each opening filled with a pair of wooden garage doors, glazed in the upper halves. The roof is covered with slate.

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form or NPS use only

received

date entered

Continuation sheet

Merestead/Former Sloane Estate, Mt. Kisco, Westchester Co., NY Item number 7

Page 3

- 6. Tenant Farmhouse, mid-nineteenth century
 A two-story mid-nineteenth century frame farmhouse built prior to the development of Merestead is located southeast of the mansion on the north side of Byram Lake Road. It forms the nucleus of the extant farm complex purchased by Willaim Sloane to augment his Merestead estate. Originally built as a simple, vernacular structure at an undetermined date, it was modified around 1907 by the addition of dormer windows and a central pediment with lunette in order to make the house more architecturally compatible with the new buildings erected on the estate. The house is rectangular in form and features a full width (five-bay) front porch, a small, two-story east side extension, and gable roofs. An entrance with sidelights occurs at the center of the first story on the main facade which is flanked by two-over-two windows with shutters. The early twentieth century windows in the second story have six-over-six sash. The structure is sheathed with clapboard siding.
- 7. Cow Barn, circa 1907

 North of the tenant farmhouse stands a large frame cow barn with a jerkin head gable roof. The barn is constructed above a raised stone foundation with primary entry gained through sliding barn doors at the center of the east side. A ramp with stone retaining walls leads directly to this entrance from the farmyard. The walls of the barn above the foundation are sheathed in clapboard siding and the roof is covered with asphalt shingles. Octagonal ventilation cupolas rise at each end of the roof ridge, which is itself ventilated by a low, full-length monitor.
- 8. Stable, late nineteenth century
 A simple, late nineteenth century stable building pre-dating the estate is
 located immediately north of the cow barn. The structure is built on a partially
 raised stone foundation with clapboard siding and a gable roof. Fenestration
 consists of small, square four-over-four windows. Sliding barn doors are
 located at the south side facing the farmyard. An octagonal gable end window
 and a small ventilation cupola appearing at the center of the roof ridge appear
 to be later modifications dating from the early development of the Merestead
 estate.
- 9. Storage/Playhouse Building, early twentieth century
 This small, one-story, three-bay, early twentieth century frame structure is
 situated directly behind the tenant farmhouse. It has clapboard sheathing,
 a gable roof, six-over-six windows, and a small bracketed hood over the center
 front door. The building has been used for a variety of purposes including
 storage and a children's playhouse.

United States Department of the Interior National Park Service

National Register of Historic Places Inventory—Nomination Form

Merestead/Former Sloane Estate, Mt. Kisco,
Continuation sheet Westchester Co., NY Item number 7

For NPS use only received date entered

Page 4

^{10.} Farm support structures, circa 1900
This small farm building group includes four small shed/storage structures which are simple, undecorated, wooden and appear to date from the turn-of-the-century(1900). These structures contribute to the entire farm complex's historic appearance.

8. Significance

Period prehistoric 1400–1499 1500–1599 1600–1699 1700–1799 x 1800–1899 1900–	Areas of Significance—C archeology-prehistoric agriculture x architecture art commerce communications		ing landscape architecture law literature military music	religion science sculpture social/ humanitarian theater transportation other (specify
Specific dates	circa 1850 - 1907	Builder/Architect	Delano & Aldrich	

Statement of Significance (in one paragraph)

Merestead, the former Sloane Estate, is architecturally and historically significant as a distinguished, architect-designed estate which reflects the early twentieth century lifestyle of the well-to-do who established country seats in scenic northern Westchester County. Merestead, the 1907 country seat of William Sloane, is an outstanding and unaltered example of a large country estate typical of those built by wealthy New York industrialists early in the twentieth century. The distinctive neo-Georgian mansion, designed by the architectural firm of Delano & Aldrich, forms the centerpiece of the estate. A complete set of service buildings designed by the firm remain on the estate, as does a tenant farm complex (portions of which pre-date the estate development). Open spaces, lawns, gardens and woodlands have been maintained in their original locations, complementing the architectural ensemble as originally conceived.

Merestead was constructed between 1906 and 1907, during a period of American architectural history in which historically derived eclectic styles prevailed. This is partially the result of influences exerted by the French Ecole des Beaux-Arts, where many of American's finest architects of this period received their formal education. search for appropriate historical sources for important residential commissions, many architects and clients turned to the Georgian architecture of eighteenth-century England and America for inspiration. Merestead represents an extremely handsome twentieth-century interpretation of this style. The mansion is characterized by simplicity and a partially symmetrical plan. Details are derived from historical precedents and are properly scaled and used with a restraint frequently absent from the more ostentatious showplaces of the rich, built contemporaneously with Merestead.

The mansion is the unifying nucleus of the 136-acre estate which in its entirety remains virtually unchanged since its original early 1900s construction. The estate contains all the appropriate hallmarks of fashionable early twentieth century estates constructed in northeastern regions of the United States, including a handsome main house, a working yet picturesque farm complex, formal and informal landscaping, and various distinctive dependencies in a variety of architectural idioms. The Sloanes established the Merestead estate in 1907 by consolidating two adjacent farmsteads. They hired prominent architects Delano and Aldrich to create a variety of new estate buildings and landscapes compatible with the original farm buildings. The result is a successful and distinctive mixture of older and newer estate structures which create a handsome country seat. Merestead contains all the amenities of a distinguished country estate which reflects and fulfills the needs, tastes, and aspirations of a wealthy, New York City based family.

9. N	najor bibliog	rapnicai	neiere	11062	
F. Withey	k, Adolf K., gen. ed ree Press: 1982 , vo , Henry F. and Elsie Los Angeles: Henness	ol. 1: <u>Delano ar</u> e R. Biographica	nd Aldrich, al Dictiona	by Stephen McI ary of American	
10.	Geographic	al Data			
	ar ar	proximately 136	5		
Quadran	of nominated property <u>ax</u> Mount Kisco gle name)		Quadran	gle scale 1:24,000
UT M Refe		ation sheet			
A			В		لسابليا
Zone	Easting North	ning	Zon	e Easting	Northing
С			D L		
E			F L		
G L			н		
Verbal I	boundary description ar	d justification			
	See accompa	nying map with	scale		
	-				
List all	states and counties for	properties overlap	ping state o	r county boundarie	s _{NA}
state		code	county		code
state		code	county	*	code
State			county		
11.	Form Prepa	rea By			
name/title	e Austin O'Brien,	Field Represer	ntative		
organiza	tion Historic Preser	vation Field Se	ervices	date August	8, 1984
street &	number Empire State	Plaza, Buildir	ng # 1	telephone 518	-474-0479
city or to	Albany			state New York	
12.	State Histo	ric Prese	rvatio	n Officer (Certification
The eval	uated significance of this p				
	national		X local		
665), I he	esignated State Historic Properties of the criteria and proceed to the criteria and the criteria an	y for inclusion in the	National Regis	ster and certify that it	Act of 1966 (Public Law 89– has been evaluated
State His	storic Preservation Officer	signature	ra S.	Stoke	
title Der	outy Commissioner fo	r Historia Pres	servation	date	8/23/84
	IPS use only		Name of the second		
I h	ereby certify that this prope	erty is included in the			
9	herre M. Sam	mons	National	Register date	9-27-84
frkeep.	er of the National Register	7			,
Attes	st:			date	
	of Registration			1.4	

United States Department of the InteriorNational Park Service

National Register of Historic Places Inventory—Nomination Form

Merestead/Former Sloane Estate, Byram Lake Road Continuation sheet Mount Kisco, NY, Westchester Item number For NPS use only received date entered

Page 2

The estate was built as a country seat for William Sloane, president of W & J Sloane, a prestigious New York City furniture manufacturing company founded during the nineteenth century by his father. The company continues to manufacture high quality furniture to this day. A collection of furniture manufactured by the company remains in the mansion. The design of Merestead is the product of Delano & Aldrich (William A. Delano 1874-1960, Chester Holmes Aldrich 1871-1940), a New York architectural partnership established in 1903. Both architects were students at the Ecole des Beaux Arts and both initiated their careers in the New York office of Carrère & Hastings. In 1902 they worked together in that office on the construction of the New York Public Library (National Historic Landmark), a monumental Neoclassical building under construction from 1897-1911. The first major commission awarded to Delano & Aldrich after the formation of their partnership was the Walters Art Gallery in Baltimore, commissioned in 1904. Merestead was commissioned in 1906, early in the partnership and a year before John D. Rockefeller commissioned the architects to design Kykuit (National Historic Landmark), his Pocantico Hills estate outside north Tarrytown. Similar to Merestead, but on a more modest scale, is the Havemeyer House in Irvington built in 1907. domestic designs by the firm included the Otto Kahn residence in Cold Spring Harbor, New York, 1915; the Burden House, Syosset New York, 1916; the Mrs. Willard Straight House, New York, 1920; and the Vicent Astor House, Syosset New York, 1922. The firm is also noted for the following institutional buildings: Christ Church Parish House, Hartford, 1922; the Knickerbocker Club, New York; the Japanese Embassy in Washington D.C.; the U.S. Embassy in Paris; the Post Office Building in Washington D.C., 1933; the Union League Club, New York, 1936; the Walland Hanover Building, New York, 1939; La Guardia Terminal, New York, 1941; and several buildings on the campuses of Smith College, Yale University and Cornell University.

Merestead is an architecturally distinguished, early twentieth century country seat in northern Westchester County. Retaining almost complete integrity of siting and design, the complex recalls the lifestyle of America's wealthy industrialists at the turn-of-the-century.

¹ Before the Sloanes aquired the property, the area was sparcely settled with scattered farmsteads. The two farms which comprise and pre-date the estate have not been fully documented, but existing information indicates they were established sometime during the mid-nineteenth century. The tenant farmhouse, stable, and farm support buildings (see number seven building list) pre-date the estate development and constitute a portion of the two original farmsteads. The remaining farm buildings were sold off during the mid-twentieth century as part of a nine-acre parcel.

United States Department of the Interior National Park Service

For NPS use only

received

date entered


National Register of Historic Places Inventory—Nomination Form

Merestead/Former Sloane Estate, Mt. Kisco,
Westchester Co., NY Item number 10

Page 2

Merestead/Former Sloane Estate Mount Kisco, Westchester County, New York UIM References, Mount Kisco Quad (All zone 18)

ABCDEFGHIJKLMNOPQRST	Easting 608930 608930 608920 608960 609010 609160 608680 608550 608520 608310 608090 608130 608300 608360 608360 608360 608360 608360 608360 608360 608360	Northing 4559030 4559500 4559510 4559450 4559030 4558770 4558780 4558720 4558720 4558710 4558830 4558850 4558990 4559030 4559030 4559190 4558440 4559460
T	608360	4559360
U	608510	4559350
V	608560	4559530



WASO Form - 177 ("R" June 1984)

☐ alterations/integrity

□ boundary selection

☐ dates

UNITED STATES DEPARTMENT OF THE INTERIOR NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES EVALUATION/RETURN SHEET

Merestead (Sloane Es	tate)		
Westchester County			0.71004
NEW YORK			Working No. AUG 2 7 1984
		Entered in the	Fed. Reg. Date: 2,5.85
		National Register	
		1.0819101	Action: VACCEPT 9-27-84
resubmission			RETURN
nomination by person of	or local government		REJECT
owner objection			Federal Agency:
☐ appeal			all cores to major at a 2000.
Substantive Review:	☐ sample ☐ request	appeal	☐ NR decision
Reviewer's comments:			
			Recom./Criteria
			Reviewer
			Discipline
			Date
			see continuation sheet
1. Name	technical corrections cited besubstantive reasons discusse		
2. Location			Control also, pay have as a vibration of remove
3. Classification			
3. Classification			
Category	Ownership Public Acquisition	Status Accessible	Present Use
4. Owner of Property		id The state at the second of	การวาท (\$1) หลุดทาง กละสารจากสาราชาการสาราชาการ การประชาการสาราช ส่วน สาราชาการสาราชาการสาราชาการ
5. Location of Legal Descr	iption	Sur Sur Recei	orate state states and
6. Representation in Existi	ng Surveys		
Has this property been dete	ermined eligible?	□ no	
7. Description			ent y
Condition		Check one	Check one
excellent	deteriorated	unaltered	original site
good	ruins	altered	moved date
☐ fair	unexposed		
Describe the present and or	iginal (if known) physical appear	ance	
summary paragraph			
☐ completeness			
Clarity			

8. Signif	ficance	/
Period	Areas of Significance—Check and justify below	
Specific Statemer	dates Builder/Architect nt of Significance (in one paragraph)	
comp clarit appli justif relati conte	cable criteria fication of areas checked ing significance to the resource ext ionship of integrity to significance fication of exception	Postend (Bloune Satzia) Westenderer Franky NEW FOLKS
9. Majo	r Bibliographical References	
10. Geo	ographical Data	
Quadran	of nominated property ngle name eferences	
Verbal b	ooundary description and justification	
11. For	rm Prepared By	
	te Historic Preservation Officer Certification luated significance of this property within the state is:	
	nationalstatelocal	
State Hi	istoric Preservation Officer signature	
title	date	
13. Oth	ner	
☐ Map ☐ Phot	tographs	
Question	ns concerning this nomination may be directed to	
Signed_	Date	Phone:



Merestead, Mt. Kisco, Westchester Co., NY By: A. O'Brien, 1982 Neg: OPRHP, Albany, NY Main House (east side)



Main House (west side)



Main House (south side)



Main House (north side)



Main House/Main east entrance



Main House/main entrance hall



Main House/Living Room



Main House/view looking from Living Room to Dining Room 8



Main House/Dining Room



Garden House and Garden



Carriage House



(Carriage House) Garage 12



Tenant Farmhouse (main facade)
13



Farm Building (behind farmhouse)



Farm Building Complex

15



Main (Cow) Barn

16



Stable

17







DEPARTMENT OF PARKS, RECREATION & CONSERVATION

JOSEPH M. CAVERLY Commissioner

ROBERT E. DISPENZA Deputy Commissioner

JAMES E. ARLES Deputy Commissioner

Commissioner Orin Lehman State Historic Preservation Officer New York State Parks & Recreation Agency Building I Empire State Plaza Albany, New York 12238

Dear Commissioner Lehman:

October 21, 1982

OCT 2 6 1988

RE: "MERESTEAD" ESTATE - HISTORIC PRESERVATION

We would like to strongly recommend that Merestead be selected for the Register of the New York State Board for Historic Preservation, as well as the National Register. We have been actively involved with Mrs. and Dr. Patterson in their donation of Merestead to the Westchester County and believe that it merits such registration.

The 26-room Georgian Mansion and its surrounding 135 acres will allow the public to view the elegant lifestyle of this family and be able to re-live this lifestyle when it is opened by Westchester as its first County-owned and operated museum. This 74 year old Georgian-style brick mansion was designed by Delano and Aldrich and exhibits outstanding workmanship reflecting the craftsmanship of that period. The current lady of the house, Margaret Sloane Patterson, was born in an upstairs bedroom and wants to share, as an educational process, the day-to-day living process with the future generations. The house still looks as it did when she was a child-with the hunting prints lining the staircase, family portraits, and autographs of Charles Lamb, Robert Southey, and almost all the American Presidents. Many of the Presidential autographs are on letters addressed to her family, including one from Theodore Roosevelt thanking her father for his work in establishing Young Men's Christian Association Chapters, some which have memorialized him by taking the name Sloane House.

Her husband, Dr. Robert Patterson, a retired orthopedic surgeon, was surgeon in chief of the hospital for special surgery and professor of orthopedics at Cornell Medical College and is now consultant for several veterans' hospitals. Dr. Patterson served in World War II as an army doctor in Europe. They moved into Merestead when Mrs. Patterson's mother died in 1962.

The Pattersons have added treasures of their own, some are gifts from Dr. Patterson's patients, including an autograph photo of the Duke and Dutchess of Windsor and a letter from Eugene O'Neill. They plan to bring a collection of old engravings of New York from their city apartment such as an 18th Century sideboard. Most of the furniture came from W. & J. Sloane, the furnishings store that her great grandfather

founded. Her father was president of the store when he built the house in 1907. There is also a piano, a Steinway, given to her father by Mr. Steinway.

"People will be able to see just how we lived in those days," said Mrs. Patterson, who was born in 1910, as she reminisced about a bygone lifestyle.

We think it is vitally important that this outstanding mansion and adjoining property be listed on the Register to help insure that this facility will remain a living museum to the lifestyle of that era.

If you need any additional information, please let us know.

Sincerely yours,

Joseph Caverly Commissioner

By Robert E. Dispenza/ Deputy Commissioner

JC:RED:mp

cc: Ms. Ann Webster Smith
Deputy Comr. for Historic Preservation

file Ny Mille 7-31-85

H32 (413)

AUG 1 1985

Mrs. Robert L. Patterson Post Office Box 59 Mount Kisco, New York 10549

Dear Mrs. Patterson:

Thank you for your letter of May 5, 1985, requesting confirmation that "Merestead" in Westchester County, New York, is listed in the National Register of Historic Places.

This letter certifies that "Merestead," also known as Sloane Estate, was listed in the National Register on September 27, 1984. For your information, we are enclosing a copy of the National Register nomination form. The National Park Service does not provide plaques for properties listed in the National Register. We suggest that you contact Orin Lehman, the New York State Historic Preservation Officer, to ascertain whether or not a State or local organization might do so. Mr. Lehman's address is: Commissioner, Office of Parks, Recreation and Historic Preservation, Agency Building #1, Empire State Plaza, Albany, New York 12238.

If we can provide further information or assistance, please let us know. We appreciate your interest in the historic preservation programs of the National Park Service.

Sincerely.

Carol D. Shull (Sgd.)

Carol D. Shull Chief of Registration National Register of Historic Places Interagency Resources Division

Enclosure

bec:413

Reading Files Records Center

FNP:DMiller:dm/kb:07/29/85:343-9536

Sys 8 (NRH) Patterson

Basic Files Retained in 413

research

"MERESTEAD"
P. O. BOX 59
MOUNT KISCO, N. Y. 10549

National Register of Historice Process National Paul Services Workington D.C.

Dear Sirs-

In November of 1984.

I received a letter from

Commissioner or in Lehman

Commissioner or in Lehman

My State informing

My State informing

Me that my house
Marester has been

1, Grad in the State and

Matimal régisters 7 historic places. I have had no notice from you to this effect and am Threfre instant to ask you to emfirm this listing and to give me any unformation be the qualifications of my home, and how or may ger a plaque or sign to authoricate t. My home so designated and so is the Country

"MERESTEAD" P. O. BOX 59 MOUNT KISCO, N. Y. 10549 Raks Dept of merichester (New Yeld) , to whom we have granted its use by our wills. MAY 9 1985 Mayans Trave Vallerson (Mrs. Robert L. Patters L) 1/ by 5 =