OWNERSHIP OF DOCUMENTS
This document, and the ideas and designs incorporated herein, as an instrument of service is the property of the architect and is not to be used, in whole or in part, for any other project without the written authorization of the architect.

REVISIONS

NO.	DATE	DESCRIPTION

H' = 4'-0" WIDE M.O.

EXTERIOR FINISH SYSTEM COLOR 'M' COLOR 'B'

NEW SCUPPER, R.W.L, BOOT & TRANSITION PIECE TO 6" UNDERGROUND DRAINAGE SYSTEM. (TYP.)

REMOVE EXIST. CONST. INSTALL NEW WINDOWS IE. SPLIT FACE C.M.U. (TYP. 3 WINDOWS)

ACTUAL OPEN AREA 1152 SQ.IN.

CONNECT EXIST. R.W.L TO 6" UNDERGROUND DRAINAGE SYSTEM. (TYP. EXISTING)

TYPICAL NEW FACE BRICK, EXISTING BRICK COLUMN COVER, NEW SCUPPER, R.W.L & BOOT

NEW LOUVER SIZE SHALL MATCH THAT OF THE EXISTING. (BASE BID TYP.) DELETE LOUVER & ADD SPLIT FACE C.M.U. IF ALT. BID NO. 10 IS ACCEPTED (TYP.).

STEP FLASHING COLOR SHALL MATCH THAT OF METAL ROOFING

FACE BRICK

SPLIT FACE CMU

LIGHT FIXTURE

1 1/2" OD. PIPE RAILING

1/A-9 Partial West Elevation
scale: 1/8" = 1'-0"

EXISTING BRICK COLUMN COVERS TO REMAIN TYPICAL

EXISTING WINDOW WALL CONSTRUCTION TO BE REMOVED IN IT'S ENTIRETY (TYP.)

REMOVAL OF ASBESTOS CONTAINING PANELS N.I.C. G.C. SHALL CO-ORDINATE WORK WITH OWNER'S CONTRACTOR FOR ASBESTOS REMOVAL (TYP.)

2/A-9 Exsiting Window Wall Layout

show wall caps

EXT. FINISH SYSTEM

SPLIT FACE C.M.U.

FACE BRICK

REMOVE EXISTING C.M.U. & INSTALL NEW WINDOW, SPLIT FACE C.M.U. & FACE BRICK. BOTTOM OF FOOTING ELEV. TO MATCH EXISTING

KEY PLAN

3/A-9 Partial South Elevation
scale: 1/8" = 1'-0"

1152 S.F. C.J. & ST. COL. (TYP. UNLESS NOTED OTHERWISE)

FACE BRICK CHIMNEY

12" METAL STANDING SEAM ROOFING SYST.

ACTUAL OPEN AREA 1152 SQ.IN.

EXTERIOR FINISH SYSTEM COLOR 'A'

FACE BRICK

SPLIT FACE CMU (BAND)

Bolton Elementary School

OUTLINE OF GREEN HOUSE

1 1/2" OD. PIPE RAILING

EXTERIOR

C.J.

B.O.F. 753.50

B.O.F. 754.50

TOP OF SLAB 759.50
TOP OF "BRICK" SHELF
FIN. GRADE AT EXT. WALL
APPROX. EXIST. GRADE
BOTTOM OF FOOTING

4/A-9 Partial West Elevation
scale: 1/8" = 1'-0"

EXTERIOR FINISH SYSTEM COLOR 'A'

FACE BRICK

12" METAL STANDING SEAM SYSTEM

SPLIT FACE CMU (BAND)

LIGHT FIXTURE

TOP OF SHELF

CONC. FOUNDATION WALL

5/A-9 Partial South Elevation
scale: 1/8" = 1'-0"

SW FOUND, PLANK. SHOW EXT. 7 of 8 SHEETS

EXT. WALL	CONC. ENTRY PAD & FROST WALL	WALK PERPENDICULAR TO BUILDING DIMENSION VARIES	WALK PARALLEL TO BUILDING

CROSS SLOPE GRADE FROM PAD

SLOPE 1/4" PER FT.

SLOPE 15% MAX

SLOPE 1/4" PER FT.

SLOPE FIN. GRADE 5% MIN.

6/A-9 TYP. BLDG/WALK/GRADING RELATIONSHIP

KEY PLAN

NOTE:
SEE MECH. & ELEC. DRAWINGS FOR LOCATION OF ITEMS TO BE BUILT-IN THE CONSTRUCTION. EXACT HEIGHT AND LOCATION OF SUCH ITEMS IF NOT SHOWN, SHALL BE DETERMINED IN THE FIELD BY THE ARCHITECT.

THE LAWRENCE ASSOCIATES
ARCHITECTS / PLANNERS
1099 TOLLAND TURNPIKE MANCHESTER, CONNECTICUT 06040
(203) 649-8585

PROJECT NUMBER 2155.01

ALTERATIONS AND ADDITIONS TO:
BOLTON ELEMENTARY SCHOOL
NOTCH ROAD
BOLTON, CONNECTICUT

DRAWING TITLE
EXTERIOR ELEVATIONS

SCALE 1/8"=1'-0" | DATE 5-17-1992

A-9
DRAWING 17 OF 89