OWNERSHIP OF DOCUMENTS
THIS DRAWING AND THE IDEAS AND DESIGN INCORPORATED HEREIN, AS AN INSTRUMENT OF PROFESSIONAL SERVICE, IS THE PROPERTY OF THE ARCHITECT AND SHALL NOT BE USED IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF THE ARCHITECT.

REVISIONS

NO.	DATE	DESCRIPTION

FOOD STORAGE 77
LAV. 74
EXISTING CEILING TO REMAIN
LOCKERS 75
REMOVE EXISTING CEILING AS REQ'D. FOR NEW HOOD INSTALATION (NEW CEILING TILES SHALL MATCH EXISTING)
KITCHEN AREA 72
NEW CLOSURE PANEL SEE NOTE ON DRAWING A-5
LOCATION OF NEW HOOD
REMOVE EXISTING CEILING TILES AND REPLACE W/ NEW TO MATCH EXISTING AS REQ'D. FOR EXISTING CORRIDOR WALL EXTENSION
REMOVE EXISTING CEILING TILES AND REPLACE W/ NEW TO MATCH EXISTING AS REQ'D. FOR EXISTING CORRIDOR WALL EXTENSION
ART ROOM (K-3) 83
EXISTING CEILING TO REMAIN
NEW CEILING TILE AND GRID TO MATCH EXISTING IN HEIGHT AND ALIGNMENT
MUSIC ROOM 84
EXISTING CEILING TO REMAIN
CORRIDOR 71
REMOVE EXISTING CEILING TILES AND REPLACE W/ NEW TO MATCH EXISTING AS REQ'D. FOR EXISTING CORRIDOR WALL EXTENSION
CAFETERIA 78 (2ND CEILING) - PAINT EXISTING
REMOVE AND REPAIR EXISTING CEILING TILES AS REQ'D. FOR NEW INTERIOR PARTITION CONSTRUCTION
GIFTED 86
EXISTING CEILING TO REMAIN
REMOVE EXISTING CEILING TILES AND REPLACE W/ NEW TO MATCH EXISTING AS REQ'D. FOR RECONSTRUCTION OF EXISTING EXTERIOR WALL.
EXISTING CEILING TO REMAIN
STAFF LOUNGE 85
STOR. 69
NO CEILING
PANEL ACCESS OR
LOCATION OF ACCESS PANEL
SUPERINTENDANT 60
LAV. 66
MEETING 67
LAV. 65
CLO. 64
REMOVE AND REPAIR EXISTING CEILING TILES AS REQ'D. FOR NEW INTERIOR PARTITION CONSTRUCTION
VAULT 62
LAV. 61
KITCHEN 63
ADMIN. ASST. 59
CONFERENCE AREA 58
REMOVE EXISTING CEILING TILES AND REPLACE W/ NEW TO MATCH EXISTING AS REQ'D. FOR RECONSTRUCTION OF EXISTING EXTERIOR WALL.
BUSINESS OFFICE 57
COVERED AREA 55
RECEP. 56
CORRIDOR 68
VEST. 54
GIRLS LAV. 82
BOYS LAV. 87
EXISTING CEILING TO REMAIN
STORAGE 88
CLASSROOM 98
CLASSROOM 91
CLASSROOM 92
CLASSROOM 93
EXISTING CEILING TO REMAIN
CORRIDOR 49
REMOVE EXISTING CEILING TILES AND REPLACE W/ NEW TO MATCH EXISTING AS REQ'D. FOR EXISTING CORRIDOR WALL EXTENSION
REMOVE EXISTING CEILING TILES AND REPLACE W/ NEW TO MATCH EXISTING AS REQ'D. FOR RECONSTRUCTION OF EXISTING EXTERIOR WALL.
REMOVE EXISTING CEILING TILES AND REPLACE W/ NEW TO MATCH EXISTING AS REQ'D. FOR REPLACEMENT OF ROOF STRUCTURE
CLASSROOM 53
CLASSROOM 52
CLASSROOM 51
CLASSROOM 50
CLASSROOM 48
CLASSROOM 47
EXISTING CEILING TO REMAIN
REMOVE EXISTING CEILING TILES AND REPLACE W/ NEW TO MATCH EXISTING AS REQ'D. FOR EXISTING CORRIDOR) WALL EXTENSION
REMOVE EXISTING CEILING TILES AND REPLACE W/ NEW TO MATCH EXISTING AS REQ'D. FOR RECONSTRUCTION OF EXISTING EXTERIOR WALL.
VEST. 46
COVERED AREA 47A
COURTYARD

LIGHTS (TYP.) SEE ELEC.
COVERED WALKWAY
CAN TYPICAL
CEILING DROP
VEST.
EXTERIOR FINISH SYSTEM ON EXTERIOR CEMENT BOARD, TYP.
FIELD STORAGE ROOM 79
ELECT ROOM 80
CUSTODIAL AREA 81
EXISTING CEILING TO REMAIN
VEST. 62
EXISTING CEILING TO REMAIN IF NO CEILING THEN REPAINT
LOADING DOCK 76
RECEIVING AREA 70
CAN WASH 75
REMOVE AND REPAIR EXISTING CEILING TILES AS REQ'D. FOR NEW INTERIOR PARTITION CONSTRUCTION. RELOCATE EXISTING LIGHT AS REQ'D. FOR NEW WALL CONSTRUCTION
LAV. 74
FOOD STORAGE 77
REMOVE EXISTING CEILING TILES AND REPLACE W/ NEW TO MATCH EXISTING AS REQ'D. FOR EXISTING CORRIDOR WALL EXTENSION
EXISTING CEILING TO REMAIN

CEILING 'GRID'
1. LOCATE ALL LIGHTS, SPEAKERS, SIGNALS, DETECTORS, DIFFUSERS, ETC... IN THE EXACT CENTER OF CEILING TILES.
2. CONTACT THE ARCHITECT IN THE EVENT OF CONFLICT BETWEEN ITEMS BEFORE INSTALLATION.

1/A-33 ITEMS IN CEILING DETAIL
1/4" = 1'-0"

SPECIAL EDUCATION 99
SPEECH 97
SPECIAL EDUCATION 96
KINDERGARTEN CLASSROOM 38
EXISTING CEILING TO REMAIN
REMOVE AND REPAIR EXISTING CEILING TILES AS REQ'D. FOR NEW INTERIOR PARTITION CONSTRUCTION
LAV. 40
STORAGE ROOM 41
LAV. 39
KINDERGARTEN CLASSROOM 42
CORRIDOR 43
REMOVE EXISTING CEILING TILES AND REPLACE W/ NEW TO MATCH EXISTING AS REQ'D. FOR EXISTING CORRIDOR WALL EXTENSION
CLASSROOM 44
REMOVE EXISTING CEILING TILES AND REPLACE W/ NEW TO MATCH EXISTING AS REQ'D. FOR RECONSTRUCTION OF EXISTING EXTERIOR WALL.
STORAGE ROOM 94
CUST. ROOM 95
CLASSROOM 45
EXISTING CEILING TO REMAIN

Partial 1st Floor Reflected Ceiling Plan

scale: 1/8"= 1'-0"

NOTE:
All new and existing roof/ceiling and floor/ceiling assemblies shall have a one hour fire rating unless noted otherwise. See detail(schedule) 1/A-2 for U.L. design No.'s at various ceiling assemblies.

THE LAWRENCE ASSOCIATES
ARCHITECTS / PLANNERS, P.C.
1075 TOLLAND TURNPIKE, MANCHESTER, CONNECTICUT 06040
(203) 649-8344

STATE PROJ. # 012-69-027EA
PROJECT NUMBER 2155.01

PROJECT TITLE
ALTERATIONS AND ADDITIONS TO :
BOLTON ELEMENTARY SCHOOL
NOTCH ROAD
BOLTON, CONNECTICUT

DRAWING TITLE
PARTIAL REFLECTED CEILING PLAN.

SCALE 1/8"=1'-0" DATE 8-17-1992

A-33
DRAWING 41 OF 89