



Westin Building, Room 1920
2001 Sixth Avenue
Seattle, Washington 98121


DESCRIPTION AND BACKGROUND HISTORY INCLUDING CONSTRUCTION DATE(S), PHYSICAL DIMENSIONS, MATERIALS, MAJOR ALTERATIONS, IMPORTANT BUILDERS, ARCHITECTS, ENGINEERS, ETC.	CURRENT USE	ORIGINAL USE
Vernacular Farmhouse with Bungalow elements. Wood frame set on post and block foundation; rectangle (20'x36') with flat roof addition on north facade; 2 bays wide; 1½-stories; wood shake siding with wood shingles on gable ends; wood-shingled gable roof with extended eaves; off-center entrance on south facade with glass and wood-panelled door; exterior end chimney on west facade. Exterior features include 2/2-pane fixed sash; metal sliding sash; 2/1, 4/1, 6/1, 8/1, 6/6 double-hung sash all with moulded surrounds; gable-roofed portico on south facade supported by plain posts; 3-sided bay window on west facade; knee braces; exposed rafter ends; plain fascia board. Notable landscape features include 2 wood frame gable-roofed outbuildings; orchard remnants. This farmhouse was built by Charlie Mitchell c. 1900, who lived here for many years. The house was later bought by Glen Darst, a potato farmer. Glen never lived in the house, opting to rent out the house and farm the land. The house was passed to Glen's son Gerald in 1948, and he lived here with his family until he sold the house c. 1979 to Dr. Palmetter. 1995: The house does not have integrity due to alterations, but the barn is a contributing structure in the cultural landscape.	Residence	Residence

SIGNIFICANCE This property is significant under National Register criterion A, for its association with agricultural land use patterns first established during the period of early settlement in the 1850s. It retains integrity of location, setting, materials, design, workmanship, feeling and association.

PHOTOGRAPHS AND SKETCH MAP OF LOCATION



FROM SE



FROM NW



FROM NE

NEGATIVE NO. L20-24,25; C22-12,15,17¹⁸ HABS/HAER QUALITY ☐ YES ☒ NO

REFERENCES

Cook. Personal Interview. September 1983.
Arnold, Chuck. Telephone Interview. 20 September 1983.
Darst, Mrs. Gerald. Telephone Interview. September 1983.

INVENTORIED BY
Luxenberg/Castellano/Lein

AFFILIATION
National Park Service

DATE
Summer, 1983