

EBEY'S LANDING
NATIONAL
HISTORICAL RESERVE


PNRO
INVENTORY

National Park Service
Pacific Northwest Region
Cultural Resources Division

Westin Building, Room 1920
2001 Sixth Avenue
Seattle, Washington 98121

NAME(S) OF STRUCTURE Fisher/Hingston/Trumbull General Store		DATE OF CONSTRUCTION c. 1903	SITE ID. NO. 	
SITE ADDRESS (STREET & NO.) 694 N. State Hwy 20 Corner of North Highway 20 and Penn Cove Road		ADDITION(S)	SCALE 1:24000	
CITY/VICINITY Coupeville			QUAD NAME Coupeville	
COUNTY Island		UTM ZONE 10		EASTING 520683
STATE Washington		NORTHING 5342298		CROSS REFERENCE LA19
OWNER/ADMIN ADDRESS Raymond and Audrey Getty 904 Ocean Bluff Lane Coupeville, WA 98239 parcel #S8060-00-10001-0		☒ CONTRIBUTING ☐ NON-CONTRIBUTING		DANGER OF DEMOLITION? (SPECIFY THREAT) ☐ YES ☒ NO ☐ UNKNOWN
DESCRIPTION AND BACKGROUND HISTORY INCLUDING CONSTRUCTION DATE(S), PHYSICAL DIMENSIONS, MATERIALS, MAJOR ALTERATIONS, IMPORTANT BUILDERS, ARCHITECTS, ENGINEERS, ETC. False Front Commercial Building. Wood frame set on post and block foundation; rectangle (18' x 36'); 3 bays wide; 1-story; shiplap siding with vertical wood panel on false front ends; tarpaper/asphalt-shingled gable roof; center entrance on north facade. Exterior features include 1/1 fixed sash; aluminum sliding sash; recessed entry with wood panel double door flanked by 2-pane sash and transom on north facade; enclosed shed roof porch with exposed rafter ends on south facade. L.P. Byrne built this building c. 1903. In 1904, Chris Fisher purchased the structure and ran a general store until it was sold to M.E. Hingston in 1922. The entrance was originally on the south facade facing Penn Cove Road. When Highway 20 was constructed the entrance was changed to the north facade facing the new highway. The Trumbull family purchased the store in 1945 and for a few years lived in the back of it. In 1956, the store was sold to Helen Baker. Over the past few years, the store has had several owners and a variety of businesses. The building is currently vacant. 1995: one contributing structure.		CURRENT USE Vacant		ORIGINAL USE General Store
		PUBLIC ACCESSIBILITY ☒ YES, LIMITED ☐ NO		EXISTING SURVEYS ☐ NR ☐ HABS ☐ NHL ☐ LCS ☐ NPS ☐ STATE ☐ COUNTY ☐ LOCAL ☐ OTHER
LOCATED IN AN HISTORIC DISTRICT? ☒ YES ☐ NAME Cent. Whid. Isl. Hist. Dist.		CONDITION ☐ EXCELLENT ☐ GOOD		☒ FAIR ☐ DETERIORATED ☐ RUINS
SIGNIFICANCE This property is significant under National Register criterion A, for its association with commercial enterprises which established a stable economic foundation for the community from the period of early settlement in the 1850s through 1945. It retains integrity of location, setting, materials, design, workmanship, feeling and association.				


PHOTOGRAPHS AND SKETCH MAP OF LOCATION



FROM N



HISTORIC VIEW



FROM NE



NEGATIVE NO. C19-35; L16-16

HABS/HAER QUALITY

☐ YES

☒ NO

REFERENCES Armstrong, Susie. "A Short History of San de Fuca, Wn. and Vicinity." Unpublished Manuscript. 1934.
Trumbull, Bill. Telephone Interview. 16 August 1983.

INVENTORIED BY

Luxenberg/Castellano/Lein

AFFILIATION

National Park Service

DATE

Summer, 1983