

EBEY'S LANDING
NATIONAL
HISTORICAL RESERVE

PNRO
INVENTORY

National Park Service
Pacific Northwest Region
Cultural Resources Division

Westin Building, Room 1920
2001 Sixth Avenue
Seattle, Washington 98121

NAME(S) OF STRUCTURE James Wanamaker House/Martin House		DATE OF CONSTRUCTION 1892	SITE ID. NO. [] [] [] [] [] [] [] [] [] []	
SITE ADDRESS (STREET & NO.) 607 South Main Street		ADDITION(S)	SCALE 1:24000	QUAD NAME Coupeville
CITY/VICINITY Coupeville			UTM ZONE [] [] [] [] [] [] [] [] [] []	EASTING [] [] [] [] [] [] [] [] [] []
COUNTY Island		STATE Washington	CROSS REFERENCE LA41	
OWNER/ADMIN ADDRESS John & Darlene Martin & Michael S. Martin 607 S. Main St. parcel #R13104-331-4200 Coupeville, WA 98239	☒ CONTRIBUTING ☐ NON-CONTRIBUTING		DANGER OF DEMOLITION? (SPECIFY THREAT) ☐ YES ☒ NO ☐ UNKNOWN	

DESCRIPTION AND BACKGROUND HISTORY INCLUDING CONSTRUCTION DATE(S), PHYSICAL DIMENSIONS, MATERIALS, MAJOR ALTERATIONS, IMPORTANT BUILDERS, ARCHITECTS, ENGINEERS, ETC.

Vernacular Farmhouse with Italianate elements. Wood frame set on post and block foundation; L-shape (36' x 30'); 1 1/2-stories; shiplap siding, partially covered by asbestos siding; asphalt-shingled gable roof; off-set entrance on west facade; 2 corbelled interior chimneys. Exterior features include 2/2 double-hung sash; plain cornice and frieze board; corner boards; carved wood panel front door with fanlight; 1-story shed roof enclosed porch on east facade. Notable landscape features include 1 gable roof outbuilding.

This house was built for James Wanamaker, a local merchant and public official, in 1892. The house remained in the family for many years. The back porch has been enclosed and a few of the original windows have been moved or replaced. During the 1950's, asbestos siding was placed over the original shiplap. The current owners purchased the house in 1975 and are currently renovating the house.

1995: owners have removed non-historic siding; one contributing building; one contrib. structure.

PUBLIC ACCESSIBILITY	☒ YES, LIMITED ☐ NO	☐ YES, UNLIMITED ☐ UNKNOWN	EXISTING SURVEYS	☐ NR	☐ HABS ☐ NHL	☐ LCS ☐ NPS	☐ STATE ☐ COUNTY	☐ LOCAL ☐ OTHER
LOCATED IN AN HISTORIC DISTRICT?	☒ YES ☐ NAME	☐ NO Cent. Whid. Isl. Hist. Dist.	CONDITION	☐ EXCELLENT ☐ GOOD	☒ FAIR ☐ DETERIORATED	☐ RUINS		

SIGNIFICANCE

This property is significant under National Register criterion C, because it embodies the distinctive characteristics of architectural expressions and methods of construction that represent the period of community development in the Reserve, from 1871 until 1910. It retains integrity of location, setting, materials, design, workmanship, feeling and association.


PHOTOGRAPHS AND SKETCH MAP OF LOCATION



FROM W



FROM SW



FROM SW



NEGATIVE NO. L12-31-33

HABS/HAER QUALITY

☐ YES

☒ NO

REFERENCES

Cook. Penn's Cove. p. 113.

Martin, Mrs. Patrick. Personal Interview. 4 August 1983.

INVENTORIED BY Luxenberg/Castellano/Lein

AFFILIATION National Park Service

DATE Summer, 1983