

EBEY'S LANDING **PNRO** NATIONAL INVENTORY HISTORICAL RESERVE

National Park Service
Pacific Northwest Region
Cultural Resources Division


Westin Building, Room 1920
2001 Sixth Avenue
Seattle, Washington 98121

NAME(S) OF STRUCTURE Tom Howell's Barbershop/Mitchell's Antiques		DATE OF CONSTRUCTION 1936 ADDITION(S)	SITE ID. NO.	
SITE ADDRESS (STREET & NO.) 13 N.W. Front Street			SCALE 1:24000	
CITY/VICINITY Coupeville		COUNTY Island	STATE Washington	QUAD NAME Coupeville
OWNER/ADMIN ADDRESS Shelby Quinn parcel #R13233-385-3830 71 Carriage Hts. lane Coupeville, WA 98239		☒ CONTRIBUTING ☐ NON-CONTRIBUTING		UTM ZONE EASTING NORTHING CROSS REFERENCE LA29
DESCRIPTION AND BACKGROUND HISTORY INCLUDING CONSTRUCTION DATE(S), PHYSICAL DIMENSIONS, MATERIALS, MAJOR ALTERATIONS, IMPORTANT BUILDERS, ARCHITECTS, ENGINEERS, ETC. False Front Commercial. Wood frame set on post and block foundation; rectangle (25' x 30'); 4 bays wide; 1-story; clapboard siding; asphalt-shingled saltbox roof with stepped parapet on false front; paired entrances on north facade with large pane sash on doors, and transoms, with plain surrounds; off-set interior chimney. Exterior features include large, single pane sash with 5-pane transom, plain surrounds, flanking entrance doors; 6/6 double-hung sash; plain frieze board; corner boards; double stair entrance with plain wood rail and multiple newell posts. This building was constructed in 1936 to house Tom Howell's Barber Shop. In 1945, it was purchased by Lois May Hansen and run as a beauty shop until 1968. Since then, a variety of businesses have occupied the building. <i>1995: One contributing building.</i>		DANGER OF DEMOLITION? (SPECIFY THREAT) ☐ YES ☒ NO ☐ UNKNOWN		
CURRENT USE Commercial		ORIGINAL USE Commercial		
PUBLIC ACCESSIBILITY ☒ YES, LIMITED ☐ NO		EXISTING SURVEYS ☐ NR ☐ HABS ☐ NHL ☐ LCS ☐ NPS ☐ STATE ☐ COUNTY ☐ LOCAL ☐ OTHER		
LOCATED IN AN HISTORIC DISTRICT? ☒ YES ☐ NO NAME Cent. Whid. Isl. Hist. Dist.		CONDITION ☐ EXCELLENT ☒ GOOD ☐ FAIR ☐ DETERIORATED ☐ RUINS		
SIGNIFICANCE This property is significant under National Register criterion A, for its association with commercial enterprises which established a stable economic foundation for the community from the period of early settlement in the 1850s through 1945. This property is also significant under National Register criterion C, because it embodies the distinctive characteristics of architectural expressions and methods of construction that represent the period of community stabilization and economic slowdown (evidenced by simpler forms lacking ornamentation) and the theme of recreation and tourism (evidenced by structures built with natural materials set in scenic locations), from 1911 until 1945. It retains integrity of location, setting, materials, design, workmanship, feeling and association.				

PHOTOGRAPHS AND SKETCH MAP OF LOCATION



FROM N



FROM NE



NEGATIVE NO. L5-31, 32

HABS/HAER QUALITY

☐ YES

☒ NO

REFERENCES Cook. Penn's Cove. p. 127.

INVENTORIED BY Luxenberg/Castellano/Lein

AFFILIATION National Park Service

DATE Summer, 1983