



EBEY'S LANDING NATIONAL HISTORICAL RESERVE

PNRO INVENTORY

National Park Service
Pacific Northwest Region
Cultural Resources Division

Westin Building, Room 1920
2001 Sixth Avenue
Seattle, Washington 98121


NAME(S) OF STRUCTURE Cushen House/Penn Cove Bed and Breakfast		DATE OF CONSTRUCTION c.1916	SITE ID. NO. [] [] [] [] [] [] [] [] [] []	
SITE ADDRESS (STREET & NO.) 15 Northwest Coveland Street		ADDITION(S)	SCALE 1:24000	QUAD NAME Coupeville
CITY/VICINITY Coupeville		COUNTY Island	STATE Washington	UTM ZONE [] [] [] [] [] [] [] [] [] []
OWNER/ADMIN ADDRESS Richard Calantropo P. O. Box 1162 Coupeville, WA 98239		parcel #R13233-363-355	EASTING [] [] [] [] [] [] [] [] [] []	
			NORTHING [] [] [] [] [] [] [] [] [] []	
			CROSS REFERENCE LA 29	
		☒ CONTRIBUTING ☐ NON-CONTRIBUTING	DANGER OF DEMOLITION? (SPECIFY THREAT) ☐ YES ☒ NO ☐ UNKNOWN	
DESCRIPTION AND BACKGROUND HISTORY INCLUDING CONSTRUCTION DATE(S), PHYSICAL DIMENSIONS, MATERIALS, MAJOR ALTERATIONS, IMPORTANT BUILDERS, ARCHITECTS, ENGINEERS, ETC. Bungalow. Wood frame set on concrete foundation; rectangle (32' x 25') with small gable-roofed addition on south facade; 5 bays wide; 1-story; clapboard siding with wood shingles in gable ends; wood-shingled gable roof; center entrance on north facade. Exterior features include 6/1 double-hung sash and multi-pane /1 fixed sash with plain surrounds; 1-story, slightly extended bay on west facade; plain cornice and frieze board; extended gable ends with exposed purlins; extended eaves with exposed rafter ends; pedimented porch on north facade with panelled boxed posts, plain wood railing and center front stairs; wood sill; latticework skirting. This house was built c.1916 by Otto VanDyk, a craftsman/builder from Oak Harbor for C.C. Cushen, a Coupeville businessman. The house was later owned by Lewis Matthews and purchased in 1941 by Michael Criscola. In 1968, a small addition was built on the south facade. No other exterior alterations have been made to the structure. The house was purchased by the Wienringa's in 1976 and converted to a Bed and Breakfast Inn. 1995: This building is a private residence today; one contributing building.		CURRENT USE Bed & Breakfast Inn		ORIGINAL USE Residence
PUBLIC ACCESSIBILITY ☒ YES, LIMITED ☐ NO	☐ YES, UNLIMITED ☐ UNKNOWN	EXISTING SURVEYS ☐ NR	☐ HABS ☐ NHL	☐ LCS ☐ NPS
LOCATED IN AN HISTORIC DISTRICT? ☒ YES ☐ NAME Cent. Whid. Isl. Hist. Dist.		CONDITION ☒ EXCELLENT ☐ GOOD		
		☐ FAIR ☐ DETERIORATED ☐ RUINS		
SIGNIFICANCE This property is significant under National Register criterion C, because it embodies the distinctive characteristics of architectural expressions and methods of construction that represent the period of community stabilization and economic slowdown (evidenced by simpler forms lacking ornamentation) and the theme of recreation and tourism (evidenced by structures built with natural materials set in scenic locations), from 1911 until 1945. It retains integrity of location, setting, materials, design, workmanship, feeling and association.				

PHOTOGRAPHS AND SKETCH MAP OF LOCATION



FROM N

FROM NW



NEGATIVE NO. L3-18; C4-16

HABS/HAER QUALITY

☐ YES

☒ NO

REFERENCES Wienringa, Joan. Personal Interview. 28 July 1983.

INVENTORIED BY Luxenberg/Castellano/Lein

AFFILIATION National Park Service

DATE Summer, 1983