



EBEY'S LANDING **PNRO**
NATIONAL INVENTORY
HISTORICAL RESERVE

National Park Service
Pacific Northwest Region
Cultural Resources Division
Westin Building, Room 1920
2001 Sixth Avenue
Seattle, Washington 98121

NAME(S) OF STRUCTURE Smith Net House		DATE OF CONSTRUCTION c. 1920's ADDITION(S)	SITE ID. NO.			
SITE ADDRESS (STREET & NO.) 1982 West Madrona Way			SCALE 1:24000	QUAD NAME Coupeville		
CITY/VICINITY Coupeville			UTM ZONE 10	EASTING 5206305340000		
COUNTY Island	STATE Washington		CROSS REFERENCE LA78			
OWNER/ADMIN ADDRESS Arlie Ostling P.O. Box 794 Coupeville, WA 98239		parcel #R13232-143-034	☒ CONTRIBUTING ☐ NON-CONTRIBUTING		DANGER OF DEMOLITION? (SPECIFY THREAT)	☐ YES ☒ NO ☐ UNKNOWN

DESCRIPTION AND BACKGROUND HISTORY INCLUDING CONSTRUCTION DATE(S), PHYSICAL DIMENSIONS, MATERIALS, MAJOR ALTERATIONS, IMPORTANT BUILDERS, ARCHITECTS, ENGINEERS, ETC.
Vernacular Beach Cottage. Wood frame set on post and block foundation; rectangle (8' x 15') with extensions on east, south facades; 3 bays wide; 1-story; board and batten siding; wood-shingled gable roof with slightly extended eaves sloping down to porch on north facade; off-center entrance with vertical wood panel door on north facade; interior end stovepipe on west facade. Exterior features include multi-pane sash; porch supported by plain posts with panelled rail; plain frieze board; shed-roofed extension on south facade.

This net house was built by one of the Smiths, possibly Frank, in the 1920's. It is located on Good Beach, a small area along Penn Cove that was once owned by the Smith family. The Smith's built a number of small cottages here that they rented out to visitors. A few of these remain, although not in their original locations. This place was moved back from the beach c.1940 to make room for a larger residence.


1995: One contributing building.

PUBLIC ACCESSIBILITY	☐ YES, LIMITED ☒ NO	☐ YES, UNLIMITED ☐ UNKNOWN	EXISTING SURVEYS	☐ NR ☐ HABS ☐ NHL	☐ LCS ☐ NPS	☐ STATE ☐ COUNTY	☐ LOCAL ☐ OTHER
LOCATED IN AN HISTORIC DISTRICT?	☒ YES ☐ NAME	☐ NO Cent. Whid. Isl. Hist. Dist.	CONDITION	☐ EXCELLENT ☐ GOOD	☒ FAIR ☐ DETERIORATED	☐ RUINS	


SIGNIFICANCE This property is significant under National Register criterion A, for its association with the important theme of recreation and tourism in the Reserve and represents a period of community development (1871-1910) followed by a period of economic stability (1911-1945). This property is also significant under National Register criterion C, because it embodies the distinctive characteristics of architectural expressions and methods of construction that represent the period of community stabilization and economic slowdown (evidenced by simpler forms lacking ornamentation) and the theme of recreation and tourism (evidenced by structures built with natural materials set in scenic locations), from 1911 until 1945. It retains integrity of location, setting, materials, design, workmanship, feeling and association.

260


PHOTOGRAPHS AND SKETCH MAP OF LOCATION



FROM NW



FROM NE



FROM NW



NEGATIVE NO. C15-5; L11-12

HABS/HAER QUALITY

☐ YES

☒ NO

REFERENCES Huffstetler, Lillian. Interview. 14 September 1983.

INVENTORIED BY Luxenberg/Castellano/Lein

AFFILIATION National Park Service

DATE Summer, 1983