



EBEY'S LANDING
NATIONAL
HISTORICAL RESERVE

PNRO
INVENTORY

National Park Service
Pacific Northwest Region
Cultural Resources Division

Westin Building, Room 1920
2001 Sixth Avenue
Seattle, Washington 98121

NAME(S) OF STRUCTURE Walton Aubert House - "Fiddlers Green" / Titus			DATE OF CONSTRUCTION 1907		SITE ID. NO. [] [] [] [] [] [] [] [] [] []	
SITE ADDRESS (STREET & NO.) 320 Rhodena Dr.			ADDITION(S)		SCALE 1:24000	
CITY/VICINITY Coupeville			COUNTY Island		QUAD NAME Coupeville	
STATE Washington			UTM ZONE 10		EASTING 527300	
OWNER/ADMIN ADDRESS Gilbert L. Titus 320 W. Rhodena Dr. Coupeville, WA. 93239			parcel #S8010-00-00006-0		NORTHING 05340430	
DESCRIPTION AND BACKGROUND HISTORY INCLUDING CONSTRUCTION DATE(S), PHYSICAL DIMENSIONS, MATERIALS, MAJOR ALTERATIONS, IMPORTANT BUILDERS, ARCHITECTS, ENGINEERS, ETC. Bungalow. Log frame set on concrete block foundation; square (24' x 24'); 4 bays wide; 1½-stories; horizontal log siding with wood shingles on gable ends; wood-shingled hip roof with extended eaves and cross gables on all facades; off-center entrance on south facade; center chimney. Exterior features include 1/1 double-hung sash; single pane fixed sash; raised deck connecting with wrap-around porch on north and east facades, supported by log posts; pedimented log portico on north facade; exposed rafter ends; plain fascia board. Notable landscape include 2 wood frame, gable-roofed outbuildings; siting on slope overlooking Penn Cove. "Fiddler's Green" was built by Walton L. Aubert, a successful Alaskan goldminer who settled in Coupeville. He was known for his collection of Chinese furniture and artifacts acquired at the Alaska-Yukon Exposition in Seattle. Aubert and his wife lived here for 30 years. The house passed through many hands until the Laten family sold the property to its current owners. 1995: Two contributing buildings.			☒ CONTRIBUTING ☐ NON-CONTRIBUTING		CROSS REFERENCE LA35	
CURRENT USE Residence			ORIGINAL USE Residence			
PUBLIC ACCESSIBILITY ☒ YES, LIMITED ☐ NO			EXISTING SURVEYS ☐ NR ☐ HABS ☐ NHL		☐ LCS ☐ NPS ☐ STATE ☐ COUNTY ☐ LOCAL ☐ OTHER	
LOCATED IN AN HISTORIC DISTRICT? ☒ YES ☐ NO NAME Cent. Whid. Isl. Hist. Dist.			CONDITION ☐ EXCELLENT ☒ GOOD ☐ FAIR ☐ DETERIORATED ☐ RUINS			

SIGNIFICANCE This property is significant under National Register criterion A, for its association with the important theme of recreation and tourism in the Reserve and represents a period of community development (1871-1910) followed by a period of economic stability (1911-1945). This property is also significant under National Register criterion C, because it embodies the distinctive characteristics of architectural expressions and methods of construction that represent the period of community development in the Reserve, from 1871 until 1910. It retains integrity of location, setting, materials, design, workmanship, feeling and association.


PHOTOGRAPHS AND SKETCH MAP OF LOCATION



FROM N



FROM NW



FROM SE



NEGATIVE NO. L10-20, 21, 23; L21-17, HABS/HAER QUALITY

☐ YES

☒ NO

REFERENCES 18; C24-2, 3

Pickard, Herb. Personal Interview. 19 September 1983.

Heydlauff, Donald. Personal Interview. September 1983.

INVENTORIED BY Luxenberg/Castellano/Lein

AFFILIATION National Park Service

DATE Summer, 1983