

EBEY'S LANDING **PNRO** NATIONAL INVENTORY HISTORICAL RESERVE

National Park Service
Pacific Northwest Region
Cultural Resources Division

Westin Building, Room 1920
2001 Sixth Avenue
Seattle, Washington 98121

NAME(S) OF STRUCTURE Old Anderson Place		DATE OF CONSTRUCTION 1902 ADDITION(S)	SITE ID. NO.	
SITE ADDRESS (STREET & NO.) 710 South Fort Casey Road			SCALE 1:24000	QUAD NAME Coupeville
CITY/VICINITY Coupeville			UTM ZONE 10	EASTING 5245805336665
COUNTY Island	STATE Washington	CROSS REFERENCE LA 54		
OWNER/ADMIN ADDRESS Frank Stowe parcel #R13110-085-1980 655 S. Engle Rd. Coupeville, WA 98239		☒ CONTRIBUTING ☐ NON-CONTRIBUTING	DANGER OF DEMOLITION? (SPECIFY THREAT) ☐ YES ☒ NO ☐ UNKNOWN	

DESCRIPTION AND BACKGROUND HISTORY INCLUDING CONSTRUCTION DATE(S), PHYSICAL DIMENSIONS, MATERIALS, MAJOR ALTERATIONS, IMPORTANT BUILDERS, ARCHITECTS, ENGINEERS, ETC.

Vernacular Farmhouse. Wood frame set on post and block

foundation; L-shape (20' x 30') with shed-roofed addition on west facade; 4 bays wide; 1½-stories; cedar shake siding with shiplap on upper gables; asphalt-shingled gable roof; center entrance on north facade; center chimney. Exterior features include 1/1, 2/2 double-hung sash; boxed cornice; plain frieze board; corner boards; shed-roofed porch with chamfered posts. Notable landscape features include 1 wood frame gambrel-roofed barn with multi-pane fixed sash and corner boards; 1 wood frame gable-roofed outbuilding.

This farmhouse was built for the Anderson's by carpenter John Jofferson. Jofferson also built the large barn on the property. The Andersons lived here until the late 1960's. The farmland around the place is rented by Edwin Sherman, and the house itself is a rental.

1995: New metal barn added; one contributing building; two contributing structures; one contributing structure.

CURRENT USE

Residence


ORIGINAL USE

Residence


PUBLIC ACCESSIBILITY	☐ YES, LIMITED ☒ NO	☐ YES, UNLIMITED ☐ UNKNOWN	EXISTING SURVEYS	☐ NR ☐ HABS ☐ NHL	☐ LCS ☐ NPS	☐ STATE ☐ COUNTY	☐ LOCAL ☐ OTHER
LOCATED IN AN HISTORIC DISTRICT?	☒ YES ☐ NAME Cent. Whid. Isl. Hist. Dist.	☐ NO	CONDITION	☐ EXCELLENT ☐ GOOD	☒ FAIR ☐ DETERIORATED	☐ RUINS	

SIGNIFICANCE This property is significant under National Register criterion A, for its association with agricultural land use patterns first established during the period of early settlement in the 1850s. It retains integrity of location, setting, materials, design, workmanship, feeling and association.

PHOTOGRAPHS AND SKETCH MAP OF LOCATION



FROM W



FROM SW

FROM SW



NEGATIVE NO. C23-30,31; L20-37

HABS/HAER QUALITY

☐ YES

☒ NO

REFERENCES Reuble, Lawrence. Telephone Interview. 20 September 1983.

INVENTORIED BY Luxenberg/Castellano/Lein

AFFILIATION National Park Service

DATE Summer, 1983