

EBEY'S LANDING
NATIONAL
HISTORICAL RESERVE


PNRO
INVENTORY

National Park Service
Pacific Northwest Region
Cultural Resources Division


Westin Building, Room 1920
2001 Sixth Avenue
Seattle, Washington 98121

NAME(S) OF STRUCTURE Clarence Wanamaker House		DATE OF CONSTRUCTION 1928	SITE ID. NO. [] [] [] [] [] [] [] [] [] []					
SITE ADDRESS (STREET & NO.) 932 Wanamaker Rd.		ADDITION(S)	SCALE 1:24000		QUAD NAME Coupeville			
CITY/VICINITY Coupeville			UTM ZONE 10		EASTING 526115		NORTHING 55335780	
COUNTY Island	STATE Washington		CROSS REFERENCE LA 61					
OWNER/ADMIN ADDRESS Gladys Sumner parcel #R13115-333-2810 932 Fort Casey Rd. Coupeville, WA 98239		☒ CONTRIBUTING ☐ NON-CONTRIBUTING	DANGER OF DEMOLITION? (SPECIFY THREAT) Deteriorated-For Sale		☐ YES ☐ NO ☒ UNKNOWN			
DESCRIPTION AND BACKGROUND HISTORY INCLUDING CONSTRUCTION DATE(S), PHYSICAL DIMENSIONS, MATERIALS, MAJOR ALTERATIONS, IMPORTANT BUILDERS, ARCHITECTS, ENGINEERS, ETC. Bungalow. Wood frame set on concrete foundation; rectangle (30'x26'); 3 bays wide; 1½-stories; clapboard siding with coursed wood shingles in upper gables; asphalt-shingled gable roof sloping down to porch on north facade; center entrance on north facade with single panelled door, cornice and stickwork screen door; corbelled exterior end chimney on west facade. Exterior features include 1/1 double-hung sash; tri-partite fixed sash; 2 and 4-pane sliding sash; gable-roofed dormer on north facade; shed-roofed dormer on south facade; porch supported by short, boxed columns with moulded trim; boxed clapboard rail; projecting gable-roofed portico with entrance on east facade; exposed rafter ends; fascia board; knee braces; latticework skirting. Notable landscape features include 1 wood frame clerestory-roofed barn; 1 wood frame gable-roofed barn; 4 wood frame outbuildings. Clarence I. Wanamaker, a merchant of Port Townsend, contracted Otto Van Dyk to build this bungalow. Few changes have occurred to the structure since it was built, and although in disrepair, it is a fine example of this local builder's work. In 1966, the house was sold to Mr. Bud Wagner, who in turn, sold to Mr. Scholz, c. 1976. <i>1995: Changes to dormers; new windows; new metal storage building added to property; one contributing building; five contributing structures; one non-contributing structure.</i>			CURRENT USE Vacant		ORIGINAL USE Residence			
PUBLIC ACCESSIBILITY ☒ YES, LIMITED ☐ NO		EXISTING SURVEYS ☐ NR ☐ HABS ☐ NHL ☐ LCS ☐ NPS ☐ STATE ☐ COUNTY ☐ LOCAL ☐ OTHER		LOCATED IN AN HISTORIC DISTRICT? ☒ YES ☐ NO ☐ NAME Cent. Whid. Isl. Hist. Dist.		CONDITION ☐ EXCELLENT ☐ GOOD ☒ FAIR ☐ DETERIORATED ☐ RUINS		
SIGNIFICANCE This property is significant under National Register criterion A, for its association with agricultural land use patterns first established during the period of early settlement in the 1850s. This property is also significant under National Register criterion C, because it embodies the distinctive characteristics of architectural expressions and methods of construction that represent the period of community stabilization and economic slowdown (evidenced by simpler forms lacking ornamentation) and the theme of recreation and tourism (evidenced by structures built with natural materials set in scenic locations), from 1911 until 1945. It retains integrity of location, setting, materials, design, workmanship, feeling and association.								

PHOTOGRAPHS AND SKETCH MAP OF LOCATION



FROM NW



FROM SE



FROM NW



FROM SE



NEGATIVE NO. C1-19-21; C15-11;
L11-16,17; L1-10,12 HABS/HAER QUALITY ☐ YES ☒ NO

REFERENCES Wanamaker, Floyd. Telephone Interview. 16 September 1983.
Cook. Penn's Cove. p. 26,27.

INVENTORIED BY
Luxenberg/Castellano/Lein

AFFILIATION
National Park Service

DATE
Summer, 1983