

July, 1929

Railway Projects,

Algoma Eastern Ry. is building an extension to its coal dock and storage facilities at Turner, Ont., opposite Little Current. It will have a length of 40 ft. of timber crib, rock filled, with a concrete top above water level, carrying the front portal rail, and the back portal rail will be carried on concrete wall supported by the rock fill in rear of the dock. The rear or shear leg rail will be carried on a concrete wall on the limestone, which lies close to the surface. Part of the storage bottom is bare limestone rock and part on rock fill which will be paved with concrete. The Randolph Macdonald Co. has the contract for the dock structure. The timber cribs are placed and filled and the balance of the work is to be complete by June 30. This extension will give the Algoma Eastern Ry. much needed facilities for increasing coal business in the Sudbury district. The cost is expected to be in excess of \$150,000. Canadian Railway and Marine World is indebted to Wm. Seath Wilson, B.Sc., Sault Ste. Marie, Ont., for the foregoing information.

Central Vermont Ry.—Thirty miles of

July 1929