

TOWN OF DUNDEE

RFP# 19-02 – Road Resurfacing and Milling Services

QUESTIONS FROM VENDORS

1. Would the Town consider changing the calendar days from 20 to 50 days? 50 calendar days at a 5-day workweek would provide approximately 10 weeks of work. The road widening aspect will be very tedious to construct and keeping in mind the asphalt has a cure time of 20 days prior to application of Thermoplastic.
 - a. **ANSWER: Yes, 50 days (including thermoplastic striping installation) would be acceptable.**

2. In regards to Item #46: Tests and Inspections, will the contractor need to provide tests and inspections, subgrade, base for tonnage under 2,000 tons. FDOT specs currently exempt less than 2,000 tons from testing. Please confirm testing required.
 - a. **ANSWER: Compaction testing of subgrade and base is required for all widening.**

3. Are as built drawings required for the widening projects?
 - a. **ANSWER: No, as-builts are not required.**

4. In regards to GENERAL CONDITIONS Item #4 – Manufactures...”Alternate bids will not be considered unless alternate bids are specifically required by the technical specifications.” Does this mean that a crushed concrete base will not be acceptable as an alternate for limerock base?
 - a. **ANSWER: Alternate bid substituting crushed concrete for limerock will be acceptable.**

5. Please Confirm the Following Bid Quantity Calculations:
 - a. **ANSWER: Dawn Drive: Quantity should be “1”, unit should be “EA”. Ridgewood Avenue and Race Road need to be submitted for bid quantities as provided on the bid document. Bidders are expected to verify their own calculations.**

6. Is the Contract responsible for replacing survey markers?
 - a. **ANSWER: Yes, per State Law the markers must be replaced.**

7. Does the contractor need a line item for Density Testing/Asphalt Testing in the bid?
 - a. **ANSWER: This should be included in unit costs.**

8. All the roads have a Mill Line Item and Pave, but the Pave Line Items on Ridgewood Ave and Race Road do not reflect the same SqYds as the Mill.
 - a. **ANSWER: Paving quantity is more than milling due to road widening**

9. With regards to Mill and Pave thickness. On the Original Bid it was 1.5", but on the new bid sheet it states 1" on Ridgewood Ave. and Dawn Drive, but not on Race Road. Can we get a clarification on thickness for the Mill and Pave?
- a. ANSWER: The new bid documents inadvertently did not edit Section 1.01A regarding Asphalt. Contractors should disregard that number. Paving is to be 1" on Dawn Drive and 1.5" on Ridgewood Ave. and Race Road.**
10. Should contractors supply a line item to re-install the survey points?
- a. ANSWER: This should be included with the MOT cost.**
11. With these clarifications will the bid date be extended?
- a. ANSWER: No. The bids shall remain due on Monday, February 11th @ 4:30PM.**