

# WM408i installation checklist

## Installation estimate

The estimated on-site, hands-on installation time by 2 trained installers is as follows:

- Nureva Wall WM408i **single** configuration – 1.5 hours
- Nureva Wall WM408i **dual** configuration – 2.5 hours

This estimate does not include project management, preparation time at the warehouse, transportation time, unloading time, onsite material handling, unpackaging time, packaging disposal or resolution of any wall preparation issues, among other things.

## Installation requirements

This checklist outlines preparations and recommendations for ensuring an efficient and successful installation. Planning and coordination between the reseller, installer and customer are critical.

### Training

Installer has received Nureva's installer training and Installation best practices doc	<input type="checkbox"/>
Installer has reviewed the <a href="#">system installation video</a>	<input type="checkbox"/>
Installer has participated in a hands-on installation, at a location other than the customer installation site, preferably under the guidance of Nureva support and services	<input type="checkbox"/>

### Site assessment

Installer Manager has made a site assessment, including...

Overall install footprint and ceiling height (e.g. is there sufficient space to install the requested configuration)	<input type="checkbox"/>
Identification of obstructions, including <ul style="list-style-type: none"> <li>• Heaters, building bulkheads, ceiling sprinkler housings, ceiling panel lighting, ceiling electrical drops, HVAC grills, breakout electrical panels, outlet rails, chair rails, working ledges, wall jogs, paneled treatment, changing wall surfaces (e.g. plywood to drywall, etc.), immovable furniture, legacy A/V (brackets, wiring, etc.), building plumbing, light switches, thermostats, etc.</li> <li>• Reasonable wall type (non-compatible surfaces include architectural brick, glass, free-standing partition wall)</li> <li>• Restricted designations (e.g. controlled substances like asbestos, etc.)</li> </ul>	<input type="checkbox"/>

## Connection diagram

Installer manager has reviewed the connection diagram from the reseller and...

Has assessed the location for the system	<input type="checkbox"/>
Has assessed location of the PC	<input type="checkbox"/>
Has followed the site assessment and has proper tools	<input type="checkbox"/>
Has prepared the appropriate wall-mounting hardware for the wall-type	<input type="checkbox"/>
Has identified the necessary cable management and length (e.g. HDMI, USB extenders per Nureva's recommendation as given on the online support site, etc.)	<input type="checkbox"/>
Has predetermined the location and organization of the power sources for <ul style="list-style-type: none"> <li>• The touch panel</li> <li>• The projector</li> <li>• Other considerations (speakers, computer, etc.)</li> </ul>	<input type="checkbox"/>
Installer is familiar with the <a href="#">supporting documentation</a> , including <ul style="list-style-type: none"> <li>• Outline drawing</li> <li>• Quick start guide</li> <li>• Mounting template</li> <li>• Installation drawing</li> <li>• Installation guide (online)</li> </ul>	<input type="checkbox"/>
Installer manager has pre-loaded Windows 10 and performed all current updates prior to arriving at customer site	<input type="checkbox"/>
Installer manager has identified 2-3 local hardware or A/V stores as contingency (where applicable)	<input type="checkbox"/>
Installer has the contact information for the Nureva support team	<input type="checkbox"/>

## Additional considerations

Customer has acknowledged receipt of the product (if shipped directly)	<input type="checkbox"/>
Customer has identified any issues moving from the loading dock to the installation location (elevator restrictions, stairwell issues, access timing to restrictive areas, etc.)	<input type="checkbox"/>
Customer has identified an onsite resource/contact for the entire restricted installation period	<input type="checkbox"/>
Customer has provided access to guest Wi-Fi	<input type="checkbox"/>
Customer has ensured local admin privileges (for the PC to be used for the system). Alternatively, make sure an IS designate is available to log you in.	<input type="checkbox"/>
Customer has booked the meeting space for the entire installation period (e.g. a full day)	<input type="checkbox"/>
Customer has not arranged for any executive demonstrations on day of installation	<input type="checkbox"/>