GENERAL NOTES

A. REFER TO IMPROVEMENT DETAILS FOR NOTE REFERENCES.

B. REFER TO TOWN STANDARDS FOR DEVELOPMENT STANDARDS.

○ PLAN NOTES

1. ASPHALT PAVEMENT.
2. CONCRETE CURB AND WALK.
3. ACCESSIBLE RAMP.
4. 4" WIDE PAINTED PARKING STRIPE.
5. CONCRETE WALK.
6. STRAIGHT CONCRETE CURB.
7. ACCESSIBLE PARKING SPACE.
8. CONCRETE STOOP.
9. WASTE CONTAINER PAD AND ENCLOSURE.
10. CONCRETE INLET COLLAR .
11. STOP SIGN.
12. CURB TAPER.
13. TRANSFORMER SUPPORT PAD.
14. PAINTED STOP BAR.(PROVIDE THERMOPLASTIC STRIPING.)
15. PAINTED DIRECTIONAL ARROWS AND STRIPING.(PROVIDE THERMOPLASTIC STRIPING.)
16. (3) EXTENDED SQUARE 'U' RACKS AS SOLD BY BELSON OUTDOORS. MODEL UX200-LB-IG-G. IN-GROUND MOUNT. COLOR BLACK.
17. MONUMENT SIGN. REFER TO ARCHITECTURAL PLAN FOR MORE INFORMATION.
18. FLAGPOLES.
19. DESIGNATED SMOKING AREA COVERED STRUCTURE. REFER TO ARCHITECTURAL FOR MORE INFORMATION ON STRUCTURES
20. (1) KENSINGTON COLLECTION PARK BENCH AS SOLD BY BELSON OUTDOORS. MODEL 43 SM-S6 IN BLACK COLOR.
21. CONCRETE PAVEMENT.

SITE DESIGN DATA	
SITE AREA	1.3 acres
SLEEP INN	8,738 SF
PARKING	57 spaces
HC PARKING	3 spaces
TOTAL PARKING	60 spaces

SEE SHEET C001 FOR GENERAL NOTES.

0 30 60 FEET
SCALE:1"=30'

JPS CONSULTING ENGINEERS, LLC
9365 Counselors Row, Suite 116
Indianapolis, IN 46240
ph 317.617.4270
www.jpsconsultingengineers.com

SLEEP INN
6030 GATEWAY DRIVE
PLAINFIELD, IN

PERMIT SET

NUMBER	DATE	DESCRIPTION

SITE IMPROVEMENT PLAN

SCALE:	1" = 30'
DATE:	09 MAY 2025
PROJECT #:	24JPSC91
DRAWN:	CLM
COORD:	TPJ
APPROVED:	ADS

C500

JPS Consulting Engineers - K:\Civil Projects\2024\24JPSC91 Sleep Inn - Plainfield\Drawing\C500.dwg August 11, 2025 - 10:48 AM TJones