



PLEASE READ!

Important Addendum to the Installation Guide

Check for Proper Grounding

Perform the following steps to ensure that the TV-Hub is properly grounded.

1. Ensure that all receivers are connected in their final wiring configurations and powered on.
2. Connect power to the TV-Hub, but do **not** power it on.
3. Using a multimeter, measure the AC and DC voltages between the ground stud on the rear of the TV-Hub and ship's ground. The measured voltage should be less than 2 VAC and 2 VDC. **A higher voltage indicates a dangerous floating ground condition.**
4. Repeat step 3 with the TV-Hub powered on, looking for the same measured result.



WARNING

If you measure 2 volts or greater between the ground stud on the rear of the TV-Hub and ship's ground, notify the ship's electrician or authorized vessel representative immediately. This is a dangerous condition. Do not touch the TV-Hub rear panel or connect anything to it until the problem is fixed.