

Faith Home Sunshine Project: Phase I

SOLAR EQUIPMENT:

System one on School, System two on Workshop

2 TURNKEY Solar PV Systems (13.7kW each)

(112) Solar PV Modules SUNTECH 245W

(4) Grid-Tied Inverters 6.6kW SOLECTRIA

On roof mounting Structure and related hardware SFLEX

Electrical Installation Materials

Installation labor and Local Transportation

Bi-Directional Electrical Meter

Additional SOLUZ Services

Preliminary Site Evaluation and Plan

Educational Presentations (4 presentations)

Monitoring and Service Contract (8 quarterly visits)

PV System Monitoring (Internet Connection and web monitoring)