ComCents Consultants

RR#1 S-18 C-57
Celista, BC V0E 1L0
(250) 955-6400 fax (250) 955-6408

Invoice No: 797
Date: 9-Sep-07

INVOICE

Name: Matt Zorrio
Address: 405 West Westeria Blvd.
Stoney Plain Alberta T T7Z 2X1

Telephone: 780-968-8191
Cell:
Fax:
E-mail:

Site Location if Different: lot 41 Klondike Trail

Description of Work: perc test and design

Total Parts:	$0.00
Total Labour:	$0.00
Total Cost:	$1,300.00
GST	$78.00
TOTAL INVOICE	$1,378.00

due upon receipt

Sept. 7/07

ComCents Consultants Ltd.
RR # 1 Site 18 Comp 57
Celista B.C. V0E 1L0

Matt Zorrio
405 West Westeria Bulvd.
Stoney Plain Alberta T7Z 2X1

Subject Lot 41 Klondike Trail, Anglemont

This is to advise that we have completed the site assessment on the above mentioned lot.

We conducted 2 permeameter tests. Both were done on the lower portion of the lot. Permeameter test #! Was in the south east portion and had a 20mm per minute stable rate of fall. Permeameter test #2 w2as in the south west portion and had a 60mm per minute stable rate of fall for a combined average of 20mm per minute. Using a soils factor of 47.2, the field saturated hydraulic conductivity would average 944 mm/day combined with a loading rate of .6.

A 3 bedroom 1,800 square foot residence would require a field dispersal area of 500 square foot or 166 feet of 3 foot trenches.

At today's costs a system would cost approx. $8,500.00 to $9,000.00.

If you have any questions please call 250-955-6400 or email lancegeary@telus.net

Sincerely,

Lance Geary ROWP