

J's PUMPS & PLUMBING

4050-40th St. NW, Salmon Arm, BC V1E 3A7 (250) 832-7911 Fax (250) 832-7699

Mr. & Mrs. Steve Andersen

Apr. 23/94

Thank you for the opportunity to quote your water system at Lot #2 Kault Hill Road.

We will supply & install the following:

- (1) Gould 3/4 horsepower submersible pump 5 gpm series pump set at 280 feet.
- (2) 1" Sch 80 threaded pipe c/w brass couplings down well for pump discharge pipe.
- (3) 12-4 pump wire from pump to top of well plus 2 feet.
- (4) Model 140 air captivated pressure tank which will give a draw down of 12 us gallons at 40/60 on off pressure setting.
- (5) Tank tee, pressure switch, gauge and mixe. piping at pressure tank c/w check valve. Our plumbing of water system stops at 3/4 inch shut off valve at pressure tank and house plumber takes over there.
- (6) Clearway pitless adapter c/w check valve.
- (7) Pumptec electronic low water control which shuts pump down should it run out of water and automatically resets when well has recovered a predetermined time.
- (8) 4" conduit c/w sweep fittings which starts 3 feet from well and goes into mechanical room of shop for a maximum length of 60 feet c/w marker warning tape.
- (9) Crane truck to set pump down well and labour t to do the above job.

We have not included the following:

- (1) Electrical wire from well head to mechanical room or wiring of controls. This to be done by house electrician "estimated" cost of this work \$400.00.
- (2) Any digging, backfilling of trench or bedding sand. "estimated" cost of this work is \$450.00.
- (3) Any work to do with water treatment. I would set aside a minimum of \$2000.00 for this work.

The price for our work as described in items 1-9 inclusive for this quality job is \$4,260.00 plus GST or \$4,558.20.

If any questions, please feel free to call.

Yours truly,


Jerry E. Jones

Steve Anderson Well MCHAIG DRILLING LTD.

7938 CARRIE ROAD - SALMON ARM, B.C. V1E 4M3 - PHONE 832-3384 - FAX 832-0503

Date Dec 8-9 1992

Telephone 832-5446

Owner's Name Don HINDEN

Address 1281-11 AVE C.E. SALMON ARM B.C.

Location Lot #2 KALEE Hill Rd Postal Code _____

Formation & Remarks

0-43 OVERBURDEN

43-166 - BEDROCK

1.5 GPM @ 26.1 ft

1.0 GPM @ 12.1 ft

Total Depth 166 ft

Air Lift Test (approx) 7 GPM
* Estimate only. For accuracy a pump test is required.

Recommend Pump 5 GPM Series Pump

Static Level _____ Recommended Pump Setting @ 12.1 to 166

Well Construction

Casing Size 6 5/8 Type 10R steel

Set from 12 to 43

Screen Size 4" I.D. Type P.V.C.

Set from 26 to 166

COSTS

Drilling & Casing 43 ft @ 26.12 ft 1170.00

Drilling - Bedrock 120 ft @ 18.00 ft 2160.00

Additional Remarks
and/or Costs

Drive Shoe 15.00

Well Cap 25.00

Screen _____

Screen Bottom _____

X Packer & Riser _____

Develop Well _____

Equipment Travel _____

7-36 P.V.C. LINER ASS. 140.00 @ 5.00 700.00

Well Cost: 4140.00

GST #R 103 594 495 289.00

TOTAL 4429.00

TERMS: Payment due upon receipt of this invoice

CUSTOMER
SIGNATURE

MCHAIG
DRILLING

for Rob. Wampler

Printer Print 1992 LM