### **INVITATION FOR BID**

### CITY OF NEW BEDFORD, MASSACHUSETTS DEPARTMENT OF PUBLIC INFRASTRUCTURE

Fort Taber Pier - Stone Masonry Rehabilitation

### **BID #23434039**



Bids Due: Tuesday, November 22, 2022 at 3:00 pm

Jonathan F. Mitchell Mayor

Department of Public Infrastructure 1105 Shawmut Ave New Bedford, MA 02746

#### **TABLE OF CONTENTS**

SECTION	PDF PAGE#
ADVERTISEMENT – INVITATION TO BID	3
INSTRUCTIONS TO BIDDERS	5
FORMS	
BID FORM*	21
CERTIFICATE OF NON-COLLUSION & TAX COMPLIANCE*	27
VOTE OF CORPORATION <b>OR</b> LLC CERTIFICATE*	28
OSHA CERTIFICATION*	30
CONTRACTOR CERTIFICATION*	31
W-9*	32
CORPORATE TAX COMPLIANCE*	34
INDIVIDUAL TAX COMPLIANCE*	35
INELIGIBLE CONTRACTORS*	36
PERFORMANCE BOND	38
PAYMENT BOND	41
GENERAL CONDITIONS	43
SUPPLEMENTARY CONDITIONS	92
EQUAL EMPLOYMENT OPPORTUNITY PACKAGE*	116
DEP WPA FORM 5	158
SPECIAL CONDITIONS	171
SPECIFICATIONS	174
MA PREVAILING WAGE RATES	236

<sup>\*</sup> SECTIONS MARKED WITH AN ASTERISK (\*) ARE REQUIRED TO BE COMPLETED AND RETURNED WITH BIDS



#### CITY OF NEW BEDFORD, MASSACHUSETTS Invitation for Bid #23434039

### FORT TABER PIER – STONE MASONRY REHABILITATION ADVERTISEMENT

The City of New Bedford, Purchasing Department, in conjunction with the Department of Public Infrastructure, is soliciting sealed bids for the construction of the Fort Taber Pier – Stone Masonry Rehabilitation Project. The Project consists of rehabilitating portions of the Fort Taber pier that have been subject to settlement and loss of granite support and faces stones. The pier will be repaired through utilizing the existing granite stones that have been dislodged to restore the pier. Stone fill will be used between the stones and will be pressure filled with grout to secure the stones in place. The bid process and award of this Contract will be under the provisions of M.G.L. Chapter 30, Section 39M. The estimated budget for this project is \$100,000.00 and the estimated substantial completion date is the end of April 2023.

Contract documents may be obtained and/or examined electronically by visiting the City's website <a href="https://www.newbedford-ma.gov/purchasing/">https://www.newbedford-ma.gov/purchasing/</a> on or after Thursday, November 03, 2022.

A pre-bid site visit will be conducted for the benefit of all potential bidders on **Tuesday**, **November 8, 2022 at 1:00 p.m.** at Fort Taber Pier inside of Fort Rodman, 1000 S Rodney French Blvd, New Bedford, MA 02744.

Sealed bids will be received by the Purchasing Department until **Tuesday, November 22, 2022 at 3:00 p.m. E.S.T.** All bids must be submitted via mail or in-person delivery to the Purchasing Department, 133 William Street, Room 208, New Bedford, MA 02740 during business hours (8:00 a.m. – 4:00 p.m.) until the above time and date. Immediately following the deadline for bids, all bids received within the time specified will be publicly opened and read aloud. Bidders can participate in the bid opening at Purchasing's office and the opening will also be live streamed via Zoom audio. Instructions for participating are posted on the City's website under the Purchasing page. It is strongly recommended to submit bids via mail delivery services. Bidders must email <a href="mailto:purchasing@newbedford-ma.gov">purchasing@newbedford-ma.gov</a> to confirm they have submitted a bid. The bid **must** clearly state on the exterior that it is for IFB # 23434039 Fort Taber Pier – Stone Masonry Rehabilitation Project, attention to the Purchasing Department. Bids received after the above time and date will be rejected and returned unopened. Emailed and/or faxed bids will not be accepted.

If at the time of scheduled bid opening, City Hall is closed due to uncontrolled events such as fire, ice, pandemic, or building evacuation, the bid opening will be postponed until the same time on the next normal business day. Bids will be accepted until that date and time.

Attention is called to the fact that supplies furnished as part of this Contract are exempt from the Sales and Use Tax. All bids submitted should take this factor into consideration and be calculated accordingly. The contract will be awarded within sixty (60) calendar days after the bid opening. The time for award may be extended by mutual agreement between the City and the awarded bidder. No Bidder may withdraw his/her bid for a period of sixty (60) calendar days, after the actual date of the opening thereof. Bids <u>must</u> include <u>ALL DOCUMENTS</u> required by the Invitation for Bid. The Awarding Authority reserves the right to waive any informality, reject any

or all bids, or accept other than the lowest priced bid if the City determines that it is in the best interests of the City.

Each bid shall be accompanied by a bid deposit that is five percent (5%) of the bid amount. Bid deposits may be in the form of Certified Check, Certificate of Deposit, or Bid Bond made payable to the City of New Bedford, Massachusetts. The Awarded Bidder must furnish a 100 percent (100%) Performance Bond and a 100 percent (100%) Payment Bond with a surety company acceptable to the City.

Minimum Wage Rates as determined by the Commissioner of the Department of Workforce Development under the provision of the Massachusetts General Laws, Chapter 149, Section 26 to 27H, as amended, apply to this project. It is the responsibility of the Contractor, before bid opening, to request if necessary, any additional information on Minimum Wage Rate for those tradespeople who may be employed for the proposed work under this contract.

Disadvantaged Business Enterprise (DBE) goals of the City of New Bedford are applicable to the total dollars paid to the construction contract. The City of New Bedford goals for this project are a minimum of 11.00 percent D/MBE participation and 5.00 percent D/WBE participation by certified DBEs. The City of New Bedford also has minimum goals for employment (workforce utilization) of 18.00% minority and 6.90% female participation. The employment percentages shall apply to the contractor and all subcontractors, regardless of tier, for all on-site work. Bidders shall submit all required completed City of New Bedford forms with their bid. Failure to comply with the requirements of this paragraph may be deemed to render a proposal non-responsive. No waiver of any provision of this section will be granted unless approved by the City of New Bedford, Massachusetts.

United States Occupational Safety and Health Administration (OSHA) Construction Training is required for this Contract. As of July 1, 2006, under M.G.L. Chapter 30, Section 39S, any person submitting a bid for, or signing a contract to work on, the construction, reconstruction, alteration, remodeling or repair of any public work by the Commonwealth of Massachusetts and/or City of New Bedford that is estimated by the awarding authority to cost more than \$10,000.00 shall certify on the Bid and Agreement, under penalty of perjury, that all employees to be employed on the Work shall have successfully completed a course in construction safety and health that is approved by OSHA and at least ten hours in duration.

The City encourages D/MBEs and D/WBEs to submit Bids.

Awarding Authority
City of New Bedford
Purchasing Department
Molly Gilfeather, Director of Purchasing

# CITY OF NEW BEDFORD DEPARTMENT OF PUBLIC INFRASTRUCTURE INVITATION FOR BIDS (IFB) FORT TABER PIER – STONE MASONRY REHABILITATION

#### INSTRUCTION TO BIDDERS

#### **ARTICLE 1. QUANTITY OF WORK**

- 1.1 Quantities in the Bid Form are approximate only, being given as a basis for comparison of bids. The City of New Bedford (Owner) does not expressly or by implication agree that the actual amount of Work will correspond therewith, but reserves the right to increase or decrease the amount of any class or portion of the Work, as may be deemed necessary or expedient by the Owner. The Contractor shall only be reimbursed on a unit price basis for the quantities ultimately provided to the Owner; Contractor shall not be entitled to any profit associated with unused quantities nor shall there be any modification of unit prices if lesser or more quantities are utilized.
- 1.2 The Contract to be awarded hereunder is non-exclusive, and the Owner specifically reserves the right to seek Bids for and/or award contracts, agreements, work orders, and other authorizations, however characterized, to others to perform work of the same type and category as described in this Request for Bids and resulting in contract in whatever quantities it deems to be in the best interest of the Owner.
- 1.3 Bidders shall submit their Bid upon the express condition that an increase or decrease in the quantity for any item shall not be regarded as cause for an increase or decrease in the Contract unit prices, nor in the time allowed for the completion of the Work, except as provided in the Contract, which shall become part of every Bid received.

#### **ARTICLE 2. PRICE ADJUSTMENTS**

Omitted.

#### **ARTICLE 3. COPIES OF CONTRACT DOCUMENTS**

3.1 Complete sets of Contract Documents shall be used in preparing Bids; Owner does not assume any responsibility for errors or misinterpretations resulting from the use of incomplete sets of Contract Documents. The following constitutes the Contract Documents:

Invitation to Bid Instruction to Bidders Bid Form

Agreement

Performance Bond – EJCDC C-610, 2013 Edition

Payment Bond – EJCDC C-615, 2013 Edition

Standard General Conditions to the Construction Contract – EJCDC C-700, 2007 Edition

Supplementary Conditions (Part I and Part II)

Specifications (as listed in Table of Contents)

Drawings and Figures

All Contract Addenda

Any modifications including Change Orders, duly delivered after execution of Agreement

Certification of Insurance with the coverage described in the General Conditions.

3.2 Owner in making copies of Contract Documents available do so only for the purpose of obtaining Bids on the Work and do not confer a license or grant for any other use.

#### **ARTICLE 4. LOCATION OF WORK**

4.1 The work herein specified is located on the Fort Taber Pier located in the City of New Bedford. Work will not take place on roadways under the jurisdiction of the MassDOT.

#### **ARTICLE 5. EXAMINATION OF CONTRACT DOCUMENTS AND SITE**

- 5.1 Before submitting a Bid, each prospective bidder shall do the following at his/her own expense:
  - 1. Examine the Contract Documents thoroughly.
  - 2. Visit the site to become familiar with observable conditions that may, in any manner, affect cost, progress, or performance of work.
  - 3. Be familiar with Federal, State, and local laws, ordinances, rules and regulations that may, in any manner affect cost, progress, or performance of the work.
  - 4. Study and correlate information thus determined with the Contract Documents.
  - 5. By submitting a bid, the Bidder represents that every requirement of this Article and all other Articles as applicable, have been complied with and that the Contract Documents are sufficient in scope and detail to indicate and convey understanding of all terms and conditions for performance of the work.
- 5.2 In addition to visiting the site for purposes as specified in Article 4, the Bidders shall, at his or her own expense, visit the site or complete any needed test(s) to ascertain pertinent local conditions readily determined by inspection and inquiry, such as the location, accessibility, traffic conditions and general character of the site, labor conditions, the character and extent of existing work within or adjacent thereto, and any other work being performed.
- 5.3 The Owner does not guarantee or represent that existing construction or conditions conform to the Drawings and/or Photos. The Bidder shall visit the site and satisfy him/herself as to existing conditions. All necessary information shall be verified in the field before fabrication of new products/materials. No claim for extra cost or time extension will be granted by the Owner because of the Bidder's unfamiliarity with site conditions.
- 5.4 On request, Owner will provide each Bidder access to the site to conduct such investigations and tests as each Bidder deems necessary for the submission of a Bid.

#### **ARTICLE 6. QUALIFICATIONS OF BIDDERS**

- 6.1 Bidders may be investigated by Owner to determine if they are qualified to perform the Work. All Bidders shall be prepared to submit within five days of Owner's request, written evidence of such information and data necessary to make this determination.
- 6.2 The investigation of a Bidder will seek to determine whether the organization is adequate in size, is authorized to do business in the jurisdiction where the project is located, has had previous experience and whether available equipment and financial resources are adequate to assure Owner that the Work will be completed in accordance with the terms of the Agreement. The amount of other work to which the Bidder is committed may also be considered.

- 6.3 In evaluating Bids, Owner will consider the qualifications of only those Bidders whose Bids are in compliance with the prescribed requirements.
- 6.4 Owner reserves the right to reject any Bid if the evidence submitted by, or the investigation of, such Bidder fails to satisfy Owner that such Bidder is properly qualified to carry out the obligations of the Contract Documents and to complete the Work contemplated therein.
- 6.5 Omitted.

#### ARTICLE 7. PRE-BID CONFERENCE

7.1 A pre-bid conference to be held on-site on Tuesday, November 8, 2022 at 1:00 pm. Refer to Invitation to Bidders section for additional information.

#### **ARTICLE 8. INTERPRETATIONS**

- 8.1 All questions about the meaning or intent of the Contract Documents shall be received via email to purchasing@newbedford-ma.gov and shawn.syde@newbedford-ma.gov by Friday, November 11, 2022 at 4 pm.
- 8.2 Written clarifications or interpretations will be issued by Addenda by Wednesday, November 16, 2022. Only questions answered by formal written Addenda will be binding. Oral and other clarifications or interpretations will be without legal effect. Addenda will be emailed only to those people that are on the certified plan holders list at the Purchasing Department. Addenda will also be posted to the Purchasing Department's website.
- 8.3 Bidders are responsible for determining that they have received all Addenda issued. Bidders shall ensure that they are on the list of plan holders by contacting the Purchasing Department. It is the responsibility of the vendor/contractor to check the Purchasing Department website (https://www.newbedford-ma.gov/purchasing/request-proposals-rfps-invitation-bids-ifbs/) for addenda. The City of New Bedford accepts no liability to provide accommodation to those who submit a response based upon information obtained from any source other than this website. Bidders may not alter (manually or electronically) the bid language or bid documents. Unauthorized modifications to the bid, specifications, terms or conditions are prohibited and any associated submittal may be rejected.
- 8.4 All addenda so issued will become part of the Contract Documents.
- 8.5 Obvious discrepancies in the Contract Documents that are not addressed by a Bidder in accordance with the above procedure will be construed against the successful Bidder should a dispute arise.

#### **ARTICLE 9. PREPARATION OF BIDS**

9.1 The Bidder shall submit his/her bid on the Bid Form. **The Bidder shall submit one original and one copy of the Bid.** The Bid Form, the Bid Security/Guaranty, and all other forms provided and other documents, as may be required, shall be executed and submitted by the Bidder with the Bid Form and Bid Guaranty/Security. The Bid Form, the Bid Guaranty/Security, forms, certifications, and documents constitute the Bid.

- 9.2 All blank spaces for Bid prices in the Bid Form shall be filled in with a unit price or lump sum, as applicable to the item.
- 9.3 All words and figures shall be in ink, written legibly or typed. Bid prices of each item in the Bid Form shall be stated in words and numbers.
- 9.4 In case of conflict between written words and numbers, the written words shall govern.
- 9.5 If unit prices are required on the Bid Form, discrepancies between unit prices and their respective total amounts will be resolved in favor of the unit prices. Discrepancies between the indicated sum of any column of figures and the correct sum thereof will be resolved in favor of the correct sum.
- 9.6 If erasures or changes appear in the Bid Form and the Schedule of Bid Prices, each erasure or change shall be initialed and dated in ink by the individual signing the Bid Form.
- 9.7 The price for any item, bid and contracted for, unless otherwise noted or specified, shall include full compensation for all products/materials, equipment, tools, labor, testing, and incidental work necessary to complete the item to the satisfaction of the Owner.
- 9.8 Minimum Wage Rates as determined by the Commissioner of Department of Workforce Development, Division of Occupational Safety, under the provision of the Massachusetts General Laws, Chapter 149, Section 26 to 27H, as amended, apply to this project. It is the responsibility of the Contractor, before bid opening, to request if necessary, any additional information on Minimum Wage Rates for those tradespeople who may be employed for the proposed work under this Contract.
- 9.9 It is the Contractor's responsibility to ensure that he/she has the most up-to-date wage rates.
- 9.10 Bidders shall submit all required completed Owner forms with their bid. Failure to comply with the requirements of this paragraph may be deemed to render a proposal non-responsive. No waiver of any provision of this section will be granted unless approved by the Owner.
- 9.11 The attention of the Bidders is directed to the Massachusetts Sales Tax, Chapter 64H, Section 6 and the Massachusetts Use Tax, Chapter 64I, Section 7, which states that these taxes are not applicable to the sales of construction materials and supplies incorporated, employed, or expended in construction projects of the Owner. This exemption is also applicable to rental charges for construction vehicles, equipment, and machinery rented, specifically for the use on the site of the Owner's construction projects. Bidders are directed to exclude any allowances for Sales or Use Tax from their Bid Form, and said tax would relate to the foregoing specified categories.
- 9.11.1 The materials and supplies to be used in the work will be subject to the requirement of Paragraph 6.1 of the Conditions of the Contract as amended by the Supplementary Conditions.
- 9.12 The Schedule of Bid Prices, included in the Bid Form will be used for indicating the Bid Price information specified above.
- 9.13 All bid prices submitted in response to this IFB must remain in effect for thirty (30) days following the Bid opening.
- 9.14 All Bidders must furnish a certified Non-Collusion statement.

- 9.15 Bidder shall acknowledge receipt of any and all Addenda in writing in the Bid Form by writing the number of Addenda in the Bid Form.
- 9.16 The following list has been prepared for the convenience of the Bidder. Bidder is responsible for verifying and determining the required forms to be submitted with his/her bid. Bidders shall complete and submit the following attachments with their Bids:
  - Form for General Bids
  - City of New Bedford Non-Collusion and Tax Compliance Form
  - City of New Bedford Vote of Corporation
  - OSHA Certification Requirement
  - Contractor Certification
  - Request for Taxpayer Identification Number and Certification (Form W-9)
  - Commonwealth of Massachusetts Corporate Certificate of Tax Compliance
  - Commonwealth of Massachusetts Individual Certificate of Tax Compliance
  - Bidders Certification of Understanding
  - Schedule of Participation Disadvantage/Minority/Women Business
  - Letter of Intent
  - Contractor Identification Statement
  - Bidders Certification
  - Unavailable Certifications
  - Request for Waiver (if required)
  - Certification Pertaining to Ineligible Contractors
  - Bid Security

#### ARTICLE 10. SIGNATURES OF BIDDERS

- 10.1 The firm, corporate, or individual name of the Bidder must be signed by the Bidder in the space provided for signatures on the Bid Form.
- 10.2 Bids by corporations shall be executed in the corporate name by the president or a vice-president (or other corporate officer accompanied by evidence of authority to sign) and the corporate seal shall be affixed and attested by the secretary or an assistant secretary. The corporate address and state of incorporation shall be shown below the signature.
- 10.3 Bids by Limited Liability Companies shall be executed in the Limited Liability name by the Manager (or other Limited Liability Company officer/representative accompanied by evidence of authority to sign.) The Limited Liability Company address and state where the Limited Liability Company was formed shall be shown below the signature.
- 10.4 Bids by partnerships shall be executed in the partnership name and signed by a partner, whose title shall appear under the signature. The official address of the partnership shall be shown below the signature.
- 10.5 Bids by individuals, that person's name and post office address shall be stated.
- 10.6 Bids made by two or more individuals, partnerships or corporations, or any combination thereof, each party joining to make the Bid shall submit, attached to and made part of the Bid, information and signatures in compliance with the foregoing provisions applicable to an individual, firm, partnership

corporation. In addition, if any members of the joint venture are a corporation, an attested copy of the Vote of Corporation authorizing such joint venture shall be attached to the Bid.

- 10.7 All names shall be typed or printed below the signature.
- 10.8 The address to which communication regarding the Bid are to be directed shall be shown.

#### **ARTICLE 11. DELIVERY OF BIDS**

- 11.1 **One original and one electronic (USB, CD, etc.) copy** of the Bid shall be delivered to the City of New Bedford Purchasing Department as stated in the Invitation to Bid.
- 11.2 If Bid is hand delivered to the City of New Bedford Purchasing Department, it shall be submitted in a sealed opaque envelope that is properly sealed bearing on the outside the Bidder's name, address, the Project Title for which the Bid is submitted, the Bid Number, date and time of Bid Opening. The envelope shall be clearly marked as "BID FOR CITY OF NEW BEDFORD". The Bid Security shall be submitted in a separate envelope from the Bid and attached to the envelope containing the Bid. Bid Security envelope shall be clearly marked as "BID SECURITY". Bid Security envelope shall be clearly marked on the outside the Bidder's name, address, the Project Title for which the Bid is submitted, the Bid Number, date and time of Bid Opening.
- 11.3 If Bid is mailed, the Bidder shall submit the Bid by certified mail with return-receipt requested, or a private delivery service, such as Federal Express or United Parcel, which requires evidence of receipt. The Bid shall be placed in an envelope and placed in the mailing envelope, with both envelopes properly sealed.
- 11.3.1 The words "BID FOR THE CITY OF NEW BEDFORD", with the Bid No. of the project being bid, shall be written on the mailer envelope. The mailer envelope shall also indicate the Date and Time of the Bid Opening.
- 11.3.2 The inside envelope containing the Bid shall be labeled and prepared as described above. Bid Security shall also be prepared and submitted as described herein.
- 11.4 The Owner may consider informal any Bid not prepared and submitted in accordance with the provisions hereof.
- 11.5 Bidders are cautioned that it is the responsibility of each individual bidder to assure that their bid is in the possession of the responsible official or the designated alternate prior to the stated time and at the place of the Bid Opening. Owner is not responsible for bids delayed by mail and/or delivery services, of any nature. Bidders shall email the Purchasing Department at <a href="mailto:purchasing@newbedford-ma.gov">purchasing@newbedford-ma.gov</a> to confirm that their bid has been submitted and received.
- 11.6 The only acceptable evidence to establish the date and time of receipt of a Bid at the location stated in Invitation to Bid, shall be the date/time stamp of the Owner on the envelope, or other documentary evidence of receipt maintained by the Purchasing Department.
- 11.7 Bids received after the stated time in the Invitation to Bid for receipt of bids will not be accepted by the Purchasing Department and will be returned to the Bidder unopened.

#### ARTICLE 12. DISQUALIFICATION OF BIDDERS

- 12.1 More than one proposal from an individual, a firm or partnership, a corporation, or an association under the same or different names, will not be considered. Reasonable grounds for believing that any Bidder is interested in more than on proposal for the work contemplated will cause the rejection of all proposals in which such Bidder is interested.
- 12.2 Any and all proposals will be rejected if there is a reason for believing that collusion exists among the Bidders, and all participants in such collusion will not be considered in future proposals for the same work.
- 12.3 Bids may be rejected from any Bidder whose name appears on the US Comptroller General's List of ineligible contractor for federally-financed and assisted construction.
- 12.4 Bidders are advised that the Bid Form's Schedule of Bid Prices shall include a Bid price for each of the items listed in the Schedule of Bid Prices. The omission of a Bid price for any of the items may be cause for rejection of all Bid prices listed in the Bid and the Bid itself.
- 12.5 Refer to other Articles in Instructions to Bidders.

#### **ARTICLE 13. MODIFICATION AND WITHDRAWAL OF BIDS**

- 13.1 Bids may be modified only by an appropriate document duly executed (in the manner that a Bid must be executed) and delivered to the place where Bids are to be submitted at any time prior to the opening of Bids.
- 13.2 Bids may be withdrawn prior to the scheduled time (or authorized postponement thereof) for the opening of Bids.
- 13.2.1 Request must be made in writing and in the hands of the Purchasing Department prior to the established opening time and date.
- 13.2.2 If not earlier returned, when any such Bid is reached during the opening of the Bids, it will be returned to the Bidder unread.
- 13.3 A Bid may be withdrawn or modified in person by a Bidder or the Bidder's Authorized Representative, provided the Bidder's identity is known and the Bidder signs a receipt for the Bid, but only if the modification or withdrawal is made prior to the time set for receipt of Bids.
- 13.4 Any Bid received after the time and date specified for receipt of bids shall not be considered. No Bid may be withdrawn for a period of thirty (30) days, excluding Saturdays, Sundays, and legal holidays, after the actual date of approval by the officer, board or agency of the Federal Government or of the Commonwealth of Massachusetts or, if no such approval is required, for a period of thirty (30) days excluding Saturdays, Sundays and legal holidays, after the actual date of the opening of the Bids.

#### **ARTICLE 14. PUBLIC OPENING OF BIDS**

- 14.1 Bids will be publicly opened and the total price of each bid read at the time and the location stated in Invitation to Bid. In person attendance at the bid opening is not allowed. Refer to Section 00010 for specific requirements regarding viewing of the bid opening.
- 14.2 Any person may, at reasonable times, and in the presence of a duly authorized representative of the Owner, examine any or all Bids after they have been opened and read.

#### ARTICLE 15. SUPERINTENDENCY BY CONTRACTOR

15.1 Except where the Contractor is an individual and gives his personal superintendency to the work, the Contractor shall have a competent superintendent, satisfactory to the Owner, on the work at all times during working hours, with full authority to act for him/her. The Contractor shall also provide an adequate staff for the proper coordination and expedition of the work.

#### ARTICLE 16. AWARD OF CONTRACT

- 16.1 The Contract will be awarded to the lowest responsible and eligible bidder (Successful Bidder) conforming to the solicitation, who will be most advantageous to the Owner, considering only price, and any price related factors specified in this solicitation based on the Total Base Bid Price. To be considered responsive, the entire Bid Form must be completed. Such Bidder(s) shall possess the skill, ability, and integrity necessary for the faithful performance of the work. The term "lowest responsible and eligible Bidder" as used herein shall mean the Bidder whose Bid is the lowest of those Bidders possessing the skill, ability and integrity necessary to the faithful performance of the Work.
- 16.2 All decisions in reference to the bidding and the selection of the Contractor(s) will be made by the City of New Bedford Purchasing Agent or an authorized agent. The Owner reserves the right to reject any and all bids or any portion of any bids, to advertise new bids, or to waive any and all bid formalities if it is in the best interest of the Owner to do so, and the right to disregard all non-conforming, non-responsive or conditional bids.
- 16.3 All bids shall remain open for sixty (60) days, excluding Saturdays, Sundays, and legal holidays, after the actual date of the opening of the Bids but Owner may, at Owner's sole discretion, release any Bid and return the Bid Security prior to that date.
- 16.4 The successful Bidder will be notified by email that their Bid has been accepted and the items they have been awarded.
- 16.5 A Bid which includes for any item a Bid Price that is abnormally low or high may be rejected as unbalanced.
- 16.6 Owner also reserves the right to reject the Bid of any Bidder that Owner considers to be unqualified relative to Article 6 above.
- 16.7 If the Contract is to be awarded, Owner will give the Successful Bidder a Notice to Proceed within 30 days, excluding Saturdays, Sundays, and legal holidays after the date of approval by the officer, board or agency of the Federal Government or the Commonwealth of Massachusetts or if no such approval is required, after the actual date of the opening of the Bids. All bids shall remain open for thirty days, excluding Saturdays, Sundays, and legal holidays, after the actual date of the opening of the Bids but the Owner may, at Owner's sole discretion, release any Bid and return the Bid Security prior to that date.
- 16.8 If Eligible and ineligible items are included in the Bid Form, the unit prices established that appear in both shall be the same.

#### ARTICLE 17. EXECUTION OF THE CONTRACT

17.1 The successful Bidder shall execute and deliver to the Owner the Contract, Agreement, Purchase Order or Work Order and furnish the required surety, bonds and the certificates of insurance to the Owner

within five (5) calendar days after receipt of Notice to Award, Saturdays, Sundays and Legal Holidays excluded.

- 17.2 All contracts shall be signed by electronic signature via DocuSign. The Successful Bidder shall provide Owner the contact email as to where the Contract should be sent for signature within five (5) calendar days after receipt of Notice to Award, Saturdays, Sundays and Legal Holidays excluded.
- 17.3 Within five (5) calendar days of receipt of notice by the Owner, the lowest, responsible, and eligible Bidder shall submit to the Owner a list of references. The list of references shall include the following:
- 17.4 Business Reference Submit three (3) business references including the following:
  - Name and title
  - Company name and address
  - Telephone number
  - Relationship to bidder
- 17.5 Project References and Project Contacts Submit three (3) references with the respective project contacts. The projects shall have been completed within the last five (5) years and shall have been of a similar type of work, scope and construction dollar value. The contacts shall have been involved in the project as part of the Owner's project team and have knowledge of the overall project.
- 17.6 Project references shall include the following:
  - Name and address of the Owner
  - Name and address of the project
  - Type of Project
  - As bid construction contract dollar value and final project cost
  - State and end dates of the work
- 17.7 Project contacts shall include the following information:
  - Name and title of contact
  - Project responsibility
  - Address of contact
  - Telephone number

#### **ARTICLE 18. BID SECURITY**

18.1 In order to ensure faithful fulfillment of its term, each Bid shall be accompanied by a Bid Guaranty (a.k.a. Bid Deposit or Bid Security) on the amount stated in the Invitation to Bid. The Bid Guaranty shall be in the form of an acceptable bid bond, certified check, treasure's or cashier's check, made payable to the City of New Bedford, by a responsible bank or trust company or by a surety or insurance company licensed or authorized by the Massachusetts Division of Insurance to engage in the business of surety in the Commonwealth, and satisfactory to the Owner. The Bid Guaranty shall be enclosed in a sealed envelope and submitted with the Bid Form (Refer to Article 11 of the Instruction to Bidders). The envelope containing the Bid Guaranty shall be clearly marked in ink: Bid Guaranty for City of New Bedford, name of bidder, address of bidder, contact information, and date and time of bid opening.

- 18.2 All Bid Securities except those of the three lowest responsible and eligible Bidders will be returned within five days, Saturdays, Sundays, and legal holidays excluded, after opening of the Bids. All Bid Securities will be returned upon the execution of the Agreement or if no award is made, within sixty days, excluding Saturdays, Sundays and legal holidays after the actual date of opening of the Bids, unless forfeited under the conditions herein stipulated.
- 18.3 If a party to whom a Contract is awarded shall fail or neglect to execute the Agreement and furnish the satisfactory bonds within the time specified, Owner may determine that the Bidder has abandoned the Contract, and thereupon the Bid Forms and acceptance shall be null and void and the Bid Security accompanying the Bid Form shall be forfeited to Owner as liquidated damages for such failure or neglect and to indemnify said Owner for any loss which may be sustained by failure of the Bidder to execute the Agreement and furnish the bonds as aforesaid, provided that the amount forfeited to Owner shall not exceed the difference between the Bid Price of said Bidder and that of the next lowest responsible and eligible bidder and provided further that, in case of death, disability, or other unforeseen circumstances affecting the Bidder, such Bid Security may be returned to the Bidder. After execution of the Agreement and acceptance of the bonds by Owner, the Bid Security accompanying the Bid Form of the Successful Bidder will be returned.
- 18.4 If after sixty days from the opening of Bids, the Contract is not awarded by the Awarding Authority, any or all of the three lowest, responsible and eligible Bidders may request in writing that their Bid Guaranty be returned. Bidder's whose Bid Guaranty is returned will not be considered for the awarding of the Contract.

#### ARTICLE 19. LIQUIDATED DAMAGES FOR FAILURE TO ENTER INTO CONTRACT

- 19.1 Refer to Article 18 of the Instruction to Bidders.
- 19.2 It is agreed that this Article and referenced Articles shall not be construed and treated by the parties to the Contract not as imposing a penalty upon said Bidder for failing to fully execute the Contract as agreed on or before the time state in the Contract Documents, but a liquidated damages to compensate the awarding Authority for all additional costs incurred by the Awarding Authority because of the failure of the Bidder to fully execute the Contract on or before the time specified in the Contract Documents.

#### ARTICLE 20. CANCELLATION OF AWARD

20.1 The Owner reserves the right to cancel the award of any contract at any time before the execution of the said contract by all parties without any liability against the Owner.

#### ARTICLE 21. PERFORMANCE, PAYMENT AND OTHER BONDS

- 21.1 All Bonds required as Contract Security shall be furnished with the executed Agreement.
- 21.2 The successful bidder must deliver to the Owner an executed Bond as security in the amount of 100-percent of the contract price, as security for the faithful performance of his/her contract and the payment of all persons performing labor and furnishing materials in connection therewith, prepared in the form of a Performance & Payment Bond, and having a surety thereon such surety company or companies are as approved by the Owner, and as are authorized to transact business in the Commonwealth of Massachusetts and must be licensed by the Massachusetts Division of Insurance. Such bond shall acknowledge and permit use and occupancy of the project or any portion thereof prior to formal acceptance by the Owner.

- 21.3 Attorney In Fact and/or other officer who sign Contract Bonds must file with each Bond a certified copy of their power of attorney to sign said bonds.
- 21.4 All modifications, extensions of time, extra work and other changes authorized under the Contract Documents may be made without obtaining the consent of the Surety of the Contract Bonds.
- 21.5 The Performance and Payment Bond shall remain in force until the validity of all claims is determined and if valid, are paid by the Surety.
- 21.6 Performance, payment and other bonds shall be provided in accordance with Article 5 of the General Conditions of the Contract.

#### **ARTICLE 22. COMMENCEMENT AND COMPLETION OF WORK**

22.1 The Contractor shall commence work under this Contract as specified in the Notice to Proceed, Work Order, Purchase Order or Contract at those locations specified by the Owner. The Work shall be completed by the date specified in the Notice to Proceed.

#### ARTICLE 23. LIQUIDATED DAMAGES FOR FAILURE TO COMPLETE WORK

23.1 The Owner reserves the right to assess liquidated damages depending on the type and classification of work being completed, and losses resulting from delays in completing the project beyond the time set in the Notice to Proceed, Agreement, Work Order, Contract, or Purchase Order.

#### **ARTICLE 24. ASSIGNMENTS**

Omitted.

#### **ARTICLE 25. INSURANCE**

- 25.1 The Contractor shall take out and maintain during the life of the contract such Workmen's Compensation and Comprehensive General Liability Coverage Insurance as shall protect him an any subcontractor performing work covered by this Contract, from claims and damages for personal injury, including accidental death, as well as from claims for property damage, which may arise from operations under this contract, whether such operations by himself or by any subcontractor or by anyone directly or indirectly employed by either of them. All policies must allow use and occupancy of the Project or any portion thereof prior to formal acceptance by the Owner.
- 25.2 Minimum insurance requirements are included in the General Conditions and Supplementary Conditions.
- 25.3 The Contractor must furnish the Owner with a signed contract agreement and Certificate of Insurance in compliance with this Contract before the Contract is signed.

#### **ARTICLE 26. SAFETY AND HEALTH REGULATIONS**

26.1 As mandated by Chapter 82A of the Massachusetts General Law (MGL), the trench safety regulations require that all Contractors, whether public or private, take specific precautions to protect the general public and prevent unauthorized access to unattended trenches. Accordingly, unattended trenches must be covered, barricaded or backfilled. Covers shall be road plates at least 3/4 –in thick or equivalent; barricades shall be fences at least 6-ft high with no openings greater than 4-in between vertical supports;

backfilling shall be sufficient to eliminate the trench. Alternatively, Contractors may choose to attend trenches at all times, for instances by hiring a police detail, security guard or other attendant who shall be present during times when the trench will be unattended by the Contractor. For purposes of this Paragraph, a "trench" shall be defined as an excavation which is narrow in relation to its length, made below the surface ground in excess of 3 feet below grade and the depth of which is, in general, greater than the width, but the width of the trench, as measured at the bottom, is no greater than 15 feet and the words "excavator", "excavation" and "emergency" shall have the same meanings as defined in Section 40 of Chapter 82 of the MGL. The word "excavator" as used in this Paragraph shall also mean "Contractor".

- 26.2 This project is subject to the Safety and Health regulations of the U.S. Department of Labor set forth in Title 29 CFR, Part 1926 and to all subsequent amendments, and to the Massachusetts Department of Labor and Industries, Division of Industrial Safety "Rules and Regulations for the Prevention of Accidents in Construction Operations" (Chapter 454 CMR 10.00 et seq.). Contractors shall be familiar with the requirements of these regulations.
- 26.3 The Successful Bidder shall comply with the Department of Labor Safety and Health Regulations for Construction promulgated under the Occupational Safety and Health Act of 1970 (PL-91-596) and under Section 107 of the Contract Work Hours and Safety Standards Act (PL-91-54).
- 26.4 The Successful Bidder shall have a competent person or persons, as required under the Occupational Safety and Health Act on the Site to inspect the Work and to supervise the conformance of the Work with the regulations of the Act.
- 26.5 United States Occupational Safety and Health Administration (OSHA) Construction Training is required for this Contract. As of July 1, 2006, under M.G.L. Chapter 30, Section 39S, any person submitting a bid for, or signing a contract to work on, the construction, reconstruction, alteration, remodeling or repair of any public work by the Commonwealth of Massachusetts and/or City of New Bedford that is estimated by the awarding authority to cost more than \$10,000.00 shall certify on the Bid and Agreement, under penalty of perjury, that all employees to be employed on the work shall have successfully completed a course in Construction Safety and Health that is approved by OSHA and at least 10 hours in duration.

#### ARTICLE 27. NONDISCRIMINATION IN EMPLOYMENT

27.1 Contracts for work under this proposal will obligate the Contractor and sub-contractor not to discriminate in employment practices.

#### ARTICLE 28. ALTERNATES, SUBSTITUTIONS AND CONTRACTOR'S OPTIONS

- 28.1 Whenever in the Plans, Specifications, Work Orders, Contracts, Purchase Orders, Notice to Proceed, any item or equipment or material is designated by reference to a particular brand, manufacturer, or trade name, it is understood that an approved equal product, acceptable to the Owner, may be substituted by the Bidder or the Contractor.
- 28.2 In the event of acceptance of any alternative or substitution, it shall be the responsibility of the Contractor to coordinate such alternate or substitute items with all other items to be furnished, to assure the proper fitting together of all items. Any additional cost incident to the coordination and/or fitting together with alternate or substitute items shall be borne by the Contractor at no extra cost to the Owner. Similar responsibility applies to items which are left to the Contractor's option.

#### **ARTICLE 29. TECHNICAL SPECIFICATIONS**

29.1 The Technical Specifications for this project are, unless otherwise specifically stated, based on the Massachusetts Department of Transportation, Highway Division, Standard Specification for Highways and Bridges, latest edition including any and all addenda, the City of New Bedford Construction Specifications latest edition including all addenda, and any supplemental specifications provided in the Contract Documents. In the event of a conflict, the more stringent specification shall apply unless specifically notified by the Engineer and/or Owner to deviate from a specification. Bidders are required to have a copy of the latest edition thereof, and are responsible for being thoroughly familiar with them.

#### **ARTICLE 30. FEDERAL WAGE RATES**

Omitted.

#### ARTICLE 31. MANUFACTURER'S EXPERIENCE

31.1 Whenever it is written that an equipment manufacturer must have a specified period of experience with his product, equipment which does not meet the specified experience period can be considered if the equipment supplier or manufacturer is willing to provide an Efficiency Guarantee Bond or cash deposit for the duration of the specified time period which will guarantee replacement of that equipment in the event of failure.

#### **ARTICLE 32. ACCESS TO SITE**

32.1 Representatives of the Commonwealth, Owner and any local agencies having a direct interest in the Work shall have access to the Work under this contract wherever it is in preparation or progress and the Contractor shall provide proper facilities for such access and inspection.

#### ARTICLE 33. UNDERGROUND PLANT DAMAGE PREVENTION SYSTEM

33.1 All excavations within public or private ways are subject to the requirements of Massachusetts General Law, Chapter 82, Section 40 included in the Supplementary Conditions.

#### **ARTICLE 34. COMPETITIVE BIDDING**

34.1 The bidding and award of the Contract shall be in full compliance with Section 39 M inclusive of Chapter 30 of the General Laws of the Commonwealth of Massachusetts as last revised.

#### **ARTICLE 35. GUARANTEE**

35.1 The Contractor guarantees that the Work and Services to be performed under the Contract, and all workmanship, materials and equipment performed, furnished, used or installed in the construction of the same shall be free from defects and flaws, and shall be performed and furnished in strict accordance with the Drawings, Specifications, and other contract documents, that the strength of all parts of all manufactured equipment shall be adequate and as specified and that the performance test requirements of the Contract shall be fulfilled. This guarantee shall be for a period of one year minimum from and after the date of completion and acceptance of the Work as stated in the final estimate. If part of the Work is accepted in accordance with that subsection of this AGREEMENT titled "Partial Acceptance", the guarantee for that part of the Work shall be for a minimum period of one year from the date fixed for such acceptance.

- 35.2 If at any time within the said period of guarantee any part of the Work requires repairing, correction or replacement, the Owner may notify the Contractor in writing to make the required repairs, corrections or replacements. If the Contractor neglects to commence making such repairs, corrections or replacements to the satisfaction of the Owner within seven (7) days from the date of receipt of such notice, or having commenced fails to prosecute such Work with diligence, the Owner may employ other persons to make said repairs, corrections or replacements, and charge the costs, including compensation for additional professional services, to the Contractor.
- 35.3 The Bidder may be required to furnish, at no additional cost to the Owner, a complete statement of the origin, composition, and manufacture of any or all products/materials, proposed to be used in the construction of the Work, together with samples that may be subject for testing, as determined by the Owner, to determine the quality and fitness of the products/materials.
- 35.4 The Owner reserves the right to complete any tests it deems appropriate and to reject any and all deliveries not meeting any of the required specifications.

#### ARTICLE 36. FINES, SUSPENSE AND DEBARMENT

- 36.1 Bidders must fully comply with Subpart C of 2 CFR Part 108 and 2 CFR Part 1532, entitled Responsibilities of Participants Regarding Transactions (Doing Business with Other Persons). Contractors, subcontractors, or suppliers that appear on the Excluded Parties List System at <a href="https://www.sams.gov">www.sams.gov</a> are not eligible for award of any contracts funded in whole or part by the Commonwealth of Massachusetts or Federal Government.
- 36.2 That within the past five (5) years, no officers, directors, employees, agents, or subcontractors of which the Contractor has knowledge, been the subject of:
  - A. an indictment, judgement, conviction, or grant of immunity, including pending actions, for any business related conduct constituting a crime under state or federal law; and
  - B. a government suspension or debarment, rejection of any bid or disapproval of any proposed contract subcontract, including pending actions, for lack of responsibility, denial or revocation of prequalification or a voluntary exclusion agreement; or any governmental determination of any public works law or regulations, or labor law or any OSHA violation deemed "serious or willful."
- 36.3 Contractor certifies that neither it nor any of its subcontractors are currently debarred or suspended by the federal or state government under any law or regulation including; Executive Order 147, G.L. C. 29 s. 29F ss 39R, G.L. c 149, ss 27C, G.L. c 149 ss 44C, G.L. c 149 ss 148B and G.L. c. 152 s 25C.
- 36.4 The Contractor understands and agrees that breach of any of the terms and conditions outlined within this Contract during the Contract Period may be regarded as a material breach, subjecting the Contractor to sanctions, including but not limited to monetary penalties, withholding of payments, contract suspension or termination of Contract. Contractor is responsible for payment of any and all fines incurred by Owner resulting from Contractor's negligence and adherence to Contract.

#### ARTICLE 37. MASSACHUSETTS GENERAL LAWS AND REGULATIONS

37.1 Applicable provisions of Massachusetts General Laws and Regulations and/or the United States Code and Code of Federal Regulations govern this Contract and any provision in violation of the foregoing shall be deemed null, void and of no effect. Where conflict between Code of Federal Regulations and State Laws and Regulations exist, the more stringent requirement shall apply.

- 37.2 All applicable State laws, municipal ordinances, and the rules and regulations of all authorities having jurisdiction over construction of the Project shall apply to the Contract throughout, and they will be deemed to be included in the Contract the same as though herein. Particular reference is made to the Assurances made by the Owner in its application for Community Development Block Grants and MassWorks Infrastructure Grants and to applicable regulations issued by various Federal and State agencies pursuant to receipt of said Grants, which are hereby incorporated by reference.
- 37.3 It is not the responsibility of the Contractor to make certain that the Contract Documents are in accordance with applicable laws, statutes, building codes and regulations. If the Contractor observes that any of the Contract Documents are at variance therewith in any respect, it shall promptly notify the Owner in writing, and any necessary changes shall be accomplished by appropriate modification.
- 37.4 If the Contractor performs any work knowing it is to be contrary to such laws, ordinances, rules and regulations and without such notice to the Engineer, it shall assume full responsibility therefore and shall bear all costs attributed thereto.

#### **ARTICLE 38. MINORITY AND WORKFORCE PARTICIPATION GOALS**

- 38.1 Disadvantaged Business Enterprise (DBE) goals of the City of New Bedford are applicable to the total dollars paid to the construction contract. The City of New Bedford goals for this project are a minimum of 11.00 percent D/MBE participation by certified DBEs. The MassWorks Infrastructure Program MBE and WBE goal is 10.4 percent combined MBE/WBE by State certified MBE and WBE firms. The employment percentages shall apply to the contractor and all subcontractors, regardless of tier, for all on-site work. Bidders shall submit all required completed City of New Bedford forms with their bid. Failure to comply with the requirements of this paragraph may be deemed to render a proposal non-responsive. No waiver of any provision of this section will be granted unless approved by the City of New Bedford, Massachusetts.
- 38.2 The Contractor shall not discriminate against or exclude any person from participation herein on grounds of race, religion, color, sex, age, or national origin; and that it shall take affirmative actions to insure that applicants are employed, and that employees are treated during their employment, without regard to race religion, color, sex, age, handicapped status, or national origin.

#### **ARTICLE 39. COMMONWEALTH OF MASSACHUSETTS PROVISIONS**

Omitted.

#### ARTICLE 40. FEDERAL CONTRACT PROVISIONS

Omitted.

#### **ARTICLE 41. EXECUTIVE ORDERS**

Omitted.

#### ARTICLE 42. CITY OF NEW BEDFORD SUPPLEMENTAL CONDITIONS

42.1 The Contractor shall comply with the City of New Bedford, Massachusetts contract requirements including Instruction to Bidders for Affirmative Action Issues for Public Works and Construction Projects. A copy of these requirements and compliance reporting forms are included in Part II of the

Supplementary Conditions. Certification forms required with the bid submittal and Contract are included in the Bid Form and Agreement respectively. Failure to include fully completed forms required with the bid may be deemed to render the bid non-responsive.

MOLLY GILFEATHER DIRECTOR OF PURCHASING CITY OF NEW BEDFORD, MASSACHUSETTS

#### BID FORM TO CITY OF NEW BEDFORD, MASSACHUSETTS FORT TABER PIER – STONE MASONRY REHABILITATION Bid No. 23434039

The undersigned declares that the only persons or parties interested in this Bid as principals are as stated; that the Bid is made without any collusion with other persons, firms, or corporations; that all the Contract Documents and information contained within this Request for Bids (RFB) have been carefully examined; that the undersigned is fully informed in regard to all conditions pertaining to the Work and the place where it is to be done, and from them the undersigned makes this Bid. These prices shall cover all expenses incurred in performing the Work required under the Contract Documents, of which this Bid Form is a part.

The Contract will be evaluated and awarded to the responsible Bidder, based on the Total Base Bid whose bid, conforming to the solicitation, will be most advantageous, the lowest responsible bidder, to the City of New Bedford Department of Public Infrastructure, considering only price and any price related factors specified in the solicitation.

The Contract Term will commence twenty days following the effective signing date of the agreement and extend through April 2023.

The time period for holding bids is sixty (60) days, Saturdays, Sundays and legal holidays excluded, after the opening of bids.

The Bid Security accompanying this Bid shall be in the amount of 5 percent of the Bid. The Bid Security/Bid Guarantee amount shall NOT be calculated based on a presumed or assumed contract value or amount that may be anticipated by the City.

If a Notice of Award accompanied by at least six unsigned copies of the Agreement and all other applicable Contract Documents is delivered to the undersigned within sixty (60) days, excluding Saturdays, Sundays, and legal holidays, after the actual date of the opening of the Bids, the undersigned will within five days, excluding Saturdays, Sundays, and legal holidays, after the date of receipt of such notification, execute and return all copies of the Agreement and all other applicable Contract Documents to OWNER. The premiums for all Bonds required shall be paid by CONTRACTOR and shall be included in the Contract Price. The undersigned Bidder further agrees that the Bid Security accompanying this Bid shall become the property of OWNER if the Bidder fails to execute the Agreement as stated above.

The Bid Security shall be sealed in a separate envelope from the Bid and then attached to the envelope containing the Bid. Refer to Instructions to Bidders.

If the Bidder is a foreign corporation, it agrees, in case this Bid is accepted, to comply with the applicable provisions of Massachusetts General Laws, Chapter 156d, before the time for execution of the contract, as hereinafter provided, occurs.

Bidder hereby agrees to commence work under this Contract on or before the date to be specified in the Notice to Proceed and to complete the project before or on the date of the Notice to Proceed. Bidder further acknowledges that the Owner reserves the right to assess liquidated damages depending on the type and classification of work being completed, and losses resulting from delays in completing the project beyond the time set in the Notice to Proceed, Work Order, Contract, or Purchase Order.

The City reserves the right to reject any and all bids and to waive any informalities in the bidding.

#### BID FORM TO CITY OF NEW BEDFORD, MASSACHUSETTS FORT TABER PIER – STONE MASONRY REHABILITATION Bid No. 23434039

The undersigned acknowledges receipt of addenda numbered:

\_\_\_\_\_

In accordance with the above understanding, the undersigned proposes to perform the Work, furnish all materials and complete the Work in its entirety in the manner and under the conditions required at the prices listed as follows:

#### Bid Price Notes:

- 1. All Prices shall be written in ink or types. Unit prices shall be written in words and figures. In the case of discrepancy, the amount in words shall govern.
- 2. All prices shall include the price of labor, equipment, materials, and incidentals required for carrying out the work in accordance with the Contract Documents unless otherwise noted.
- 3. Rental rate for equipment shall include equipment delivered to City of New Bedford project site, fuel, operator, and all costs connected with satisfactory operation.
- 4. The quantities of work as given for each item in the proposal are only approximate and are assumed only for the comparison of proposals.
- 5. The Contractor shall only be reimbursed on a unit price basis for the quantities ultimately provided to the Owner; Contractor shall not be entitled to any profit associated with unused quantities.

# BID FORM TO CITY OF NEW BEDFORD, MASSACHUSETTS FORT TABER PIER – STONE MASONRY REHABILITATION Bid No. 23434039

Item Number	Item Name and Unit Bid Prices Written in Words and Figures	Estimated Quantity	Total Amount of Item (in figures)
1	General Conditions, Mobilization and Demobilization, per lump sum, the price of:	lump sum* =	\$
	(\$ ) *Not to exceed 5 percent of the total Bid price	wanp own	<u> </u>
2	Quality Control, per lump sum, the price of:	lump sum =	\$
	(\$ )	iump sum —	Ψ
3	Turbidity Barrier, per lump sum, the price of:		
	(\$ )	lump sum=	\$
4	Demolition and Removal, per lump sum, the price of:		
		lump sum=	\$
	(\$		
5	Granite reconstruction - Setting Existing granite blocks and furnish misc. materials, per lump sum, the price of:	lump sum=	\$
	(\$ )		

# BID FORM TO CITY OF NEW BEDFORD, MASSACHUSETTS FORT TABER PIER – STONE MASONRY REHABILITATION Bid No. 23434039

6	Concrete fill material- Place Concrete fill, per cubic yard, the price of:	x 4 c.y. =	\$
	(\$ ) BID FORM		
TOTAL	AMOUNT OF BID – Items 1 through 6		dollars
	(words)		
(\$	<u>)</u>		
	(figures)		
This Bio	d includes Addenda numbered		
	dersigned agrees that extra work, if any, will be performe ons of the Contract and will be paid for in accordance with t.		
The bide	ding and award of this Contract will be in accordance with	th M.G.L. Chapter	30, Section 39M.
	dersigned must furnish a 100 percent Performance Bond a ompany acceptable to OWNER.	and a 100 percent P	ayment Bond with a
	ts shall be shown in both words and figures, where indican words will govern.	ated. In case of disc	crepancy, the amount
	ove prices shall include all labor, materials, bailing, shoring dentals required to complete the Work.	ng, removal, overho	ead, profit, insurance
The nan follows:	nes and residences of all persons and parties interested in	the foregoing Bid	as principals are as
the signate by the M	rst and last names in full. In the case of a corporation, in ature and affix the corporate seal, in the case of a limited Manager and address and state where the Limited Liability, give the full names and residential addresses of all products.)	liability company y Company was for	(LLC), give the name rmed, in the case of a

#### BID FORM TO CITY OF NEW BEDFORD, MASSACHUSETTS FORT TABER PIER – STONE MASONRY REHABILITATION Bid No. 23434039

Pursuant to M.G.L. Ch. 62C, sec. 49A, I certify under the penalties of perjury that I, to my best knowledge and belief, have filed all state tax returns and paid all state taxes required under law.

The undersigned hereby certifies that he is able to furnish labor that can work in harmony with all other elements of labor employed or to be employed on the work; that all employees to be employed at the worksite will have successfully completed a course in construction safety and health approved by the United States Occupational Safety and Health Administration that is at least 10 hours in duration at the time the employee begins work and who shall furnish documentation of successful completion of said course with the first certified payroll report for each employee.

The undersigned bidder hereby certifies he/she will comply with the specific affirmative action steps contained in the Equal Employment Opportunity/Affirmative Action (EEO/AA) provisions of this Contract, including compliance with the Disadvantaged Business Enterprise provisions as required under these contract provisions. **The attached DBE Forms must be completed and submitted as part of the Bid Proposal.** The Contractor receiving the award of the contract shall incorporate the EEO/AA provisions of this contract into all subcontracts and purchase orders so that such provisions will be binding upon each subcontractor or vendor.

The attached City of New Bedford forms must be completed and submitted as part of the Bid Proposal.

Bidders must fully comply with Subpart C of 2 CFR Part 180 and 2 CFR Part 1532, entitled Responsibilities of Participants Regarding Transactions (Doing Business with Other Persons). Contractors, subcontractors, or suppliers that appear on the Excluded Parties List System at <a href="https://www.sam.gov">www.sam.gov</a> are not eligible for award of any contracts funded by the Commonwealth of Massachusetts.

The undersigned warrants, represents, and agrees that during the time of this Contract is in effect, neither it nor any affiliated company, as hereinafter defined, participates or cooperates with an international boycott, as defined in Section 999(b)(3) and (4) of the Internal Revenue Code of 1954, as amended, or engages in conduct declared to be unlawful by Section 2 of Chapter 151E, Massachusetts General Laws. If there shall be a breach in the representation and agreement contained in this paragraph then without limiting such other rights as it may have, the Awarding Authority shall be intitled to rescind this Contract. As used herein, an affiliated company shall be any business entity of which at least 51-percent of the ownership interests are directly or indirectly owned by the Bidder, or which directly or indirectly owns at least 51-percent of the ownership interest of the Contractor.

he Remainder of This Page Intentionally Left Blank

#### BID FORM TO CITY OF NEW BEDFORD, MASSACHUSETTS FORT TABER PIER – STONE MASONRY REHABILITATION Bid No. 23434039

The undersigned hereby certifies under the penalties of perjury that this bid is in all respects bona fide, fair and made without collusion or fraud with any other person. As used in this section, the word "person" shall mean any natural person, joint venture, partnership, corporation, limited liability company, or other business or legal entity. The undersigned further certifies under penalty of perjury that the said undersigned is not presently debarred from doing public construction work in the Commonwealth under the provisions of Section Twenty-nine F of Chapter Twenty-nine, or any other applicable debarment provisions of any other chapter of the General Laws or any rule or requisition promulgated thereunder; and is not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency.

By:Corporate Officer (if applicable)
llowing:
(Name)
y:(Title)
ate

Stone Masonry Rehabilitation City of New Bedford, Massachusetts

address.

## CITY OF NEW BEDFORD MASSACHUSETTS

#### NON-COLLUSION AND TAX COMPLIANCE FORM

#### **CERTIFICATE OF NON-COLLUSION**

good faith and without collusion or frauc	s of perjury that this bid has been made and submitted in I with any other person. As used in this certification, the ral person, business, partnership, corporation, union, ntity or group of individuals.
Signature of individual submitting bid	-
Name of business/organization	-
TAY COMPI	
TAX COMP	LIANCE CERTIFICATION
Pursuant to M.G.L. c. 62C, §49A, I cert knowledge and belief, I am in complian	ify under the penalties of perjury that, to the best of my
Pursuant to M.G.L. c. 62C, §49A, I cert knowledge and belief, I am in complian	ify under the penalties of perjury that, to the best of my ce with all laws of the Commonwealth relating to taxes
Pursuant to M.G.L. c. 62C, §49A, I cert knowledge and belief, I am in complian	ify under the penalties of perjury that, to the best of my ce with all laws of the Commonwealth relating to taxes

## CITY OF NEW BEDFORD MASSACHUSETTS

## VOTE OF CORPORATION AUTHORIZING EXECUTION OF CORPORATE AGREEMENTS

At a meeting of the Boa	rd of Directors of		_duly called and held	d on
	0 at which a qu	uorum was present a	nd acting throughou	t, the
following vote was duly	adopted.			
VOTED: That		, the		_ of the
corporation, be and here	eby is authorized to a	ffix the Corporate So	eal, sign and deliver	in the name
and behalf of the corpor	ration contract docum	nents with the City o	f New Bedford, the	above
mentioned documents to	o include but not be l	imited to Bids, Prop	osals, Deeds, Purcha	ase and
Sales Agreements, Agree	eements, Contracts, L	eases, Licenses, Rel	eases and Indemnifi	cations; and
also to seal and execute	, as above, surety cor	npany bonds to secu	re bids and proposal	ls and the
performance of said con	tract and payment fo	or labor and material	s, all in such form ar	nd on such
terms and conditions as	he/she, by the execu	tion thereof, shall de	em proper. A true c	copy
ATTEST:				
Name (printed)		<u> </u>		
		(Affix Corporate	Seal)	
Signature		-		
Title				

# CITY OF NEW BEDFORD, MASSACHUSETTS LLC CERTIFICATE OF INCUMBENCY AND AUTHORITY

			, LLC
I,		, do	hereby certify that:
1. I am the duly elected and a LLC, a limited liability comp	cting of _ any organized and existing in a	good standing under t	the laws of the State of
(the	"Company").		
2. Attached hereto as Exhibit	A is a true and correct copy of	f resolutions which w	ere duly adopted by
the members of the Company	on	, 20	,
	ave not been amended, rescindered form originally adopted, and Agreement of the Company.		
4. Attached hereto as Exhibit	B is a true and correct copy of	the Articles of Organ	nization dated
	_ and the Operating Agreemen	nt dated	, 20
	rganization and Operating Agreece and effect on the date herec		n amended, rescinded,
<b>U</b> 1	the Authorized Officers of the heir names and titles are their t		
Name	Office	<u>Signat</u>	<u>ure</u>
Witness, my signature and th	e seal of the Company this	day of	, 20
	Name: Title:		

### OSHA CERTIFICATION REQUIREMENT

Effective **July 1, 2006**, all employees of a contractor to be employed on **public building and public works** worksites must have successfully completed at least a 10 hour course in construction safety and health approved by OSHA at the time the employee begins work.

I,	, as	, of the
(Print Name)	, as(Position with the	entity submitting bid)
joint venture/corporation/pa	rtnership or other legal entity	submitting this bid for a public works
project falling under §39M	of Chapter 30 of the Massachu	usetts General Laws and Chapter 149 or
the same, do hereby certify	that any and all employees for	und on my worksite for this project
have, or will have by the sta	rt of their work on the project	s, successfully completed a course in
construction safety and heal	th approved by the United Sta	ates Occupational Safety and Health
Administration that was at le	east 10 hours in duration.	
A copy of the OSHA compl	etion cards for each employee	e must be submitted to the City of New
Bedford before work on this	s project is to begin and must	be supplemented as new employees are
hired or contracted to work	on this project.	
<u>a.</u>	, as	
Signature		
Position	, of	
Company/Corporation/Joint	, on	
Company/Corporation/Joint	v enture/Partnership/Etc.	
Date	_	

#### **CONTRACTOR CERTIFICATION**

As evidenced by the signature of the Contractor's Authorized signatory below, the Contractor certifies under the pains and penalties of perjury that the Contractor shall not knowingly use undocumented workers in connection with the performance of any City contract; that pursuant to federal and state requirements, the Contractor shall verify the immigration status of all workers assigned to such contracts without engaging in unlawful discrimination; and that the Contractor shall not knowingly or recklessly alter, falsify, or accept altered or falsified documents from any such worker(s). The Contractor understands and agrees that breach of any of these terms during the period of each contract may be regarded as a material breach, subjecting the Contractor to sanctions, including but not limited to monetary penalties, withholding of payments, contract suspension or termination.

Contractor Authorized Signature	
Printed Name	
Date	
Title:	Telephone:
Fax:	Email·

## Form W-9 (Massachueetts Substitute W-9 Form)

# Request for Taxpayer Identification Number and Certification

Completed form should be given to the requesting department or the department you are currently doing business with:

Name (Liat legal name, if joint names, list first & circle the name of the person whose TIN you enter in Part I-See Specific inatruction on page 2)			
Business name, if different from above. (See Specific Instruction on page 2)			
Check the appropriate box:   individual/Sole proprietor   Corp			
Legai Addrese: number, street, and apt. or suite no.	Remittance Addreas: if different from legel address number, street, and apt. or sulte no.		
City, state and ZIP code	City, state and ZiP code		
Phone # ( ) Fax # ( )	Email address:		
Part I Taxpayer Identification Number (TIN)			
Enter your TIN in the appropriate box. For individuals, this is your social security number (SSN). However, for a resident alien, sole proprietor, or disregarded entity, see the Part I instruction on page 2. For other entities, it is your employer identification number (EIN). If you do not have a number, see How to get a TIN on page 2. Note: If the account is in more than one name, see the chart on page 2 for guidelines on whose number to enter.	Social security number  Social security number  OR Employer identification number		
Part II Certification			
Under penalties of perjury, I certify that:  1. The number shown on this form is my correct texpeyer identification.			
<ol> <li>I am not subject to backup withholding because: (a) I am exempt in Revenue Services (IRS) that I am subject to backup withholding a notified me that I am no longer subject to backup withholding, and</li> </ol>	rom backup withholding, or <b>(b)</b> I have not been notified by the Internal is a result of a fallure to report ell Interest or dividends, or <b>(c)</b> the IRS has		
3. I am an U.S. person (including an U.S. resident allen).			
4. I am currently a Commonwealth of Measechusetts's state employee: (check one): No			
Sign Here Authorized Signature ▶	Date ►		

#### **Purpose of Form**

A person who is required to file en information return with the IRS must get your correct taxpayer identification number (TIN) to report, for example, income paid to you, real estate transactions, mortgage interest you paid, acquisition or debt, or contributions you made to an IRA.

Use Form W-9 only if you are e U.S. person (including e realdent allen), to give your correct TIN to the person requesting it (the requester) and, when epplicable, to:

- Certify the TiN you are giving is correct (or you ere waiting for a number to be issued).
- Certify you are not aubject to backup withholding

If you ere a foreign person, use the appropriate Form W-8. See Pub 515, Withholding of Tax on Nonresident Allens and Foreign Corporations.

What is backup withholding? Persons making certain payments to you must withhold a designeted percentage, currently 29% and pay to the IRS of such payments under certain

conditione. This is called "beckup withholding." Peyments that may be aubject to backup withholding include interest, dividends, broker end berter exchange transactions, rents, royeltiee, nonemployee pey, and certain payments from fishing boat operators. Reel estate transactions are not aubject to backup withholding.

If you give the requester your correct TIN, make the proper certifications, and report all your taxeble interest and dividends on your tax return, peyments you receive will not be subject to backup withholding. Payments you receive will be subject to beckup withholding if:

- 1. You do not furnish your TIN to the requeater, or
- You do not certify your TIN when required (see the Pert II instructions on page 2 for details), or
- The IRS tells the requester that you furnished an incorrect TIN, or
- The iRS tells you that you are subject to beckup withholding because you did not report all your interest and dividends only), or

5. You do not certify to the requester that you are not subject to beckup withholding under 4 above (for reportable interest and dividend accounts opened after 1983 only).

Certain payees and payments are exempt from backup withholding. See the Part II instructions on page 2.

#### **Penaities**

Failure to furnish TIN. If your fell to furnish your correct TIN to e requester, you are subject to a penalty of \$50 for each such fellure unless your fellure is due to reasonable cause end not to willful neglect.

Civil penalty for felee information with respect to withholding. If you make a false etetement with no reesonable basis that results in no backup withholding, you are aubject to a \$500 penalty.

Criminal penalty for falaifying information. Willfully falsifying certifications or affirmations may subject you to criminal penalties including fines and/or imprisonment.

Misuse of TiNe. If the requester discloses or uses TiNs in violation of Fedsrel lew, the requester may be subject to civil and criminal penalties.

#### **Specific Instructions**

Name. If you are an individual, you must generally enter the name shown on your social security card. However, if you heve chenged your lest neme, for instance, due to marriage without informing the Social Security Administration of the neme change, anter your first name, the last name shown on your social security card, and your new last name.

If the account is in joint nemes, list first and then circle the name of the person or entity whose number you anter in Part I of the form.

Sole proprietor. Enter your individual name, as shown on your social security card on the "Name" line. You may enter your business, trade, or "doing business as (DBA)" name on the "Business name" line.

Limited tiebility company (LLC). If you are a single-member LLC (including a foreign LLC with a domestic owner) that is disregarded as en entity separate from its owner under Treasury regulations section 301.7701-3, enter the owner's name on the "Name" line. Enter the LLC's name on the "Business name" line.

Caution: A disregarded domestic entily that has a foreign owner must use the appropriate Form W-8.

Other entities. Enter your business neme as shown on raquired Federel tax documents on the 'Name' line. This name should metch the name shown on the oharter or other leget document creating the entity. You may enter any business, trade, or DBA name on the "Business name" line,

### Part 1 - Taxpayer Identification Number (TIN)

### Enter your TIN in the appropriate box.

If you ere e resident atten and you do not have and ere not eligible to get an SSN, your TIN is your IRS individual taxpayer identification number (TIN). Enter it in the social security number box. If you do not heve an ITIN, see How to get a TIN below.

If you are a sote proprietor and you have an EIN, you may enter either your SSN or EIN. However, the IRS prefers that you use your SSN.

if you are an LLC thet is dtaregarded es an entity saperete from its owner (see Limited Iteblity company (LLC) above), and are owned by an individuel, enter your SSN (or "pre-LLC" EIN, if desired). If the owner of a disregarded LLC is a corporation, partnership, etc., enter the owner's EIN.

Note: See the chart on this page for further clarification of name and TIN combinetions.

How to get a TIN. If you do not have a TIN, apply for one immediately. To apply for an SSN, get Form SS-5, Application for a Social Security Card, from your local Social Security Administration office. Get Form W-7, Application for IRS Individual Texpayer Identification Number, to epply for an ITIN or Form SS-4, Application for Employer Identification Number, to apply for an EIN. You can get Forms W-7 and SS-4 from the IRS by calling 1-800-TAX-FORM (1-800-829-3676) or from the IRS's Internet Web Sita www.fra.gov.

If you do not heve a TIN, write "Applied For" in the space for the TIN, sign and dete the form, and give it to the requester. For interest and dividend payments, and certein payments made with reapect to readily tradable instruments, ganerally you will heve 60 deys to get a TIN and give it to the requester before you are subject to backup withholding on payments.

The 60-dey rule does not apply to other types of peyments. You will be subject to beckup withholding on all such payments until you provide your TIN to the requester.

Note: Writing "Applied For" means that you have alreedy epplied for a TIN or that you intend to apply for one soon.

#### Part II - Certification

To establish to the paying agent that your TiN is correct or you are a U.S. person, or resident alien, sign Form W-9.

For a joint account, only the person whole TIN is shown in Part I should sign (when required).

Real estete transactions: You must sign the certification. You may cross out item 2 of the certification.

#### **Privacy Act Notice**

Section 6109 of the Internal Revenue Code requires you to give your correct TIN to parsons who must file Information returns with the IRS to report interest, dividends, and certain other income paid to you, mortgage interest you paid, the ecquisition or abendonment of secured property, cencetlation of dabt, or contributions you mede to an IRA or MSA. The IRS uses the numbers for Identification purposes and to help verify the accuracy of your tax return. The IRS mey also provide this information to the Department of Justice for civil end criminal litigation, and to cities, states, and the District of Columbia to carry out their tax laws

You must provide your TiN whether or not you are required to file e tax retum. Payers must generelly withhold e designated percentage, currently 29% of taxable interest, dividend, and certain other payments to a payee who doas not give a TiN to e payer. Certain peneitles may also apply.

## What Name and Number to Give the Requester

G	ive the Request	ter
For	this type of account:	Give neme and SSN of
1.	Individual	The individual
2.	Two or more	The ectual owner of the
	individuals (joint	account or, if combined
	eccount)	funds, the first
		individuel on the
		account 1
3.	Custodian account of	The minor <sup>2</sup>
	a minor (Uniform Gift	
4.	to Minors Act) a. The usual	The exertes to use a 1
4.	revocable savings	The grantor-trustee 1
	trust (grentor is	
	also trustee)	
	b. So-called trust	The actual owner 1
	account that is not	
	a legal or velid	
	trust under state	
_	law	
5.	Sole proprietorship	The owner 3
For	this type of account:	Give name and EIN of:
6.	Sole proprietorship	The owner 3
7.	A velid trust, estate, or	Legal entity 4
_	pansion trust	
8.	Corporate	The corporation
9.	Associetion, club, religious, charitable,	The organization
	educationat, or other	
	tax-exempt organization	
10.		The pertnership
11.	A broker or registered	The broker or nominee
	nominee	
12.	Account with the	The public entity
	Department of	
	Agriculture in the name	
	of a public entity (such	
	as a state or local	
	government, school district, or prison) thet	
	receives agricultural	
	program payments	
	L O L L	

List first and circle the name of the person whose number you fumish. If only one person on e joint account has an SSN, that person's numbar must be furnished.

Note: If no name is circled whan more than one name is listed, the number will be considered to be that of the first name listed.

if you heve questions on completing this form, pleese contact the Office of the State Comptroller. (617) 973-2311 or 973-2655

Upon completion of this form, please send it to the Commonwealth of Massachusetts Department you are doing business with.

<sup>&</sup>lt;sup>2</sup> Circle the minor's name and furnish the minor's SSN.

<sup>&</sup>lt;sup>3</sup> You must show your individual name, but you may also enter your business or "DBA" neme. You may use either your SSN or EtN (if you heve one).

<sup>4.</sup> List first and circle the name of the lagal trust, estate, or pension trust. (Do not furnish the TIN of the parsonal representative or trustee unless tha legat entity itself is not designated in the account title.)

# COMMONWEALTH OF MASSACHUSETTS CORPORATE CERTIFICATE OF TAX COMPLIANCE

rursuant to the requirements o	1 G.H. C. 02C, S. 47A, CHE
undersigned does hereby state the	following:
I,, as	theof
, whose p	principal place of business is
located at	do
hereby certify that the above named	firm has complied with all laws
of the Commonwealth of Massachuset	ts relating to taxes and has no
outstanding obligation to the Mass	achusetts Department of Revenue.
Signed under the penalties of perj	ury:
Federal Identification Number Name	of Corporation/
Unincorporated Association	
Date Signature of President	
Date Signature of Treasurer	
COMMONWEALTH	OF MASSACHUSETTS
On this day of	, before me,
the undersigned notary pu	ablic, personally appeared
proved to me through satisfactory e	evidence of identification, which
consisted of	
	e the person whose name is signed
on the preceding or attached docum	_
he/she signed it as	for
	, a corporation, voluntarily
for its stated purpose.	
	NAME:
	Notary Public My commission
	evnires:

# COMMONWEALTH OF MASSACHUSETTS INDIVIDUAL CERTIFICATE OF TAX COMPLIANCE

Pursuant to the requirements of G.L. c. 62C, s. 49A, the		
undersigned does hereby state the following:		
I,, certify that I have		
filed all state tax returns, have paid all state taxes required		
under law, and have no outstanding obligation or unpaid debt to		
the Massachusetts Department of Revenue.		
the massachusetts beparement of hevenue.		
Signed under the penalties of perjury:		
Date Signature		
Social Security Number Typed or Printed Name		
COMMONWEALTH OF MASSACHUSETTS		
On this day of, before me,		
On this, before me, the undersigned notary public, personally appeared		
the undersigned notary public, personally appeared		
the undersigned notary public, personally appeared		
the undersigned notary public, personally appeared proved to me through satisfactory evidence of identification, which		
the undersigned notary public, personally appeared  proved to me through satisfactory evidence of identification, which consisted of  , to be the person whose name is signed		
the undersigned notary public, personally appeared  proved to me through satisfactory evidence of identification, which consisted of  to be the person whose name is signed on the preceding or attached document, and acknowledged to me that		
the undersigned notary public, personally appeared  proved to me through satisfactory evidence of identification, which consisted of  to be the person whose name is signed on the preceding or attached document, and acknowledged to me that		
the undersigned notary public, personally appeared  proved to me through satisfactory evidence of identification, which consisted of  to be the person whose name is signed on the preceding or attached document, and acknowledged to me that		
the undersigned notary public, personally appeared  proved to me through satisfactory evidence of identification, which consisted of  to be the person whose name is signed on the preceding or attached document, and acknowledged to me that		
proved to me through satisfactory evidence of identification, which consisted of, to be the person whose name is signed on the preceding or attached document, and acknowledged to me that he/she signed it voluntarily for its stated purpose.		

#### CERTIFICATION PERTAINING TO INELIGIBLE CONTRACTORS

Date:
A. The
(Name and Address of Bidder)
Hereby certifies that it is not included on the Commonwealth of Massachusetts – EOEF/DCPO – List of Debarred or Suspended Contractors, or the Concerns on Debarment List from the Massachusetts Attorney General's Fair Labor and Business Practices Division.
Signature of Authorized Representative of Bidder
Title
B. The
(Name and Address of Bidder)
Hereby certifies that it is included on the Commonwealth of Massachusetts – EOEF/DCPO – List of Debarred or Suspended Contractors, or the Concerns on Debarment List from the Massachusetts Attorney General's Fair Labor and Business Practices Division.
Signature of Authorized Representative of Bidder
Title

NOTE: A bidder may not be eligible for award of a contract(s) under this notice to bidders unless such bidder has submitted as part of its bid the following certification pertaining to ineligible contractors which will be deemed a part of the resulting contract(s).

It is a condition of this Bid, and shall be made a condition of each sub-contract entered into pursuant to this Contract, that the Contractor and any subcontractor shall not require any laborer or mechanic employed in performance of the Contract to work in surroundings or under working conditions which are unsanitary, hazardous, or dangerous to his/her health or safety, as determined under construction safety and health regulation (Title 29, Code of Federal Regulations, Part 1518, published in the Federal Register on April 17, 1971.) promulgated by the United States Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act, (83 Stat. 96).

The undersigned hereby certifies that he/she is able to furnish labor that can work in harmony with all
other elements of labor employed or to be employed on the work.

Ful	l Name and	l address	of th	ne individ	lual or	concern s	ubmitting t	his Bid
-----	------------	-----------	-------	------------	---------	-----------	-------------	---------

Date: 20	
Name of Bidder:	
Signed:	
Title:	
Address:	

Notice: Bidders must set forth, accurate and complete information as required by this solicitation. Failure to do so may render the offer non-responsive or unacceptable.

### SECTION 00610 PERFORMANCE BOND

KNOW ALL M	IEN BY THESE PRESEN	ITS: That we	
		(Na	ame of Contractor)
a		hereinafter call	led "Principal" and
(Corporation, Partner	ship, Joint Venture or Ind	ividual)	
	of	, State of	(City & State)
(Surety)			(City & State)
	nusetts, hereinafter called '	Do	ollars
(\$			or the payment of which sum well and
firmly by these present		ecutors, administrator	rs and successors, jointly and severally,
contract with the City,		of	reas, the Principal entered into a certain, 20 (the "Construction Contract"),

NOW, THEREFORE, if the Principal shall well, truly and faithfully perform its duties, all the undertakings, covenants, terms, conditions, and agreements of the Construction Contract during the original term thereof, and any extensions thereof which may be granted by the City, with or without notice to the Surety, and if he shall satisfy all claims and demands incurred under the Construction Contract, and shall fully indemnify and save harmless the City from all costs and damages which it may suffer by reason of failure to do so, and shall reimburse and repay the City all outlay and expense which the City may incur in making good any default, then this obligation shall be void; otherwise to remain in full force and effect.

PROVIDED, FURTHER, that the Surety's obligation under this Bond shall arise after (1) the City has declared the Principal in default of the Construction Contract or any provision thereof or (2) has declared that the Principal has failed, or is otherwise unable or unwilling, to execute the work consistent with, and in conformance to, the Construction Contract (collectively referred to as a "Contractor Default"). The determination of a Contractor Default shall be made solely by the City. The City need not terminate the Construction Contract to declare a Contractor Default or to invoke its rights under this Bond.

When the Surety's obligation under this Bond arises, the Surety, at its sole expense and at the consent and election of the City, shall promptly take one of the following steps: (1) arrange for the Principal to perform and complete the work of the Construction Contract: (2) arrange for a contractor other than the Principal to perform and complete the work of the Construction Contract; (3) reimburse the City, in a manner and at such time as the City shall decide, for all costs and expenses incurred by the City in performing and completing the work of the Construction Contract. Surety will keep City reasonably informed of the progress, status and results of any investigation of any claim of the City.

If the Surety does not proceed as provided in this Bond with due diligence and all deliberate speed, the Surety shall be deemed to be in default of this Bond, and the City shall be entitled to enforce any remedy available to the City.

After the Surety's obligation under this Bond arises, the Surety is obligated, to the limit of the amounts of this Bond, for (1) the correction of defective work and completion of the Construction Contract; (2) additional design, professional services, and legal costs, including attorneys' fees, resulting from the Contractor Default or from the default of the Surety under this Bond; (3) any additional work beyond the Construction Contract made necessary by the Contractor Default or default of the Surety under this Bond; (4) indemnification obligation of the Principal, if any, as provided in the Construction Contract; and (5) liquidated damages as provided in the Construction Contract, or if none are so specified, actual and foreseeable consequential damages resulting from the Contractor Default or default of the Surety under this Bond.

Any proceeding, legal or equitable, under this Bond shall be instituted in any court of competent jurisdiction in the Commonwealth of Massachusetts.

The Surety, for value received, hereby stipulates and agrees that no change, extension of time, alteration or addition to the terms of the Construction Contract or to the work to be performed thereunder or the specifications accompanying the same shall in any way affect its obligation on this Bond, and it does hereby waive notice of any such change, extension of time, alteration or addition to the terms of the Construction Contract or to the work or to the specifications.

		Principal
	_	•
(Principal Secretary)	By _	
Finicipal Secretary)		
		(Address-Zip Code)
	(SEAL)	
Witness as to Principal		
(Address-Zip Code)		
ATTEST:		
		Surety
	By	
		(Attorney-in-Fact)
		(Address-Zip Code)
Witness as to Surety	(SEAL)	
withess as to Surety		

NOTE: Date of Bond must not be prior to date of Contract. If Contractor is a Partnership, all partners should execute Bond.

### SECTION 00615 PAYMENT BOND

KNOW ALL MEN BY THESE PRESENTS. That we

KNOW ALL MEN DI THE	ESET RESERVES. That we
	a
(Name of Contractor)	(Corporation, Partnership, Joint Venture or Individual)
hereinafter called "Principal" and	of
	(Surety)
State of	hereinafter called the "Surety" and licensed by the State
(City and State)	<u> </u>
	s under the laws of the Commonwealth of Massachusetts, are held and dford, Massachusetts, hereinafter called "City", in the penal sum of Dollars
· <del></del>	money of the United States, for the payment of which sum well and truly to rs, executors, administrators and successors, jointly and severally, firmly by
	S OBLIGATION is such that Whereas, the Principal entered into a certain day of, 20, for the construction

NOW, THEREFORE, if the Principal shall promptly make payment to all persons, firms, subcontractors, and corporations furnishing materials for or performing labor in the prosecution of the work provided for in such contract, and any authorized extension or modification thereof, including all amounts due for materials, lubricants, oil, gasoline, coal and coke, repairs on machinery, equipment and tools, consumed or used in connection with the construction of such work, and all insurance premiums on said work, and for all labor, performed in such work whether by subcontractor or otherwise, then this obligation shall be void; otherwise to remain in full force and effect.

PROVIDED, FURTHER, that the said Surety, for value received hereby stipulates and agrees that no change, extension of time, alteration or addition to the terms of the contract or to the work to be performed thereunder or the specifications accompanying the same shall in any way affect its obligation on this bond, and it does hereby waive notice of any such change, extension of time, alteration or addition to the terms of this contract or to the work or to the specifications.

PROVIDED, FURTHER, that no final settlement between the City and the Contractor shall abridge the right of any beneficiary hereunder, whose claim may be unsatisfied.

ATTEST:			
	_	Surety	
	By _		
		(Attorney-in-Fact)	
	-		
	_	(Address-Zip Code)	
	(SEAL)	(Fidd. 255 2.p = 5000)	
Witness as to Surety			
	_		
(Address-Zip Code)	<u> </u>		

should execute Bond.

This document has important legal consequences; consultation with an attorney is encouraged with respect to its use or modification. This document should be adapted to the particular circumstances of the contemplated Project and the controlling Laws and Regulations.

#### STANDARD GENERAL CONDITIONS OF THE CONSTRUCTION CONTRACT

Prepared by

#### ENGINEERS JOINT CONTRACT DOCUMENTS COMMITTEE

and

Issued and Published Jointly by









AMERICAN COUNCIL OF ENGINEERING COMPANIES

ASSOCIATED GENERAL CONTRACTORS OF AMERICA

AMERICAN SOCIETY OF CIVIL ENGINEERS

PROFESSIONAL ENGINEERS IN PRIVATE PRACTICE A Practice Division of the NATIONAL SOCIETY OF PROFESSIONAL ENGINEERS

Endorsed by



CONSTRUCTION SPECIFICATIONS INSTITUTE

These General Conditions have been prepared for use with the Suggested Forms of Agreement Between Owner and Contractor (EJCDC C-520 or C-525, 2007 Editions). Their provisions are interrelated and a change in one may necessitate a change in the other. Comments concerning their usage are contained in the Narrative Guide to the EJCDC Construction Documents (EJCDC C-001, 2007 Edition). For guidance in the preparation of Supplementary Conditions, see Guide to the Preparation of Supplementary Conditions (EJCDC C-800, 2007 Edition).

Copyright © 2007 National Society of Professional Engineers 1420 King Street, Alexandria, VA 22314-2794 (703) 684-2882 www.nspe.org

> American Council of Engineering Companies 1015 15th Street N.W., Washington, DC 20005 (202) 347-7474 www.acec.org

American Society of Civil Engineers 1801 Alexander Bell Drive, Reston, VA 20191-4400 (800) 548-2723 www.asce.org

Associated General Contractors of America 2300 Wilson Boulevard, Suite 400, Arlington, VA 22201-3308 (703) 548-3118 www.agc.org

The copyright for this EJCDC document is owned jointly by the four EJCDC sponsoring organizations and held in trust for their benefit by NSPE.

## STANDARD GENERAL CONDITIONS OF THE CONSTRUCTION CONTRACT

### TABLE OF CONTENTS

		Page
Article 1 – D	Pefinitions and Terminology	6
1.01	Defined Terms	
1.02	Terminology	
A -41-1-2 D	will with an Markey	0
	reliminary Matters	
2.01	Delivery of Bonds and Evidence of Insurance	
2.02	Copies of Documents	
2.03	Commencement of Contract Times; Notice to Proceed	
2.04	Starting the Work	
2.05	Before Starting Construction.	
2.06	Preconstruction Conference; Designation of Authorized Representatives	
2.07	Initial Acceptance of Schedules	10
	ontract Documents: Intent, Amending, Reuse	
3.01	Intent	
3.02	Reference Standards	
3.03	Reporting and Resolving Discrepancies	
3.04	Amending and Supplementing Contract Documents	
3.05	Reuse of Documents	
3.06	Electronic Data	12
Article 4 – A	vailability of Lands; Subsurface and Physical Conditions; Hazardous Environmental Condition	ns; Reference Points12
4.01	Availability of Lands	
4.02	Subsurface and Physical Conditions	
4.03	Differing Subsurface or Physical Conditions	
4.04	Underground Facilities	
4.05	Reference Points	
4.06	Hazardous Environmental Condition at Site	
Article 5 – B	onds and Insurance	16
5.01	Performance, Payment, and Other Bonds	
5.02	Licensed Sureties and Insurers	
5.03	Certificates of Insurance.	
5.04	Contractor's Insurance	
5.05	Owner's Liability Insurance	
5.06	Property Insurance	
5.07	Waiver of Rights	
5.08	Receipt and Application of Insurance Proceeds	
5.09	Acceptance of Bonds and Insurance; Option to Replace	
5.10	Partial Utilization, Acknowledgment of Property Insurer	
5.10	1 attai Guilzation, Acknowledgment of Troperty Insurer	20
	ontractor's Responsibilities	
6.01	Supervision and Superintendence	
6.02	Labor; Working Hours	
6.03	Services, Materials, and Equipment	
6.04	Progress Schedule	
6.05	Substitutes and "Or-Equals"	
6.06	Concerning Subcontractors, Suppliers, and Others	23

6.07	Patent Fees and Royalties	24
6.08	Permits	
6.09	Laws and Regulations	
6.10	Taxes	
6.11	Use of Site and Other Areas	
6.12	Record Documents	
6.13	Safety and Protection	
6.14	Safety Representative	
6.15	Hazard Communication Programs	
6.16	Emergencies.	
6.17	Shop Drawings and Samples	
6.18	Continuing the Work	
6.19	Contractor's General Warranty and Guarantee	
6.20	Indemnification	
6.21	Delegation of Professional Design Services	
Article 7 – O	ther Work at the Site	30
7.01	Related Work at Site	30
7.02	Coordination	
7.03	Legal Relationships	
Article 8 – O	wner's Responsibilities	31
8.01	Communications to Contractor	
8.02	Replacement of Engineer	
8.03	Furnish Data	
8.04	Pay When Due	
8.05	Lands and Easements; Reports and Tests	
8.06	Insurance	
8.07	Change Orders	
8.08	Inspections, Tests, and Approvals	
8.09	Limitations on Owner's Responsibilities	
8.10	Undisclosed Hazardous Environmental Condition	31
8.11	Evidence of Financial Arrangements	31
8.12	Compliance with Safety Program	
Article 9 – Eı	ngineer's Status During Construction	32
9.01	Owner's Representative	32
9.02	Visits to Site	
9.03	Project Representative	32
9.04	Authorized Variations in Work	32
9.05	Rejecting Defective Work	32
9.06	Shop Drawings, Change Orders and Payments	32
9.07	Determinations for Unit Price Work	
9.08	Decisions on Requirements of Contract Documents and Acceptability of Work	
9.09	Limitations on Engineer's Authority and Responsibilities	
9.10	Compliance with Safety Program	34
Article 10 – 0	Changes in the Work; Claims	34
10.01	Authorized Changes in the Work	
10.02	Unauthorized Changes in the Work	34
10.03	· · · · · · · · · · · · · · · · · · ·	
10.04	Notification to Surety	
	Claims	
Article 11 – 0	Cost of the Work; Allowances; Unit Price Work	35
	Cost of the Work	

11.02	Allowances	37
	Unit Price Work	
	Change of Contract Price; Change of Contract Times	
	Change of Contract Price	
	Change of Contract Times	
12.03	Delays	39
Article 13 – T	Fests and Inspections; Correction, Removal or Acceptance of Defective Work	39
	Notice of Defects	
13.02		
13.03		
13.04	1	
13.05	· ·	
13.06	• 1	
13.07		
13.08	Acceptance of Defective Work	
13.09	Owner May Correct Defective Work	
Article 14 – F	Payments to Contractor and Completion	
14.01		
14.02		
14.03	•	
14.04	1 · · · · · · · · · · · · · · · · · · ·	
14.05		
14.06	Final Inspection	45
14.07	•	
14.08	1	
14.09	Waiver of Claims	47
Article 15	Suspension of Work and Termination	47
	Owner May Suspend Work	
	Owner May Terminate for Cause	
	Owner May Terminate For Convenience	
	Contractor May Stop Work or Terminate	
13.04	Contractor way Stop work or Terminate	40
Article 16 – I	Dispute Resolution	48
16.01	Methods and Procedures	48
Article 17 N	Miscellaneous	40
17.01	Giving Notice	
17.01	Computation of Times.	
17.02	Cumulative Remedies.	
17.03	Survival of Obligations	
17.04	Controlling Law.	
17.05	č	
17.00	110au11150	

#### ARTICLE 1 – DEFINITIONS AND TERMINOLOGY

#### 1.01 Defined Terms

- A. Wherever used in the Bidding Requirements or Contract Documents and printed with initial capital letters, the terms listed below will have the meanings indicated which are applicable to both the singular and plural thereof. In addition to terms specifically defined, terms with initial capital letters in the Contract Documents include references to identified articles and paragraphs, and the titles of other documents or forms.
  - Addenda—Written or graphic instruments issued prior to the opening of Bids which clarify, correct, or change the Bidding Requirements or the proposed Contract Documents.
  - Agreement—The written instrument which is evidence of the agreement between Owner and Contractor covering the Work.
  - Application for Payment—The form acceptable to Engineer which is to be used by Contractor during the course of the Work in requesting progress or final payments and which is to be accompanied by such supporting documentation as is required by the Contract Documents.
  - 4. Asbestos—Any material that contains more than one percent asbestos and is friable or is releasing asbestos fibers into the air above current action levels established by the United States Occupational Safety and Health Administration.
  - 5. *Bid*—The offer or proposal of a Bidder submitted on the prescribed form setting forth the prices for the Work to be performed.
  - 6. *Bidder*—The individual or entity who submits a Bid directly to Owner.
  - 7. Bidding Documents—The Bidding Requirements and the proposed Contract Documents (including all Addenda).
  - 8. *Bidding Requirements*—The advertisement or invitation to bid, Instructions to Bidders, Bid security of acceptable form, if any, and the Bid Form with any supplements.

- Change Order—A document recommended by Engineer which is signed by Contractor and Owner and authorizes an addition, deletion, or revision in the Work or an adjustment in the Contract Price or the Contract Times, issued on or after the Effective Date of the Agreement.
- 10. Claim—A demand or assertion by Owner or Contractor seeking an adjustment of Contract Price or Contract Times, or both, or other relief with respect to the terms of the Contract. A demand for money or services by a third party is not a Claim.
- 11. *Contract*—The entire and integrated written agreement between the Owner and Contractor concerning the Work. The Contract supersedes prior negotiations, representations, or agreements, whether written or oral.
- 12. Contract Documents—Those items so designated in the Agreement. Only printed or hard copies of the items listed in the Agreement are Contract Documents. Approved Shop Drawings, other Contractor submittals, and the reports and drawings of subsurface and physical conditions are not Contract Documents.
- 13. Contract Price—The moneys payable by Owner to Contractor for completion of the Work in accordance with the Contract Documents as stated in the Agreement (subject to the provisions of Paragraph 11.03 in the case of Unit Price Work).
- 14. Contract Times—The number of days or the dates stated in the Agreement to: (i) achieve Milestones, if any; (ii) achieve Substantial Completion; and (iii) complete the Work so that it is ready for final payment as evidenced by Engineer's written recommendation of final payment.
- 15. *Contractor*—The individual or entity with whom Owner has entered into the Agreement.
- 16. *Cost of the Work*—See Paragraph 11.01 for definition.
- 17. *Drawings*—That part of the Contract Documents prepared or approved by Engineer which graphically shows the scope, extent, and character of the Work to be

- performed by Contractor. Shop Drawings and other Contractor submittals are not Drawings as so defined.
- 18. Effective Date of the Agreement—The date indicated in the Agreement on which it becomes effective, but if no such date is indicated, it means the date on which the Agreement is signed and delivered by the last of the two parties to sign and deliver.
- 19. *Engineer*—The individual or entity named as such in the Agreement.
- 20. Field Order—A written order issued by Engineer which requires minor changes in the Work but which does not involve a change in the Contract Price or the Contract Times.
- 21. *General Requirements*—Sections of Division 1 of the Specifications.
- 22. Hazardous Environmental Condition—The presence at the Site of Asbestos, PCBs, Petroleum, Hazardous Waste, or Radioactive Material in such quantities or circumstances that may present a substantial danger to persons or property exposed thereto.
- 23. *Hazardous Waste*—The term Hazardous Waste shall have the meaning provided in Section 1004 of the Solid Waste Disposal Act (42 USC Section 6903) as amended from time to time.
- 24. Laws and Regulations; Laws or Regulations—Any and all applicable laws, rules, regulations, ordinances, codes, and orders of any and all governmental bodies, agencies, authorities, and courts having jurisdiction.
- 25. *Liens*—Charges, security interests, or encumbrances upon Project funds, real property, or personal property.
- 26. Milestone—A principal event specified in the Contract Documents relating to an intermediate completion date or time prior to Substantial Completion of all the Work.
- 27. Notice of Award—The written notice by Owner to the Successful Bidder stating that upon timely compliance by the Successful Bidder with the conditions precedent listed

- therein, Owner will sign and deliver the Agreement.
- 28. *Notice to Proceed*—A written notice given by Owner to Contractor fixing the date on which the Contract Times will commence to run and on which Contractor shall start to perform the Work under the Contract Documents.
- 29. *Owner*—The individual or entity with whom Contractor has entered into the Agreement and for whom the Work is to be performed.
- 30. PCBs—Polychlorinated biphenyls.
- 31. Petroleum—Petroleum, including crude oil or any fraction thereof which is liquid at standard conditions of temperature and pressure (60 degrees Fahrenheit and 14.7 pounds per square inch absolute), such as oil, petroleum, fuel oil, oil sludge, oil refuse, gasoline, kerosene, and oil mixed with other non-Hazardous Waste and crude oils.
- 32. *Progress Schedule*—A schedule, prepared and maintained by Contractor, describing the sequence and duration of the activities comprising the Contractor's plan to accomplish the Work within the Contract Times.
- 33. *Project*—The total construction of which the Work to be performed under the Contract Documents may be the whole, or a part.
- 34. *Project Manual*—The bound documentary information prepared for bidding and constructing the Work. A listing of the contents of the Project Manual, which may be bound in one or more volumes, is contained in the table(s) of contents.
- 35. Radioactive Material—Source, special nuclear, or byproduct material as defined by the Atomic Energy Act of 1954 (42 USC Section 2011 et seq.) as amended from time to time.
- 36. Resident Project Representative—The authorized representative of Engineer who may be assigned to the Site or any part thereof.
- 37. Samples—Physical examples of materials, equipment, or workmanship that are representative of some portion of the Work

- and which establish the standards by which such portion of the Work will be judged.
- 38. Schedule of Submittals—A schedule, prepared and maintained by Contractor, of required submittals and the time requirements to support scheduled performance of related construction activities.
- 39. Schedule of Values—A schedule, prepared and maintained by Contractor, allocating portions of the Contract Price to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment.
- 40. Shop Drawings—All drawings, diagrams, illustrations, schedules, and other data or information which are specifically prepared or assembled by or for Contractor and submitted by Contractor to illustrate some portion of the Work.
- 41. Site—Lands or areas indicated in the Contract Documents as being furnished by Owner upon which the Work is to be performed, including rights-of-way and easements for access thereto, and such other lands furnished by Owner which are designated for the use of Contractor.
- 42. Specifications—That part of the Contract Documents consisting of written requirements for materials, equipment, systems, standards and workmanship as Work. applied to the and certain administrative requirements and procedural matters applicable thereto.
- 43. *Subcontractor*—An individual or entity having a direct contract with Contractor or with any other Subcontractor for the performance of a part of the Work at the Site.
- 44. Substantial Completion—The time at which the Work (or a specified part thereof) has progressed to the point where, in the opinion of Engineer, the Work (or a specified part thereof) is sufficiently complete, in accordance with the Contract Documents, so that the Work (or a specified part thereof) can be utilized for the purposes for which it is intended. The terms "substantially complete" and "substantially completed" as applied to all or part of the Work refer to Substantial Completion thereof.

- 45. Successful Bidder—The Bidder submitting a responsive Bid to whom Owner makes an award.
- 46. Supplementary Conditions—That part of the Contract Documents which amends or supplements these General Conditions.
- 47. Supplier—A manufacturer, fabricator, supplier, distributor, materialman, or vendor having a direct contract with Contractor or with any Subcontractor to furnish materials or equipment to be incorporated in the Work by Contractor or Subcontractor.
- 48. *Underground Facilities*—All underground pipelines, conduits, ducts, cables, wires, manholes, vaults, tanks, tunnels, or other such facilities or attachments, and any encasements containing such facilities, including those that convey electricity, gases, steam, liquid petroleum products, telephone or other communications, cable television, water, wastewater, storm water, other liquids or chemicals, or traffic or other control systems.
- 49. *Unit Price Work*—Work to be paid for on the basis of unit prices.
- 50. Work—The entire construction or the various separately identifiable parts thereof required to be provided under the Contract Documents. Work includes and is the result of performing or providing all labor, services, and documentation necessary to produce such construction, and furnishing, installing, and incorporating all materials and equipment into such construction, all as required by the Contract Documents.
- 51. Work Change Directive—A written statement to Contractor issued on or after the Effective Date of the Agreement and signed by Owner and recommended by Engineer ordering an addition, deletion, or revision in the Work, or responding to differing or unforeseen subsurface or physical conditions under which the Work is to be performed or to emergencies. A Work Change Directive will not change the Contract Price or the Contract Times but is evidence that the parties expect that the change ordered or documented by a Work Change Directive will be incorporated in a subsequently issued Change Order following negotiations by the parties as to its

effect, if any, on the Contract Price or Contract Times.

#### 1.02 *Terminology*

A. The words and terms discussed in Paragraph 1.02.B through F are not defined but, when used in the Bidding Requirements or Contract Documents, have the indicated meaning.

#### B. Intent of Certain Terms or Adjectives:

The Contract Documents include the terms "as allowed," "as approved," "as ordered," "as directed" or terms of like effect or import to authorize an exercise of professional judgment by Engineer. In addition, the adjectives "reasonable," "suitable." "acceptable," "proper," "satisfactory," or adjectives of like effect or import are used to describe an action or determination of Engineer as to the Work. It is intended that such exercise of professional judgment, action, or determination will be solely to evaluate, in general, the Work for compliance with the information in the Contract Documents and with the design concept of the Project as a functioning whole as shown or indicated in the Contract Documents (unless there is a specific statement indicating otherwise). The use of any such term or adjective is not intended to and shall not be effective to assign to Engineer any duty or authority to supervise or direct the performance of the Work, or any duty or authority to undertake responsibility contrary to the provisions of Paragraph 9.09 or any other provision of the Contract Documents.

#### C. Day:

1. The word "day" means a calendar day of 24 hours measured from midnight to the next midnight.

#### D. Defective:

- 1. The word "defective," when modifying the word "Work," refers to Work that is unsatisfactory, faulty, or deficient in that it:
  - a. does not conform to the Contract Documents; or
  - b. does not meet the requirements of any applicable inspection, reference standard,

test, or approval referred to in the Contract Documents; or

c. has been damaged prior to Engineer's recommendation of final payment (unless responsibility for the protection thereof has been assumed by Owner at Substantial Completion in accordance with Paragraph 14.04 or 14.05).

#### E. Furnish, Install, Perform, Provide:

- 1. The word "furnish," when used in connection with services, materials, or equipment, shall mean to supply and deliver said services, materials, or equipment to the Site (or some other specified location) ready for use or installation and in usable or operable condition.
- 2. The word "install," when used in connection with services, materials, or equipment, shall mean to put into use or place in final position said services, materials, or equipment complete and ready for intended use.
- 3. The words "perform" or "provide," when used in connection with services, materials, or equipment, shall mean to furnish and install said services, materials, or equipment complete and ready for intended use.
- 4. When "furnish," "install," "perform," or "provide" is not used in connection with services, materials, or equipment in a context clearly requiring an obligation of Contractor, "provide" is implied.
- F. Unless stated otherwise in the Contract Documents, words or phrases that have a well-known technical or construction industry or trade meaning are used in the Contract Documents in accordance with such recognized meaning.

#### ARTICLE 2 – PRELIMINARY MATTERS

- 2.01 Delivery of Bonds and Evidence of Insurance
  - A. When Contractor delivers the executed counterparts of the Agreement to Owner, Contractor shall also deliver to Owner such bonds as Contractor may be required to furnish.
  - B. *Evidence of Insurance:* Before any Work at the Site is started, Contractor and Owner shall each deliver to the other, with copies to each additional

insured identified in the Supplementary Conditions, certificates of insurance (and other evidence of insurance which either of them or any additional insured may reasonably request) which Contractor and Owner respectively are required to purchase and maintain in accordance with Article 5.

#### 2.02 Copies of Documents

A. Owner shall furnish to Contractor up to ten printed or hard copies of the Drawings and Project Manual. Additional copies will be furnished upon request at the cost of reproduction.

#### 2.03 Commencement of Contract Times; Notice to Proceed

A. The Contract Times will commence to run on the thirtieth day after the Effective Date of the Agreement or, if a Notice to Proceed is given, on the day indicated in the Notice to Proceed. A Notice to Proceed may be given at any time within 30 days after the Effective Date of the Agreement. In no event will the Contract Times commence to run later than the sixtieth day after the day of Bid opening or the thirtieth day after the Effective Date of the Agreement, whichever date is earlier.

#### 2.04 Starting the Work

A. Contractor shall start to perform the Work on the date when the Contract Times commence to run. No Work shall be done at the Site prior to the date on which the Contract Times commence to run.

#### 2.05 Before Starting Construction

- A. *Preliminary Schedules:* Within 10 days after the Effective Date of the Agreement (unless otherwise specified in the General Requirements), Contractor shall submit to Engineer for timely review:
  - a preliminary Progress Schedule indicating the times (numbers of days or dates) for starting and completing the various stages of the Work, including any Milestones specified in the Contract Documents;
  - 2. a preliminary Schedule of Submittals; and
  - a preliminary Schedule of Values for all of the Work which includes quantities and prices of items which when added together equal the Contract Price and subdivides the Work into component parts in sufficient

detail to serve as the basis for progress payments during performance of the Work. Such prices will include an appropriate amount of overhead and profit applicable to each item of Work.

## 2.06 Preconstruction Conference; Designation of Authorized Representatives

- A. Before any Work at the Site is started, a conference attended by Owner, Contractor, Engineer, and others as appropriate will be held to establish a working understanding among the parties as to the Work and to discuss the schedules referred to in Paragraph 2.05.A, procedures for handling Shop Drawings and other submittals, processing Applications for Payment, and maintaining required records.
- B. At this conference Owner and Contractor each shall designate, in writing, a specific individual to act as its authorized representative with respect to the services and responsibilities under the Contract. Such individuals shall have the authority to transmit instructions, receive information, render decisions relative to the Contract, and otherwise act on behalf of each respective party.

#### 2.07 Initial Acceptance of Schedules

- A. At least 10 days before submission of the first Application for Payment a conference attended by Contractor, Engineer, and others as appropriate will be held to review for acceptability to Engineer as provided below the schedules submitted in accordance with Paragraph 2.05.A. Contractor shall have an additional 10 days to make corrections and adjustments and to complete and resubmit the schedules. No progress payment shall be made to Contractor until acceptable schedules are submitted to Engineer.
  - The Progress Schedule will be acceptable to Engineer if it provides an orderly progression of the Work to completion within the Contract Times. Such acceptance will not impose on Engineer responsibility for the Progress Schedule, for sequencing, scheduling, or progress of the Work, nor interfere with or relieve Contractor from Contractor's full responsibility therefor.
  - 2. Contractor's Schedule of Submittals will be acceptable to Engineer if it provides a

- workable arrangement for reviewing and processing the required submittals.
- Contractor's Schedule of Values will be acceptable to Engineer as to form and substance if it provides a reasonable allocation of the Contract Price to component parts of the Work.

## ARTICLE 3 – CONTRACT DOCUMENTS: INTENT, AMENDING, REUSE

#### 3.01 Intent

- A. The Contract Documents are complementary; what is required by one is as binding as if required by all.
- B. It is the intent of the Contract Documents to describe a functionally complete project (or part thereof) to be constructed in accordance with the Contract Documents. Any labor, documentation, services, materials, or equipment that reasonably may be inferred from the Contract Documents or from prevailing custom or trade usage as being required to produce the indicated result will be provided whether or not specifically called for, at no additional cost to Owner.
- C. Clarifications and interpretations of the Contract Documents shall be issued by Engineer as provided in Article 9.

#### 3.02 Reference Standards

- A. Standards, Specifications, Codes, Laws, and Regulations
  - Reference to standards, specifications, manuals, or codes of any technical society, organization, or association, or to Laws or Regulations, whether such reference be specific or by implication, shall mean the standard, specification, manual, code, or Laws or Regulations in effect at the time of opening of Bids (or on the Effective Date of the Agreement if there were no Bids), except as may be otherwise specifically stated in the Contract Documents.
  - No provision of any such standard, specification, manual, or code, or any instruction of a Supplier, shall be effective to change the duties or responsibilities of Owner, Contractor, or Engineer, or any of their subcontractors, consultants, agents, or

employees, from those set forth in the Contract Documents. No such provision or instruction shall be effective to assign to Owner, Engineer, or any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors, any duty or authority to supervise or direct the performance of the Work or any duty or authority to undertake responsibility inconsistent with the provisions of the Contract Documents.

#### 3.03 Reporting and Resolving Discrepancies

#### A. Reporting Discrepancies:

- 1. Contractor's Review of Contract Documents
  Before Starting Work: Before undertaking
  each part of the Work, Contractor shall
  carefully study and compare the Contract
  Documents and check and verify pertinent
  figures therein and all applicable field
  measurements. Contractor shall promptly
  report in writing to Engineer any conflict,
  error, ambiguity, or discrepancy which
  Contractor discovers, or has actual
  knowledge of, and shall obtain a written
  interpretation or clarification from Engineer
  before proceeding with any Work affected
  thereby.
- Contractor's Review of Contract Documents During Performance of Work: If, during the performance of the Work, Contractor discovers any conflict, error, ambiguity, or discrepancy within the Contract Documents, or between the Contract Documents and (a) any applicable Law or Regulation . (b) any standard, specification, manual, or code, or (c) any instruction of any Supplier, then Contractor shall promptly report it to Engineer in writing. Contractor shall not proceed with the Work affected thereby (except in an emergency as required by Paragraph 6.16.A) until an amendment or supplement to the Contract Documents has been issued by one of the methods indicated in Paragraph 3.04.
- 3. Contractor shall not be liable to Owner or Engineer for failure to report any conflict, error, ambiguity, or discrepancy in the Contract Documents unless Contractor had actual knowledge thereof.
- B. Resolving Discrepancies:

- Except as may be otherwise specifically stated in the Contract Documents, the provisions of the Contract Documents shall take precedence in resolving any conflict, error, ambiguity, or discrepancy between the provisions of the Contract Documents and:
  - a. the provisions of any standard, specification, manual, or code, or the instruction of any Supplier (whether or not specifically incorporated by reference in the Contract Documents); or 3.06
  - the provisions of any Laws or Regulations applicable to the performance of the Work (unless such an interpretation of the provisions of the Contract Documents would result in violation of such Law or Regulation).
- 3.04 Amending and Supplementing Contract Documents
  - A. The Contract Documents may be amended to provide for additions, deletions, and revisions in the Work or to modify the terms and conditions thereof by either a Change Order or a Work Change Directive.
  - B. The requirements of the Contract Documents may be supplemented, and minor variations and deviations in the Work may be authorized, by one or more of the following ways:
    - 1. A Field Order:
    - 2. Engineer's approval of a Shop Drawing or Sample (subject to the provisions of Paragraph 6.17.D.3); or
    - Engineer's written interpretation or clarification.
- 3.05 Reuse of Documents
  - A. Contractor and any Subcontractor or Supplier shall not:
    - 1. have or acquire any title to or ownership rights in any of the Drawings, Specifications, or other documents (or copies of any thereof) prepared by or bearing the seal of Engineer or its consultants, including electronic media 4.01 editions; or
    - reuse any such Drawings, Specifications, other documents, or copies thereof on

- extensions of the Project or any other project without written consent of Owner and Engineer and specific written verification or adaptation by Engineer.
- B. The prohibitions of this Paragraph 3.05 will survive final payment, or termination of the Contract. Nothing herein shall preclude Contractor from retaining copies of the Contract Documents for record purposes.

#### Electronic Data

- A. Unless otherwise stated in the Supplementary Conditions, the data furnished by Owner or Engineer to Contractor, or by Contractor to Owner or Engineer, that may be relied upon are limited to the printed copies (also known as hard copies). Files in electronic media format of text, data, graphics, or other types are furnished only for the convenience of the receiving party. Any conclusion or information obtained or derived from such electronic files will be at the user's sole risk. If there is a discrepancy between the electronic files and the hard copies, the hard copies govern.
- B. Because data stored in electronic media format can deteriorate or be modified inadvertently or otherwise without authorization of the data's creator, the party receiving electronic files agrees that it will perform acceptance tests or procedures within 60 days, after which the receiving party shall be deemed to have accepted the data thus transferred. Any errors detected within the 60-day acceptance period will be corrected by the transferring party.
- C. When transferring documents in electronic media format, the transferring party makes no representations as to long term compatibility, usability, or readability of documents resulting from the use of software application packages, operating systems, or computer hardware differing from those used by the data's creator.

# have or acquire any title to or ownership rights in any of the Drawings, Specifications, or other documents (or copies of any thereof) ARTICLE 4 – AVAILABILITY OF LANDS; SUBSURFACE AND PHYSICAL CONDITIONS; HAZARDOUS ENVIRONMENTAL CONDITIONS; REFERENCE POINTS

- 4.01 Availability of Lands
  - A. Owner shall furnish the Site. Owner shall notify Contractor of any encumbrances or restrictions not of general application but specifically related to

use of the Site with which Contractor must comply in performing the Work. Owner will obtain in a timely manner and pay for easements for permanent structures or permanent changes in existing facilities. If Contractor and Owner are unable to agree on entitlement to or on the amount or extent, if any, of any adjustment in the Contract Price or Contract Times, or both, as a result of any delay in Owner's furnishing the Site or a part thereof, Contractor may make a Claim therefor as provided in Paragraph 10.05.

- B. Upon reasonable written request, Owner shall furnish Contractor with a current statement of record legal title and legal description of the lands upon which the Work is to be performed and Owner's interest therein as necessary for giving notice of or filing a mechanic's or construction lien against such lands in accordance with applicable Laws and Regulations.
- C. Contractor shall provide for all additional lands and access thereto that may be required for temporary construction facilities or storage of materials and equipment.
- 4.02 Subsurface and Physical Conditions
  - A. *Reports and Drawings:* The Supplementary Conditions identify:
    - those reports known to Owner of explorations and tests of subsurface conditions at or contiguous to the Site; and
    - those drawings known to Owner of physical conditions relating to existing surface or subsurface structures at the Site (except Underground Facilities).
  - B. Limited Reliance by Contractor on Technical Data Authorized: Contractor may rely upon the accuracy of the "technical data" contained in such reports and drawings, but such reports and drawings are not Contract Documents. Such "technical data" is identified in the Supplementary Conditions. Except for such reliance on such "technical data," Contractor may not rely upon or make any claim against Owner or Engineer, or any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors with respect to:
    - the completeness of such reports and drawings for Contractor's purposes, including, but not limited to, any aspects of

the means, methods, techniques, sequences, and procedures of construction to be employed by Contractor, and safety precautions and programs incident thereto; or

- 2. other data, interpretations, opinions, and information contained in such reports or shown or indicated in such drawings; or
- any Contractor interpretation of or conclusion drawn from any "technical data" or any such other data, interpretations, opinions, or information.

#### .03 Differing Subsurface or Physical Conditions

- A. *Notice:* If Contractor believes that any subsurface or physical condition that is uncovered or revealed either:
  - 1. is of such a nature as to establish that any "technical data" on which Contractor is entitled to rely as provided in Paragraph 4.02 is materially inaccurate; or
  - 2. is of such a nature as to require a change in the Contract Documents; or
  - 3. differs materially from that shown or indicated in the Contract Documents; or
  - is of an unusual nature, and differs materially from conditions ordinarily encountered and generally recognized as inherent in work of the character provided for in the Contract Documents;

then Contractor shall, promptly after becoming aware thereof and before further disturbing the subsurface or physical conditions or performing any Work in connection therewith (except in an emergency as required by Paragraph 6.16.A), notify Owner and Engineer in writing about such condition. Contractor shall not further disturb such condition or perform any Work in connection therewith (except as aforesaid) until receipt of written order to do so.

B. *Engineer's Review*: After receipt of written notice as required by Paragraph 4.03.A, Engineer will promptly review the pertinent condition, determine the necessity of Owner's obtaining additional exploration or tests with respect thereto, and advise Owner in writing (with a copy to Contractor) of Engineer's findings and conclusions.

#### C. Possible Price and Times Adjustments:

- The Contract Price or the Contract Times, or both, will be equitably adjusted to the extent that the existence of such differing subsurface 4.04 or physical condition causes an increase or decrease in Contractor's cost of, or time required for, performance of the Work; subject, however, to the following:
  - a. such condition must meet any one or more of the categories described in Paragraph 4.03.A; and
  - b. with respect to Work that is paid for on a unit price basis, any adjustment in Contract Price will be subject to the provisions of Paragraphs 9.07 and 11.03.
- Contractor shall not be entitled to any adjustment in the Contract Price or Contract Times if:
  - a. Contractor knew of the existence of such conditions at the time Contractor made a final commitment to Owner with respect to Contract Price and Contract Times by the submission of a Bid or becoming bound under a negotiated contract; or
  - b. the existence of such condition could reasonably have been discovered or revealed as a result of any examination, investigation, exploration, test, or study of the Site and contiguous areas required by the Bidding Requirements or Contract Documents to be conducted by or for Contractor prior to Contractor's making such final commitment; or
  - c. Contractor failed to give the written notice as required by Paragraph 4.03.A.
- 3. If Owner and Contractor are unable to agree on entitlement to or on the amount or extent, if any, of any adjustment in the Contract Price or Contract Times, or both, a Claim may be made therefor as provided in Paragraph 10.05. However, neither Owner or Engineer, or any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors shall be liable to Contractor for any claims, costs, losses, or damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or

arbitration or other dispute resolution costs) sustained by Contractor on or in connection with any other project or anticipated project.

#### 4 Underground Facilities

- A. Shown or Indicated: The information and data shown or indicated in the Contract Documents with respect to existing Underground Facilities at or contiguous to the Site is based on information and data furnished to Owner or Engineer by the owners of such Underground Facilities, including Owner, or by others. Unless it is otherwise expressly provided in the Supplementary Conditions:
  - 1. Owner and Engineer shall not be responsible for the accuracy or completeness of any such information or data provided by others; and
  - 2. the cost of all of the following will be included in the Contract Price, and Contractor shall have full responsibility for:
    - a. reviewing and checking all such information and data;
    - b. locating all Underground Facilities shown or indicated in the Contract Documents;
    - c. coordination of the Work with the owners of such Underground Facilities, including Owner, during construction; and
    - d. the safety and protection of all such Underground Facilities and repairing any damage thereto resulting from the Work.

#### B. Not Shown or Indicated:

1. If an Underground Facility is uncovered or revealed at or contiguous to the Site which was not shown or indicated, or not shown or indicated with reasonable accuracy in the Contract Documents, Contractor shall, promptly after becoming aware thereof and before further disturbing conditions affected thereby or performing any Work in connection therewith (except in an emergency as required by Paragraph 6.16.A), identify the owner of such Underground Facility and give written notice to that owner and to Owner and Engineer. Engineer will promptly review the Underground Facility and determine the

- extent, if any, to which a change is required in the Contract Documents to reflect and document the consequences of the existence or location of the Underground Facility. During such time, Contractor shall be responsible for the safety and protection of such Underground Facility.
- 2. If Engineer concludes that a change in the Contract Documents is required, a Work Change Directive or a Change Order will be issued to reflect and document such consequences. An equitable adjustment shall be made in the Contract Price or Contract Times, or both, to the extent that they are attributable to the existence or location of any Underground Facility that was not shown or indicated or not shown or indicated with reasonable accuracy in the Contract Documents and that Contractor did not know of and could not reasonably have been expected to be aware of or to have anticipated. If Owner and Contractor are unable to agree on entitlement to or on the amount or extent, if any, of any such adjustment in Contract Price or Contract Times, Owner or Contractor may make a Claim therefor as provided in Paragraph 10.05.

#### 4.05 Reference Points

A. Owner shall provide engineering surveys to establish reference points for construction which in Engineer's judgment are necessary to enable Contractor to proceed with the Work. Contractor shall be responsible for laying out the Work, shall protect and preserve the established reference points and property monuments, and shall make no changes or relocations without the prior written approval of Owner. Contractor shall report to Engineer whenever any reference point or property monument is lost or destroyed or requires relocation because of necessary changes in grades or locations, and shall be responsible for the accurate replacement or relocation of such reference points or property monuments by professionally qualified personnel.

#### 4.06 Hazardous Environmental Condition at Site

A. Reports and Drawings: The Supplementary Conditions identify those reports and drawings known to Owner relating to Hazardous Environmental Conditions that have been identified at the Site.

- B. Limited Reliance by Contractor on Technical Data Authorized: Contractor may rely upon the accuracy of the "technical data" contained in such reports and drawings, but such reports and drawings are not Contract Documents. Such "technical data" is identified in the Supplementary Conditions. Except for such reliance on such "technical data," Contractor may not rely upon or make any claim against Owner or Engineer, or any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors with respect to:
  - the completeness of such reports and drawings for Contractor's purposes, including, but not limited to, any aspects of the means, methods, techniques, sequences and procedures of construction to be employed by Contractor and safety precautions and programs incident thereto; or
  - 2. other data, interpretations, opinions and information contained in such reports or shown or indicated in such drawings; or
  - any Contractor interpretation of or conclusion drawn from any "technical data" or any such other data, interpretations, opinions or information.
- C. Contractor shall not be responsible for any Hazardous Environmental Condition uncovered or revealed at the Site which was not shown or indicated in Drawings or Specifications or identified in the Contract Documents to be within the scope of the Work. Contractor shall be responsible for a Hazardous Environmental Condition created with any materials brought to the Site by Contractor, Subcontractors, Suppliers, or anyone else for whom Contractor is responsible.
- D. If Contractor encounters Hazardous Environmental Condition or if Contractor or anyone for whom Contractor is responsible creates a Hazardous Environmental Condition, Contractor shall immediately: (i) secure or otherwise isolate such condition; (ii) stop all Work in connection with such condition and in any area affected thereby (except in an emergency as required by Paragraph 6.16.A); and (iii) notify Owner and Engineer (and promptly thereafter confirm such notice in writing). Owner shall promptly consult with Engineer concerning the necessity for Owner to retain a qualified expert to evaluate such condition or take corrective action,

if any. Promptly after consulting with Engineer, Owner shall take such actions as are necessary to permit Owner to timely obtain required permits and provide Contractor the written notice required by Paragraph 4.06.E.

- E. Contractor shall not be required to resume Work in connection with such condition or in any affected area until after Owner has obtained any required permits related thereto and delivered written notice to Contractor: (i) specifying that such condition and any affected area is or has been rendered safe for the resumption of Work; or (ii) specifying any special conditions under which such Work may be resumed safely. If Owner and Contractor cannot agree as to entitlement to or on the amount or extent, if any, of any adjustment in Contract Price or Contract Times, or both, as a result of such Work stoppage or such special conditions under which Work is agreed to be resumed by Contractor, either party may make a Claim therefor as provided in Paragraph 10.05.
- If after receipt of such written notice Contractor does not agree to resume such Work based on a reasonable belief it is unsafe, or does not agree to resume such Work under such special conditions, then Owner may order the portion of the Work that is in the area affected by such condition to be **ARTICLE 5 – BONDS AND INSURANCE** deleted from the Work. If Owner and Contractor cannot agree as to entitlement to or on the amount 5.01 or extent, if any, of an adjustment in Contract Price or Contract Times as a result of deleting such portion of the Work, then either party may make a Claim therefor as provided in Paragraph 10.05. Owner may have such deleted portion of the Work performed by Owner's own forces or others in accordance with Article 7.
- G. To the fullest extent permitted by Laws and Regulations, Owner shall indemnify and hold harmless Contractor, Subcontractors, Engineer, and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to a Hazardous Environmental Condition, provided that such Hazardous Environmental Condition: (i) was not shown or indicated in the Drawings or Specifications or identified in the Contract Documents to be included within the scope of the Work, and (ii) was not created by

Contractor or by anyone for whom Contractor is responsible. Nothing in this Paragraph 4.06.G shall obligate Owner to indemnify any individual or entity from and against the consequences of that individual's or entity's own negligence.

- H. To the fullest extent permitted by Laws and Regulations, Contractor shall indemnify and hold harmless Owner and Engineer, and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to a Hazardous Environmental Condition created by Contractor or by anyone for whom Contractor is responsible. Nothing in this Paragraph 4.06.H shall obligate Contractor to indemnify any individual or entity from and against the consequences of that individual's or entity's own negligence.
- The provisions of Paragraphs 4.02, 4.03, and 4.04 do not apply to a Hazardous Environmental Condition uncovered or revealed at the Site.

- Performance, Payment, and Other Bonds
  - A. Contractor shall furnish performance and payment bonds, each in an amount at least equal to the Contract Price as security for the faithful performance and payment of all of Contractor's obligations under the Contract Documents. These bonds shall remain in effect until one year after the date when final payment becomes due or until completion of the correction period specified in Paragraph 13.07, whichever is later, except as provided otherwise by Laws or Regulations or by the Contract Documents. Contractor shall also furnish such other bonds as are required by the Contract Documents.
  - B. All bonds shall be in the form prescribed by the Contract Documents except as provided otherwise by Laws or Regulations, and shall be executed by such sureties as are named in the list of "Companies Holding Certificates of Authority as Acceptable Sureties on Federal Bonds and as Acceptable Reinsuring Companies" as published in Circular 570 (amended) by the Financial Management Service, Surety Bond Branch, U.S. Department of the Treasury. All bonds signed by

- an agent or attorney-in-fact must be accompanied by a certified copy of that individual's authority to bind the surety. The evidence of authority shall show that it is effective on the date the agent or attorney-in-fact signed each bond.
- C. If the surety on any bond furnished by Contractor is declared bankrupt or becomes insolvent or its right to do business is terminated in any state where any part of the Project is located or it ceases to meet the requirements of Paragraph 5.01.B, Contractor shall promptly notify Owner and Engineer and shall, within 20 days after the event giving rise to such notification, provide another bond and surety, both of which shall comply with the requirements of Paragraphs 5.01.B and 5.02.

#### 5.02 Licensed Sureties and Insurers

A. All bonds and insurance required by the Contract Documents to be purchased and maintained by Owner or Contractor shall be obtained from surety or insurance companies that are duly licensed or authorized in the jurisdiction in which the Project is located to issue bonds or insurance policies for the limits and coverages so required. Such surety and insurance companies shall also meet such additional requirements and qualifications as may be provided in the Supplementary Conditions.

#### 5.03 Certificates of Insurance

- A. Contractor shall deliver to Owner, with copies to each additional insured and loss payee identified in the Supplementary Conditions, certificates of insurance (and other evidence of insurance requested by Owner or any other additional insured) which Contractor is required to purchase and maintain.
- B. Owner shall deliver to Contractor, with copies to each additional insured and loss payee identified in the Supplementary Conditions, certificates of insurance (and other evidence of insurance requested by Contractor or any other additional insured) which Owner is required to purchase and maintain.
- C. Failure of Owner to demand such certificates or other evidence of Contractor's full compliance with these insurance requirements or failure of Owner to identify a deficiency in compliance from the evidence provided shall not be construed as a waiver of Contractor's obligation to maintain such insurance.

- D. Owner does not represent that insurance coverage and limits established in this Contract necessarily will be adequate to protect Contractor.
- E. The insurance and insurance limits required herein shall not be deemed as a limitation on Contractor's liability under the indemnities granted to Owner in the Contract Documents.

#### .04 Contractor's Insurance

- A. Contractor shall purchase and maintain such insurance as is appropriate for the Work being performed and as will provide protection from claims set forth below which may arise out of or result from Contractor's performance of the Work and Contractor's other obligations under the Contract Documents, whether it is to be performed by Contractor, any Subcontractor or Supplier, or by anyone directly or indirectly employed by any of them to perform any of the Work, or by anyone for whose acts any of them may be liable:
  - claims under workers' compensation, disability benefits, and other similar employee benefit acts;
  - claims for damages because of bodily injury, occupational sickness or disease, or death of Contractor's employees;
  - claims for damages because of bodily injury, sickness or disease, or death of any person other than Contractor's employees;
  - 4. claims for damages insured by reasonably available personal injury liability coverage which are sustained:
    - a. by any person as a result of an offense directly or indirectly related to the employment of such person by Contractor, or
    - b. by any other person for any other reason;
  - claims for damages, other than to the Work itself, because of injury to or destruction of tangible property wherever located, including loss of use resulting therefrom; and
  - claims for damages because of bodily injury or death of any person or property damage arising out of the ownership, maintenance or use of any motor vehicle.

- B. The policies of insurance required by this Paragraph 5.04 shall:
  - 1. with respect to insurance required by Paragraphs 5.04.A.3 through 5.04.A.6 inclusive, be written on an occurrence basis, include as additional insureds (subject to any 5.05 customary exclusion regarding professional liability) Owner and Engineer, and any other individuals or entities identified in the Supplementary Conditions, all of whom shall be listed as additional insureds, and include coverage for the respective officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of all such additional insureds, and the insurance afforded to these additional 5.06 insureds shall provide primary coverage for all claims covered thereby;
  - include at least the specific coverages and be written for not less than the limits of liability provided in the Supplementary Conditions or required by Laws or Regulations, whichever is greater;
  - 3. include contractual liability insurance covering Contractor's indemnity obligations under Paragraphs 6.11 and 6.20;
  - 4. contain a provision or endorsement that the coverage afforded will not be canceled, materially changed or renewal refused until at least 30 days prior written notice has been given to Owner and Contractor and to each other additional insured identified in the Supplementary Conditions to whom a certificate of insurance has been issued (and the certificates of insurance furnished by the Contractor pursuant to Paragraph 5.03 will so provide);
  - remain in effect at least until final payment and at all times thereafter when Contractor may be correcting, removing, or replacing defective Work in accordance with Paragraph 13.07; and
  - 6. include completed operations coverage:
    - a. Such insurance shall remain in effect for two years after final payment.
    - Contractor shall furnish Owner and each other additional insured identified in the Supplementary Conditions, to whom a

certificate of insurance has been issued, evidence satisfactory to Owner and any such additional insured of continuation of such insurance at final payment and one year thereafter.

#### .05 Owner's Liability Insurance

A. In addition to the insurance required to be provided by Contractor under Paragraph 5.04, Owner, at Owner's option, may purchase and maintain at Owner's expense Owner's own liability insurance as will protect Owner against claims which may arise from operations under the Contract Documents.

#### 06 Property Insurance

- A. Unless otherwise provided in the Supplementary Conditions, Owner shall purchase and maintain property insurance upon the Work at the Site in the amount of the full replacement cost thereof (subject to such deductible amounts as may be provided in the Supplementary Conditions or required by Laws and Regulations). This insurance shall:
  - include the interests of Owner, Contractor, Subcontractors, and Engineer, and any other individuals or entities identified in the Supplementary Conditions, and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them, each of whom is deemed to have an insurable interest and shall be listed as a loss payee;
  - 2. be written on a Builder's Risk "all-risk" policy form that shall at least include insurance for physical loss or damage to the Work, temporary buildings, falsework, and materials and equipment in transit, and shall insure against at least the following perils or causes of loss: fire, lightning, extended coverage, theft, vandalism and malicious mischief, earthquake, collapse, debris removal. demolition occasioned enforcement of Laws and Regulations, water damage (other than that caused by flood), and such other perils or causes of loss as may be specifically required by the Supplementary Conditions.
  - 3. include expenses incurred in the repair or replacement of any insured property

- (including but not limited to fees and charges of engineers and architects);
- cover materials and equipment stored at the Site or at another location that was agreed to in writing by Owner prior to being incorporated in the Work, provided that such materials and equipment have been included in an Application for Payment recommended by Engineer;
- allow for partial utilization of the Work by Owner:
- 6. include testing and startup; and
- be maintained in effect until final payment is made unless otherwise agreed to in writing by Owner, Contractor, and Engineer with 30 days written notice to each other loss payee to whom a certificate of insurance has been issued.
- B. Owner shall purchase and maintain such equipment breakdown insurance or additional property insurance as may be required by the Supplementary Conditions or Laws and Regulations which will include the interests of Owner, Contractor, Subcontractors, and Engineer, and any other individuals or entities identified in the Supplementary Conditions, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them, each of whom is deemed to have an insurable interest and shall be listed as a loss payee.
- C. All the policies of insurance (and the certificates or other evidence thereof) required to be purchased and maintained in accordance with this Paragraph 5.06 will contain a provision or endorsement that the coverage afforded will not be canceled or materially changed or renewal refused until at least 30 days prior written notice has been given to Owner and Contractor and to each other loss payee to whom a certificate of insurance has been issued and will contain waiver provisions in accordance with Paragraph 5.07.
- D. Owner shall not be responsible for purchasing and maintaining any property insurance specified in this Paragraph 5.06 to protect the interests of Contractor, Subcontractors, or others in the Work to the extent of any deductible amounts that are identified in the Supplementary Conditions. The risk of loss within such identified deductible

- amount will be borne by Contractor, Subcontractors, or others suffering any such loss, and if any of them wishes property insurance coverage within the limits of such amounts, each may purchase and maintain it at the purchaser's own expense.
- E. If Contractor requests in writing that other special insurance be included in the property insurance policies provided under this Paragraph 5.06, Owner shall, if possible, include such insurance, and the cost thereof will be charged to Contractor by appropriate Change Order. Prior to commencement of the Work at the Site, Owner shall in writing advise Contractor whether or not such other insurance has been procured by Owner.

#### 07 Waiver of Rights

A. Owner and Contractor intend that all policies purchased in accordance with Paragraph 5.06 will protect Owner, Contractor, Subcontractors, and Engineer, and all other individuals or entities identified in the Supplementary Conditions as loss payees (and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them) in such policies and will provide primary coverage for all losses and damages caused by the perils or causes of loss covered thereby. All such policies shall contain provisions to the effect that in the event of payment of any loss or damage the insurers will have no rights of recovery against any of the insureds or loss payees thereunder. Owner and Contractor waive all rights against each other and their respective officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them for all losses and damages caused by, arising out of or resulting from any of the perils or causes of loss covered by such policies and any other property insurance applicable to the Work; and, in addition, waive all such rights against Subcontractors and Engineer, and all other individuals or entities identified in the Supplementary Conditions as loss payees (and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them) under such policies for losses and damages so caused. None of the above waivers shall extend to the rights that any party making such waiver may have to the proceeds of insurance held by Owner as trustee or otherwise payable under any policy so issued.

- B. Owner waives all rights against Contractor, Subcontractors, and Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them for:
  - loss due to business interruption, loss of use, or other consequential loss extending beyond direct physical loss or damage to Owner's property or the Work caused by, arising out of, or resulting from fire or other perils 5.09 whether or not insured by Owner; and
  - 2. loss or damage to the completed Project or part thereof caused by, arising out of, or resulting from fire or other insured peril or cause of loss covered by any property insurance maintained on the completed Project or part thereof by Owner during partial utilization pursuant to Paragraph 14.05, after Substantial Completion pursuant to Paragraph 14.04, or after final payment pursuant to Paragraph 14.07.
- C. Any insurance policy maintained by Owner covering any loss, damage or consequential loss referred to in Paragraph 5.07.B shall contain provisions to the effect that in the event of payment of any such loss, damage, or consequential loss, the insurers will have no rights of recovery against Contractor, Subcontractors, or Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them.
- 5.08 Receipt and Application of Insurance Proceeds
  - A. Any insured loss under the policies of insurance required by Paragraph 5.06 will be adjusted with Owner and made payable to Owner as fiduciary for the loss payees, as their interests may appear, subject to the requirements of any applicable mortgage clause and of Paragraph 5.08.B. Owner shall deposit in a separate account any money so received and shall distribute it in accordance with such agreement as the parties in interest may reach. If no other special agreement is reached, the damaged Work shall be repaired or replaced, the moneys so received applied on account thereof, and the Work and the cost thereof covered by an appropriate Change Order.
  - B. Owner as fiduciary shall have power to adjust and settle any loss with the insurers unless one of the parties in interest shall object in writing within 15 days after the occurrence of loss to Owner's

exercise of this power. If such objection be made, Owner as fiduciary shall make settlement with the insurers in accordance with such agreement as the parties in interest may reach. If no such agreement among the parties in interest is reached, Owner as fiduciary shall adjust and settle the loss with the insurers and, if required in writing by any party in interest, Owner as fiduciary shall give bond for the proper performance of such duties.

Acceptance of Bonds and Insurance; Option to Replace

- A. If either Owner or Contractor has any objection to the coverage afforded by or other provisions of the bonds or insurance required to be purchased and maintained by the other party in accordance with Article 5 on the basis of non-conformance with the Contract Documents, the objecting party shall so notify the other party in writing within 10 days after receipt of the certificates (or other evidence requested) required by Paragraph 2.01.B. Owner and Contractor shall each provide to the other such additional information in respect of insurance provided as the other may reasonably request. If either party does not purchase or maintain all of the bonds and insurance required of such party by the Contract Documents, such party shall notify the other party in writing of such failure to purchase prior to the start of the Work, or of such failure to maintain prior to any change in the required coverage. Without prejudice to any other right or remedy, the other party may elect to obtain equivalent bonds or insurance to protect such other party's interests at the expense of the party who was required to provide such coverage, and a Change Order shall be issued to adjust the Contract Price accordingly.
- .10 Partial Utilization, Acknowledgment of Property Insurer
  - A. If Owner finds it necessary to occupy or use a portion or portions of the Work prior to Substantial Completion of all the Work as provided in Paragraph 14.05, no such use or occupancy shall commence before the insurers providing the property insurance pursuant to Paragraph 5.06 have acknowledged notice thereof and in writing effected any changes in coverage necessitated thereby. The insurers providing the property insurance shall consent by endorsement on the policy or policies, but the property insurance shall not be canceled or permitted to lapse on account of any such partial use or occupancy.

#### ARTICLE 6 – CONTRACTOR'S RESPONSIBILITIES

#### 6.01 Supervision and Superintendence

- A. Contractor shall supervise, inspect, and direct the Work competently and efficiently, devoting such attention thereto and applying such skills and expertise as may be necessary to perform the Work in accordance with the Contract Documents. Contractor shall be solely responsible for the means, methods, techniques, sequences, and procedures of construction. Contractor shall not be responsible for the negligence of Owner or Engineer in the design or specification of a specific means, method, technique, sequence, or procedure of construction which is shown or indicated in and expressly required by the Contract Documents.
- B. At all times during the progress of the Work, 6.04 Contractor shall assign a competent resident superintendent who shall not be replaced without written notice to Owner and Engineer except under extraordinary circumstances.

#### 6.02 Labor; Working Hours

- A. Contractor shall provide competent, suitably qualified personnel to survey and lay out the Work and perform construction as required by the Contract Documents. Contractor shall at all times maintain good discipline and order at the Site.
- B. Except as otherwise required for the safety or protection of persons or the Work or property at the Site or adjacent thereto, and except as otherwise stated in the Contract Documents, all Work at the Site shall be performed during regular working hours. Contractor will not permit the performance of Work on a Saturday, Sunday, or any legal holiday without Owner's written consent (which will not be unreasonably withheld) given after prior written notice to Engineer.

### 6.03 Services, Materials, and Equipment

A. Unless otherwise specified in the Contract Documents, Contractor shall provide and assume full responsibility for all services, materials, equipment, labor, transportation, construction equipment and machinery, tools, appliances, fuel, power, light, heat, telephone, water, sanitary facilities, temporary facilities, and all other facilities and incidentals necessary for the performance, testing, start-up, and completion of the Work.

- B. All materials and equipment incorporated into the Work shall be as specified or, if not specified, shall be of good quality and new, except as otherwise provided in the Contract Documents. All special warranties and guarantees required by the Specifications shall expressly run to the benefit of Owner. If required by Engineer, Contractor shall furnish satisfactory evidence (including reports of required tests) as to the source, kind, and quality of materials and equipment.
- C. All materials and equipment shall be stored, applied, installed, connected, erected, protected, used, cleaned, and conditioned in accordance with instructions of the applicable Supplier, except as otherwise may be provided in the Contract Documents.

#### 04 Progress Schedule

- A. Contractor shall adhere to the Progress Schedule established in accordance with Paragraph 2.07 as it may be adjusted from time to time as provided below.
  - 1. Contractor shall submit to Engineer for acceptance (to the extent indicated in Paragraph 2.07) proposed adjustments in the Progress Schedule that will not result in changing the Contract Times. Such adjustments will comply with any provisions of the General Requirements applicable thereto.
  - Proposed adjustments in the Progress Schedule that will change the Contract Times shall be submitted in accordance with the requirements of Article 12. Adjustments in Contract Times may only be made by a Change Order.

#### 6.05 Substitutes and "Or-Equals"

A. Whenever an item of material or equipment is specified or described in the Contract Documents by using the name of a proprietary item or the name of a particular Supplier, the specification or description is intended to establish the type, function, appearance, and quality required. Unless the specification or description contains or is followed by words reading that no like, equivalent, or "or-equal" item or no substitution is permitted, other items of material or equipment or material or equipment of other Suppliers may be

submitted to Engineer for review under the circumstances described below.

- 1. "Or-Equal" Items: If in Engineer's sole discretion an item of material or equipment proposed by Contractor is functionally equal to that named and sufficiently similar so that no change in related Work will be required, it may be considered by Engineer as an "or-equal" item, in which case review and approval of the proposed item may, in Engineer's sole discretion, be accomplished without compliance with some or all of the requirements for approval of proposed substitute items. For the purposes of this Paragraph 6.05.A.1, a proposed item of material or equipment will be considered functionally equal to an item so named if:
  - a. in the exercise of reasonable judgment Engineer determines that:
    - it is at least equal in materials of construction, quality, durability, appearance, strength, and design characteristics;
    - it will reliably perform at least equally well the function and achieve the results imposed by the design concept of the completed Project as a functioning whole; and
    - 3) it has a proven record of performance and availability of responsive service.
  - b. Contractor certifies that, if approved and incorporated into the Work:
    - there will be no increase in cost to the Owner or increase in Contract Times; and
    - it will conform substantially to the detailed requirements of the item named in the Contract Documents.

#### 2. Substitute Items:

a. If in Engineer's sole discretion an item of material or equipment proposed by Contractor does not qualify as an "orequal" item under Paragraph 6.05.A.1, it will be considered a proposed substitute item.

- b. Contractor shall submit sufficient information as provided below to allow Engineer to determine if the item of material or equipment proposed is essentially equivalent to that named and an acceptable substitute therefor. Requests for review of proposed substitute items of material or equipment will not be accepted by Engineer from anyone other than Contractor.
- c. The requirements for review by Engineer will be as set forth in Paragraph 6.05.A.2.d, as supplemented by the General Requirements, and as Engineer may decide is appropriate under the circumstances.
- d. Contractor shall make written application to Engineer for review of a proposed substitute item of material or equipment that Contractor seeks to furnish or use. The application:
  - shall certify that the proposed substitute item will:
    - a) perform adequately the functions and achieve the results called for by the general design,
    - b) be similar in substance to that specified, and
    - c) be suited to the same use as that specified;
  - 2) will state:
    - a) the extent, if any, to which the use of the proposed substitute item will prejudice Contractor's achievement of Substantial Completion on time,
    - b) whether use of the proposed substitute item in the Work will require a change in any of the Contract Documents (or in the provisions of any other direct contract with Owner for other work on the Project) to adapt the design to the proposed substitute item, and

- whether incorporation or use of the proposed substitute item in connection with the Work is subject to payment of any license fee or royalty;
- 3) will identify:
  - a) all variations of the proposed substitute item from that specified, and
  - available engineering, sales, maintenance, repair, and replacement services; and
- shall contain an itemized estimate of all costs or credits that will result directly or indirectly from use of such substitute item, including costs 6.06 of redesign and claims of other contractors affected by any resulting change.
- B. Substitute Construction Methods or Procedures: If a specific means, method, technique, sequence, or procedure of construction is expressly required by the Contract Documents, Contractor may furnish or utilize a substitute means, method, technique, sequence, or procedure of construction approved by Engineer. Contractor shall submit sufficient information to allow Engineer, in Engineer's sole discretion, to determine that the substitute proposed is equivalent to that expressly called for by the Contract Documents. The requirements for review by Engineer will be similar to those provided in Paragraph 6.05.A.2.
- C. Engineer's Evaluation: Engineer will be allowed a reasonable time within which to evaluate each proposal or submittal made pursuant to Paragraphs 6.05.A and 6.05.B. Engineer may require Contractor to furnish additional data about the proposed substitute item. Engineer will be the sole judge of acceptability. No "or equal" or substitute will be ordered, installed or utilized until Engineer's review is complete, which will be evidenced by a Change Order in the case of a substitute and an approved Shop Drawing for an "or equal." Engineer will advise Contractor in writing of any negative determination.
- D. Special Guarantee: Owner may require Contractor to furnish at Contractor's expense a special performance guarantee or other surety with respect to any substitute.

- E. Engineer's Cost Reimbursement: Engineer will record Engineer's costs in evaluating a substitute proposed or submitted by Contractor pursuant to Paragraphs 6.05.A.2 and 6.05.B. Whether or not Engineer approves a substitute so proposed or submitted by Contractor, Contractor shall reimburse Owner for the reasonable charges of Engineer for evaluating each such proposed substitute. Contractor shall also reimburse Owner for the reasonable charges of Engineer for making changes in the Contract Documents (or in the provisions of any other direct contract with Owner) resulting from the acceptance of each proposed substitute.
- F. *Contractor's Expense*: Contractor shall provide all data in support of any proposed substitute or "or-equal" at Contractor's expense.

Concerning Subcontractors, Suppliers, and Others

- A. Contractor shall not employ any Subcontractor, Supplier, or other individual or entity (including those acceptable to Owner as indicated in Paragraph 6.06.B), whether initially or as a replacement, against whom Owner may have reasonable objection. Contractor shall not be required to employ any Subcontractor, Supplier, or other individual or entity to furnish or perform any of the Work against whom Contractor has reasonable objection.
- B. If the Supplementary Conditions require the identity of certain Subcontractors, Suppliers, or other individuals or entities to be submitted to Owner in advance for acceptance by Owner by a specified date prior to the Effective Date of the Agreement, and if Contractor has submitted a list thereof in accordance with the Supplementary Conditions, Owner's acceptance (either in writing or by failing to make written objection thereto by the date indicated for acceptance or objection in the Bidding Documents or the Contract Documents) of any such Subcontractor, Supplier, or other individual or entity so identified may be revoked on the basis of reasonable objection after due investigation. Contractor shall submit an replacement for acceptable the rejected Subcontractor, Supplier, or other individual or entity, and the Contract Price will be adjusted by the difference in the cost occasioned by such replacement, and an appropriate Change Order will be issued. No acceptance by Owner of any such Subcontractor, Supplier, or other individual or entity, whether initially or as a replacement,

- shall constitute a waiver of any right of Owner or Engineer to reject defective Work.
- C. Contractor shall be fully responsible to Owner and Engineer for all acts and omissions of the Subcontractors, Suppliers, and other individuals or entities performing or furnishing any of the Work just as Contractor is responsible for Contractor's own acts and omissions. Nothing in the Contract Documents:
  - shall create for the benefit of any such Subcontractor, Supplier, or other individual or entity any contractual relationship between Owner or Engineer and any such 6.07 Subcontractor, Supplier or other individual or entity; nor
  - shall create any obligation on the part of Owner or Engineer to pay or to see to the payment of any moneys due any such Subcontractor, Supplier, or other individual or entity except as may otherwise be required by Laws and Regulations.
- D. Contractor shall be solely responsible for scheduling and coordinating the Work of Subcontractors, Suppliers, and other individuals or entities performing or furnishing any of the Work under a direct or indirect contract with Contractor.
- E. Contractor shall require all Subcontractors, Suppliers, and such other individuals or entities performing or furnishing any of the Work to communicate with Engineer through Contractor.
- F. The divisions and sections of the Specifications and the identifications of any Drawings shall not control Contractor in dividing the Work among Subcontractors or Suppliers or delineating the Work to be performed by any specific trade.
- G. All Work performed for Contractor by a Subcontractor or Supplier will be pursuant to an appropriate agreement between Contractor and the Subcontractor or Supplier which specifically binds the Subcontractor or Supplier to the applicable terms and conditions of the Contract Documents for the benefit of Owner and Engineer. Whenever any such agreement is with a Subcontractor or Supplier who is listed as a loss payee on the property insurance provided in Paragraph 5.06, the agreement between the Contractor and the Subcontractor or Supplier will contain provisions whereby the Subcontractor or Supplier waives all rights against Owner, Contractor, Engineer, and

all other individuals or entities identified in the Supplementary Conditions to be listed as insureds or loss payees (and the officers, directors, partners, members, employees, agents, consultants, and subcontractors of each and any of them) for all losses and damages caused by, arising out of, relating to, or resulting from any of the perils or causes of loss covered by such policies and any other property insurance applicable to the Work. If the insurers on any such policies require separate waiver forms to be signed by any Subcontractor or Supplier, Contractor will obtain the same.

#### .07 Patent Fees and Royalties

- A. Contractor shall pay all license fees and royalties and assume all costs incident to the use in the performance of the Work or the incorporation in the Work of any invention, design, process, product, or device which is the subject of patent rights or copyrights held by others. If a particular invention, design, process, product, or device is specified in the Contract Documents for use in the performance of the Work and if, to the actual knowledge of Owner or Engineer, its use is subject to patent rights or copyrights calling for the payment of any license fee or royalty to others, the existence of such rights shall be disclosed by Owner in the Contract Documents.
- B. To the fullest extent permitted by Laws and Regulations, Owner shall indemnify and hold harmless Contractor, and its officers, directors, members, partners, employees, agents, consultants, and subcontractors from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals, and all court or arbitration or other dispute resolution costs) arising out of or relating to any infringement of patent rights or copyrights incident to the use in the performance of the Work or resulting from the incorporation in the Work of any invention, design, process, product, or device specified in the Contract Documents, but not identified as being subject to payment of any license fee or royalty to others required by patent rights or copyrights.
- C. To the fullest extent permitted by Laws and Regulations, Contractor shall indemnify and hold harmless Owner and Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them from and against all claims, costs, losses,

and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to any infringement of patent rights or copyrights incident to the use in the performance of the Work or resulting from the incorporation in the Work of any invention, design, process, 6.10 product, or device not specified in the Contract Documents.

#### 6.08 Permits

A. Unless otherwise provided in the Supplementary Conditions, Contractor shall obtain and pay for all construction permits and licenses. Owner shall 6.11 assist Contractor, when necessary, in obtaining such permits and licenses. Contractor shall pay all governmental charges and inspection fees necessary for the prosecution of the Work which are applicable at the time of opening of Bids, or, if there are no Bids, on the Effective Date of the Agreement. Owner shall pay all charges of utility owners for connections for providing permanent service to the Work.

#### 6.09 Laws and Regulations

- A. Contractor shall give all notices required by and shall comply with all Laws and Regulations applicable to the performance of the Work. Except where otherwise expressly required by applicable Laws and Regulations, neither Owner nor Engineer shall be responsible for monitoring Contractor's compliance with any Laws or Regulations.
- B. If Contractor performs any Work knowing or having reason to know that it is contrary to Laws or Regulations, Contractor shall bear all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to such Work. However, it shall not be Contractor's to make responsibility certain that Specifications and Drawings are in accordance with Laws and Regulations, but this shall not relieve Contractor of Contractor's obligations under Paragraph 3.03.
- C. Changes in Laws or Regulations not known at the time of opening of Bids (or, on the Effective Date of the Agreement if there were no Bids) having an effect on the cost or time of performance of the

Work shall be the subject of an adjustment in Contract Price or Contract Times. If Owner and Contractor are unable to agree on entitlement to or on the amount or extent, if any, of any such adjustment, a Claim may be made therefor as provided in Paragraph 10.05.

#### Taxes

A. Contractor shall pay all sales, consumer, use, and other similar taxes required to be paid by Contractor in accordance with the Laws and Regulations of the place of the Project which are applicable during the performance of the Work.

#### 1 Use of Site and Other Areas

- A. Limitation on Use of Site and Other Areas:
  - Contractor shall confine construction equipment, the storage of materials and equipment, and the operations of workers to the Site and other areas permitted by Laws and Regulations, and shall not unreasonably encumber the Site and other areas with construction equipment or other materials or equipment. Contractor shall assume full responsibility for any damage to any such land or area, or to the owner or occupant thereof, or of any adjacent land or areas resulting from the performance of the Work.
  - Should any claim be made by any such owner or occupant because of the performance of the Work, Contractor shall promptly settle with such other party by negotiation or otherwise resolve the claim by arbitration or other dispute resolution proceeding or at law.
  - To the fullest extent permitted by Laws and Regulations, Contractor shall indemnify and hold harmless Owner and Engineer, and the partners, officers, directors, members, employees, agents, consultants subcontractors of each and any of them from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to any claim or action, legal or equitable, brought by any such owner or occupant against Owner, Engineer, or any other party indemnified hereunder to the extent caused by or based upon Contractor's performance of the Work.

- B. Removal of Debris During Performance of the Work: During the progress of the Work Contractor shall keep the Site and other areas free from accumulations of waste materials, rubbish, and other debris. Removal and disposal of such waste materials, rubbish, and other debris shall conform to applicable Laws and Regulations.
- C. Cleaning: Prior to Substantial Completion of the Work Contractor shall clean the Site and the Work and make it ready for utilization by Owner. At the completion of the Work Contractor shall remove from the Site all tools, appliances, construction equipment and machinery, and surplus materials and shall restore to original condition all property not designated for alteration by the Contract Documents.
- D. Loading Structures: Contractor shall not load nor permit any part of any structure to be loaded in any manner that will endanger the structure, nor shall Contractor subject any part of the Work or adjacent property to stresses or pressures that will endanger it.

#### 6.12 Record Documents

A. Contractor shall maintain in a safe place at the Site one record copy of all Drawings, Specifications, Addenda, Change Orders, Work Change Field Orders, written Directives. and interpretations and clarifications in good order and annotated to show changes made during construction. These record documents together with all approved Samples and a counterpart of all approved Shop Drawings will be available to Engineer for reference. Upon completion of the Work, these record documents, Samples, and Shop Drawings will be delivered to Engineer for Owner.

#### 6.13 Safety and Protection

A. Contractor shall be solely responsible for initiating, maintaining and supervising all safety precautions and programs in connection with the Work. Such responsibility does not relieve Subcontractors of their responsibility for the safety of persons or property in the performance of their work, nor for compliance with applicable safety Laws and Regulations. Contractor shall take all necessary precautions for the safety of, and shall provide the necessary protection to prevent damage, injury or loss to:

- 1. all persons on the Site or who may be affected by the Work;
- 2. all the Work and materials and equipment to be incorporated therein, whether in storage on or off the Site; and
- other property at the Site or adjacent thereto, including trees, shrubs, lawns, walks, pavements, roadways, structures, utilities, and Underground Facilities not designated for removal, relocation, or replacement in the course of construction.
- B. Contractor shall comply with all applicable Laws and Regulations relating to the safety of persons or property, or to the protection of persons or property from damage, injury, or loss; and shall erect and maintain all necessary safeguards for such safety and protection. Contractor shall notify owners of adjacent property and of Underground Facilities and other utility owners when prosecution of the Work may affect them, and shall cooperate with them in the protection, removal, relocation, and replacement of their property.
- C. Contractor shall comply with the applicable requirements of Owner's safety programs, if any. The Supplementary Conditions identify any Owner's safety programs that are applicable to the Work.
- D. Contractor shall inform Owner and Engineer of the specific requirements of Contractor's safety program with which Owner's and Engineer's employees and representatives must comply while at the Site.
- All damage, injury, or loss to any property referred to in Paragraph 6.13.A.2 or 6.13.A.3 caused, directly or indirectly, in whole or in part, by Contractor, any Subcontractor, Supplier, or any other individual or entity directly or indirectly employed by any of them to perform any of the Work, or anyone for whose acts any of them may be liable, shall be remedied by Contractor (except damage or loss attributable to the fault of Drawings or Specifications or to the acts or omissions of Owner or Engineer or anyone employed by any of them, or anyone for whose acts any of them may be liable, and not attributable, directly or indirectly, in whole or in part, to the fault or negligence of Contractor or any Subcontractor, Supplier, or other individual or

- entity directly or indirectly employed by any of them).
- F. Contractor's duties and responsibilities for safety and for protection of the Work shall continue until such time as all the Work is completed and Engineer has issued a notice to Owner and Contractor in accordance with Paragraph 14.07.B that the Work is acceptable (except as otherwise expressly provided in connection with Substantial Completion).

#### 6.14 Safety Representative

A. Contractor shall designate a qualified and experienced safety representative at the Site whose duties and responsibilities shall be the prevention of accidents and the maintaining and supervising of safety precautions and programs.

#### 6.15 Hazard Communication Programs

A. Contractor shall be responsible for coordinating any exchange of material safety data sheets or other hazard communication information required to be made available to or exchanged between or among employers at the Site in accordance with Laws or Regulations.

#### 6.16 Emergencies

A. In emergencies affecting the safety or protection of persons or the Work or property at the Site or adjacent thereto, Contractor is obligated to act to prevent threatened damage, injury, or loss. Contractor shall give Engineer prompt written notice if Contractor believes that any significant changes in the Work or variations from the Contract Documents have been caused thereby or are required as a result thereof. If Engineer determines that a change in the Contract Documents is required because of the action taken by Contractor in response to such an emergency, a Work Change Directive or Change Order will be issued.

#### 6.17 Shop Drawings and Samples

A. Contractor shall submit Shop Drawings and Samples to Engineer for review and approval in accordance with the accepted Schedule of Submittals (as required by Paragraph 2.07). Each submittal will be identified as Engineer may require.

#### 1. Shop Drawings:

- a. Submit number of copies specified in the General Requirements.
- b. Data shown on the Shop Drawings will be complete with respect to quantities, dimensions, specified performance and design criteria, materials, and similar data to show Engineer the services, materials, and equipment Contractor proposes to provide and to enable Engineer to review the information for the limited purposes required by Paragraph 6.17.D.

#### 2. Samples:

- a. Submit number of Samples specified in the Specifications.
- b. Clearly identify each Sample as to material, Supplier, pertinent data such as catalog numbers, the use for which intended and other data as Engineer may require to enable Engineer to review the submittal for the limited purposes required by Paragraph 6.17.D.
- B. Where a Shop Drawing or Sample is required by the Contract Documents or the Schedule of Submittals, any related Work performed prior to Engineer's review and approval of the pertinent submittal will be at the sole expense and responsibility of Contractor.

#### C. Submittal Procedures:

- 1. Before submitting each Shop Drawing or Sample, Contractor shall have:
  - a. reviewed and coordinated each Shop Drawing or Sample with other Shop Drawings and Samples and with the requirements of the Work and the Contract Documents;
  - determined and verified all field measurements, quantities, dimensions, specified performance and design criteria, installation requirements, materials, catalog numbers, and similar information with respect thereto;
  - c. determined and verified the suitability of all materials offered with respect to the

- indicated application, fabrication, shipping, handling, storage, assembly, and installation pertaining to the performance of the Work; and
- d. determined and verified all information relative to Contractor's responsibilities for means, methods, techniques, sequences, and procedures of construction, and safety precautions and programs incident thereto.
- Each submittal shall bear a stamp or specific written certification that Contractor has satisfied Contractor's obligations under the Contract Documents with respect to Contractor's review and approval of that submittal.
- 3. With each submittal, Contractor shall give Engineer specific written notice of any variations that the Shop Drawing or Sample may have from the requirements of the Contract Documents. This notice shall be both a written communication separate from the Shop Drawings or Sample submittal; and, in addition, by a specific notation made on each Shop Drawing or Sample submitted to Engineer for review and approval of each 6.18 such variation.

#### D. Engineer's Review:

- 1. Engineer will provide timely review of Shop Drawings and Samples in accordance with the Schedule of Submittals acceptable to Engineer. Engineer's review and approval will be only to determine if the items covered by the submittals will, after installation or 6.19 incorporation in the Work, conform to the information given in the Contract Documents and be compatible with the design concept of the completed Project as a functioning whole as indicated by the Contract Documents.
- 2. Engineer's review and approval will not extend to means, methods, techniques, sequences, or procedures of construction (except where a particular means, method, technique, sequence, or procedure of construction is specifically and expressly called for by the Contract Documents) or to safety precautions or programs incident thereto. The review and approval of a separate item as such will not indicate

- approval of the assembly in which the item functions.
- 3. Engineer's review and approval shall not relieve Contractor from responsibility for any variation from the requirements of the Contract Documents unless Contractor has complied with the requirements of Paragraph 6.17.C.3 and Engineer has given written approval of each such variation by specific written notation thereof incorporated in or accompanying the Shop Drawing or Sample. Engineer's review and approval shall not relieve Contractor from responsibility for complying with the requirements of Paragraph 6.17.C.1.

#### E. Resubmittal Procedures:

 Contractor shall make corrections required by Engineer and shall return the required number of corrected copies of Shop Drawings and submit, as required, new Samples for review and approval. Contractor shall direct specific attention in writing to revisions other than the corrections called for by Engineer on previous submittals.

#### Continuing the Work

A. Contractor shall carry on the Work and adhere to the Progress Schedule during all disputes or disagreements with Owner. No Work shall be delayed or postponed pending resolution of any disputes or disagreements, except as permitted by Paragraph 15.04 or as Owner and Contractor may otherwise agree in writing.

#### 19 Contractor's General Warranty and Guarantee

- A. Contractor warrants and guarantees to Owner that all Work will be in accordance with the Contract Documents and will not be defective. Engineer and its officers, directors, members, partners, employees, agents, consultants, and subcontractors shall be entitled to rely on representation of Contractor's warranty and guarantee.
- B. Contractor's warranty and guarantee hereunder excludes defects or damage caused by:
  - abuse, modification, or improper maintenance or operation by persons other than Contractor, Subcontractors, Suppliers, or any other

- individual or entity for whom Contractor is responsible; or
- 2. normal wear and tear under normal usage.
- C. Contractor's obligation to perform and complete the Work in accordance with the Contract Documents shall be absolute. None of the following will constitute an acceptance of Work that is not in accordance with the Contract Documents or a release of Contractor's obligation to perform the Work in accordance with the Contract Documents:
  - 1. observations by Engineer;
  - 2. recommendation by Engineer or payment by Owner of any progress or final payment;
  - 3. the issuance of a certificate of Substantial Completion by Engineer or any payment related thereto by Owner;
  - 4. use or occupancy of the Work or any part thereof by Owner;
  - any review and approval of a Shop Drawing or Sample submittal or the issuance of a notice of acceptability by Engineer;
  - 6. any inspection, test, or approval by others; or
  - 7. any correction of defective Work by Owner.

#### 6.20 Indemnification

A. To the fullest extent permitted by Laws and 6.21 Regulations, Contractor shall indemnify and hold harmless Owner and Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to the performance of the Work, provided that any such claim, cost, loss, or damage is attributable to bodily injury, sickness, disease, or death, or to injury to or destruction of tangible property (other than the Work itself), including the loss of use resulting therefrom but only to the extent caused by any negligent act or omission of Contractor, any Subcontractor, any Supplier, or any individual or entity directly or indirectly employed by any of them to perform any of the

- Work or anyone for whose acts any of them may be liable .
- B. In any and all claims against Owner or Engineer or any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors by any employee (or the survivor or personal representative of such employee) of Contractor, any Subcontractor, any Supplier, or any individual or entity directly or indirectly employed by any of them to perform any of the Work, or anyone for whose acts any of them may be liable, the indemnification obligation under Paragraph 6.20.A shall not be limited in any way by any limitation on the amount or type of damages, compensation, or benefits payable by or for Contractor or any such Subcontractor, Supplier, or other individual or entity under workers' compensation acts, disability benefit acts, or other employee benefit acts.
- C. The indemnification obligations of Contractor under Paragraph 6.20.A shall not extend to the liability of Engineer and Engineer's officers, directors, members, partners, employees, agents, consultants and subcontractors arising out of:
  - 1. the preparation or approval of, or the failure to prepare or approve maps, Drawings, opinions, reports, surveys, Change Orders, designs, or Specifications; or
  - 2. giving directions or instructions, or failing to give them, if that is the primary cause of the injury or damage.

#### 6.21 Delegation of Professional Design Services

- A. Contractor will not be required to provide professional design services unless such services are specifically required by the Contract Documents for a portion of the Work or unless such services are required to carry out Contractor's responsibilities for construction means, methods, techniques, sequences and procedures. Contractor shall not be required to provide professional services in violation of applicable law.
- B. If professional design services or certifications by a design professional related to systems, materials or equipment are specifically required of Contractor by the Contract Documents, Owner and Engineer will specify all performance and design criteria that such services must satisfy. Contractor shall cause such services or

certifications to be provided by a properly licensed professional, whose signature and seal shall appear on all drawings, calculations, specifications, certifications, Shop Drawings and other submittals prepared by such professional. Shop Drawings and other submittals related to the Work designed or certified by such professional, if prepared by others, shall bear such professional's written approval when submitted to Engineer.

- C. Owner and Engineer shall be entitled to rely upon the adequacy, accuracy and completeness of the services, certifications or approvals performed by such design professionals, provided Owner and Engineer have specified to Contractor all performance and design criteria that such services must satisfy.
- D. Pursuant to this Paragraph 6.21, Engineer's review and approval of design calculations and design drawings will be only for the limited purpose of checking for conformance with performance and design criteria given and the design concept expressed in the Contract Documents. Engineer's review and approval of Shop Drawings and other submittals (except design calculations and design drawings) will be only for the purpose stated in Paragraph 6.17.D.1.
- E. Contractor shall not be responsible for the adequacy of the performance or design criteria required by the Contract Documents.

#### ARTICLE 7 - OTHER WORK AT THE SITE

#### 7.01 Related Work at Site

- A. Owner may perform other work related to the 7.02 Project at the Site with Owner's employees, or through other direct contracts therefor, or have other work performed by utility owners. If such other work is not noted in the Contract Documents, then:
  - written notice thereof will be given to Contractor prior to starting any such other work; and
  - if Owner and Contractor are unable to agree on entitlement to or on the amount or extent, if any, of any adjustment in the Contract Price or Contract Times that should be allowed as a result of such other work, a Claim may be made therefor as provided in Paragraph 10.05.

- B. Contractor shall afford each other contractor who is a party to such a direct contract, each utility owner, and Owner, if Owner is performing other work with Owner's employees, proper and safe access to the Site, provide a reasonable opportunity for the introduction and storage of materials and equipment and the execution of such other work, and properly coordinate the Work with theirs. Contractor shall do all cutting, fitting, and patching of the Work that may be required to properly connect or otherwise make its several parts come together and properly integrate with such other work. Contractor shall not endanger any work of others by cutting, excavating, or otherwise altering such work; provided, however, that Contractor may cut or alter others' work with the written consent of Engineer and the others whose work will be affected. The duties and responsibilities of Contractor under this Paragraph are for the benefit of such utility owners and other contractors to the extent that there are comparable provisions for the benefit of Contractor in said direct contracts between Owner and such utility owners and other contractors.
- C. If the proper execution or results of any part of Contractor's Work depends upon work performed by others under this Article 7, Contractor shall inspect such other work and promptly report to Engineer in writing any delays, defects, or deficiencies in such other work that render it unavailable or unsuitable for the proper execution and results of Contractor's Work. Contractor's failure to so report will constitute an acceptance of such other work as fit and proper for integration with Contractor's Work except for latent defects and deficiencies in such other work.

#### 7.02 Coordination

- A. If Owner intends to contract with others for the performance of other work on the Project at the Site, the following will be set forth in Supplementary Conditions:
  - 1. the individual or entity who will have authority and responsibility for coordination of the activities among the various contractors will be identified;
  - 2. the specific matters to be covered by such authority and responsibility will be itemized; and
  - 3. the extent of such authority and responsibilities will be provided.

B. Unless otherwise provided in the Supplementary Contractor copies of reports of explorations and tests of subsurface conditions and drawings of Conditions, Owner shall have sole authority and responsibility for such coordination. physical conditions relating to existing surface or subsurface structures at the Site. Legal Relationships 8.06 Insurance A. Paragraphs 7.01.A and 7.02 are not applicable for utilities not under the control of Owner. A. Owner's responsibilities, if any, with respect to purchasing and maintaining liability and property B. Each other direct contract of Owner under insurance are set forth in Article 5. Paragraph 7.01.A shall provide that the other contractor is liable to Owner and Contractor for 8.07 Change Orders the reasonable direct delay and disruption costs incurred by Contractor as a result of the other A. Owner is obligated to execute Change Orders as contractor's wrongful actions or inactions. indicated in Paragraph 10.03. C. Contractor shall be liable to Owner and any other 8.08 Inspections, Tests, and Approvals contractor under direct contract to Owner for the reasonable direct delay and disruption costs A. Owner's responsibility with respect to certain incurred by such other contractor as a result of inspections, tests, and approvals is set forth in Contractor's wrongful action or inactions. Paragraph 13.03.B. ARTICLE 8 – OWNER'S RESPONSIBILITIES 8.09 Limitations on Owner's Responsibilities Communications to Contractor A. The Owner shall not supervise, direct, or have control or authority over, nor be responsible for, A. Except as otherwise provided in these General means, methods, Contractor's techniques, Conditions, Owner shall issue all communications sequences, or procedures of construction, or the safety precautions and programs incident thereto, to Contractor through Engineer. or for any failure of Contractor to comply with Laws and Regulations applicable to the Replacement of Engineer performance of the Work. Owner will not be A. In case of termination of the employment of responsible for Contractor's failure to perform the Engineer, Owner shall appoint an engineer to Work accordance with the Contract in whom Contractor makes no reasonable objection, Documents. whose status under the Contract Documents shall 8.10 be that of the former Engineer. Undisclosed Hazardous Environmental Condition Furnish Data A. Owner's responsibility in respect to an undisclosed Hazardous Environmental Condition is set forth in Paragraph 4.06. A. Owner shall promptly furnish the data required of Owner under the Contract Documents. Evidence of Financial Arrangements 8.11

8.03

7.03

8.01

8.02

8.04 Pay When Due

> A. Owner shall make payments to Contractor when they are due as provided in Paragraphs 14.02.C and 14.07.C.

8.05 Lands and Easements; Reports and Tests

> A. Owner's duties with respect to providing lands and easements and providing engineering surveys to establish reference points are set forth in Paragraphs 4.01 and 4.05. Paragraph 4.02 refers to Owner's identifying and making available to

A. Upon request of Contractor, Owner shall furnish Contractor reasonable evidence that financial arrangements have been made to satisfy Owner's obligations under the Contract Documents.

8.12 Compliance with Safety Program

> A. While at the Site, Owner's employees and representatives shall comply with the specific applicable requirements of Contractor's safety programs of which Owner has been informed pursuant to Paragraph 6.13.D.

### ARTICLE 9 – ENGINEER'S STATUS DURING CONSTRUCTION

#### 9.01 *Owner's Representative*

A. Engineer will be Owner's representative during the construction period. The duties and responsibilities and the limitations of authority of Engineer as Owner's representative during construction are set forth in the Contract Documents.

#### 9.02 Visits to Site

- A. Engineer will make visits to the Site at intervals appropriate to the various stages of construction as Engineer deems necessary in order to observe as an experienced and qualified design professional the progress that has been made and the quality of the various aspects of Contractor's executed Work. Based on information obtained during such visits and observations, Engineer, for the benefit of Owner, will determine, in general, if the Work is proceeding in accordance with the Contract Documents. Engineer will not be required to make exhaustive or continuous inspections on the Site to check the quality or quantity of the Work. Engineer's efforts will be directed toward providing for Owner a greater degree of confidence that the completed Work will conform generally to the Contract Documents. On the basis of such visits and observations, Engineer will keep Owner informed of the progress of the Work and 9.05 will endeavor to guard Owner against defective Work.
- B. Engineer's visits and observations are subject to all the limitations on Engineer's authority and responsibility set forth in Paragraph 9.09. Particularly, but without limitation, during or as a result of Engineer's visits or observations of Contractor's Work, Engineer will not supervise, direct, control, or have authority over or be responsible for Contractor's means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto, or for any failure of 9.06 Contractor to comply with Laws and Regulations applicable to the performance of the Work.

#### 9.03 Project Representative

A. If Owner and Engineer agree, Engineer will furnish a Resident Project Representative to assist Engineer in providing more extensive observation of the Work. The authority and responsibilities of any such Resident Project Representative and assistants will be as provided in the Supplementary Conditions, and limitations on the responsibilities thereof will be as provided in Paragraph 9.09. If Owner designates another representative or agent to represent Owner at the Site who is not Engineer's consultant, agent or employee, the responsibilities and authority and limitations thereon of such other individual or entity will be as provided in the Supplementary Conditions.

#### 9.04 Authorized Variations in Work

A. Engineer may authorize minor variations in the Work from the requirements of the Contract Documents which do not involve an adjustment in the Contract Price or the Contract Times and are compatible with the design concept of the completed Project as a functioning whole as indicated by the Contract Documents. These may be accomplished by a Field Order and will be binding on Owner and also on Contractor, who shall perform the Work involved promptly. If Owner or Contractor believes that a Field Order justifies an adjustment in the Contract Price or Contract Times, or both, and the parties are unable to agree on entitlement to or on the amount or extent, if any, of any such adjustment, a Claim may be made therefor as provided in Paragraph 10.05.

#### 05 Rejecting Defective Work

A. Engineer will have authority to reject Work which Engineer believes to be defective, or that Engineer believes will not produce a completed Project that conforms to the Contract Documents or that will prejudice the integrity of the design concept of the completed Project as a functioning whole as indicated by the Contract Documents. Engineer will also have authority to require special inspection or testing of the Work as provided in Paragraph 13.04, whether or not the Work is fabricated, installed, or completed.

#### Shop Drawings, Change Orders and Payments

- A. In connection with Engineer's authority, and limitations thereof, as to Shop Drawings and Samples, see Paragraph 6.17.
- B. In connection with Engineer's authority, and limitations thereof, as to design calculations and design drawings submitted in response to a

- delegation of professional design services, if any, see Paragraph 6.21.
- C. In connection with Engineer's authority as to Change Orders, see Articles 10, 11, and 12.

9.09

D. In connection with Engineer's authority as to Applications for Payment, see Article 14.

#### 9.07 Determinations for Unit Price Work

A. Engineer will determine the actual quantities and classifications of Unit Price Work performed by Contractor. Engineer will review with Contractor the Engineer's preliminary determinations on such matters before rendering a written decision thereon (by recommendation of an Application for Payment or otherwise). Engineer's written decision thereon will be final and binding (except as modified by Engineer to reflect changed factual conditions or more accurate data) upon Owner and Contractor, subject to the provisions of Paragraph 10.05.

## 9.08 Decisions on Requirements of Contract Documents and Acceptability of Work

- A. Engineer will be the initial interpreter of the requirements of the Contract Documents and judge of the acceptability of the Work thereunder. All matters in question and other matters between Owner and Contractor arising prior to the date final payment is due relating to the acceptability of the Work, and the interpretation of the requirements of the Contract Documents pertaining to the performance of the Work, will be referred initially to Engineer in writing within 30 days of the event giving rise to the question.
- B. Engineer will, with reasonable promptness, render a written decision on the issue referred. If Owner or Contractor believes that any such decision entitles them to an adjustment in the Contract Price or Contract Times or both, a Claim may be made under Paragraph 10.05. The date of Engineer's decision shall be the date of the event giving rise to the issues referenced for the purposes of Paragraph 10.05.B.
- C. Engineer's written decision on the issue referred will be final and binding on Owner and Contractor, subject to the provisions of Paragraph 10.05.
- D. When functioning as interpreter and judge under this Paragraph 9.08, Engineer will not show

partiality to Owner or Contractor and will not be liable in connection with any interpretation or decision rendered in good faith in such capacity.

#### Limitations on Engineer's Authority and Responsibilities

- A. Neither Engineer's authority or responsibility under this Article 9 or under any other provision of the Contract Documents nor any decision made by Engineer in good faith either to exercise or not exercise such authority or responsibility or the undertaking, exercise, or performance of any authority or responsibility by Engineer shall create, impose, or give rise to any duty in contract, tort, or otherwise owed by Engineer to Contractor, any Subcontractor, any Supplier, any other individual or entity, or to any surety for or employee or agent of any of them.
- B. Engineer will not supervise, direct, control, or have authority over or be responsible for Contractor's means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto, or for any failure of Contractor to comply with Laws and Regulations applicable to the performance of the Work. Engineer will not be responsible for Contractor's failure to perform the Work in accordance with the Contract Documents.
- C. Engineer will not be responsible for the acts or omissions of Contractor or of any Subcontractor, any Supplier, or of any other individual or entity performing any of the Work.
- D. Engineer's review of the final Application for Payment and accompanying documentation and all maintenance and operating instructions, schedules, guarantees, bonds, certificates of inspection, tests and approvals, and other documentation required to be delivered by Paragraph 14.07.A will only be to determine generally that their content complies with the requirements of, and in the case of certificates of inspections, tests, and approvals that the results certified indicate compliance with, the Contract Documents.
- E. The limitations upon authority and responsibility set forth in this Paragraph 9.09 shall also apply to the Resident Project Representative, if any, and assistants, if any.

#### 9.10 Compliance with Safety Program

A. While at the Site, Engineer's employees and representatives shall comply with the specific applicable requirements of Contractor's safety programs of which Engineer has been informed pursuant to Paragraph 6.13.D.

#### ARTICLE 10 - CHANGES IN THE WORK; CLAIMS

#### 10.01 Authorized Changes in the Work

- A. Without invalidating the Contract and without notice to any surety, Owner may, at any time or from time to time, order additions, deletions, or revisions in the Work by a Change Order, or a Work Change Directive. Upon receipt of any such document, Contractor shall promptly proceed with the Work involved which will be performed under the applicable conditions of the Contract Documents (except as otherwise specifically 10.04 provided).
- B. If Owner and Contractor are unable to agree on entitlement to, or on the amount or extent, if any, of an adjustment in the Contract Price or Contract Times, or both, that should be allowed as a result of a Work Change Directive, a Claim may be made therefor as provided in Paragraph 10.05.

#### 10.02 Unauthorized Changes in the Work

A. Contractor shall not be entitled to an increase in the Contract Price or an extension of the Contract Times with respect to any work performed that is not required by the Contract Documents as amended, modified, or supplemented as provided in Paragraph 3.04, except in the case of an emergency as provided in Paragraph 6.16 or in the case of uncovering Work as provided in Paragraph 13.04.D.

#### 10.03 Execution of Change Orders

- A. Owner and Contractor shall execute appropriate Change Orders recommended by Engineer covering:
  - changes in the Work which are: (i) ordered by Owner pursuant to Paragraph 10.01.A, (ii) required because of acceptance of defective Work under Paragraph 13.08.A or Owner's correction of defective Work under Paragraph 13.09, or (iii) agreed to by the parties;

- changes in the Contract Price or Contract Times which are agreed to by the parties, including any undisputed sum or amount of time for Work actually performed in accordance with a Work Change Directive;
- 3. changes in the Contract Price or Contract Times which embody the substance of any written decision rendered by Engineer pursuant to Paragraph 10.05; provided that, in lieu of executing any such Change Order, an appeal may be taken from any such decision in accordance with the provisions of the Contract Documents and applicable Laws and Regulations, but during any such appeal, Contractor shall carry on the Work and adhere to the Progress Schedule as provided in Paragraph 6.18.A.

#### 0.04 Notification to Surety

A. If the provisions of any bond require notice to be given to a surety of any change affecting the general scope of the Work or the provisions of the Contract Documents (including, but not limited to, Contract Price or Contract Times), the giving of any such notice will be Contractor's responsibility. The amount of each applicable bond will be adjusted to reflect the effect of any such change.

#### 0.05 *Claims*

- A. Engineer's Decision Required: All Claims, except those waived pursuant to Paragraph 14.09, shall be referred to the Engineer for decision. A decision by Engineer shall be required as a condition precedent to any exercise by Owner or Contractor of any rights or remedies either may otherwise have under the Contract Documents or by Laws and Regulations in respect of such Claims.
- B. *Notice:* Written notice stating the general nature of each Claim shall be delivered by the claimant to Engineer and the other party to the Contract promptly (but in no event later than 30 days) after the start of the event giving rise thereto. The responsibility to substantiate a Claim shall rest with the party making the Claim. Notice of the amount or extent of the Claim, with supporting data shall be delivered to the Engineer and the other party to the Contract within 60 days after the start of such event (unless Engineer allows additional time for claimant to submit additional

or more accurate data in support of such Claim). A Claim for an adjustment in Contract Price shall be prepared in accordance with the provisions of Paragraph 12.01.B. A Claim for an adjustment in Contract Times shall be prepared in accordance with the provisions of Paragraph 12.02.B. Each Claim shall be accompanied by claimant's written statement that the adjustment claimed is the entire adjustment to which the claimant believes it is entitled as a result of said event. The opposing party shall submit any response to Engineer and the claimant within 30 days after receipt of the claimant's last submittal (unless Engineer allows additional time).

- C. Engineer's Action: Engineer will review each Claim and, within 30 days after receipt of the last submittal of the claimant or the last submittal of the opposing party, if any, take one of the following actions in writing:
  - 1. deny the Claim in whole or in part;
  - 2. approve the Claim; or
  - notify the parties that the Engineer is unable to resolve the Claim if, in the Engineer's sole discretion, it would be inappropriate for the Engineer to do so. For purposes of further resolution of the Claim, such notice shall be deemed a denial.
- D. In the event that Engineer does not take action on a Claim within said 30 days, the Claim shall be deemed denied.
- E. Engineer's written action under Paragraph 10.05.C or denial pursuant to Paragraphs 10.05.C.3 or 10.05.D will be final and binding upon Owner and Contractor, unless Owner or Contractor invoke the dispute resolution procedure set forth in Article 16 within 30 days of such action or denial.
- F. No Claim for an adjustment in Contract Price or Contract Times will be valid if not submitted in accordance with this Paragraph 10.05.

## ARTICLE 11 – COST OF THE WORK; ALLOWANCES; UNIT PRICE WORK

- 11.01 Cost of the Work
  - A. Costs Included: The term Cost of the Work means the sum of all costs, except those excluded in Paragraph 11.01.B, necessarily incurred and

paid by Contractor in the proper performance of the Work. When the value of any Work covered by a Change Order or when a Claim for an adjustment in Contract Price is determined on the basis of Cost of the Work, the costs to be reimbursed to Contractor will be only those additional or incremental costs required because of the change in the Work or because of the event giving rise to the Claim. Except as otherwise may be agreed to in writing by Owner, such costs shall be in amounts no higher than those prevailing in the locality of the Project, shall not include any of the costs itemized in Paragraph 11.01.B, and shall include only the following items:

- Payroll costs for employees in the direct employ of Contractor in the performance of Work under schedules of job classifications agreed upon by Owner and Contractor. Such employees shall include, without limitation, superintendents, foremen, and other personnel employed full time on the Work. Payroll costs for employees not employed full time on the Work shall be apportioned on the basis of their time spent on the Work. Payroll costs shall include, but not be limited to, salaries and wages plus the cost of fringe benefits, which shall include social security contributions, unemployment, and payroll taxes, excise. workers' compensation, health and retirement benefits, bonuses, sick leave, vacation and holiday pay applicable thereto. The expenses of performing Work outside of regular working hours, on Saturday, Sunday, or legal holidays, shall be included in the above to the extent authorized by Owner.
- 2. Cost of all materials and equipment furnished and incorporated in the Work, including costs of transportation and storage thereof, and Suppliers' field services required in connection therewith. All cash discounts shall accrue to Contractor unless Owner deposits funds with Contractor with which to make payments, in which case the cash discounts shall accrue to Owner. All trade discounts, rebates and refunds and returns from sale of surplus materials and equipment shall accrue to Owner, and Contractor shall make provisions so that they may be obtained.
- Payments made by Contractor to Subcontractors for Work performed by Subcontractors. If required by Owner, Contractor shall obtain competitive bids from

subcontractors acceptable to Owner and Contractor and shall deliver such bids to Owner, who will then determine, with the advice of Engineer, which bids, if any, will be acceptable. If any subcontract provides that the Subcontractor is to be paid on the basis of Cost of the Work plus a fee, the Subcontractor's Cost of the Work and fee shall be determined in the same manner as Contractor's Cost of the Work and fee as provided in this Paragraph 11.01.

- Costs of special consultants (including but not limited to engineers, architects, testing laboratories, surveyors, attorneys, and accountants) employed for services specifically related to the Work.
- 5. Supplemental costs including the following:
  - a. The proportion of necessary transportation, travel, and subsistence expenses of Contractor's employees incurred in discharge of duties connected with the Work.
  - b. Cost, including transportation and maintenance, of all materials, supplies, equipment, machinery, appliances, office, and temporary facilities at the Site, and hand tools not owned by the workers, which are consumed in the performance of the Work, and cost, less market value, of such items used but not consumed which remain the property of Contractor.
  - c. Rentals of all construction equipment and machinery, and the parts thereof whether rented from Contractor or others in accordance with rental agreements approved by Owner with the advice of Engineer, and the costs of transportation, loading, unloading, assembly, dismantling, and removal thereof. All such costs shall be in accordance with the terms of said rental agreements. The rental of any such equipment, machinery, or parts shall cease when the use thereof is no longer necessary for the Work.
  - d. Sales, consumer, use, and other similar taxes related to the Work, and for which Contractor is liable, as imposed by Laws and Regulations.

- e. Deposits lost for causes other than negligence of Contractor, any Subcontractor, or anyone directly or indirectly employed by any of them or for whose acts any of them may be liable, and royalty payments and fees for permits and licenses.
- Losses and damages (and related expenses) caused by damage to the Work, not compensated by insurance or otherwise, sustained by Contractor in connection with the performance of the Work (except losses and damages within the deductible amounts of property insurance established in accordance with Paragraph 5.06.D), provided such losses and damages have resulted from causes other than the negligence of Contractor, any Subcontractor, or anyone directly or indirectly employed by any of them or for whose acts any of them may be liable. Such losses shall include settlements made with the written consent and approval of Owner. No such losses, damages, and expenses shall be included in the Cost of the Work for the purpose of determining Contractor's fee.
- g. The cost of utilities, fuel, and sanitary facilities at the Site.
- h. Minor expenses such as telegrams, long distance telephone calls, telephone service at the Site, express and courier services, and similar petty cash items in connection with the Work.
- The costs of premiums for all bonds and insurance Contractor is required by the Contract Documents to purchase and maintain.
- B. *Costs Excluded:* The term Cost of the Work shall not include any of the following items:
  - Payroll costs and other compensation of Contractor's officers, executives, principals (of partnerships and sole proprietorships), general managers, safety managers, engineers, architects, estimators, attorneys, auditors, accountants, purchasing and contracting agents, expediters, timekeepers, clerks, and other personnel employed by Contractor, whether at the Site or in Contractor's principal or branch office for

general administration of the Work and not specifically included in the agreed upon schedule of job classifications referred to in Paragraph 11.01.A.1 or specifically covered by Paragraph 11.01.A.4, all of which are to be considered administrative costs covered by the Contractor's fee.

- Expenses of Contractor's principal and branch offices other than Contractor's office at the Site.
- 3. Any part of Contractor's capital expenses, including interest on Contractor's capital employed for the Work and charges against Contractor for delinquent payments.
- 4. Costs due to the negligence of Contractor, any Subcontractor, or anyone directly or indirectly employed by any of them or for whose acts any of them may be liable, including but not limited to, the correction of defective Work, disposal of materials or equipment wrongly supplied, and making good any damage to property.
- Other overhead or general expense costs of any kind and the costs of any item not specifically and expressly included in Paragraphs 11.01.A.
- C. Contractor's Fee: When all the Work is performed on the basis of cost-plus, Contractor's fee shall be determined as set forth in the Agreement. When the value of any Work covered by a Change Order or when a Claim for an adjustment in Contract Price is determined on the 11.03 basis of Cost of the Work, Contractor's fee shall be determined as set forth in Paragraph 12.01.C.
- D. Documentation: Whenever the Cost of the Work for any purpose is to be determined pursuant to Paragraphs 11.01.A and 11.01.B, Contractor will establish and maintain records thereof in accordance with generally accepted accounting practices and submit in a form acceptable to Engineer an itemized cost breakdown together with supporting data.

#### 11.02 Allowances

A. It is understood that Contractor has included in the Contract Price all allowances so named in the Contract Documents and shall cause the Work so covered to be performed for such sums and by such persons or entities as may be acceptable to Owner and Engineer.

#### B. Cash Allowances:

#### 1. Contractor agrees that:

- a. the cash allowances include the cost to Contractor (less any applicable trade discounts) of materials and equipment required by the allowances to be delivered at the Site, and all applicable taxes; and
- b. Contractor's costs for unloading and handling on the Site, labor, installation, overhead, profit, and other expenses contemplated for the cash allowances have been included in the Contract Price and not in the allowances, and no demand for additional payment on account of any of the foregoing will be valid.

#### C. Contingency Allowance:

- 1. Contractor agrees that a contingency allowance, if any, is for the sole use of Owner to cover unanticipated costs.
- D. Prior to final payment, an appropriate Change Order will be issued as recommended by Engineer to reflect actual amounts due Contractor on account of Work covered by allowances, and the Contract Price shall be correspondingly adjusted.

#### 1.03 Unit Price Work

- A. Where the Contract Documents provide that all or part of the Work is to be Unit Price Work, initially the Contract Price will be deemed to include for all Unit Price Work an amount equal to the sum of the unit price for each separately identified item of Unit Price Work times the estimated quantity of each item as indicated in the Agreement.
- B. The estimated quantities of items of Unit Price Work are not guaranteed and are solely for the purpose of comparison of Bids and determining an initial Contract Price. Determinations of the actual quantities and classifications of Unit Price Work performed by Contractor will be made by Engineer subject to the provisions of Paragraph 9.07.

- C. Each unit price will be deemed to include an amount considered by Contractor to be adequate to cover Contractor's overhead and profit for each separately identified item.
- D. Owner or Contractor may make a Claim for an adjustment in the Contract Price in accordance with Paragraph 10.05 if:
  - the quantity of any item of Unit Price Work performed by Contractor differs materially and significantly from the estimated quantity of such item indicated in the Agreement; and
  - 2. there is no corresponding adjustment with respect to any other item of Work; and
  - Contractor believes that Contractor is entitled
    to an increase in Contract Price as a result of
    having incurred additional expense or Owner
    believes that Owner is entitled to a decrease
    in Contract Price and the parties are unable to
    agree as to the amount of any such increase or
    decrease.

## ARTICLE 12 – CHANGE OF CONTRACT PRICE; CHANGE OF CONTRACT TIMES

- 12.01 Change of Contract Price
  - A. The Contract Price may only be changed by a Change Order. Any Claim for an adjustment in the Contract Price shall be based on written notice submitted by the party making the Claim to the Engineer and the other party to the Contract in accordance with the provisions of Paragraph 10.05.
  - B. The value of any Work covered by a Change Order or of any Claim for an adjustment in the Contract Price will be determined as follows:
    - 1. where the Work involved is covered by unit prices contained in the Contract Documents, by application of such unit prices to the quantities of the items involved (subject to the provisions of Paragraph 11.03); or
    - 2. where the Work involved is not covered by unit prices contained in the Contract Documents, by a mutually agreed lump sum (which may include an allowance for overhead and profit not necessarily in accordance with Paragraph 12.01.C.2); or

- 3. where the Work involved is not covered by unit prices contained in the Contract Documents and agreement to a lump sum is not reached under Paragraph 12.01.B.2, on the basis of the Cost of the Work (determined as provided in Paragraph 11.01) plus a Contractor's fee for overhead and profit (determined as provided in Paragraph 12.01.C).
- C. Contractor's Fee: The Contractor's fee for overhead and profit shall be determined as follows:
  - 1. a mutually acceptable fixed fee; or
  - 2. if a fixed fee is not agreed upon, then a fee based on the following percentages of the various portions of the Cost of the Work:
    - a. for costs incurred under Paragraphs 11.01.A.1 and 11.01.A.2, the Contractor's fee shall be 15 percent;
    - b. for costs incurred under Paragraph 11.01.A.3, the Contractor's fee shall be five percent;
    - where one or more tiers of subcontracts are on the basis of Cost of the Work plus a fee and no fixed fee is agreed upon, the intent of Paragraphs 12.01.C.2.a and 12.01.C.2.b is that the Subcontractor who actually performs the Work, at whatever tier, will be paid a fee of 15 percent of the costs incurred by such Subcontractor under **Paragraphs** 11.01.A.1 and 11.01.A.2 and that any higher tier Subcontractor and Contractor will each be paid a fee of five percent of the amount paid to the next lower tier Subcontractor;
    - d. no fee shall be payable on the basis of costs itemized under Paragraphs 11.01.A.4, 11.01.A.5, and 11.01.B;
    - e. the amount of credit to be allowed by Contractor to Owner for any change which results in a net decrease in cost will be the amount of the actual net decrease in cost plus a deduction in Contractor's fee by an amount equal to five percent of such net decrease; and

when both additions and credits are involved in any one change, the adjustment in Contractor's fee shall be computed on the basis of the net change accordance with **Paragraphs** 12.01.C.2.a 12.01.C.2.e, through inclusive.

#### 12.02 Change of Contract Times

- A. The Contract Times may only be changed by a Change Order. Any Claim for an adjustment in the Contract Times shall be based on written notice submitted by the party making the Claim to the Engineer and the other party to the Contract in accordance with the provisions of Paragraph 10.05.
- B. Any adjustment of the Contract Times covered by a Change Order or any Claim for an adjustment in the Contract Times will be determined in accordance with the provisions of this Article 12.

#### 12.03 Delays

- A. Where Contractor is prevented from completing any part of the Work within the Contract Times due to delay beyond the control of Contractor, the Contract Times will be extended in an amount ARTICLE 13 - TESTS AND INSPECTIONS; is made therefor as provided in Paragraph DEFECTIVE WORK 12.02.A. Delays beyond the control of Contractor shall include, but not be limited to, acts or neglect 13.01 by Owner, acts or neglect of utility owners or other contractors performing other work as contemplated by Article 7, fires, floods, epidemics, abnormal weather conditions, or acts of God.
- B. If Owner, Engineer, or other contractors or utility owners performing other work for Owner as 13.02 contemplated by Article 7, or anyone for whom Owner is responsible, delays, disrupts, or interferes with the performance or progress of the Work, then Contractor shall be entitled to an equitable adjustment in the Contract Price or the Contract Times, or both. Contractor's entitlement to an adjustment of the Contract Times is conditioned on such adjustment being essential to Contractor's ability to complete the Work within the Contract Times.
- C. If Contractor is delayed in the performance or progress of the Work by fire, flood, epidemic, abnormal weather conditions, acts of God, acts or failures to act of utility owners not under the

control of Owner, or other causes not the fault of and beyond control of Owner and Contractor, then Contractor shall be entitled to an equitable adjustment in Contract Times, if such adjustment is essential to Contractor's ability to complete the Work within the Contract Times. Such an adjustment shall be Contractor's sole and exclusive remedy for the delays described in this Paragraph 12.03.C.

- D. Owner, Engineer, and their officers, directors, partners, employees, members. agents, consultants, or subcontractors shall not be liable to Contractor for any claims, costs, losses, or damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) sustained by Contractor on or in connection with any other project or anticipated project.
- E. Contractor shall not be entitled to an adjustment in Contract Price or Contract Times for delays within the control of Contractor. Delays attributable to and within the control of a Subcontractor or Supplier shall be deemed to be delays within the control of Contractor.

# equal to the time lost due to such delay if a Claim CORRECTION, REMOVAL OR ACCEPTANCE OF

#### Notice of Defects

A. Prompt notice of all defective Work of which Owner or Engineer has actual knowledge will be given to Contractor. Defective Work may be rejected, corrected, or accepted as provided in this Article 13.

#### Access to Work

A. Owner, Engineer, their consultants and other representatives and personnel of independent testing laboratories, and governmental agencies with jurisdictional interests will have access to the Site and the Work at reasonable times for their observation, inspection, and testing. Contractor shall provide them proper and safe conditions for such access and advise them of Contractor's safety procedures and programs so that they may comply therewith as applicable.

- A. Contractor shall give Engineer timely notice of readiness of the Work for all required inspections, 13.04 tests, or approvals and shall cooperate with inspection and testing personnel to facilitate required inspections or tests.
- B. Owner shall employ and pay for the services of an independent testing laboratory to perform all inspections, tests, or approvals required by the Contract Documents except:
  - 1. for inspections, tests, or approvals covered by Paragraphs 13.03.C and 13.03.D below;
  - that costs incurred in connection with tests or inspections conducted pursuant to Paragraph 13.04.B shall be paid as provided in Paragraph 13.04.C; and
  - as otherwise specifically provided in the Contract Documents.
- C. If Laws or Regulations of any public body having jurisdiction require any Work (or part thereof) specifically to be inspected, tested, or approved by an employee or other representative of such public body, Contractor shall assume full responsibility for arranging and obtaining such inspections, tests, or approvals, pay all costs in connection therewith, and furnish Engineer the required certificates of inspection or approval.
- D. Contractor shall be responsible for arranging and obtaining and shall pay all costs in connection with any inspections, tests, or approvals required for Owner's and Engineer's acceptance of materials or equipment to be incorporated in the Work; or acceptance of materials, mix designs, or equipment submitted for approval prior to Contractor's purchase thereof for incorporation in the Work. Such inspections, tests, or approvals shall be performed by organizations acceptable to Owner and Engineer.
- E. If any Work (or the work of others) that is to be 13.05 inspected, tested, or approved is covered by Contractor without written concurrence of Engineer, Contractor shall, if requested by Engineer, uncover such Work for observation.
- F. Uncovering Work as provided in Paragraph 13.03.E shall be at Contractor's expense unless Contractor has given Engineer timely notice of Contractor's intention to cover the same and

Engineer has not acted with reasonable promptness in response to such notice.

#### Uncovering Work

- A. If any Work is covered contrary to the written request of Engineer, it must, if requested by Engineer, be uncovered for Engineer's observation and replaced at Contractor's expense.
- B. If Engineer considers it necessary or advisable that covered Work be observed by Engineer or inspected or tested by others, Contractor, at Engineer's request, shall uncover, expose, or otherwise make available for observation, inspection, or testing as Engineer may require, that portion of the Work in question, furnishing all necessary labor, material, and equipment.
- C. If it is found that the uncovered Work is defective. Contractor shall pay all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or such uncovering, relating to exposure, observation, inspection, and testing, and of replacement or reconstruction satisfactory (including but not limited to all costs of repair or replacement of work of others); and Owner shall be entitled to an appropriate decrease in the Contract Price. If the parties are unable to agree as to the amount thereof, Owner may make a Claim therefor as provided in Paragraph 10.05.
- D. If the uncovered Work is not found to be defective, Contractor shall be allowed an increase in the Contract Price or an extension of the Contract Times, or both, directly attributable to such uncovering, exposure, observation, inspection, testing, replacement, and reconstruction. If the parties are unable to agree as to the amount or extent thereof, Contractor may make a Claim therefor as provided in Paragraph 10.05.

#### 3.05 Owner May Stop the Work

A. If the Work is defective, or Contractor fails to supply sufficient skilled workers or suitable materials or equipment, or fails to perform the Work in such a way that the completed Work will conform to the Contract Documents, Owner may order Contractor to stop the Work, or any portion thereof, until the cause for such order has been eliminated; however, this right of Owner to stop

the Work shall not give rise to any duty on the part of Owner to exercise this right for the benefit of Contractor, any Subcontractor, any Supplier, any other individual or entity, or any surety for, or employee or agent of any of them.

#### 13.06 Correction or Removal of Defective Work

- A. Promptly after receipt of written notice, Contractor shall correct all defective Work, whether or not fabricated, installed, or completed, or, if the Work has been rejected by Engineer, remove it from the Project and replace it with Work that is not defective. Contractor shall pay all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to such correction or removal (including but not limited to all costs of repair or replacement of work of others).
- B. When correcting defective Work under the terms of this Paragraph 13.06 or Paragraph 13.07, Contractor shall take no action that would void or otherwise impair Owner's special warranty and guarantee, if any, on said Work.

#### 13.07 Correction Period

- A. If within one year after the date of Substantial Completion (or such longer period of time as may be prescribed by the terms of any applicable special guarantee required by the Contract Documents) or by any specific provision of the Contract Documents, any Work is found to be defective, or if the repair of any damages to the land or areas made available for Contractor's use by Owner or permitted by Laws and Regulations as contemplated in Paragraph 6.11.A is found to be defective, Contractor shall promptly, without cost to Owner and in accordance with Owner's written instructions:
  - 1. repair such defective land or areas; or
  - 2. correct such defective Work; or
  - 3. if the defective Work has been rejected by Owner, remove it from the Project and replace it with Work that is not defective, and
  - satisfactorily correct or repair or remove and replace any damage to other Work, to the work of others or other land or areas resulting therefrom.

- B. If Contractor does not promptly comply with the terms of Owner's written instructions, or in an emergency where delay would cause serious risk of loss or damage, Owner may have the defective Work corrected or repaired or may have the rejected Work removed and replaced. All claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to such correction or repair or such removal and replacement (including but not limited to all costs of repair or replacement of work of others) will be paid by Contractor.
- C. In special circumstances where a particular item of equipment is placed in continuous service before Substantial Completion of all the Work, the correction period for that item may start to run from an earlier date if so provided in the Specifications.
- D. Where defective Work (and damage to other Work resulting therefrom) has been corrected or removed and replaced under this Paragraph 13.07, the correction period hereunder with respect to such Work will be extended for an additional period of one year after such correction or removal and replacement has been satisfactorily completed.
- E. Contractor's obligations under this Paragraph 13.07 are in addition to any other obligation or warranty. The provisions of this Paragraph 13.07 shall not be construed as a substitute for, or a waiver of, the provisions of any applicable statute of limitation or repose.

#### 3.08 Acceptance of Defective Work

A. If, instead of requiring correction or removal and replacement of defective Work, Owner (and, prior to Engineer's recommendation of final payment, Engineer) prefers to accept it, Owner may do so. Contractor shall pay all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) attributable to Owner's evaluation of and determination to accept such defective Work (such costs to be approved by Engineer as to reasonableness) and for the diminished value of the Work to the extent not otherwise paid by Contractor pursuant to this sentence. If any such acceptance occurs prior to

Engineer's recommendation of final payment, a Change Order will be issued incorporating the necessary revisions in the Contract Documents with respect to the Work, and Owner shall be entitled to an appropriate decrease in the Contract Price, reflecting the diminished value of Work so accepted. If the parties are unable to agree as to the amount thereof, Owner may make a Claim therefor as provided in Paragraph 10.05. If the acceptance occurs after such recommendation, an appropriate amount will be paid by Contractor to Owner.

#### 13.09 Owner May Correct Defective Work

- A. If Contractor fails within a reasonable time after written notice from Engineer to correct defective Work, or to remove and replace rejected Work as ARTICLE 14 - PAYMENTS TO CONTRACTOR AND required by Engineer in accordance with COMPLETION Paragraph 13.06.A, or if Contractor fails to perform the Work in accordance with the Contract 14.01 Documents, or if Contractor fails to comply with any other provision of the Contract Documents, Owner may, after seven days written notice to Contractor, correct, or remedy any such deficiency.
- B. In exercising the rights and remedies under this Paragraph 13.09, Owner shall proceed expeditiously. In connection with such corrective or remedial action, Owner may exclude 14.02 Contractor from all or part of the Site, take possession of all or part of the Work and suspend Contractor's services related thereto, take possession of Contractor's tools, appliances, construction equipment and machinery at the Site, and incorporate in the Work all materials and equipment stored at the Site or for which Owner has paid Contractor but which are stored elsewhere. Contractor shall allow Owner, Owner's representatives, agents and employees, Owner's other contractors, and Engineer and Engineer's consultants access to the Site to enable Owner to exercise the rights and remedies under this Paragraph.
- C. All claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) incurred or sustained by Owner in exercising the rights and remedies under this Paragraph 13.09 will be charged against Contractor, and a Change Order will be issued incorporating the necessary revisions in the Contract Documents with respect to the Work;

and Owner shall be entitled to an appropriate decrease in the Contract Price. If the parties are unable to agree as to the amount of the adjustment, Owner may make a Claim therefor as provided in Paragraph 10.05. Such claims, costs, losses and damages will include but not be limited to all costs of repair, or replacement of work of others destroyed or damaged by correction, removal, or replacement of Contractor's defective Work.

D. Contractor shall not be allowed an extension of the Contract Times because of any delay in the performance of the Work attributable to the exercise by Owner of Owner's rights and remedies under this Paragraph 13.09.

#### Schedule of Values

A. The Schedule of Values established as provided in Paragraph 2.07.A will serve as the basis for progress payments and will be incorporated into a form of Application for Payment acceptable to Engineer. Progress payments on account of Unit Price Work will be based on the number of units completed.

#### **Progress Payments**

#### A. Applications for Payments:

1. At least 20 days before the date established in the Agreement for each progress payment (but not more often than once a month), Contractor shall submit to Engineer for review an Application for Payment filled out and signed by Contractor covering the Work completed as of the date of the Application and accompanied by such supporting documentation as is required by the Contract Documents. If payment is requested on the basis of materials and equipment not incorporated in the Work but delivered and suitably stored at the Site or at another location agreed to in writing, the Application for Payment shall also be accompanied by a bill of sale, invoice, or other documentation warranting that Owner has received the materials and equipment free and clear of all Liens and evidence that the materials and equipment are covered by appropriate property insurance or other arrangements to

- protect Owner's interest therein, all of which must be satisfactory to Owner.
- Beginning with the second Application for Payment, each Application shall include an affidavit of Contractor stating that all previous progress payments received on account of the Work have been applied on account to discharge Contractor's legitimate obligations associated with prior Applications for Payment.
- 3. The amount of retainage with respect to progress payments will be as stipulated in the Agreement.

#### B. Review of Applications:

- 1. Engineer will, within 10 days after receipt of each Application for Payment, either indicate in writing a recommendation of payment and present the Application to Owner or return the Application to Contractor indicating in writing Engineer's reasons for refusing to recommend payment. In the latter case, Contractor may make the necessary corrections and resubmit the Application.
- 2. Engineer's recommendation of any payment requested in an Application for Payment will constitute a representation by Engineer to Owner, based on Engineer's observations of the executed Work as an experienced and qualified design professional, and on Engineer's review of the Application for Payment and the accompanying data and schedules, that to the best of Engineer's knowledge, information and belief:
  - a. the Work has progressed to the point indicated;
  - the quality of the Work is generally in accordance with the Contract Documents (subject to an evaluation of the Work as a functioning whole prior to or upon Substantial Completion, the results of any subsequent tests called for in the Contract Documents, determination of quantities and classifications for Unit Price Work under Paragraph 9.07, and any other qualifications the stated in recommendation); and

- the conditions precedent to Contractor's being entitled to such payment appear to have been fulfilled in so far as it is Engineer's responsibility to observe the Work.
- 3. By recommending any such payment Engineer will not thereby be deemed to have represented that:
  - a. inspections made to check the quality or the quantity of the Work as it has been performed have been exhaustive, extended to every aspect of the Work in progress, or involved detailed inspections of the Work beyond the responsibilities specifically assigned to Engineer in the Contract Documents; or
  - there may not be other matters or issues between the parties that might entitle Contractor to be paid additionally by Owner or entitle Owner to withhold payment to Contractor.
- 4. Neither Engineer's review of Contractor's Work for the purposes of recommending payments nor Engineer's recommendation of any payment, including final payment, will impose responsibility on Engineer:
  - a. to supervise, direct, or control the Work, or
  - b. for the means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto, or
  - c. for Contractor's failure to comply with Laws and Regulations applicable to Contractor's performance of the Work, or
  - d. to make any examination to ascertain how or for what purposes Contractor has used the moneys paid on account of the Contract Price, or
  - e. to determine that title to any of the Work, materials, or equipment has passed to Owner free and clear of any Liens.
- 5. Engineer may refuse to recommend the whole or any part of any payment if, in Engineer's opinion, it would be incorrect to make the

representations to Owner stated in Paragraph 14.02.B.2. Engineer may also refuse to recommend any such payment or, because of subsequently discovered evidence or the results of subsequent inspections or tests, revise or revoke any such payment recommendation previously made, to such extent as may be necessary in Engineer's opinion to protect Owner from loss because:

- a. the Work is defective, or completed Work has been damaged, requiring correction or replacement;
- b. the Contract Price has been reduced by Change Orders;
- Owner has been required to correct defective Work or complete Work in accordance with Paragraph 13.09; or
- d. Engineer has actual knowledge of the occurrence of any of the events enumerated in Paragraph 15.02.A.

#### C. Payment Becomes Due:

 Ten days after presentation of the Application for Payment to Owner with Engineer's recommendation, the amount recommended will (subject to the provisions of Paragraph 14.02.D) become due, and when due will be 14.04 paid by Owner to Contractor.

#### D. Reduction in Payment:

- Owner may refuse to make payment of the full amount recommended by Engineer because:
  - claims have been made against Owner on account of Contractor's performance or furnishing of the Work;
  - Liens have been filed in connection with the Work, except where Contractor has delivered a specific bond satisfactory to Owner to secure the satisfaction and discharge of such Liens;
  - there are other items entitling Owner to a set-off against the amount recommended;
     or
  - d. Owner has actual knowledge of the occurrence of any of the events

enumerated in Paragraphs 14.02.B.5.a through 14.02.B.5.c or Paragraph 15.02.A.

- 2. If Owner refuses to make payment of the full amount recommended by Engineer, Owner will give Contractor immediate written notice (with a copy to Engineer) stating the reasons for such action and promptly pay Contractor any amount remaining after deduction of the amount so withheld. Owner shall promptly pay Contractor the amount so withheld, or any adjustment thereto agreed to by Owner and Contractor, when Contractor remedies the reasons for such action.
- 3. Upon a subsequent determination that Owner's refusal of payment was not justified, the amount wrongfully withheld shall be treated as an amount due as determined by Paragraph 14.02.C.1 and subject to interest as provided in the Agreement.

#### 14.03 Contractor's Warranty of Title

A. Contractor warrants and guarantees that title to all Work, materials, and equipment covered by any Application for Payment, whether incorporated in the Project or not, will pass to Owner no later than the time of payment free and clear of all Liens.

#### 04 Substantial Completion

- A. When Contractor considers the entire Work ready for its intended use Contractor shall notify Owner and Engineer in writing that the entire Work is substantially complete (except for items specifically listed by Contractor as incomplete) and request that Engineer issue a certificate of Substantial Completion.
- B. Promptly after Contractor's notification, Owner, Contractor, and Engineer shall make an inspection of the Work to determine the status of completion. If Engineer does not consider the Work substantially complete, Engineer will notify Contractor in writing giving the reasons therefor.
- C. If Engineer considers the Work substantially complete, Engineer will deliver to Owner a tentative certificate of Substantial Completion which shall fix the date of Substantial Completion. There shall be attached to the certificate a tentative list of items to be completed or corrected before final payment. Owner shall have seven days after receipt of the tentative certificate during which to

make written objection to Engineer as to any provisions of the certificate or attached list. If, after considering such objections, Engineer concludes that the Work is not substantially complete, Engineer will, within 14 days after submission of the tentative certificate to Owner, notify Contractor in writing, stating the reasons therefor. If, after consideration of Owner's objections, Engineer considers the Work substantially complete, Engineer will, within said 14 days, execute and deliver to Owner and Contractor a definitive certificate of Substantial Completion (with a revised tentative list of items to be completed or corrected) reflecting such changes from the tentative certificate as Engineer believes justified after consideration of any objections from Owner.

- D. At the time of delivery of the tentative certificate of Substantial Completion, Engineer will deliver and Contractor Owner a recommendation as to division of responsibilities pending final payment between Owner and Contractor with respect to security, operation, safety, and protection of the Work, maintenance, heat, utilities, insurance, and warranties and guarantees. Unless Owner and Contractor agree otherwise in writing and so inform Engineer in writing prior to Engineer's issuing the definitive certificate of Substantial Completion, Engineer's aforesaid recommendation will be binding on Owner and Contractor until final payment.
- E. Owner shall have the right to exclude Contractor from the Site after the date of Substantial Completion subject to allowing Contractor reasonable access to remove its property and 14.06 complete or correct items on the tentative list.

#### 14.05 Partial Utilization

- A. Prior to Substantial Completion of all the Work, Owner may use or occupy any substantially completed part of the Work which has specifically been identified in the Contract Documents, or which Owner, Engineer, and Contractor agree constitutes a separately functioning and usable part of the Work that can be used by Owner for its intended purpose without significant interference with Contractor's performance of the remainder of the Work, subject to the following conditions:
  - Owner at any time may request Contractor in writing to permit Owner to use or occupy any such part of the Work which Owner believes to be ready for its intended use and

substantially complete. If and when Contractor agrees that such part of the Work is substantially complete, Contractor, Owner, and Engineer will follow the procedures of Paragraph 14.04.A through D for that part of the Work.

- Contractor at any time may notify Owner and Engineer in writing that Contractor considers any such part of the Work ready for its intended use and substantially complete and request Engineer to issue a certificate of Substantial Completion for that part of the Work.
- 3. Within a reasonable time after either such request, Owner, Contractor, and Engineer shall make an inspection of that part of the Work to determine its status of completion. If Engineer does not consider that part of the Work to be substantially complete, Engineer will notify Owner and Contractor in writing giving the reasons therefor. If Engineer considers that part of the Work to be substantially complete, the provisions of Paragraph 14.04 will apply with respect to certification of Substantial Completion of that part of the Work and the division of responsibility in respect thereof and access thereto.
- No use or occupancy or separate operation of part of the Work may occur prior to compliance with the requirements of Paragraph 5.10 regarding property insurance.

#### 4.06 Final Inspection

A. Upon written notice from Contractor that the entire Work or an agreed portion thereof is complete, Engineer will promptly make a final inspection with Owner and Contractor and will notify Contractor in writing of all particulars in which this inspection reveals that the Work is incomplete or defective. Contractor shall immediately take such measures as are necessary to complete such Work or remedy such deficiencies.

### A. Application for Payment:

- After Contractor has, in the opinion of Engineer, satisfactorily completed corrections identified during the final inspection and has delivered, in accordance the Contract Documents. with maintenance and operating instructions, schedules, guarantees, bonds, certificates or other evidence of insurance, certificates of inspection, marked-up record documents (as provided in Paragraph 6.12), and other documents, Contractor may make application for final payment following the procedure for progress payments.
- The final Application for Payment shall be accompanied (except as previously delivered) by:
  - a. all documentation called for in the Contract Documents, including but not limited to the evidence of insurance required by Paragraph 5.04.B.6;
  - b. consent of the surety, if any, to final payment;
  - a list of all Claims against Owner that Contractor believes are unsettled; and
  - d. complete and legally effective releases or waivers (satisfactory to Owner) of all Lien rights arising out of or Liens filed in connection with the Work.
- 3. In lieu of the releases or waivers of Liens specified in Paragraph 14.07.A.2 and as 14.08 approved by Owner, Contractor may furnish receipts or releases in full and an affidavit of Contractor that: (i) the releases and receipts include all labor, services, material, and equipment for which a Lien could be filed; and (ii) all payrolls, material and equipment bills, and other indebtedness connected with the Work for which Owner might in any way be responsible, or which might in any way result in liens or other burdens on Owner's property, have been paid or otherwise satisfied. If any Subcontractor or Supplier fails to furnish such a release or receipt in full, Contractor may furnish a bond or other collateral satisfactory to Owner to indemnify Owner against any Lien.

- B. Engineer's Review of Application and Acceptance:
  - If, on the basis of Engineer's observation of the Work during construction and final inspection, and Engineer's review of the final Application for Payment and accompanying documentation as required by the Contract Documents, Engineer is satisfied that the Work has been completed and Contractor's other obligations under the Contract Documents have been fulfilled, Engineer will, within ten days after receipt of the final Application for Payment, indicate in writing Engineer's recommendation of payment and present the Application for Payment to Owner for payment. At the same time Engineer will also give written notice to Owner and Contractor that the Work is acceptable subject to the provisions of Paragraph 14.09. Otherwise, Engineer will return the Application for Payment to Contractor, indicating in writing the reasons for refusing to recommend final payment, in which case Contractor shall make the necessary corrections and resubmit the Application for Payment.

#### C. Payment Becomes Due:

 Thirty days after the presentation to Owner of the Application for Payment and accompanying documentation, the amount recommended by Engineer, less any sum Owner is entitled to set off against Engineer's recommendation, including but not limited to liquidated damages, will become due and will be paid by Owner to Contractor.

#### 4.08 Final Completion Delayed

A. If, through no fault of Contractor, final completion of the Work is significantly delayed, and if Engineer so confirms, Owner shall, upon receipt of Contractor's final Application for Payment (for Work fully completed and accepted) and recommendation of Engineer, and without terminating the Contract, make payment of the balance due for that portion of the Work fully completed and accepted. If the remaining balance to be held by Owner for Work not fully completed or corrected is less than the retainage stipulated in the Agreement, and if bonds have been furnished as required in Paragraph 5.01, the written consent of the surety to the payment of the balance due for that portion of the Work fully completed and

accepted shall be submitted by Contractor to Engineer with the Application for such payment. Such payment shall be made under the terms and conditions governing final payment, except that it shall not constitute a waiver of Claims.

#### 14.09 Waiver of Claims

- A. The making and acceptance of final payment will constitute:
  - a waiver of all Claims by Owner against Contractor, except Claims arising from unsettled Liens, from defective Work appearing after final inspection pursuant to Paragraph 14.06, from failure to comply with the Contract Documents or the terms of any special guarantees specified therein, or from Contractor's continuing obligations under the Contract Documents; and
  - a waiver of all Claims by Contractor against Owner other than those previously made in accordance with the requirements herein and expressly acknowledged by Owner in writing as still unsettled.

## ARTICLE 15 – SUSPENSION OF WORK AND TERMINATION

#### 15.01 Owner May Suspend Work

A. At any time and without cause, Owner may suspend the Work or any portion thereof for a period of not more than 90 consecutive days by notice in writing to Contractor and Engineer which will fix the date on which Work will be resumed. Contractor shall resume the Work on the date so fixed. Contractor shall be granted an adjustment in the Contract Price or an extension of the Contract Times, or both, directly attributable to any such suspension if Contractor makes a Claim therefor as provided in Paragraph 10.05.

### 15.02 Owner May Terminate for Cause

- A. The occurrence of any one or more of the following events will justify termination for cause:
  - Contractor's persistent failure to perform the Work in accordance with the Contract Documents (including, but not limited to, failure to supply sufficient skilled workers or suitable materials or equipment or failure to adhere to the Progress Schedule established

- under Paragraph 2.07 as adjusted from time to time pursuant to Paragraph 6.04);
- Contractor's disregard of Laws or Regulations of any public body having jurisdiction;
- Contractor's repeated disregard of the authority of Engineer; or
- 4. Contractor's violation in any substantial way of any provisions of the Contract Documents.
- B. If one or more of the events identified in Paragraph 15.02.A occur, Owner may, after giving Contractor (and surety) seven days written notice of its intent to terminate the services of Contractor:
  - exclude Contractor from the Site, and take possession of the Work and of all Contractor's tools, appliances, construction equipment, and machinery at the Site, and use the same to the full extent they could be used by Contractor (without liability to Contractor for trespass or conversion);
  - incorporate in the Work all materials and equipment stored at the Site or for which Owner has paid Contractor but which are stored elsewhere; and
  - 3. complete the Work as Owner may deem expedient.
- C. If Owner proceeds as provided in Paragraph 15.02.B, Contractor shall not be entitled to receive any further payment until the Work is completed. If the unpaid balance of the Contract Price exceeds all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) sustained by Owner arising out of or relating to completing the Work, such excess will be paid to Contractor. If such claims, costs, losses, and damages exceed such unpaid balance, Contractor shall pay the difference to Owner. Such claims, costs, losses, and damages incurred by Owner will be reviewed by Engineer as to their reasonableness and, when so approved by Engineer, incorporated in a Change Order. When exercising any rights or remedies under this Paragraph, Owner shall not be required to obtain the lowest price for the Work performed.

- D. Notwithstanding Paragraphs 15.02.B and 15.02.C, Contractor's services will not be terminated if Contractor begins within seven days of receipt of notice of intent to terminate to correct its failure to perform and proceeds diligently to cure such failure within no more than 30 days of receipt of 15.04 said notice.
- Where Contractor's services have been so terminated by Owner, the termination will not affect any rights or remedies of Owner against Contractor then existing or which may thereafter accrue. Any retention or payment of moneys due Contractor by Owner will not release Contractor from liability.
- F. If and to the extent that Contractor has provided a performance bond under the provisions of Paragraph 5.01.A, the termination procedures of that bond shall supersede the provisions of Paragraphs 15.02.B and 15.02.C.

#### 15.03 Owner May Terminate For Convenience

- A. Upon seven days written notice to Contractor and Engineer, Owner may, without cause and without prejudice to any other right or remedy of Owner, terminate the Contract. In such case, Contractor shall be paid for (without duplication of any items):
  - completed and acceptable Work executed in accordance with the Contract Documents prior to the effective date of termination, including fair and reasonable sums for overhead and profit on such Work;
  - 2. expenses sustained prior to the effective date of termination in performing services and ARTICLE 16 - DISPUTE RESOLUTION furnishing labor, materials, or equipment as required by the Contract Documents in connection with uncompleted Work, plus fair and reasonable sums for overhead and profit on such expenses;
  - all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) incurred in settlement of terminated contracts with Subcontractors, Suppliers, and others;
  - reasonable expenses directly attributable to termination.

B. Contractor shall not be paid on account of loss of anticipated profits or revenue or other economic loss arising out of or resulting from such termination.

#### Contractor May Stop Work or Terminate

- A. If, through no act or fault of Contractor, (i) the Work is suspended for more than 90 consecutive days by Owner or under an order of court or other public authority, or (ii) Engineer fails to act on any Application for Payment within 30 days after it is submitted, or (iii) Owner fails for 30 days to pay Contractor any sum finally determined to be due, then Contractor may, upon seven days written notice to Owner and Engineer, and provided Owner or Engineer do not remedy such suspension or failure within that time, terminate the Contract and recover from Owner payment on the same terms as provided in Paragraph 15.03.
- B. In lieu of terminating the Contract and without prejudice to any other right or remedy, if Engineer has failed to act on an Application for Payment within 30 days after it is submitted, or Owner has failed for 30 days to pay Contractor any sum finally determined to be due, Contractor may, seven days after written notice to Owner and Engineer, stop the Work until payment is made of all such amounts due Contractor, including interest thereon. The provisions of this Paragraph 15.04 are not intended to preclude Contractor from making a Claim under Paragraph 10.05 for an adjustment in Contract Price or Contract Times or otherwise for expenses or damage directly attributable to Contractor's stopping the Work as permitted by this Paragraph.

#### 16.01 Methods and Procedures

A. Either Owner or Contractor may request mediation of any Claim submitted to Engineer for a decision under Paragraph 10.05 before such decision becomes final and binding. The mediation will be governed by the Construction Industry Mediation Rules of the American Arbitration Association in effect as of the Effective Date of the Agreement. The request for mediation shall be submitted in writing to the American Arbitration Association and the other party to the Contract. Timely submission of the request shall stay the effect of Paragraph 10.05.E.

- B. Owner and Contractor shall participate in the mediation process in good faith. The process shall be concluded within 60 days of filing of the request. The date of termination of the mediation shall be determined by application of the mediation rules referenced above.
- C. If the Claim is not resolved by mediation, Engineer's action under Paragraph 10.05.C or a denial pursuant to Paragraphs 10.05.C.3 or 10.05.D shall become final and binding 30 days after termination of the mediation unless, within that time period, Owner or Contractor:
  - elects in writing to invoke any dispute resolution process provided for in the Supplementary Conditions; or
  - agrees with the other party to submit the Claim to another dispute resolution process; or
  - 3. gives written notice to the other party of the intent to submit the Claim to a court of 17.05 competent jurisdiction.

#### **ARTICLE 17 – MISCELLANEOUS**

#### 17.01 Giving Notice

- A. Whenever any provision of the Contract Documents requires the giving of written notice, it will be deemed to have been validly given if:
  - delivered in person to the individual or to a member of the firm or to an officer of the corporation for whom it is intended; or
  - 2. delivered at or sent by registered or certified mail, postage prepaid, to the last business address known to the giver of the notice.

#### 17.02 *Computation of Times*

A. When any period of time is referred to in the Contract Documents by days, it will be computed to exclude the first and include the last day of such period. If the last day of any such period falls on a Saturday or Sunday or on a day made a legal holiday by the law of the applicable jurisdiction, such day will be omitted from the computation.

#### 17.03 Cumulative Remedies

A. The duties and obligations imposed by these General Conditions and the rights and remedies available hereunder to the parties hereto are in addition to, and are not to be construed in any way as a limitation of, any rights and remedies available to any or all of them which are otherwise imposed or available by Laws or Regulations, by special warranty or guarantee, or by other provisions of the Contract Documents. The provisions of this Paragraph will be as effective as if repeated specifically in the Contract Documents in connection with each particular duty, obligation, right, and remedy to which they apply.

#### 17.04 Survival of Obligations

A. All representations, indemnifications, warranties, and guarantees made in, required by, or given in accordance with the Contract Documents, as well as all continuing obligations indicated in the Contract Documents, will survive final payment, completion, and acceptance of the Work or termination or completion of the Contract or termination of the services of Contractor.

#### .05 Controlling Law

A. This Contract is to be governed by the law of the state in which the Project is located.

#### 17.06 Headings

A. Article and paragraph headings are inserted for convenience only and do not constitute parts of these General Conditions.

### SUPPLEMENTARY CONDITIONS

### TABLE OF CONTENTS

## PART I - AMENDMENTS TO STANDARD GENERAL CONDITIONS OF THE CONSTRUCTION CONTRACT

Article Number	Title
rumoer	<u>Title</u>
1	DEFINITIONS AND TERMINOLOGY
2	PRELIMINARY MATTERS
3	CONTRACT DOCUMENTS; INTENT, AMENDING, REUSE
4	AVAILABILITY OF LANDS; SUBSURFACE AND PHYSICAL CONDITIONS;
	HAZARDOUS ENVIRONMENTAL CONDITIONS; REFERENCE POINTS
5	BONDS AND INSURANCE
6	CONTRACTOR'S RESPONSIBILITIES
7	OTHER WORK AT THE SITE
8	OWNER'S RESPONSIBILITIES
9	ENGINEER'S STATUS DURING CONSTRUCTION
11	COST OF THE WORK; ALLOWANCES; UNIT PRICE WORK
12	CHANGE OF CONTRACT PRICE; CHANGE OF CONTRACT TIMES
13	TESTS AND INSPECTIONS; CORRECTION, REMOVAL OR ACCEPTANCE OF
	DEFECTIVE WORK
14	PAYMENTS TO CONTRACTOR AND COMPLETION
15	SUSPENSION OF WORK AND TERMINATION
16	DISPUTE RESOLUTION
17	MISCELLANEOUS

### PART II - LOCAL GOVERNMENT PROVISIONS

2.0. CITY OF NEW BEDFORD, MASSACHUSETTS PROVISIONS

#### SUPPLEMENTARY CONDITIONS

## PART I - AMENDMENTS TO STANDARD GENERAL CONDITIONS OF THE CONSTRUCTION CONTRACT

These Supplementary Conditions amend or supplement the Standard General Conditions of the Construction Contract (EJCDC Document No. C-700, 2007 edition) (hereinafter referred to as "General Conditions") and other provisions of the Contract Documents as indicated below. All provisions which are not so amended or supplemented remain in full force and effect.

ARTICLE 1 - DEFINITIONS AND TERMINOLOGY

SC-1.01A.44.

Insert the following at the beginning of the definition before the words "The time at....."

The Work required by the Contract has been completed except for work having a Contract Price of less than one per cent of the then adjusted total contract price, or

**ARTICLE 2 - PRELIMINARY MATTERS** 

SC-2.01B.

Delete paragraph 2.01B. of the General Conditions in its entirety and replace with the following:

B. Before any Work at the site is started, Contractor shall deliver to Owner, with copies to Engineer and each additional insured identified in Article 5 of the General Conditions and of the Supplementary Conditions, certificates of insurance (and other evidence requested by Owner) which Contractor and their subcontractors' are required to purchase and maintain in accordance with the requirements of Article 5.

No work shall be performed under this Contract until and unless the Contractor and Subcontractor(s) have obtained all the insurance required and the Owner has approved such insurance. The insurance require for the Contractor shall the same for all Subcontractors'.

SC-2.02A

Delete "ten" in the first line and replace with "three".

SC-2.03A.

Delete paragraph 2.03A of the General Conditions in its entirety and replace with the following:

A. The Contract Time will commence to run on the twentieth day following the Effective Date of the Agreement.

SC-2.05.A

Insert the following new paragraphs immediately following Paragraph 2.05.A of the General Conditions which is to read as follows:

- B. Before starting construction, the Contractor shall submit to Owner and Engineer such schedules of quantities and costs, progress schedules, payrolls, reports, estimates, records, and other data the Owner may request concerning the work performed or to be performed under this Contract.
- C. Work assignments or work directives will be given to the Contractor.
  - 1. Neither Owner nor Contractor shall, without the prior written consent of the other, assign or sublet in whole or in part any interest under any of the Contract Documents; and, specifically but without limitation. Contractor shall not assign any monies due or to become due without the prior written consent of Owner. In case Contractor assigns all or any part of any monies due or to become due under this Contract, the instrument of assignment shall contain a clause substantially to the effect that it is agreed that the right of the assignee in and to any monies due or to become due to Contractor shall be subject to prior claims or all persons, firms and corporations for services rendered or materials supplies for the performance of the Work called for in this Contract.
  - 2. Each work assignment or work directive will be issued to the Contractor in writing. Prior to the starting of a work assignment or work directive, the Owner may issue to the Contractor a set of preliminary design drawings or maps which will be marked on the cover sheet of the set of design drawings as "Preliminary Design Drawings Cost Estimating Purposes Only". This set may be used by the Contractor to develop an initial estimate to complete the work. The estimate will be provided to the Owner for review and approval prior to starting work. The "Preliminary Design Drawings" will be issued in both hard copy and electronic copy.
  - 3. Once the estimate and design are approved by the Owner and Contractor jointly in writing (the Owner reserves the right to submit additional design changes to the Contractor for review following submittal of Preliminary Design Drawing Cost Estimating Purposes Only set), three final sets of paper design drawings will be issued by the Owner to Contractor marked as "100 Percent Design Submittal" once design is complete. A set of plans will also be issued electronically by email to the Contractor. The Contractor shall coordinate with the Owner to start work.
  - 4. It is the Contractor's responsibility to ensure that he/she and any subcontractors employed by the Contractor has the most up to date set of design drawings. The Owner is not responsible for any errors caused during construction or errors in ordering materials as a result of the Contractor utilizing an incorrect set of design drawings. Any errors in materials and/or construction resulting from the use of an incorrect set of drawings shall be repaired and/or replaced by the Contractor at no additional cost to the Owner.
  - 5. The Owner may, from time to time, issue work assignments or work directives to the Contractor without a set of drawings. In this instance, the Engineer and Contractor shall hold a field meeting to review the scope of work and limits of the project. The limits will be marked jointly by the Contractor and Engineer. Contractor shall prepare an estimate for the work which will be reviewed and approved by Engineer prior to the start of work.

### ARTICLE 3 - CONTRACT DOCUMENTS: INTENT, AMENDING, REUSE

SC-3.01C.

Add the following new paragraph immediately after Paragraph 3.01C. of the General Conditions which is to read as follows:

D. Each and every provision of law and clause required by law to be inserted in these Contract Documents shall be deemed to be inserted herein, and they shall be read and enforced as though it were included herein, and if through mistake or otherwise, any such provision is not inserted, or if not correctly inserted, then upon the application of either party, the Contract Documents shall forthwith be physically amended to make such insertion.

#### SC-3.03.B

Insert the following new paragraphs immediately following Paragraph 3.03.B of the General Conditions which are to read as follows:

- C. Except as may be otherwise specifically stated in the Contract Documents, in the event of conflicts, inconsistencies or discrepancies among or within any of the Contract Documents as to the quality or quantity of work to be performed or to the level of performance required to perform the work, the better quality and/or greater quantity of work, and/or the highest performance requirement shall apply without change in the Contract Price.
  - 1. In the event of such conflicts, inconsistencies or discrepancies which do not relate to the quality or quantity of work, or the level of performance required to perform the work, the Contractor shall request instructions or interpretations from the Engineer who shall issue clarification and interpretation of the Contract Documents as provided in Article 9 of the General Conditions of the Contract. In resolving conflicts, errors or discrepancies, the Contract Documents shall be given precedence as may be reasonably inferred as being consistent with their overall intent and required to produce the intended result. Subject to such determination by the Engineer, the Contract Documents shall be given precedence in the following order: Change Orders, Owner-Contractor Agreement, Notice to Proceed, Addenda, General Conditions as modified by Supplementary Conditions, Division 1, Technical Specifications (MassDOT MSSHB latest edition including all addenda, City's Standards latest edition, Division 2 through 16 of the Specifications in the event of a conflict, the more stringent shall apply), Contract Drawings, Advertisement for Bids, Instruction to Bidders, the Form for General Bid signed by the Contractor, Bonds, Insurance Certificates.
  - 2. If the issue of priority involves the Technical Specifications (MassDOT MSSHB latest edition including all addenda, City's Standards latest edition, Division 2 through 16 of the Specifications in the event of a conflict, the more stringent shall apply) and the Drawings, in all cases, figured dimensions shall govern over scaled dimensions, but work not dimensioned shall be as directed by the Engineer, and work not particularly shown, identified, sized, or located shall be the same as similar parts that are shown or specified. Detail Drawings shall govern over general Drawings, larger scale Drawings take precedence over smaller scale Drawings, Change Order Drawings govern over Contract Drawings, and Contract Drawings govern over Shop Drawings.
- D. The Contractor shall not take advantage of any apparent error or omission in the plans, specification or other contract documents, and if any inconsistency, omission or conflict is discovered in the plans, specifications, or other contract documents, or if in any place the meaning of the plans, specifications or other contract documents, is obscure, uncertain or in dispute, the Contractor shall notify the Engineer immediately shall issue clarifications and interpretations as provided in Article 9 of the General Conditions of the Contract.
- E. Each and every provision of law and clause required by law to be inserted in these Contract Documents shall be deemed to be inserted herein, and they shall be read and enforced as though it were included herein, and if through mistake or otherwise, any such provision is not inserted, or if not correctly

inserted, then upon the application of either party, the Contract Documents shall forthwith be physically amended to make such insertion.

#### SC-3.04.B

Insert the following new paragraphs immediately following Paragraph 3.04.B of the General Conditions which are to read as follows:

- C. The Contractor may be furnished with additional information and detailed drawings for specific projects if the Owner deems it necessary. The additional drawings and instructions thus supplied to the Contractor will coordinate with the Contract Documents. The Contractor shall carry out the work in accordance with the additional detail and instructions. The Contractor and the Owner will prepare jointly:
  - a. A schedule, fixing the dates at which special detail drawings will be required; such drawings, if any to be furnished by the Owner in accordance with said schedule;
  - b. A schedule fixing the respective dates for the submission of shop drawings, the beginning of manufacture testing and installation of materials, supplies and equipment, and the completion of the various parts of the work; and
  - c. Each schedule to be subject to change from time to time in accordance with the progress of the work.

## ARTICLE 4 - AVAILABILITY OF LANDS; SUBSURFACE AND PHYSICAL CONDITIONS; HAZARDOUS ENVIRONMENTAL CONDITIONS; REFERENCE POINTS

#### SC-4.01A.

Add the following new paragraph immediately after paragraph 4.01A. of the General Conditions which is to read as follows:

1. If all lands and rights-of-way are not obtained as herein contemplated before construction begins, Contractor shall begin the Work upon such land and rights-of-way as Owner has previously acquired.

#### SC-4.03C.3.

Add the following new paragraph immediately after paragraph 4.03C.3. of the General Conditions which is to read as follows:

D. Adjustments resulting from subsurface or latent physical conditions will be in accordance with Massachusetts General Law Chapter 30, Section 39N included in PART II of the Supplementary Conditions.

#### SC-4.05A.

Add the following new paragraph immediately after paragraph 4.05A of the General Conditions which is to read as follows:

B. Engineer may check the lines, elevations, reference marks, batter boards, etc., set by Contractor, and Contractor shall correct any errors disclosed by such check. Such a check shall not be considered as approval of Contractor's work and shall not relieve Contractor of the responsibility for accurate

construction of the entire Work. Contractor shall furnish personnel to assist Engineer in checking lines and grades.

#### ARTICLE 5 – BONDS AND INSURANCE

SC-5.01A.

Delete the third sentence in paragraph 5.01A of the General Conditions and replace with the following.

Contractor shall also furnish Efficiency Guarantee Bonds in accordance with Article entitled MANUFACTURER'S EXPERIENCE in the Instructions to Bidders and executed on forms approved by the Owner.

SC-5.02.A.

Insert the following new paragraph immediately following Paragraph 5.02.A of the General Conditions which is to read as follows:

B. If at any time the Owner for justifiable cause, shall be or become dissatisfied with the Surety or Sureties for the Performance and/or Payment Bonds, the Contractor shall within five (5) calendar days after notice from the Owner to do so, substitute an acceptable Bond (or Bonds) in such form and sum and signed by such other Surety or Sureties as may be satisfactory to the Owner. The Contractor shall pay for the premiums on such Bond(s). No further payment shall be deemed due nor shall be made by Owner until the new Surety or Sureties shall have furnished such an acceptable Bond to the Owner.

SC-5.03E

Add the following new paragraphs immediately after paragraph 5.03E of the General Conditions which are to read as follows:

F. Contractor shall provide evidence of its insurance coverage on the ACORD certificate of insurance form and shall include the following statement in its entirety in the section of the form entitled "Description of Operations/Locations/Vehicles/Special Items".

"The City of New Bedford, Massachusetts and their officers, directors, partners, employees and other consultants and subcontractors are named as additional insureds with respect to the insured's Commercial General Liability and Automobile Liability Insurance Policies. All insurers waive all rights of subrogation against the City of New Bedford, Massachusetts and their officers, directors, partners, employees and other consultants and subcontractors. All insurance is primary for all claims covered thereby. Commercial General Liability Insurance includes contractual liability coverage.

The insurance coverage by this Certificate will not be cancelled or materially changed, except after thirty calendar days written notice has been received by the Owner."

SC-5.04A.

Add the following new paragraphs immediately after paragraph 5.04A of the General Conditions which are to read as follows:

All the insurance requirements for the Contractor shall be the same for all Subcontractors. The limits of liability for the insurance required by this Paragraph of the General Conditions shall provide coverage for not less than the following amounts or greater where required by law:

### For 5.04.A.1 and 5.04.A.2 Workers' Compensation

(1)	Worker's Compensation	\$100,000 minimum, in accordance with M.G.L. c.149, Sect. 34A.
(2)	Employer's Liability	\$500,000 Each Occurrence \$500,000 Disease per employee \$500,000 Annual Aggregate
(3)	Liability Insurance with General Liability Coverage	\$1,000,000
(4)	General Aggregate Liability Coverage	\$2,000,000
(5)	Certificate of Errors and Omissions Insurance	\$1,000,000 Each Claim

For 5.04A.3., 5.04A.4., and 5.04A.5. Commercial General Liability including Premise/Operations; Explosion, Collapse and Underground Property Damage; Products/Completed Operations, Broad Form Contractual, Independent Contractors; Broad Form Property Damage; and Personal Injury liabilities:

(1)	Bodily Injury:	\$1,000,000	Each Occurrence
		\$2,000,000	Annual Aggregate
(2)	Property Damage:	\$1,000,000	Each Occurrence
		\$2,000,000	Annual Aggregate
(3)	Personal Injury:	\$2,000,000	Annual Aggregate
(4)	Pollution Liability Insurance	\$5,000,000	Each Occurrence
		\$5,000,000	Annual Aggregate

And for 5.04A.6. Comprehensive Automobile Liability including all owned (private and others), hired and non-owned vehicles:

(1)	Bodily Injury		Each Person Each Accident
(2)	Property Damage	\$1,000,000	Each Occurrence

SC 5.04B.1.

Delete paragraph 5.04B.1. of the General Conditions in its entirety and replace with the following:

1. The insurance required by paragraph 5.04A.3 through 5.04A.6 inclusive will provide primary coverage for all claims covered thereby. With respect to insurance required by Paragraph 5.04.A.6 include as additional insured Owner, and any other individuals or entities identified in the Supplementary Conditions, all of whom shall be listed as additional insureds and include coverage for the respective officers, directors, partners, employees, agents, consultants and subcontractors of each and any of all such additional insureds. The Owner may add additional insured from time to time as additional firms are involved in the development of and completion of contract work.

5.04B.1.a. Include the following additional firms including their officers, directors, partners, employees and other consultants and subcontractors as an additional insured on the insurance required by Paragraph 5.04A.6:

Tighe & Bond, Inc

SC-5.04B.6.

Add the following new paragraphs immediately after paragraph 5.04.B.6.b. of the General Conditions which is to read as follows:

- 7. Contractor may purchase and maintain excess liability insurance in the umbrella form in order to satisfy the minimum amounts required for the insurance to be purchased and maintained in accordance with paragraph 5.04. Evidence of such excess liability insurance shall be delivered to Owner in accordance with paragraph 2.01B. in the form of a certificate indicating the policy numbers and minimum coverage amounts of all underlying insurance. The umbrella liability insurance shall have a combined single limit of not less than \$5,000,000.
- 8. Contractor is required to provide Contractor's Professional Liability Insurance under this Contract:
  - a. Each Claim \$1,000,000
  - b. Annual Aggregate \$2,000,000
- 9. All policies required by this paragraph 5.04 shall contain provisions to the effect that the insurer(s) waive all right of subrogation against the Owner, Engineer and their officers, directors, partners, employees and other consultants and subcontractors of each and any of them.

SC-5.05A.

Delete paragraph 5.05A. of the General Conditions in its entirety and replace with the following:

A. Contractor shall purchase and maintain a separate Owner's Protective Liability policy, issued to Owner at the expense of Contractor, including Owner and Engineer as named insured. This insurance shall provide coverage for not less than the following amounts:

5.05A.1.	Bodily Injury	\$1,000,000	Each Occurrence
5.05A.2.	Property Damage	\$1,000,000 \$1,000,000	Each Occurrence Annual Aggregate

SC-5.05A

Add the following new paragraph immediately after paragraph 5.05.A.2 of the General Conditions which is to read as follows:

B. All policies required by this paragraph 5.05 shall contain provisions to the effect that the insurer(s) waive all rights of subrogation against the Owner, Engineer and their officers, directors, partners, employees and other consultants and subcontractors of each and any of them.

SC-5.06A.

Delete paragraphs 5.06A. and A1 thru A7 of the General Conditions in their entirety.

SC-5.06B.

Delete paragraph 5.06B. of the General Conditions in its entirety.

SC-5.06C.

Delete Paragraph 5.06C. of the General Conditions in its entirety.

SC-5.06D.

Delete paragraph 5.06D. of the General Conditions in its entirety.

SC-5.06E.

Delete paragraph 5.06E. of the General Conditions in its entirety.

SC-5.07A.

Delete paragraph 5.07A. of the General Conditions in its entirety and replace with the following.

A. All insurance policies provided by the Contractor shall contain provisions to the effect that the insurer waives all rights of subrogation against any of the insured, loss payee, (and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them) Owner and the Engineer.

SC-5.07B.

Delete paragraph 5.07B. of the General Conditions in its entirety.

SC-5.07C.

Delete paragraph 5.07C. of the General Conditions in its entirety.

SC-5.08A.

Delete paragraph 5.08A. of the General Conditions in its entirety.

SC-5.08B.

Delete paragraph 5.08B. of the General Conditions in its entirety.

SC-5.09A.

Delete paragraph 5.09A. of the General Conditions in its entirety and replace with the following:

A. If Owner has any objection to the coverage afforded by or other provisions of the insurance required to be purchased and maintained by Contractor in accordance with this Article 5 on the basis of its not complying with the Contract Documents, Owner will notify Contractor in writing thereof within ten days of the date of delivery of such certificates to Owner in accordance with paragraph 2.01. Contractor will

provide such additional information in respect of insurance provided by Contractor as Owner may reasonably request.

SC-5.10A

Delete "pursuant to Paragraph 5.06" from the first sentence of Paragraph 5.10A.

#### ARTICLE 6 - CONTRACTOR'S RESPONSIBILITIES

SC-6.02

Add the following new paragraphs immediately after paragraph 6.02B. of the General Conditions which are to read as follows:

C. Regular work hours are defined as 8 hours per day. Monday through Friday, excluding state and federal holidays.

Requests to work other than regular working hours as defined above shall be submitted to the Engineer for review and potential approval by Owner not less than 72 hours prior to any proposed weekend work or scheduled extended work weeks. Occasional unscheduled overtime on weekdays may be permitted provided two hours notice is given to the Engineer.

Contractor will be allowed to transport material during non-regular working hours in accordance with all local, state and federal requirements. Contractor shall notify the Engineer 72 hours in advance of such request to transport material during non-regular working hours.

Contractor shall not exceed 8 hours per day of work. Compensate Owner for additional overtime costs above and beyond 8-hours as specified in SC 6.02.D below.

- D. Contractor shall reimburse the Owner for additional overtime and/or inspection costs incurred as a result of overtime work in excess of the regular working hours stipulated in Article SC 6.02.C. At Owner's option, overtime costs may either be deducted from the Contractor's monthly payment requests or deducted from the Contractor's retention prior to release of the final payment. Overtime costs for the Owner's personnel shall be based on the individual's current overtime wage rate. Should the Owner employ a private firm to oversee the work, overtime costs for Owner's independent testing laboratory or engineer shall be calculated based on the terms of their respective contracts with the Owner. Over time costs for personnel employed by the Owner's Engineer if an outside firm is used shall be \$120.00 per hour per site worked by the Contractor.
- E. This Agreement is subject to the applicable provisions of the Contract Work Hours and Safety Standards Act, Public Law 87-581, as amended. No Contractor or Subcontractor contracting for any part of the Work shall require or permit any laborer or mechanic to be employed on the Work in excess of forty hours in any work week unless such laborer or mechanic receives compensation at a rate not less than one and one-half times that person's basic rate of pay for all hours worked in excess of forty hours in such work week.
- F. Contractor shall employ only competent persons to do the work and whenever Owner shall notify Contractor, in writing, that any person on the Work appears to be incompetent, disorderly, or otherwise unsatisfactory, such person shall be removed from the Project and shall not again be employed on it except with the consent of Owner.

- G. Contractor and Subcontractors shall, insofar as practicable, give preference in the hiring of workers for the Project to qualified local residents with first preference being given to citizens of the United States who have served in the armed forces of the United States and have been honorably discharged therefrom or released from active duty therein.
- H. Contractor and all Subcontractors shall pay to all laborers and mechanics employed for the construction covered by this Contract the minimum rates of pay as determined by the Secretary of Labor in accordance with the Act of March 3, 1931, as amended, known as the Davis-Bacon Act (40 U.S.C. 276a through 276a-7). Furthermore, Contractor and Subcontractors shall adhere to the stipulations and provisions published by the Secretary of Health, Education, and Welfare in "Labor Standards (Federal Water Pollution Control Act)." The Wage Rate Schedule as prepared by the Secretary of Labor and the "Labor Standards" are part of this Contract and are included in PART II of these Supplementary Conditions.
- I. Except as may be otherwise required by law, all claims and disputes pertaining to the classification of labor employed on the project under this Contract shall be decided by the governing body having jurisdiction.
- J. Contractor and all Subcontractors shall comply with the Regulations of the Secretary of Labor made pursuant to the Anti-Kickback Act of June 30, 1940 (40 U.S.C. 276c) and all amendments or modifications thereto. Contractor and all Subcontractors shall furnish Owner with weekly Statements of Compliance. In case of Subcontracts, Contractor shall cause appropriate provision to be inserted in all subcontracts for the Work which Contractor may let to ensure compliance with said Anti-Kickback Act by all Subcontractors subject thereto, and Contractor shall be responsible for the submission of all Statements of Compliance required of Subcontractors by said Anti-Kickback Act except as the Secretary of Labor may specifically provide for reasonable limitations, variations, and exemptions from the requirements thereof. These Regulations are part of this Contract and are included in PART II of these Supplementary Conditions.
- K. Contractor and all subcontractors shall comply with the Massachusetts Prevailing Wage law as contained in M.G.L. chapter 149 sections 26-27 which are included in Part II of these Supplementary Conditions. Refer to Article 17 with these conditions when State and Federal wage rates differ.

#### SC-6.03.C

Add the following new paragraphs immediately after paragraph 6.03C. of the General Conditions which are to read as follows:

- D. No materials or supplies for the work shall be purchased by the Contractor or any subcontractor subject to a chattel mortgage or under a conditional sales contract or other agreement by which an interest is retained by the seller. The Contractor warrants that it has good title to all materials and supplies used by Contractor and Subcontractor in the work, which is free from all liens, claims or encumbrances.
- E. The Contractor shall and will, in good workmanlike manner, do and perform all work and furnish all supplies and materials, machinery, equipment, facilities and means, except as herein otherwise expressly specified, necessary or proper to perform and complete all the work required by this Contract, within the time herein specified, in accordance with the provisions of this Contract and said specifications and in accordance with the plans and drawings covered by this Contract and any and all supplemental plans and drawings, and in accordance with the direction of the Owner as given from time to time during the progress of the work. It shall furnish, erect, maintain and remove such construction plant and such temporary works as may be required. The Contractor shall observe, comply with, and be subject to all

terms, conditions, requirements and limitations of the Contract and Specifications, and shall do, carry on and complete the entire work to the satisfaction of the Owner.

SC-6.06A.

Delete Paragraphs 6.06A. and 6.06B. of the General Conditions in their entirety and replace with the following:

A. Contractor shall not employ any Subcontractor, Supplier or other person or organization, (including those who are to furnish the principal items of materials or equipment), whether initially or as a substitute, against whom Owner may have reasonable objection. Acceptance of any Subcontractor, other person or organization by Owner shall not constitute a waiver of any right of Owner to reject defective Work. Contractor shall not be required to employ any Subcontractor, other person or organization against whom Contractor has reasonable objection.

B. Not Used.

SC-6.06C.

Add the following new sentence at the end of paragraph 6.06C. of the General Conditions to read as follows:

Contractor shall make payments to Subcontractors in accordance with Massachusetts General Law Chapter 30, Section 39F which is included in PART II of these Supplementary Conditions.

SC-6.06E.

Add the following new sentence at the end of paragraph 6.06E of the General Conditions to read as follows:

Owner or Engineer may furnish to any such Subcontractor, Supplier or other person or organization, to the extent practicable, information about amounts paid on their behalf to Contractor in accordance with Contractor's Applications for Payment.

SC-6.07B

Delete paragraph 6.07B of the General Conditions in its entirety.

SC-6.10A

Add the following new sentences at the end of paragraph 6.10A of the General Conditions to read as follows:

The materials and supplies to be used in the Work of this Contract are exempt from the Sales and Use Tax of the Commonwealth of Massachusetts. Contractor shall obtain the proper certificates, maintain the necessary records and otherwise comply with the requirements of Chapter 14 of the Acts of 1966 and any amendments thereto.

SC-6.16A.

Delete the last sentence in paragraph 6.16A. of the General Conditions in its entirety and replace with the following:

If Engineer and/or Owner determines that the incident giving rise to the emergency action was not the responsibility of the Contractor and that a change in the Contract Documents is required because of the action taken by the Contractor in response to such an emergency, a Work Change Directive or Change Order will be issued.

SC-6.17D.1.

Add the following new sentence at the end of paragraph 6.17.D.1 of the General Conditions to read as follows:

Approval of Shop Drawings for equipment requiring Efficiency Guarantee Bonds will be withheld until the receipt of such Bonds.

SC-6.19A.

Add the following new paragraphs immediately after paragraph 6.19A. of the General Conditions which are to read as follow:

- B. The Contractor guarantees that the Work and Services to be performed under the Contract, and all workmanship, materials and equipment performed, furnished, used or installed in the construction of the same shall be free from defects and flaws, and shall be performed and furnished in strict accordance with the Drawings, Specifications, and other Contract Documents, that the strength of all parts of all manufactured equipment shall be adequate and as specified and that the performance test requirements of the Contract shall be fulfilled. This guarantee shall be for a period of one year or such longer period that may be specified in the Contract Documents from and after the date of completion and acceptance of the Work as stated in the final estimate. If part of the Work is accepted in accordance with that subsection of this AGREEMENT titled "Partial Acceptance," the guarantee for that part of the Work shall be for a period of one year or such longer period that may be specified from the date fixed for such acceptance.
- 1. If at any time within the said period of guarantee any part of the Work requires repairing, correction or replacement, the Owner may notify the Contractor in writing to make the required repairs, correction or replacements. If the Contractor neglects to commence making such repairs, corrections or replacements to the satisfaction of the Owner within seven (7) days from the date of receipt of such notice, or having commenced fails to prosecute such Work with diligence, the Owner may employ other persons to make said repairs, correction or replacements, and charge the costs, including compensation for additional professional services, to the Contractor or withhold the amount from any payment owed to the Contractor.
- 2. The Contractor's guarantee under this clause, 6.19B, is in addition to the Contractor's express or implied warranties under this Agreement and State law and in no way diminish any other rights that the Owner may have against the Contractor.

SC- 6.19C. and D.

Renumber 6.19B. and 6.19C. of the General Conditions to read 6.19C. and 6.19D.

SC-6.19D.

Add the following new paragraph immediately after paragraph 6.19D. of the General Conditions which is to read as follows:

#### E. Manufacturer's Guaranty/Warranty

- 1. The Contractor shall obtain the following guaranty/warranty from the manufacturer of all major pieces of equipment furnished and installed on this Project. Such guaranty/warranty shall be for the benefit of Owner and be furnished in writing by the manufacturer. The Contractor's and manufacturer's obligations under this provision are in addition to other express or implied warranties under the Contract Documents and under the law and in no way diminish any other right that the Owner may have against the Contractor or manufacturer for faulty material, equipment or work. The warranty period shall not be interpreted as a limitation on the time in which the Owner can enforce such other duties, obligations, rights, or remedies.
- 2. The manufacturer warrants and guarantees for a period of three years from the date of Substantial Completion, or such longer period that may be specified in the Contract Documents, that all materials and equipment furnished and installed shall be free from flaws, defects in material and workmanship and shall be in conformance with the Contract Documents.

SC-6.20A.

Delete paragraph 6.20A of the General Conditions in its entirety and replace with the following:

- A. To the fullest extent permitted by law, the Contractor shall indemnify, hold harmless, and assume the defense of the Owner, its officers, agents or employees, with counsel acceptable to Owner, which acceptance shall not be unreasonably withheld, from all liabilities, suits, claims, losses, and costs or any other damages against them or any of them arising from any act or omission of the Contractor, its agents, officers, employees, or subcontractors in any way connected with performance under this Contract:
- 1. is attributable to bodily injury, sickness, disease or death or to injury to or destruction of tangible property (other than the Work itself), including the loss of use resulting therefrom; and
- 2. is caused in whole or in part by any negligent or willful acts, errors or omission of Contractor, any Subcontractor, any Supplier, or any individual or entity directly or indirectly employed by any of them to perform any of the Work or anyone for whose acts any of them may be liable, regardless of whether or not caused in part by any negligence or omission of an individual or entity indemnified hereunder or whether liability is imposed upon such indemnified party by Laws and Regulations regardless of the negligence of any such indemnified party unless caused by the sole negligence of a party indemnified hereunder. If through the negligent or willful acts, errors or omissions on the part of Contractor, any other contractor or any Subcontractor shall suffer loss or damage on the Work, Contractor shall settle with such other contractor or Subcontractor by agreement or arbitration if such other contractor or Subcontractor will so settle. If such other contractor or Subcontractor shall assert any claim against Owner and/or Engineer, or the officers, directors, members, partners, employees, agents, consultants and subcontractors of each on account of any damage alleged to have been sustained, Owner shall notify Contractor, who shall defend, indemnify and save harmless Owner, Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each against any such claims.

SC-6.21A.

Immediately after the last sentence, insert the following:

All professional engineering services required by the Contractor or his/her sub-contractors as part of this Contract shall be performed by a Registered Professional Engineer in the Commonwealth of Massachusetts. All professional surveying services required by the Contractor or his/her sub-contractors

as part of this Contract shall be performed by a Registered Professional Land Surveyor in the Commonwealth of Massachusetts.

SC-6.21E

Delete paragraph 6.21E of the General Conditions in its entirety and replace with the following:

E. Contractor shall not be responsible for the adequacy of the performance criteria or design criteria contained in the Contract Documents.

SC-6.21E.

Add the following new paragraph immediately after paragraph 6.21E. of the General Conditions which is to read as follows:

SC-6.22 Definitions; Contract Provisions; Management and Financial Statements; Enforcement

A. Contractor shall comply with all applicable provisions of Chapter 30, Section 39R of the Massachusetts General Laws regarding Contractor's records which is included in Part II of the Supplementary Conditions.

ARTICLE 7. OTHER WORK AT THE SITE

SC-7.03C.

Add the following new paragraphs immediately after paragraph 7.03C. of the General Conditions which are to read as follows:

7.04 Damage to Other Contractor's Property

A. Should Contractor cause damage to the work or property of any separate contractor at the site, or should any claim arising out of Contractor's performance of the Work at the site be made by any separate contractor against Contractor, Owner, Engineer, Engineer's Consultants, the Construction Coordinator or any other person, Contractor shall promptly attempt to settle with such other contractor by agreement, or to otherwise resolve the dispute by arbitration or at law. Contractor shall, to the fullest extent permitted by Laws and Regulations, defend, indemnify and hold Owner, Engineer, Engineer's Consultants and the Construction Coordinator harmless from and against all claims, damages, losses and expenses (including, but not limited to, fees of engineers, architects, attorneys and other professionals, and court and arbitration or mediation costs) arising directly, indirectly or consequentially out of any action, legal or equitable, brought by any separate contractor against Owner, Engineer, Engineer's Consultants or the Construction Coordinator to the extent based on a claim arising out of Contractor's performance of the Work.

B. Should a separate contractor cause damage to the Work or property of Contractor or should the performance of work by any separate contractor at the site give rise to any other claim, Contractor shall not institute any action, legal or equitable, against Owner, Engineer, Engineer's Consultants or the Construction Coordinator or permit any action against any of them to be maintained and continued in its name or for its benefit in any court or before any arbiter which seeks to impose liability on or to recover damages from Owner, Engineer, Engineer's Consultants or the Construction Coordinator on account of any such damage or claim.

C. If Contractor is delayed at any time in performing or furnishing Work by any act or neglect of a separate contractor and Owner and Contractor are unable to agree as to the extent of any adjustment in Contract Times attributable thereto, Contractor may make a claim for an extension of times in accordance with Article 12 of the General Conditions. An extension of the Contract Times shall be Contractor's exclusive remedy with respect to Owner, Engineer, Engineer's Consultants and Construction Coordinator for any delay, disruption, interference or hindrance caused by any separate contractor. This paragraph does not prevent recovery from Owner, Engineer, Engineer's Consultant or Construction Coordinator for activities that are their respective responsibilities.

#### 7.05 Subcontracting

- A. The Contractor may utilize the services of subcontractors on those parts of the Work, which, under normal contracting practices, are performed by specialty subcontractors so long as such services are not subject to MGL law and/or policy.
- B. The Contractor shall not award any work to any subcontractor without prior written approval of the Owner, which approval will not be given until the Contractor submits to the Owner a written statement concerning the proposed award to the Subcontractor, which statement will contain such information as the Owner may require.

7.06 Mutual Responsibility of Contractors

A. Refer to Paragraph SC 6.20.A.2.

ARTICLE 8. OWNER'S RESPONSIBILITIES

SC-8.06

Delete paragraph 8.06 of the General Conditions in its entirety.

ARTICLE 9 - ENGINEER'S STATUS DURING CONSTRUCTION

SC-9.03A.

Add the following new paragraphs immediately after paragraph 9.03A of the General Conditions which are to read as follows:

- B. Owner and/or Engineer will furnish a Resident Project Representative and assistants to assist Owner and/or Engineer in observing the performance of the Work. The Owner may act at the Resident Project Representative or he/she may designate an authorized representative to work on his/her behalf. The Owner/Engineer may conduct full time or periodic visits to observe the Work depending on the nature of the activities occurring.
- C. The Authorized Representative and agents of the Owner shall be permitted to inspect all work, materials, payrolls, records of personnel, invoices of materials, and other relevant data and records.

SC-9.08.A

Add the following paragraphs immediately after Paragraph 9.08.A of the General Conditions which are to read as follows:

- 1. In resolving conflicts, error or discrepancies, the Contract Documents shall be given precedence, as may be reasonably inferred as being consistent with their overall intent and required to produce the intended result. Subject to such determination by the Engineer, the Contract Documents shall be given precedence in the following order: Change Orders, Owner-Contractor Agreement, Notice to Proceed, Addenda, General Conditions as modified by Supplementary Conditions, Division 1, Technical Specifications (MassDOT MSSHB latest edition including all addenda, City's Standards latest edition, Division 2 through 16 of the Specifications in the event of a conflict, the more stringent shall apply), Contract Drawings, Advertisement for Bids, Instruction to Bidders, the Form for General Bid signed by the Contractor, Bonds, Insurance Certificates.
- 2. If the issue of priority involves the Technical Specifications (MassDOT MSSHB latest edition including all addenda, City's Standards latest edition, Division 2 through 16 of the Specifications in the event of a conflict, the more stringent shall apply) and the Drawings, in all cases, figured dimensions shall govern over scaled dimensions, but work not dimensioned shall be as directed by the Engineer, and work not particularly shown, identified, sized, or located shall be the same as similar parts that are shown or specified. Detail Drawings shall govern over general Drawings, larger scale Drawings take precedence over smaller scale Drawings, Change Order Drawings govern over Contract Drawings, and Contract Drawings govern over Shop Drawings.

ARTICLE 10 – CLAIMS

SC-10.05.B

Deleted "30 days" in the fourth line and Insert "10 days". In the tenth line, replace "60 days" with "20 days".

SC-10.05.E

In the sixth line replace "30 days" with "10 days".

ARTICLE 11 - COST OF THE WORK; ALLOWANCES; UNIT PRICE WORK

SC-11.01A.1.

Delete the second sentence in paragraph 11.01A.1. of the General Conditions in its entirety and replace with the following:

Such employees shall only include foremen at the site.

SC-11.01A.1.

Add the following new paragraph immediately after paragraph 11.01A.1. of the General Conditions which is to read as follows:

a. Following award and prior to execution of a construction contract Contractor shall establish, in the Agreement, the Direct Labor Cost percentage. This percentage, where approved by Owner, will be used in the determination of the Direct Labor Cost listed in the Change Order Form included in Part II of the Supplementary Conditions. The Direct Labor Costs are defined to include social security contributions, unemployment, excise and payroll taxes, workers' and workmen's compensation, health and retirement benefits, sick leave, vacation and holiday pay, and cost of premiums for all additional insurance required because of changes in the Work.

#### SC-11.01B.1

Eighth line, insert "superintendent(s)" after the word clerks.

SC-11.02D.

Add the following new paragraph immediately after paragraph 11.02.D of the General Conditions which is to read as follows:

E. For unused work as part of the allowances included with Contract, the Contractor is eligible for payment on what is actually used. Contractor is not eligible for payment on presumed profit on un-used allowance funds or quantities.

SC-11.03D.

Delete paragraph 11.03D. of the General Conditions in its entirety and replace with the following two new paragraphs:

- D. The unit price of an item of Unit Price Work shall be subject to re-evaluation and adjustment under the following conditions:
  - 1. if the total cost of a particular item of Unit Price Work amounts to 5 percent or more of the Contract Price and the variation in the quantity of that particular item of Unit Price Work performed by Contractor differs by more than 15 percent from the estimated quantity of such item indicated in the Agreement; and
  - 2. if there is no corresponding adjustment with respect to any other item of Work; and
  - 3. if Contractor believes that Contractor has incurred additional expense as a result thereof; or if Owner believes that the quantity variation entitles Owner to an adjustment in the unit price, either Owner or Contractor may make a claim for an adjustment in the Unit Price for that quantity by which is less than 85% of or the actual quantity exceeds 115% of the estimated quantity in accordance with Article 10.05 if the parties are unable to agree as to the effect of any such variations in the quantity of Unit Price Work performed.
  - 4. Contractor shall not be entitled to any profit associated with unused quantities.
- E. Wherever the estimated quantity of work to be done and materials to be furnished on a unit price basis under this Contract are shown in any of the Contract Documents including the proposal, they are given for use in comparing bids, and the right is expressly reserved by Owner, except as herein otherwise specifically limited, to increase or diminish them as may be deemed reasonably necessary or desirable by the Owner to complete the Work contemplated by this Contract, and such increase or diminution shall in no way vitiate the Contract, nor shall any such increase or diminution give cause for claims or liability for damages.

ARTICLE 12 - CHANGE OF CONTRACT PRICE; CHANGE OF CONTRACT TIME

SC-12.01C.2.b.

In the second line of paragraph 12.01C.2.b, before the semicolon add the following words "based on subcontractor's Cost of the Work before subcontractor's fee is added";

### ARTICLE 13 - TESTS AND INSPECTIONS; CORRECTION, REMOVAL OR ACCEPTANCE OF DEFECTIVE WORK

SC-13.05A.

Add the following new paragraph immediately after paragraph 13.05A. of the General Conditions to read as follows:

B. If Owner stops Work under Paragraph 13.05A. Contractor shall not be entitled to any extension of Contract Time or increase in Contract Price.

#### ARTICLE 14 - PAYMENTS TO CONTRACTOR AND COMPLETION

SC-14.02A.1.

In the first sentence of paragraph 14.02.A.1 of the General Conditions delete the number "20" and replace with the number "ten".

SC-14.02A.3.

Add the following new paragraph immediately after paragraph 14.02A.3 of the General Conditions which is to read as follows:

4. Contractor shall furnish evidence that payment received on the basis of materials and equipment not incorporated and suitably stored, has in fact been paid to the respective supplier(s) within sixty days of payment by Owner. Failure to provide such evidence of payment may result in the withdrawal of previous approval(s) and removal of the cost of related materials and equipment from the next submitted Application for Payment.

SC-14.02B.1

Delete paragraph 14.02B.1. of the General Condition in its entirety and replace with the following:

1. Progress Payments will be made in accordance with Massachusetts General Law Chapter 30, Section 39G, which is included in PART II of these Supplementary Conditions.

SC-14.02.B.5

Add the following new paragraphs immediately after paragraph 14.02.B.5.d of the General Conditions to read as follows:

- e. Third party claims were filed or reasonable evidence indicate probable filing of such claims;
- f. Of failure of the Contractor to make payments property to Subcontractors or for labor, materials or equipment.
- g. Reasonable evidence exists that the Work cannot be completed for the unpaid balance of the Contract sum; or
- h. Of damage to the Owner or another Contractor.

SC-14.03A.

Add the following new paragraphs immediately after paragraph 14.03A of the General Conditions which are to read as follows:

- B. No materials or supplies for the Work shall be purchased by Contractor or any Subcontractor subject to a chattel mortgage or under a conditional sale contract or other agreement by which an interest is retained by the seller. The Contractor warrants that it has good title to all materials and supplies used by Contractor and Subcontractor(s) in the Work, free from all liens, claims or encumbrances.
- C. Contractor shall defend, indemnify and save Owner and Engineer harmless from all claims growing out of the lawful demands of Subcontractors, laborers, workmen, mechanics, materialmen, and furnishers of machinery and parts thereof, equipment, power tools, and all supplies, including commissary, incurred in the furtherance of the performance of this Contract. Contractor shall at Owner's request, furnish satisfactory evidence that all obligations of the nature hereinabove designated have been paid, discharged, or waived. If Contractor fails to do so, then Owner may, after having served written notice on the said Contractor either pay unpaid bills, of which Owner has written notice, direct, or withhold from the Contractor's unpaid compensation a sum of money deemed reasonably sufficient to pay any and all such lawful claims until satisfactory evidence is furnished that all liabilities have been fully discharged whereupon payment to Contractor shall be resumed, in accordance with the terms of this Contract, but in no event shall the provisions of this sentence be construed to impose any obligations upon Owner to either Contractor or Contractor's Surety. In paying any unpaid bills of the Contractor, Owner shall be deemed the agent of Contractor and any payment so made by Owner shall be considered as payment made under the Contract by Owner to Contractor and Owner shall not be liable to Contractor for any such payment made in good faith.

SC-14.07.A.2

Add the following new paragraphs immediately after paragraph 14.07.A.2.d of the General Conditions to read as follows:

e. An affidavit that all payrolls, bill for materials and equipment, and other indebtedness connected with the Work for which the Owner or its property might in any way be responsible, have been paid or otherwise satisfied.

SC-14.07B.1.

Delete paragraph 14.07B.1. of the General Conditions in its entirety and replace with the following:

1. If, on the basis of Engineer's observation of the Work during construction and final inspection, and Engineer's review of the final Application for Payment and accompanying documentation - all as required by the Contract Documents, Engineer is satisfied that the Work has been completed and Contractor's other obligations under the Contract Documents have been fulfilled, Engineer will indicate in writing Engineer's recommendation of payment and present the Application to Owner for payment. Thereupon Engineer will give written notice to Owner and Contractor that the Work is acceptable subject to the provisions of paragraph 14.09. Otherwise, Engineer will return the Application to Contractor, indicating in writing the reasons for refusing to recommend final payment, in which case Contractor shall make the necessary corrections and resubmit the Application. If the Application and accompanying documentation are appropriate as to form and substance, Owner shall in accordance with the applicable Massachusetts General Law, pay Contractor the amount recommended by Engineer.

SC-14.09A.2.

Add the following new paragraph immediately after paragraph 14.09.A.2 of the General Conditions which is to read as follows:

3. No payment, final or otherwise, shall operate to release the Contractor or its subcontractors from any obligation under this Contract or the Performance and Payment Bond.

ARTICLE 15 - SUSPENSION OF WORK AND TERMINATION

SC-15.01A.

Delete paragraph 15.01A. of the General Conditions in its entirety and replace with the following:

A. Owner may order, at any time and without cause, suspension of the Work in accordance with Massachusetts General Law Chapter 30, Section 39O, which is included in Part II of the Supplementary Conditions.

SC-15.02A.4.

Add the following new paragraph immediately after paragraph 15.02.A.4 of the General Conditions which is to read as follows:

5. If Contractor abandons the Work, or sublets this Contract or any part thereof, without the previous written consent of Owner, or if the Contract or any claim thereunder shall be assigned by Contractor otherwise than as herein specified;

**ARTICLE 16 - DISPUTE RESOLUTION** 

SC-16.01A

Delete the paragraph 16.01A of the General Conditions in its entirety and replace with the following:

Either Owner or Contractor may request mediation of any Claim submitted to Engineer for a decision under Paragraph 10.05 within 60 days of when such decision becomes final and binding. The mediation will be governed by the Construction Industry Mediation Rules of the American Arbitration Association in effect as of the Effective Date of this Agreement. The request for mediation shall be submitted in writing to the American Arbitration Association and the other party to the Contract.

SC-16.01C.3.

Add a new paragraph immediately after paragraph 16.01C.3. of the General Conditions which is to read as follows:

D. Contractor shall carry on the Work and maintain the progress schedule during the dispute resolution proceedings, unless otherwise agreed by Contractor and Owner in writing.

**ARTICLE 17 - MISCELLANEOUS** 

SC-17.05.A

Delete paragraph 17.05.A of the General Conditions in its entirety and insert the following in its place:

A. This Agreement shall be governed and constructed in accordance with the laws of the Commonwealth of Massachusetts, unless otherwise specified.

SC-17.06

Add the following new paragraphs immediately after paragraph 17.06 of the General Conditions which are to read as follows:

#### 17.07 Addresses

A. Both the address given in the Bid Form upon which this Agreement is founded, and Contractor's office at or near the site of the Work are hereby designated as places to either of which notices, letters, and other communications to Contractor shall be certified, mailed, or delivered. The delivering at the above named place, or depositing in a postpaid wrapper directed to the first-named place, in any post office box regularly maintained by the post office department, of any notice, letter or other communication to Contractor shall be deemed sufficient service thereof upon Contractor; and the date of said service shall be the date of such delivery or mailing. The first-named address may be changed at any time by an instrument in writing, executed and acknowledged by Contractor, and delivered to Owner and Engineer. Nothing herein contained shall be deemed to preclude or render inoperative the service of any notice, letter, or other communication upon Contractor personally.

#### 17.08 Wage Rates

A. The requirements and provisions of all applicable laws and any amendments thereof or additions thereto as to the employment of labor, and to the schedule of minimum wage rates established in compliance with laws shall be a part of these Contract Documents. Copies of the wage schedules are included in PART II of these Supplementary Conditions. If, after the Notice of Award, it becomes necessary to employ any person in a trade or occupation not classified in the wage determinations, such person shall be paid at not less than such rates as shall be determined by the officials administrating the laws mentioned above. Such approved minimum rate shall be retroactive to the time of the initial employment of such person in such trade or occupation. Contractor shall notify Owner of Contractor's intention to employ persons in trades or occupations not classified in sufficient time for Owner to obtain approved rates for such trades or occupations.

- B. The schedules of wages referred to above are minimum rates only, and Owner will not consider any claims for additional compensation made by Contractor because of payment by Contractor of any wage rate in excess of the applicable rate contained in these Contract Documents. All disputes between Contractor and employees of Contractor in regard to the payment of wages in excess of these specified in the schedules shall be resolved by Contractor.
- C. The said schedules of wages shall continue to be the minimum rates to be paid during the life of this Agreement and a legible copy of said schedules shall be kept posted in a conspicuous place at the site of the work.

17.09 Payment by Contractor

The Contractor shall pay:

a. For all transportation and utility services not later than the 20<sup>th</sup> day of the calendar month following that in which services are rendered.

- b. For all materials, tools, and other expandable equipment to the extent of 90-percent of the cost thereof, not later than the 20<sup>th</sup> day of the calendar month following that in which such materials, tools and equipment are delivered at the site of the Project, and the balance of the cost thereof not later than the 30<sup>th</sup> day following the completion of that part of the work in or on which such materials, tools, and equipment are incorporated or used, and
- c. To each of its subcontractors, not later than the 5<sup>th</sup> day following each payment to the Contractor, the respective amounts allowed the Contractor on account of the Work performed by its Subcontractors to the extent each Subcontractor's interest therein.

#### 17.10 Assignments

Neither Owner nor Contractor shall, without the prior written consent of the other, assign or sublet in whole or in part any interest under any of the Contract Documents and, specifically but without limitation, Contractor shall not assign any monies due or to become due without the prior written consent of Owner. In case Contractor assigns all or any part of any monies due or to become due under this Contract, the instrument of assignment shall contain a clause substantially to the effect that it is agreed that the right of the assignee in and to any monies due or to become due to Contractor shall be subject to prior claims of all persons, firms, and corporations for services rendered or material supplies for the performance of the Work call for in this Contract.

#### PART II - LOCAL GOVERNMENT PROVISIONS

Local Government Provisions included herein, have been selected from those to which specific references have been made elsewhere in the Contract Documents. Each and every other provision of law or clause required by law to be inserted in this Contract shall be deemed to be also inserted herein in accordance with paragraph 3.01D of the Supplementary Conditions.

- 1.0 CITY OF NEW BEDFORD PROVISIONS
- 1.1 Instructions to Bidders for Affirmative Action Issues for Public Works and Construction Projects.
- 1.2 Notice Regarding Responsible Employer Ordinance (REO).

#### SECTION 00800 SUPPLEMENTARY CONDITIONS PART II – STATE AND LOCAL GOVERNMENT PROVISIONS 3.0 CITY OF NEW BEDFORD, MASSACHUSETTS PROVISIONS

#### City of New Bedford

# INSTRUCTIONS TO BIDDERS For AFFIRMATIVE ACTION ISSUES

for Public Works and Construction Projects

Office of Equal Opportunity & Contract Compliance 133 William Street, Room 208 New Bedford, Massachusetts 02740 ph: 508-979-1446 / fax: 508-991-6148 Revised April 2007

III-2

This Page Intentionally Left Blank

#### **Table of Contents**

<u>Section</u>	<u>Title</u>	Page(s)
AA.01	Definitions	III-29
AA.02	Statement of Policy	III-34
AA.03	City of NB Ordinances - Synopsis	III-35
AA.04	Contractor's Agreements under 11246	III-35
AA.05	Dept. of Labor, C.F.R. Parts 60-1, 60-6	
	Government Contractors, Affirmative Action Requirements	III-36
	- Segregated Facilities -A.A. Compliance Program	
AA.06	Section 503 of the Rehabilitation Act of 1973	III-36
AA.07	/MBE/WBE Policy Requirement	III-37
AA.08	Contractor's EEO/Records Monitor	III-38
AA.09	Bidder's Eligibility	III-38
AA.10	Bid Submission Requirements	III-38
AA.11	Bid Approval or Disapproval (by EEO)	III-39
AA.12	Steps to Ensure a Responsive Bid	III-39
AA.13	Bid Award or Rejection	III-40
AA.14	Awarded Contractors Obligations	III-41
	- Minimum Minority/Female Work Hours	
	- Apprentices/Trainees - Reports Required During Life of Project	
AA.15	Recruitment/Referral Responsibilities	III-41
AA.16	Subcontracts	III-42
AA.17	Wage Rates	III-43
AA.18	Access to Compliance Info. & Reports	III-43
AA.19	Noncompliance	III- <b>4</b> 4
	- Investigation - Reports	
AA.20	Noncompliance	111-44
AA.21	Sanctions	III-45
AA.22	Appeal of Sanctions	III-45
AA.23	Severability	III-46
Appendix A	Bid Submission Documents	

#### **AA.01: Definitions**

Relevant to the requirements set forth in this bidding document

#### **Construction Bidding Statutes\***

#### **Public Works Projects**

Governed under Massachusetts General Laws, ch. 30, sec. 39M.

Includes all municipal contracts for construction, reconstruction, alteration, remodeling, and/or repair/s estimated to cost more than \$10,000 which does not include work on a building. Includes the construction and repair of roads, bridges, water mains, sewers, and the like, as well as improvement to public land (i.e.: operation of a municipal landfill, removal of waste materials, grading, erosion control, and other forms of improvement and maintenance.

Also governs contracts of \$50,000-150,000 for construction, reconstruction, installation, demolition, maintenance, or repair work on a building.

#### **Building Projects**

Governed under Massachusetts General Laws, Ch. 149, sec. 44.

Includes all contracts for the construction, reconstruction, installation, demolition, maintenance, or repair of a building at an estimated cost of more than \$25,000.

#### Lowest Eligible & Responsible Bidder\*

Massachusetts G.L. c. 30, sec. 39M; c. 149, sec. 44A state that the contract be awarded to the lowest eligible and responsible bidder.

<u>Eligible</u> means the bidder meets all of the requirements set forth in the bidding documents.

<u>Responsible</u> means the bidder possesses the skill, ability, and integrity to complete the job.

#### **Reasonable Accommodations**

Any change in work environment or the way job duties are customarily performed that enables individuals with disabilities to perform the essential functions of the job in issue, or that ensures equal opportunity for individuals with disabilities with respect to the application process or the enjoyment of benefits and privileges of employment.

#### **Administering Agency**

The agency that administers the city, state, state-assisted, or federally assisted contract awarded by the contracting agency

#### **Contracting Agency**

The agency that directly awards the contract

#### Contractor

Any general contractor and all subcontractors

<sup>\*</sup> This information is taken directly from "Designing and Constructing Municipal Facilities: Legal Requirements; Recommended Practices; Sources of Assistance" Published by, William Francis Galvin, Secretary of the Commonwealth, Office of the Inspector General, Oct. 1989.

#### AA.01: continued

#### Minority / Women Business Enterprise

As defined by the Massachusetts SDO (State Diversity Office) (formerly known as SOMWBA). In summary, an MBE/WBE is a business at least fifty-one percent (51%) owned or controlled by minority/women group members, or an individual contractor or professional who is a minority/women group member (as defined by SDO).

Minority refers to:

#### **Native American**

A person having origin in any of the original people of North America, who is recognized as American Indian by a tribe or tribal organization or is recognized as such within his/her community

#### <u>Asian</u>

A person having origin in any of the original people of the Far East, Southeast Asia, Indian Subcontinent, Korea, Philippines, and Samoa

#### Black

A person having origin in any of the black racial groups of Africa

#### Cape Verdean

A person having origin in any of the original people of the Cape Verde Islands

#### Eskimo / Aleut

A person having origin in any of the original people of Northern Canada, Greenland, Alaska, and East Siberia

#### **Hispanic**

A person of Spanish descent and culture having origin in Mexico, the Island of the Caribbean, Central America or South America

This Page Intentionally Left Blank



## City of New Bedford 133 William Street New Bedford, MA 02740

#### EEO/AA POLICY STATEMENT

********	City of New Bedford	has a statutory mandate under law to guarantee equal treatmen
for a		r opportunities for employment and advancement. No discriminati
wiii	be tolerated on the basis of race, cr	reed, political affiliation, color, sex, national origin, age, or handicap
		is organization to reflect the proportions of minority, female, and
	dicapped persons in the population	- · · · · · · · · · · · · · · · · · · ·
	City of New Bedford	will meet its legal, moral, social, and economic responsibilities fo
Equa	ai Empioyment Opportunity/Affirma	ative Action as authorized and required by ail pertinent state and
fede	erai legislation, executive orders and	ruies and regulations, including the following:
1.	Title II of the Civil Rights Act of 3	1964 (42 USC s2000e et seg, which prohibits discrimination in
emp	oloyment on the basis of race, color,	religion, sex, or national origin; and
2.	The Age Discrimination in Emplo	oyment Act of 1967 (29 USC s621 et seg.), which prohibits
discr	rimination in employment on the ba	asis of age with regard to those individuals who are at least 40 years
of ag	ge, but less than 65 years of age; an	d.
3.	Section 504 of the Rehabilitation	n Act of 1973 (29 USC s794), and the regulations promulgated
purs	suant thereto (45 CFR Part 84), which	h prohibit discrimination against qualified handicapped individuals
on th	he basis of handicap and requires er	mpioyers to make reasonable accommodations to known physical o
		d handicapped applications and employees; and
4.	M.G.L. c. 151B s4 (1), as amende	ed by Chapter 533, 1983, which prohibits discrimination in
empi	ioyment on the basis of race, coior,	sex, religious creed, national origin, ancestry, age or handicap,
in ad	dition, the Provider agrees to be fa	miliar with and abide by:
*	Massachusetts Executive	e Order 524
*	Massachusetts Executive	e Order 526
*	Equal Pay Act of 1963	•
*	Massachusetts Architect	
*	Federal Executive Order	s 11246 and 11375 as amended.

All employees, unions, sub contractors and vendors must make genuine and consistent efforts:

- 1. To ensure equal employment opportunities for present and future employees, and
- To implement affirmative action, as legally required, to remedy the effects of past employment discrimination and social inequalities.

The responsibility for implementing and monitoring this policy has been delegated to:

EEO Contract Compliance Officer

Name and Title of Employee

Furthermore, City of New Bedford

prohibits that any employee, or applicant, be subjected to coercion, intimidation, interference or discrimination for filing a complaint or assisting in an investigation under this program. No portion of this <u>Faual Employment Opportunity/Affirmative Action Policy</u> shall be construed as conflicting with any existing or future judicial or legislative mandate where a constriction consistent with that mandate is reasonable.

Mayor

Title of Chief, Executive

ture of Chief Ekecutive

#### MINORITY/WOMAN BUSINESS ENTERPRISE PROGRAM

It is the policy of the government of the United State of America, the Commonwealth of Massachusetts and the City of New Bedford, that no person shall be discriminated against in any manner whatsoever, on the grounds of race, color, age. national origin, disability, religion, or sex.

Under this policy, the minority and woman business enterprises shall have the maximum practicable opportunity to participate in federally assisted projects, and shall not be excluded from such participation, nor denied the benefits of or be subjected to discrimination under any program or activity receiving federal assistance.

The City of New Bedford unequivocally ascribes to said policies as the recipient of Federal and state financial assistance, in connection with its activities, and may receive further Federal and State financial assistance in the future.

The City of New Bedford strongly affirms that it will not discriminate in any contractual procedure against any person because of race, color, age, national origin, disability, religion, or sex, or any other condition that is a bona fide qualification. This policy shall be administered at all levels with a positive, aggressive and supportive attitude by all department heads.

It is the responsibility of all department heads and employees to take affirmative steps to implement this policy to ensure equality of opportunity in conducting the affairs of the City of New Bedford, including notifying those persons and businesses doing business with the City of New Bedford, that contracts for goods and services and construction, shall be made without, reference to race, color, age, national origin, disability, religion or sex.

This Minority/Woman Business Enterprise Program sets forth the administrative standards for the further implementation of the City of New Bedford's policy for the utilization of minority and female contractor, subcontractors, and suppliers.

Each department shall ensure that all solicitation in advertisements includes a statement of the City's affirmation action policy, in an approved format.

The city's Equal Opportunity Officer shall be responsible for ensuring that all aspects of the MBE/WBE program are initiated and undertaken. By virtue of the delegation of this responsibility and authority to direct the program, the Contract Compliance Officer will report directly to the Mayor on equal opportunity matters. The Equal Opportunity Officer shall be responsible for the development, administration, and monitoring of all activities necessary to ensure the accomplishment and success of this program.

NOW, THEREFORE IT IS HEREBY RESOLVED that the following Minority/Woman Business Enterprise Program is instituted for and in behalf of the City of New Bedford.

Mayor Conathan F. Mitchell

Date

Revised 2007

#### AA.03: City of New Bedford Ordinances - Synopsis

See Appendix A for complete City Ordinances relevant to this bid document

- (1) Residency Requirements for Certain City-Supported Construction Projects, Chap. 10, Article II.
  - (a) Shall apply to all general and subcontractors of public works projects which have a projected cost of more than \$100,000.00
  - (b) Fifty (50) percent of the total employee man-hours in each trade must be performed by residents of the City of New Bedford (excluding the employer's foreman *or* supervisor and two other key employees.)\*
  - \* Contact the N.B. EEO Dept. for further assistance in this matter.
  - (c) resident is defined as someone having his/her true, fixed, and permanent home and principal establishment in the City of New Bedford, for a *minimum of six* (6) *months* <u>prior</u> to the contract bid opening date.
- (2) Contractor Qualifications and Sanctions, a.k.a. "The Responsible Employer Plan", Chap. 10-77.
  - (a) Shall apply to all bidders and subcontractors for projects subject to MGL c. 149
  - (b) Not applicable to construction projects where the low general bid was less than \$100,000; to subcontracts bid for less than \$25,000; or to re-bids for which the City receives fewer than three (3) qualified bidders in the original bid
  - (c) Must pay appropriate lawful prevailing wage rates to employees
  - (d) Must maintain or participate in a bona fide <u>apprentice training program</u> for <u>each</u> apprenticeable trade represented in the workforce
  - (e) Must furnish hospitalization and medical benefits and maintain appropriate accident insurance coverage
  - (f) Must classify all employees as employees rather than independent contractors, and treat accordingly regarding workers compensation, unemployment taxes, social security taxes and income tax withholding.

# AA.04: Contractors Agreements under Executive Order 11246, as Amended by Executive Order 11375 During the performance of this contract, the contractor agrees as follows:

(1) The contractor will not discriminate against any employee or applicant for employment because of race, color, religion, sex, or national origin. The contractor will take affirmative action to ensure that applicants are employed, and that employees are treated during employment, without regard to their race, color, religion, sex or national origin. Such action shall include, but not be limited to the following: employment, upgrading, demotion, or transfer; recruitment or recruitment of compensation; and selection of training, including apprenticeship. The contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices to be provided by the contracting officer setting forth the provisions of this nondiscrimination clause.

- 2) The contractor will, in all solicitations or advertisements for employees placed by or on behalf of the contractor, state that all qualified applicants will receive consideration for employment without regard to race, color, religion, sex or national origin.
- (3) The contractor will send to each labor union or representative of workers with which he has a collective bargaining agreement or other contract or understanding, a notice, to be provided by the agency contracting officer, advising the labor union or workers' representative of the contractor's commitments under Section 202 of Executive Order No. 11246 of September 24, 1965, and shall post copies of the notice in conspicuous places available to employees and applicants for employment.
- (4) The contractor will comply with all provisions of Executive Order No. 11246 of Sept. 24, 1965, and of the rules, regulations, and relevant orders of the Secretary of Labor.
- (5) The contractor will furnish all information and reports required by Executive Order No. 11246 of Sept. 24, 1965, and by the rules, regulations, and orders of the Secretary of Labor, or pursuant thereto, and will permit access to his books, records, and accounts by the contracting agency and the Secretary of Labor for purposes of investigation to ascertain compliance with such rules, regulations, and orders.
- (6) In the event of the contractor's noncompliance with the nondiscrimination clauses of this contract or with any of such rules, regulations or orders, this contract may be canceled, terminated, or suspended in whole or in part and the contractor may be declared ineligible for further Government contracts in accordance with procedures authorized in Executive Order No. 11246 of Sept. 24, 1965, or by rule, regulation or order of the Secretary of Labor, or as otherwise provided by law.
- (7) The contractor will include the provisions of paragraphs (1) through (7) in every subcontract or purchase order, unless exempted by rules, regulations, or orders of the Secretary of Labor issued pursuant to Section 204 of Executive Order No. 11246 of Sept. 24, 1965, so that such provisions will be binding upon each subcontractor or vendor. The contractor will take such action with respect to any subcontract or purchase order as may be directed by the Secretary of Labor as a means of enforcing such provisions including sanctions for noncompliance: provided, however, that in the event the contractor becomes involved in, or is threatened with, litigation with a subcontractor or vendor as a result of such direction, the contractor may request the United States to enter into such litigation to protect the interests of the United States.

# AA.05: Dept. of Labor, 41 Code of Federal Regulations Parts 60-1, 60-6 - Government Contractors, Affirmative Action Requirements, Executive Order 11246

(1) <u>Segregated Facilities</u>. The contractor hereby certifies that it does not and will not maintain or provide any facilities for its employees in a segregated manner, or permit its employees to perform their services at any location, under its control, where segregated facilities are maintained. Further, the contractor shall obtain a similar certification of non-segregated facilities prior to the award of any contract or subcontract, which is subject to Executive Order 11246, and shall provide a copy thereof to the Association.

This clause prohibits segregation on the basis of race, color, religion, national origin, or sex, and applies to all contracts regardless of the amount thereof. The term facilities includes, but is not limited to, waiting rooms, work areas, restaurants and other eating areas, time clock, parking

lots, drinking fountains, recreation or entertainment areas, transportation, employer-provided housing, washrooms, locker rooms or other storage or dressing areas.

(2) Affirmative Action Compliance Program. The contractor certifies that it has developed a written affirmative action compliance program for each of its establishments consistent with the rules and regulations published by the Department of Labor in 41 CFR Chapter 60, and agrees to require a similar certification from each of its nonexempt subcontractors. Such an affirmative action program shall contain a set of specific and result-oriented procedures, the objective of which shall be the achievement of equal employment opportunity. An acceptable affirmative action program must include an analysis of areas within which the contractor is deficient in the utilization of minority groups and women and further, goals and timetables to which the contractor's good faith efforts must be directed to correct any deficiencies and, thus, to achieve prompt and full utilization of minorities and women, at all levels and in all segments of his work force where deficiencies exist.

The contractor's affirmative action plan shall be summarized and updated annually and the program summary shall be submitted to the Office of Federal Contract Compliance Programs (OFCCP) on the anniversary date of the contractor's affirmative action program.

(3) <u>Contractor's Compliance with Exec. Order and 41 CFR Par 60-4</u>. The contractor's compliance with E.O. 11246 and 41 C.F.R. Part 60-4, shall be based on its implementation of the Equal Opportunity clause, specific affirmative action obligations required by the specifications set forth in 41 C.F.R. 60-4.3, and its efforts to meet the goals established for the geographical area where the contract resulting from this solicitation is to be performed.

#### AA.06: Section 503 of the Rehabilitation Act of 1973

(Dept. of Labor, 41 Code of Federal Regulations, Parts 60-250 and 60-741, Affirmative Action & Nondiscrimination Obligations of Contractors and Subcontractors Regarding Individuals with Disabilities, Disabled Veterans, and Veterans of Vietnam Era)

Parties holding a Government contract or subcontract in excess of \$10,000 must take affirmative action to employ and advance in employment-qualified individuals with disabilities. Contractors are required to use effective practices to recruit qualified individuals with disabilities.

Applicants with disabilities must be provided a reasonable accommodation if they are qualified with respect to the application process (e.g.: if they present themselves at the correct location and time to fill out an application).

#### AA.07: MBE / WBE Policy (for the life of the project)

- (1) **Eleven (11) percent** of the work on this project shall be performed by Minority Business Enterprises (MBEs) and **five (5) percent** of the work shall be performed by Women Business Enterprises (WBEs) for a total of 16% overall. **Four and one-third (4.33%) percent of all Airport projects shall be performed by Disadvantaged Business Enterprises (DBE). Proven documentation of non-availability and the filing of a MBE/WBE/DBE Request for Waiver will be required to be submitted by the general contractor in circumstances where the EEO goals are not met.**
- (2) If it is determined that one or more of the MBE/WBE or DBE contractors, as submitted by the Contractor on the EEO forms, is not SDO (State Diversity Office) (formerly known as SOMWBA)

certified or certified by the Local Government Unit, in accordance with the provision of Executive Order 237, the bidder shall have five (5) working days following notification to either find a certified MBE/WBE/DBE contractor to perform work equal to or greater than that of the uncertified contractor, or to submit a waiver request.

(4) The contractor <u>shall not enter into any subcontract with any person or firm debarred from government contracts</u>, <u>pursuant to Executive Order 11246</u>.

#### AA.08: Workforce Utilization (for the life of the project)

(1) Minimum percentages for **employment (workforce utilization)** on the project are at **18% minority** and **6.9% female** participation. The employment percentages shall apply to the contractor <u>and</u> to **all** subcontractors, regardless of tier, for all on-site work.

A single goal for minorities and a separate goal for women have been established. The Contractor, however, is required to provide equal employment opportunity and to take affirmative action for all minority groups, both male and female, and all women, both minority and non-minority. Consequently, the Contractor may be in violation of the Executive Order if a particular group is employed in a substantially disparate manner (for example, even though the contractor has achieved its goals for women generally, the contractor may be in violation of the Exec. Order if a specific minority group of women is under-utilized.)

(3) The contractor shall <u>not</u> use the goals and timetables or affirmative action standards to discriminate against any person because of race, color, religion, sex, or national origin.

#### AA.09: Contractor's EEO / Records Monitor

The contractor shall designate a responsible official to monitor all employment related activity to ensure that the company EEO policy is being carried out, to submit reports relating to the provisions hereof, as may be required by the Government, and to keep records which shall at least include, for each employee, the name, address, telephone numbers, social security number, race, sex, status, (e.g.: mechanic, apprentice, trainee, helper, or laborer) dates of changes in status, hours worked per week in the indicated trade, rate of pay, and locations at which the work was performed. Records shall be maintained in an easily understandable form; however, to the degree that existing records satisfy this requirement, contractors shall not be required to maintain separate records. Nothing herein provided shall be construed as a limitation upon the application of other laws which establish different standards of compliance or upon the application of requirements for the hiring of local or other area residents.

#### AA.10: Bidder's Eligibility

The lowest responsible and eligible bidder shall mean the General Bidder whose bid is the lowest of those bidders demonstrating possession of the skill, ability and integrity necessary for the faithful performance of the work, and

- (a) who shall certify that he/she is able to furnish labor that can work in harmony with other labor employed on the work;
- (b) who shall certify that he/she will demonstrate good faith efforts to obtain the minority workforce goal (18%) the woman workforce goal (6.9%) and, for projects \$100,000+, NB residency goal of 50%; the insurance that all subcontractors and/or sub-subcontractors are

also in compliance with workforce utilization goals; including compliance with the minority business goal (11%) and woman business goal (5%), for a total of 16% (or 4.33% for Airport projects) of the total dollar amount of the contract, and will certify that it will meet all applicable City Ordinances in accordance with this contract provision.

#### **AA.11: Bid Submission Requirements**

- (1) Required bid forms that must be completed, signed, and submitted with the bid at the time of the bid opening, are as follows:
  - (a) Certificate of Understanding; Certification of Compliance w/ Exec. Order 11246
  - (b) Schedule of Participation for MBE/WBE or DBE as required
  - (c) Letter of Intent (for each MBE/WBE/DBE participation)
  - (d) MBE/WBE/DBE Contractor Identification Statement (for each MBE/WBE/DBE)
  - (e) Bidder's Certification (to be completed by both the General Contractor and <u>each</u> MBE/WBE/DBE)
  - (f) If applicable, a completed and signed MBE/WBE/DBE Unavailability Certification in the event that the work listed on the Schedule is not sufficient to fulfill the requirement for MBE/WBE/DBE Participation. This certification must include a statement by the bidder of the reasons why it believes it is in compliance with this provision, <u>and</u> a list of the names, addresses, telephone numbers and reason given for unavailability of the Minority/Women Contractor contacted by the bidder with respect to the performance of work under the contract.
  - (g) If applicable, a completed and signed Minority / Women / Disadvantaged Business Enterprises Request for Waiver.
- (2) The successful bidder will also be required to submit, <u>prior</u> to award, its estimates of labor (permanent and trainee) and material required to carry out its work under the contract, for review by the City, so as to establish maximum feasible goals for the utilization of City residents and business concerns. These goals, and the basis for monitoring and reporting progress toward meeting them, will be established by mutual agreement, with the assistance of the City's Contract Compliance Officer, and discussed in the Pre-Construction and/or Pre-Award Conference.

#### AA.12: Bid Approval or Disapproval

- (1) At the time of the bid opening, the bidder will have five (5) days, from the date of the bid opening, to comply with the MBE/WBE/DBE requirements. Failure to meet these requirements within the five days will have the Bid/Proposal disapproved by the Office of Equal Opportunity.
- (2) Each bidder, as part of its bid submission, must agree to make good faith efforts to contract with minority and woman owned businesses (and disadvantaged business when applicable), as defined by the State Diversity Office (SDO) (formerly known as Office of Minority and Woman Business Assistance (SOMWBA)) and the City of New Bedford's affirmative action policies. The

amount of participation reserved for such enterprises shall not be less than 16% of the total bid amount, of which at least 11% of the total bid amount applies to minority businesses. The balance 5% is applied to women-owned businesses. Proven documentation of non-availability of either one of these entities provides that the available business may be awarded no less than 16% of the total contract dollar value.

- (3) If the general bidder is either an MBE or WBE and is responsible for 100% of the project work, the 16% is fulfilled. If said MBE/WBE contractor is a joint venture, the MBE/WBE must be responsible for at least 51% of the project.
- (4) The general contractor <u>must</u> submit, as part of its bid and as a condition of contract approval, signed Letters of Intent with all subcontractors and material suppliers listed on the participation schedule. Sub-bidders must submit the participation schedule with their bid and a participation schedule if they intend to sub-sub work.

#### AA.13: Steps to Ensure a Responsive Bid

The total price for work to be performed by Minority/Woman or Disadvantaged Contractors, as indicated in each bidder's bid submission, is required to be sufficient to fulfill the MBE/WBE/DBE requirements, unless the bidder shall demonstrate to the satisfaction of the Awarding Authority that:

- (1) it has made every possible effort to contact and negotiate with Minority/Women or Disadvantaged Contractors in an attempt to subcontract work, including every possible effort to select the portions of the work proposed to be subcontracted in order to meet the requirements;
- (2) it was unable, notwithstanding such efforts, to achieve the stated requirement because Minority/Woman or Disadvantaged Contractors were not qualified or were unavailable (any proven non-availability of MBE/WBE/DBE must make up the difference to still fulfill the 16% goals with the available MBE or WBE or 6.0% DBE. If neither category is available to fulfill the goal, it must have a SDO statement as to no business listed);
- (3) it included in its Schedule of Participation such proposed agreements as could be made with such efforts;
- (4) the general contractor is a MBE or WBE and said contractor is performing 16% of work or the general contractor is a DBE and is performing 6.0% of the work and therefore, will be deemed as fulfilling the affirmative action bidding requirements;
- (5) for contractors performing work under \$50,000 that can demonstrate all work will be completed under the contractor's own workforce, the contractor must be able to demonstrate how this will be accomplished and submit, at the time of the bid a statement requesting a waiver of the 16% MBE/WBE or 6.0% DBE participation goal. Said contractors will still be required to demonstrate good faith efforts regarding the prescribed employment workforce percentage goals.

#### AA.14: Bid Award or Rejection

(1) The Awarding Authority will responsible for awarding or rejecting any bid, with the

approval/disapproval of the Office of Equal Opportunity & Contract Compliance in its decision. The Awarding Authority also reserves the right to reject any or all bids, or to accept any other than the lowest bidder, should it be deemed to be in the best interest of the City of New Bedford, Massachusetts, to do so.

(2) The Awarding Authority may reject, as non-responsive, any bid, which it determines, fails to comply with the applicable requirements of this contract provision. Nothing, herein, shall relieve any bidder or any contractor performing any work under the contract, from any of the terms, conditions, or requirements of the contract.

#### AA.15: Awarded Contractor's Obligations

- (1) The Contractor shall specifically ensure that the City's EEO policy and affirmative action obligations under this contract provision, is reviewed with all employees having any responsibility for hiring, assignment, layoff, termination, or other employment decision, including specific review of these terms with on-site supervisory personnel, <u>prior</u> to the initiation of construction work at any job site. A written record shall be made and maintained identifying the time and place of these meetings, persons attending, subject matter discussed, and disposition of the subject matter.
- (2) Minority/Woman Work Hours must be maintained for the life of this project (at a minimum ratio of 18% minority work hours and 6.9% woman work hours to total work hours in each job category, including, but not limited to bricklayers, carpenters, cement masons, electricians, ironworkers, operating engineers, and those classes of work identified in Section 44C of M.G.L. ch. 149). (Please note the City of New Bedford's Residency Ordinance requiring 50% City of New Bedford residents on projects of \$100,000+)
- (3) Apprentices and Trainees must be employed by the Contractor during the training period, and the Contractor must have made a commitment to employ the apprentices and trainees at the completion of their training, subject to the availability, in order for the apprentices and trainees to be counted toward the minority/woman work hour percentage goals.
- (4) Neither the provisions of any collective bargaining agreement, nor the failure by a union with whom the contractor has a collective bargaining agreement to refer either minorities or women, shall excuse the contractor's obligation under these specifications, Exec. Order 11246 or the regulations promulgated pursuant thereto.
- (5) In the employment of journeymen, apprentices, teamsters and laborers, the Contractor shall give preference first, to citizens of the Commonwealth who have served in the armed forces of the United States in time of war and have been honorably discharged therefrom or released from active duty therein, and who are qualified to perform the work which the employment relates, and secondly, to citizens of the City of New Bedford, and if such cannot be obtained in sufficient numbers, the Commonwealth generally, then to citizens of the United States.
- (6) Reports to Be Submitted to the Office of Equal Opportunity & Contract Compliance include:
  - (a) <u>Licensing Statutes</u>: Every contractor and subcontractor must submit, <u>before starting work</u>, a plan by which he/she will satisfy the requirements of licensing statutes, including the following, where applicable: MGL Ch. 149, Sec. 6 (painters); Ch. 146, Sec. 53 (hoisting engineers); Ch. 149, Sections 6B-6F (asbestos abatement workers, supervisors & contractors); Ch. 146, Sec. 3 & 3B (plumbers & gas fitters); Ch. 141, Sec. 1

(electricians); Ch. 14, Sec. 84 (pipefitters & sprinkler fitters); and Ch. 143, Sec. 94 (construction supervisor).

- (b) <u>Work Hour Reports</u>: The contractor and each subcontractor shall prepare <u>weekly</u> reports in an approved form, of the hours worked in each trade by each employee, identified as minority or non-minority, and/or female, and/or resident. Copies of these shall be provided at the end of each such week to the City's Office of Equal Opportunity & Contract Compliance.
- (c) <u>Projected Manning Tables</u>: The contractor shall prepare projected manning tables on a quarterly basis. These shall be broken down into projections, by week, of workers required in each trade. Copies shall be furnished one week in advance of the commencement of the period covered, and also when updated, to the City. A copy of the certified payroll will be submitted with these reports.
- (d) <u>Billing Reports</u>: The contractor shall prepare and submit monthly billing reports of amounts paid to MBEs, WBEs and/or DBEs each monthly billing period, as well as the record of final payment accompanied by canceled checks.
- (e) <u>Payroll Reports</u>: Every contractor and subcontractor shall submit <u>weekly</u> payroll reports to the City, indicating the following information for each employee and/or independent contractor employed on the project; name, address, hours worked, occupational classification, wages, and fringe benefit payments, if any. Said reports shall be signed by the employer or his authorized agent under the penalties of perjury (see MGL Ch. 149, Section 27B).

#### AA.16 Recruitment/Referral Responsibilities

- (1) In the hiring of minority/woman journeymen, apprentices, teamsters, and laborers, the contractor shall rely on referrals from a multi-employer affirmative action program approved by the City, traditional referral method utilized by the construction industry, and referrals from agencies, not more than three in number at any one time, designated by the City's Equal Opportunity Officer.
- (2) Records of employment referral orders, prepared by the contractor, shall be made available to the awarding authority.
- (3) The contractor will maintain a current file of the names, addresses, and telephone numbers of each minority and female off-the-street applicant and minority or female referral from a union, a recruitment source, or community organization, and of what action was taken with respect to each such individual.
- (4) If such individual was sent to the union hiring hall for referral, and was not referred back to the contractor, this shall be documented in the file with the reason therefore, along with whatever additional actions the contractor may have taken.
- (5) The contractor will document and maintain a record of all solicitations of offers for subcontractors from minority and female construction contractors and suppliers, including circulation of solicitations to minority and female contractors associations and groups.
- (6) The contractor will, in all solicitations or advertisements for employees placed by or on

behalf of the Contractor, state that all qualified applicants will receive consideration for employment without regard to race, color, religion, sex or national origin, and maintain a record thereof.

#### **AA.17: Subcontracts**

- (1) The Contractor receiving the award of the contract shall be required to obtain from each of its subcontractors (filed or non-filed) and submit to the Authority <u>prior</u> to the performance of any work under said subcontract, a certification by said subcontractor, regardless of tier, that it will comply with the minority and women work hours/employee ratio and specific affirmative action steps, and to submit this information to the Office of Equal Opportunity, <u>prior</u> to the subcontractor's performance on the project.
- (2) In order to ensure that the said subcontractor's certification becomes a part of all subcontracts under the prime contract, no subcontract shall be executed until an authorized representative of the Authority administering this project has determined, in writing, that the said certification has been incorporated in such subcontract, regardless of tier. Any subcontract executed without such written approval shall be void.
- (3) Whenever the contractor, or any subcontractor at any tier, subcontracts a portion of the work involving any construction trade, it shall physically include in each subcontract in excess of \$10,000, the contract provisions listed in this Instructions to Bidders for Affirmative Action Issues, and the applicable goals for minority and female participation and which is set forth in the solicitation form which the contract resulted.
- (4) Noncompliance of a subcontractor in compliance with these provisions, will result in the contractor taking such action, with respect to any subcontract or purchase order, as the administering agency may direct, as a means of enforcing such equal opportunity provisions; provided that, in the event a contractor becomes involved in, or is threatened with litigation with a subcontractor or vendor, as a result of such direction, the contractor may request the United States, the State of Massachusetts or the City of New Bedford, to enter into such litigation to protect the interests of the U.S., the State or the City.

#### AA.18: Wage Rates

- (1) Attention is called to Labor Standards provisions regarding conditions of employment, including State and Federal Wage Rates, the Davis-Bacon Act, the Copeland Anti-Kickback Act, and the Contract Work Hours and Safety Standards Act. Where Federal and State wage rates differ, the higher rates shall be used as a minimum.
- (2) The rate per hour of the wages to be paid to mechanics, apprentices, teamsters, chauffeurs, and laborers employed on the work shall be not less than the rate of wages in Minimum Wage Rates as determined by the Commissioner of Labor and Industries, as required by M.G.L. Chapter 149, Sections 26 & 27-27h. This schedule shall be in place for said employees during the life of this contract.
- (3) Contractor shall keep posted on the site, a legible copy of said schedule. The Contractor shall keep on file wage rates and classifications of labor employed on this work, in order that they may be available for inspection by the Administrator, the Office of Equal Opportunity, or the Architect.
- (4) Apprentices employed pursuant to this determination of wage rates must be registered and

approved by the State Apprenticeship Council, wherever rates for journeymen or apprentices are not listed.

- (5) Pay reserve police officers employed on this work the prevailing rate of wages paid to regular police officers, as required by M.G.L. Chap. 149, Sec. 34B, as amended. Such police officers shall be covered by Workmen's Compensation Insurance and Employer's Liability Insurance by the Contractor.
- (6) Noncompliance by the contractor or any subcontractor will result in the City's Contract Compliance Office and/or Legal Office, to consult with the Department of Labor and Industries, and will result in the contractor or subcontractor receiving notification of such, and subsequently must respond to the City of New Bedford within five (5) business days.

#### AA.19: Access to Compliance Information & Reports

- (1) The contractor will provide all information and reports, required by the administering agency or the City of instructions issued by either of them, and will permit access to its facilities and any books, records, accounts, and other sources of information pertinent to the City's affirmative action contract requirements.
- (2) Where the information required is in the exclusive possession of another who fails or refuses to furnish this information, the contractor shall so certify to the administering agency or the City, and shall set forth what efforts he/she has made to obtain the information.

#### AA.20: Noncompliance

#### (1) Investigation

Whenever the administering agency or the City believe the general contractor or any subcontract may not be operating in compliance with the terms of this provision, the City directly or through it designated agent, shall conduct an appropriate investigation, and may confer with the parties, to determine if such contractor is operating in compliance with the terms of this contract provision. If noncompliance is found, then a preliminary report on noncompliance will be made, and the City or its agent will notify such contractor, in writing, of such steps as will, in the judgment of the city or its agent, bring such contractor into compliance.

#### (2) Report of Noncompliance

In the event that such contractor fails or refuses to fully perform such affirmative action steps, the City shall make a final report of non-compliance, and recommend to the administering agency, the imposition of one or more of the sanctions identified in these provisions. Within fourteen (14) days of the receipt of the recommendations of the City, the administering agency shall move to impose one or more of the following sanctions as it may deem appropriate to attain full and effective enforcement.

(3) Any disagreement between the City and a contractor or subcontractor shall be submitted for a hearing pursuant to the provisions of Chapter 30A. The City shall impose one or more of the following sanctions, as it may deem appropriate, to attain full and effective enforcement.

#### **AA.21: Sanctions**

(1) The recovery by the administering agency from the general contractor of 1/100 of 1% of the

contract award price, or \$1,000.00, whichever sum is greater, in the nature of liquidated damages, or if a subcontractor is in non-compliance, the recovery by the administering agency from the general contractor, a back charge against the subcontractor, of 1/10 of 1% of the subcontract price or \$400.00, whichever sum is greater, in the nature of liquidated damages, for each week that such party fails or refuses to comply.

- (2) The suspension of any payment or part thereof, due under the contract, until such as the general contractor or any subcontractor is able to demonstrate his/her compliance with the terms of the preceding sections of the contract.
- (3) The termination of employment of the contractor and taking possession of the site and finishing the work by whatever method he/she may deem expedient, upon giving the contractor and his/her surety, if any, seven days? written notice.
- (4) The termination or cancellation of the contract, in whole or in part.
- (5) The denial to the general contractor and any subcontractor of the right to participate in any future contract awarded by the administering agency for a period of up to three years.
- (6) Other sanctions to be applied, as stipulated in the City of New Bedford Ordinances (Residency and Responsible Employer Plan ordinances) and other local, state, and federal laws and regulations, as applicable.

#### **AA.22: Appeal of Sanctions**

If, at any time after imposition of one or more of the sanctions listed in these provisions, the contractor or subcontractor is able to demonstrate that it is in compliance with the EEO/AA program, the contractor or subcontractor may request the administering or contracting agency, in consultation with the City's Equal Employment Opportunity compliance officer, to conditionally suspend the sanction, pending final determination by the investigating officer, whether the contractor is in compliance. Upon final determination by the investigating office, the administering or contracting agency, based on the investigating officer's recommendation, shall either lift the sanctions or impose them.

Sanctions shall not be imposed by the contracting agency or administering agency except after an adjudicatory proceeding, as defined by M.G.L. Chapter 30A, has been conducted. No investigation by the Office of Equal Opportunity shall be initiated without prior notice to the contractor or the subcontractor.

#### AA.23: Severability

The provisions of this section are severable, and if any of these provisions shall be held unconstitutional by any court of competent jurisdiction, the decision of such court shall not affect or impair any of the remaining provisions.

This Page Intentionally Left Blank

# APPENDIX A BID SUBMISSION DOCUMENTS

This Page Intentionally Left Blank

#### **Bid Submission Checklist**

THE GENERAL BIDDER SHALL SUBMIT ALL THE FOLLOWING FORMS AS A PART OF ITS BID SUBMISSION, AND SHALL SUBMIT A COPY OF SUCH TO:

The City of New Bedford Office of Equal Opportunity 133 William Street Room 208 New Bedford, MA 02740 ph: 979-1446 / fax: 508-991-6148

- (1) Certificate of Understanding: Certification of Compliance with Executive Order 11246"
- (2) Schedule of Participation for Minority, Woman & Disadvantaged Business Enterprises
- (3) Letter of Intent for each MBE/WBE/DBE Participation
- (4) MBE/WBE Contractor Identification Statement for each MBE/WBE/DBE
- (5) Bidder's Certification must be completed and signed by the General Contractor <u>and</u> **all** Subcontractors who will work on the project (to include MBE/WBE/DBE **and** non-MBE/WBE/DBEs)
- (6) If applicable, a completed and signed MBE/WBE/DBE Unavailability Certification in the event that the work listed on the Schedule is not sufficient to fulfill the Requirement for MBE/WBE/DBE Participation. This certification <u>must</u> include a statement by the bidder of the reasons why it believes it is in compliance with this Provision, <u>and</u> a list of the names, addresses, telephone numbers and reason given for unavailability of the Minority /Woman/ Disadvantaged Contractor who was contacted by the Bidder with respect to the performance of work under the contract.

Title

#### **Commonwealth of Massachusetts**

#### BIDDERS CERTIFICATE OF UNDERSTANDING

	Equal Employment	Opportunity Provisio	ns	
C	Contractor	Project		
A	Address	Tel. #	Project #	
		Fax#		
	I, the undersigned, understand that:		<del>.</del>	
A.	<ol> <li>Minority Business Enterprises are to be awarded at least 11% of projects.</li> </ol>	of the total contract amo	unt for construction/public works	
B.	<ol> <li>Woman Business Enterprises are to be awarded at least 5% of projects.</li> </ol>	the total contract amoun	t for construction/public works	
C.	C. Disadvantaged Business Enterprises are to be awarded at least	4.33% of the total contr	act amount for airport projects.	
D.	D. All required MBE/WBE/DBE forms included in Instructions to	All required MBE/WBE/DBE forms included in Instructions to Bidders are to be completed and submitted with the bid.		
E.	-			
1.				
2.	. Quarterly Manpower Projection Tables (Form CAD85-1) are to	Quarterly Manpower Projection Tables (Form CAD85-1) are to be submitted with the Start Construction notification;		
3.	Any project in the amount of \$100,000+ is subject to the New Bedford Resident Hiring and Responsible Employer Plan ordinances;			
4.	<ul> <li>A minimum goal of 18% minority manpower utilization, in ter trade or craft, on each project, will be maintained. The goal fo according to regulations;</li> </ul>	ms of total work hours in r female manpower utili	n the aggregate workforce, in each zation will be maintained at 6.9%	
5.	Minority and female work hours are to be uniform in each trade, and minorities and females are to be employed evenly of each project;			
6.	Minority or female employees are not be transferred from project to project for the purpose of meeting goals;			
7.	A roster of all minority and/or female applicants for employment <u>must be maintained at each project site</u> (Federal & Non-Federal) in the New Bedford Hometown Plan Area.			
F.	. The submission of the above reports and adherence to hiring presubcontractors is the responsibility of the prime contractor.	ractices and equal opport	tunity performance of	
	The bidder hereby certifies that he/she shall comply with the montained in the EEO above, including compliance with Contractor receiving the award of the contract shall be required contracting or administering agency prior to the performance contractor, regardless of tier, that it will comply with the mir contained in this appendix.	the minority contractor I to obtain from each of of any work under said	r compliance specifications. The its subcontractors, and submit to the contract, a certification by said sub-	
	Authorized Signature		Date	

Name (Please Print or Type)

# SCHEDULE OF PARTICIPATION DISADVANTAGED/MINORITY/WOMAN BUSINESS ENTERPRISES

to be completed by the Bidder

	Address:		4 Marie - Mari
2.	Name:		
	Address:		
	Nature of Participation:		
	Dollar Value / % of Bid:		
<b>©</b>	TOTAL BID PRICE	TOTAL DBE or MBE COMMITMENT  \$	%
_			
2.	Address:  Nature of Participation:  Dollar Value / % of Bid:		
2.	Address:  Nature of Participation:  Dollar Value / % of Bid:  Name:  Address:  Nature of Participation:		
\$_ idder ag	Address:  Nature of Participation:  Dollar Value / % of Bid:  Name:  Address:  Nature of Participation:  Dollar Value / % of Bid:  TOTAL BID PRICE		

# LETTER OF INTENT to be completed by the DBE/MBE/WBE

This form is to be completed by the DBE or MBE and WBE and must be submitted by the General Bidder as part of the Bid Proposal. A separate form must be completed for each MBE, WBE or DBE involved in the project.

Project Title: \_\_\_\_\_\_ Project Location: \_\_\_\_\_\_

110,000 11110.	<del></del>	rioject Loca	alion.
To:			
(Name of Bidder)			
From:			
(Name of DBE/MBE/	WBE)		Indicate DBE/MBE/WBE status
I / we intend to perform work in connection wit	h the above proj	ect as (Check One)	
<pre>{ } an individual { } a corporation { } other (explain):</pre>	{	} a partnership } a joint venture with:	
It is understood that if you are awarded the cobelow for the prices indicated.  DBE/MBE/WBE PARTICIPATION: Description of Activity	ontract, you inte		
The undersigned certify that they will enter into	a formal agreen	nent upon execution of the c	contract for the above-referenced
Project			
BIDDER		· DBE/	MBE / WBE
Authorized Signature	Date	Authorized Signature	Date
Address		Address	
Telephone / Fax		Telephone / Fax	

#### MINORITY / WOMAN BUSINESS ENTERPRISE PROGRAM

#### CONTRACTOR IDENTIFICATION STATEMENT

Project Name:	Project #:
Total Bid Price: \$	Bid Date:
In accordance with the New Bedford Min- he/she:	ority Business Enterprise Program, the undersigned bidder certifies that
Office of Minority/Woman Busine	oman/Disadvantaged Business Enterprise currently certified by the Statess Assistance (SOMWBA); and such SOMWBA certification has not status changing, it will immediately forward written notification to the BA; and
2. intends to perform certain with the above-named project, and	work (specified by formal bid proposal) under a contract in connection that work will <u>not</u> be sublet to any company at any tier; and
contained in the EEO/AA Contract bidder's certification and submit	inority/woman workforce ratio and specific affirmative action step. Provisions and shall obtain from each of its subcontractors a copy of the to the administering agency, prior to the award of such subcontract comply with the minority/woman workforce ratio and specific affirmative the EEO/AA Contract Provisions.
SOMWBA CERTIFICATION CATEGORY	<i>τ</i> :
CONTRACTORS NAME:	
{ } MBE { } WBE { } DBE	
ADDRESS:	
TELEPHONE #:	FAX #:
REPRESENTATIVE NAME & TITLE:	
AUTHORIZED SIGNATURE:	
GENERAL BIDDERS NAME:	

#### **BIDDERS CERTIFICATION**

To be completed by General Contractor & each of its Subcontractors (MBE/WBE/DBE and non-MBE/WBE/DBE)

The undersigned bidder hereby certifies that he/she will comply with the Minority/Woman Workforce Ratio and Specific Affirmative Action Steps contained in the EEO/AA Provisions of this contract, including compliance with the Minority/Woman/Disadvantaged Business Enterprise as required under these contract provisions.

The contractor receiving the award of the contract shall be required to obtain, from each of its subcontractors, regardless of tier, a copy of this Bidder's Certification indicating that it will comply with the Minority/Woman Workforce Ratio and Specific Affirmative Action Steps contained in these EEO/AA Contract Provisions, and submit it to the contracting agency prior to the award of such contract and subcontract.

Name of General Contractor	Name of Subcontractor { } MBE { } WBE { } DBE { } Non-MBE/WBE	
Signature of Authorized Representative	Signature of Authorized Representative	
Name & Title (Printed or Typed)	Name & Title (Printed or Typed)	
Date	Date	

## MINORITY / WOMAN BUSINESS ENTERPRISES UNAVAILABILITY CERTIFICATIONS

to be completed by General Contractor

## (The Bidder shall prepare additional copies of this information form in the quantity necessary to comply with the bidding requirements)

I,Name	Title	
of	Contractor Name	
certify that on	, I contacted the belo	ow listed MBE/WBE/DBE
requesting a bid for	of Contact	
Project	as an { } MBE, { } WBE	or { } DBE for the provision of
{ } Goods & Services or { } Labor	to accomplishSubcontract Work Offered to t	his MBE/WBE/DBE Company
	Name of Prospective Sub-Contractor	
Address City	y and State	Telephone #
Contact was made by { } Telephone	{ } In Person	
Said sub-contractor was unavailable (check appropriate answer):	for work on this project or unable to p	prepare a bid for the following reason(s):
{ } MBE/WBE/DBE Firm Declined	! Job	
{ } MBE/WBE/DBE Firm offered to acceptable because:	o do a job at the price of \$	, which was not
{ } Other		
		owledge and belief. Signed under the
Signature of Authorized Repre	esentative General Contractor	Date

This Page Intentionally Left Blank

## MINORITY / WOMAN/DISAVANTAGED BUSINESS ENTERPRISES

## REQUEST FOR WAIVER

Upon exhausting all known sources and making every possible effort to meet the minimum requirements for MBE/WBE/DBE participation, the Contractor may seek relief from these requirements by filing this form (completed) NO LATER THAN FIVE (5) working days following the bid opening. Failure to comply with this process shall be cause the bidder to be rejected, thereby rendering the contractor not eligible for award of the contract.

General Info	ormat	<u>ion</u>
Project Title	e:	Location:
Bid Openin	g (tim	ne/date):Location:
Bidder:		
Mailing Ad	dress:	
Contact Per	son: _	
Telephone N	No.: (	Ext.
Minimum R	Lequir	<u>ements</u>
bidder seeki	ing re o allo	ust show that good faith efforts were undertaken to comply with the percentage goals, as specified. The blief <u>must show</u> that such efforts were taken appropriately, in advance of the time set for opening bid and adequate time for response(s) by submitting the following: (please check all that apply and attachmentation)
A.		detailed record of the effort made to contact and negotiate with minority, woman or disadvantaged usiness enterprises, to include:
( )		
( )	2	Copies of written notice(s) which were sent to MBE/WBE/DBE potential subcontractors prior to bid opening;
( )	3	1 0,
( )	4	A detailed statement as to why each subcontractor contacted (a) was not willing to do the job
( )	5	( ) = Barrer Francisco Fra
( )	6	efforts were made to reach an agreement on a competitive price  Contractor certifies that 100% of the project is to be carried out with his/her own workforce.  No subcontractors are to be utilized

- B. The Agency may require the contractor to produce such additional information, as it deems appropriate and may obtain whatever other information it deems necessary to reach a conclusion from any source.
- C. No later than fifteen (15) days after receipt of all necessary information and documentation, a decision will be made in writing to the bidder. If the waiver request is denied, the facts upon which a denial is based will be set forth. A contractor who is dissatisfied with the decision may then appeal that decision to the Equal Opportunity Employment Agency.

## Certification

The undersigned herewith certified that the above information and appropriate attachments are true and accurate to the best of my ability, and that I have been authorized to act on behalf of the bidder in this matter.	е

Submit to:

**Equal Employment Opportunity** 

(Authorized original signature)

Compliance Officer

133 William Street, Room 208 New Bedford, MA 02740

To be completed by the C	City of New Bedford's EEO
	Bid Date
Date Received by EEO	 Initials

Date

# NOTICE REGARDING RESPONSIBLE EMPLOYER ORDINANCE (REO) <u>CITY OF NEW BEDFORD</u>

**DATE:** October 21, 2016

TO: ALL POTENTIAL BIDDERS

FROM: OFFICE OF PROCUREMENT

Pursuant to the Federal Court decisions in <u>UCANE</u>, et al. v. City of Worcester, U.S. District Court (D. Mass 2002) Civ. Action 02-11877-NG, <u>Fernandes Masonry, Inc. v. City of Taunton</u>, U.S. District Court (D. Mass 2010) Civ. Action 1:2010-cv-10753-JRT, <u>UCANE</u>, et al. v. City of Fall River, U.S. District Court (D. Mass 2011) Civ. Action 10-10994-RWZ and the current 1<sup>st</sup> Circuit appeal stemming from the decision in <u>Merit Construction Alliance</u>, et al. v. City of Quincy, U. S. District Court (D. Mass 2013) Civ. Action 12-10458-RWZ, under the advisement of the City's Law Department, per Order of the City Solicitor, effective immediately, the City of New Bedford's Office of Procurement will not enforce the following sections of the City's "Responsible Employer Ordinance."

The City is temporarily suspending the enforcement of these sections because of the above referenced legal precedent. However, the City believes that the ultimate goals reflected in the REO are important and the City encourages voluntary compliance with the spirit of these provisions. Moreover, the City will monitor all contractors who are awarded contracts to determine whether they are making a good faith effort to abide by the spirit of these provisions. Moving forward, the City is particularly interested in ensuring that the hiring and training of the local workforce is a top priority on all City projects. The City is willing to work closely with all successful bidders by assisting them in identifying viable well-trained workers who are residents of the City of New Bedford.

The sections listed below will not be enforced at this time. All other sections of the City Ordinance will be strictly enforced.

## **Section 10-76:**

In order to assist to the unemployment rate, to assist the problem of businesses leaving the region, to decrease the number of businesses filing bankruptcy, to combat the recession in the region, to assist the problem caused by the reduction of local aid from the commonwealth and to assist in preventing the depletion of the tax base, all general and subcontractors constructing or rehabilitating public works projects which have a projected cost of more than one hundred thousand dollars (\$100,000.00) and are funded in full or in part with federal, state, or city funds, shall have the worker hours on a craft by craft basis performed by residents of the City of New Bedford, who shall comprise at

least fifty (50) percent of the total employee man-hours in each trade, excluding the employer's foreman or supervisor and two (2) other key employees.

## **Section 10-76 (4):**

Any person who provides false information regarding his or her residence shall be penalized three hundred dollars (\$300.00): Any contractor or subcontractor who violates the provisions of this section shall be penalized three hundred dollars (\$300.00) per day for each and every day the ordinance is in violation. Said penalty shall be levied and withheld from payments due the contractor or subcontractor.

### Section 10-77 (a)(3):

The bidder and all subcontractors under the bidder must maintain or participate in a bona fide apprentice training program, as defined by M.G.L.A. c. 23, §§ 11H and 11I, for each apprenticeable trade or occupation represented in their workforce that is approved by the division of apprentice training of the department of labor and industries and must abide by the apprentice to journeyman ratio for each trade prescribed therein in the performance of the contract.

## Section 10-77 (a)(4)

The bidder and all subcontractors under the bidder must furnish, at their expense, hospitalization and medical benefits for all their employees employed on the project and/or coverage at least comparable in value to the hospitalization and medical benefits provided by the health and welfare plans in the applicable craft recognized by M.G.L.A c. 149 § 26, in establishing minimum wage rates.



# THE COMMONWEALTH OF MASSACHUSETTS OFFICE OF THE ATTORNEY GENERAL

ONE ASHBURTON PLACE
BOSTON, MASSACHUSETTS 02108

(617) 727-2200 www.mass.gov/ago

May 23, 2011

In re:	ATTORNEY GENERAL
City of Gloucester:	
Vehicle Exhaust System )	BUSINESS AND LABOR
)	BUREAU
and )	
Air Cleaning Specialists of New )	
England, LLC )	BID PROTEST DECISION
Protestor )	
)	

#### INVESTIGATION SUMMARY

Pursuant to M.G.L. c. 149, § 44H, the undersigned conducted an investigation of the captioned matter to determine whether any violation of the Massachusetts public bidding laws had occurred with respect to the City of Gloucester's ("City") procurement of a Vehicle Exhaust System for its Fire Department ("project"). As part of this investigation, a hearing was held on April 25, 2011. The Protestor, Air Cleaning Specialists of New England, LLC ("ACS") argues that the City violated the competitive bidding laws because: 1) it did not execute a contract with low bidder Murphy Specialty, Inc. ("Murphy") within 30 days of the bid opening; 2) Murphy did not proceed with the

work within ten days of signing the contract; 3) Murphy did not complete the work within 30 days; 4) Murphy did not provide a payment bond at the time of bidding; 5) Murphy does not store parts in New England, and 6) Murphy does not meet the requirements of the specifications. The City argues that the issues raised by ACS all relate to contract performance and not bid responsiveness. The City also argues that Murphy's submittals meet the specifications.

ACS and representatives of the City attended the hearing and presented testimony and evidence. Further argument and documents were received on April 29, May 4, May 5, May 16 and May 17 and the record then closed.

For the reasons that follow, I find that the City did not violate the competitive bidding laws. The Protest is therefore, Denied, as set forth below.

#### STATEMENT OF THE FACTS

Two bids for the project were received on January 26, 2011. Murphy was the lowest bidder at \$16,000 and ACS was the other bidder at \$16,123. The estimate for the project was \$23,000. The contract was awarded to Murphy and was executed on March 11, 2011, 31 days from the bid opening, excluding Saturdays, Sundays and legal holidays. Murphy received the executed contract on March 24, 2011.

The contract provides that Murphy shall begin work within ten days of the execution of the contract, and complete the work within 30 days of the execution of the contract. Murphy ordered materials for the contract on March 25, 2011. The work has not been completed within the 30 day time period.

The bid specifications state that the successful bidder will be required to provide a payment bond for fifty percent of the contract price. There is no date set in the specifications for the provision of the bond. Murphy provided the payment bond on April 25, 2011, after the Protest was filed. ACS argues that Murphy did not include the bond premium in its bid. However, ACS provided no evidence to support this allegation.

The bid specifications also state that the contractor must stock parts in New England. The City argues that there is no timeline included in this provision of the specifications and that it was meant to cover repair and maintenance, and not the initial installation of the system.

The specifications for the project required the bidders to indicate whether they took any "exceptions" to any of the specifications. ACS points out that Murphy took no exceptions to the specifications in its bid. ACS argues, however, that Murphy does not meet the requirements of the specifications because it did not include any mention of an 8 inch pneumatic nozzle for the Pierce ladder truck in its submittals. The City argues that the part listed in Murphy's submittals can be used without voiding the Pierce warranty. ACS also argues that Murphy's submittals do not include an *adjustable* safety disconnect mechanism. The City argues that Murphy's submittals include a safety disconnect mechanism.

## **ANALYSIS**

In Signet Electronic Systems, Inc. v. Marshfield Housing Authority, Attorney
General Bid Protest Decision (January 5, 2000), we held that a c. 149 contract awarded
31 days after the opening of the bids was valid. We reasoned that "statutory provisions
that 'relate [] only to the time of performance of a duty by a public officer and do not go

to the essence of the thing to be done' are considered to be directory and not mandatory." *Accord: ACS v. Plymouth, Attorney General Bid Protest Decision (February* 23, 2009).

The City argues that Murphy started the contract within ten days of the signing of the contract. The City provided evidence to support this, including emails that established that Murphy ordered materials for the project the day after it signed the contract.

Regardless, this is matter of contract compliance, and not a matter of bid responsiveness.

So, too, is the contract provision stating that the work should be completed within 30 days. The bidding laws are not implicated in these issues and accordingly, this office has no jurisdiction over them.

Turning to the question of the payment bond, it is essential to note that the payment bond was not required by statute, see M.G.L. c. 30, § 39M(c) (bond required for projects over \$25,000), but rather, by the specifications. The provision of a bond was therefore not part of the statutory definition of a "responsible bidder." Compare *Murphy Specialty v. Truro*, Attorney General Bid Protest Decision (January 18, 2011) (seasoned bidder should have been aware of and complied with statutory payment bond requirement since the procurement was over \$25,000). However, since the City included the bond in the bidding requirements and it affects price and fair competition, it would not have been permissible to waive the bond requirement. Accordingly, Murphy is presumed to have bid with the expectation of having to submit a bond. The City correctly points out that there is no time frame spelled out in the specifications for the provision of the payment bond. It was, therefore, permissible for the City to accept Murphy's bond submitted on April 25, 2011.

The City also correctly argues that there is no timeline included in the specification that calls for parts to be stored in New England. Murphy could presumably store parts for the system in New England for repair and maintenance and warranty work and not prior to the installation of the system.

Finally, ACS argues that Murphy does not meet the specifications because it did not include an 8 inch nozzle and an adjustable quick release valve in its submittals. ACS appears to be arguing that the ability of a contractor to offer an equal product or system is forfeited if exceptions are not taken to the specifications at bid time. However, the exceptions method contained in the specifications does not supplant the statutory right to offer an equal product or system post-bid and a bidder should not be rejected for failing to take exceptions and then offering an equal product or system. See M.G.L. c. 30, § 39M(b):

Every such contract shall provide that an item equal to that named or described in the said specifications may be furnished; and an item shall be considered equal to the item so named or described if, in the opinion of the awarding authority: (1) it is at least equal in quality, durability, appearance, strength and design, (2) it will perform at least equally the function imposed by the general design for the public work being contracted for or the material being purchased, and (3) it conforms substantially, even with deviations, to the detailed requirements for the item in the said specifications.

The bidder who proposes an equal product bears the risk that the awarding authority will reject the proposed equal, and will require the bidder to provide the product or system delineated in the specifications. See *E.A. Berman v. Marlborough*, 11

Mass.App.Ct. 1009, 1010 (1981). To the extent, if any, that Murphy's submittals do not comply with the specifications, there is no basis for automatically rejecting Murphy's bid. The City must require the bidder to install a product or system that it deems consistent with the specifications as a matter of contract compliance.

For the foregoing reasons, the Protest is Denied.

Respectfully submitted,

Deborah A. Anderson

Assistant Attorney General

<sup>&</sup>lt;sup>1</sup> It should be noted that the City takes the position that Murphy's submittals comply with the specifications. We will not second-guess the City in this regard.



## WPA Form 5 - Order of Conditions

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDE
SE049-0871
MassDEP File #

eDEP Transaction # New Bedford City/Town

Δ	Gen	eral	Inf	orr	nat	ion
<b>~</b> .	<b>MCII</b>	Clai		OII	Hat	1011

Please note: this form has been modified with added space to accommodate the Registry of Deeds Requirements New Bedford

Conservation Commission

This issuance is for (check one):

a. Order of Conditions

b. Amended Order of Conditions

3. To: Applicant:

1. From:

Important:
When filling
out forms on
the
computer,
use only the
tab key to
move your
cursor - do
not use the
return key.





Shawn	Syde	
a. First Name	b. Last Name	
City of New Bedford		
c. Organization		
1105 Shawmut Avenue		
d. Mailing Address		
New Bedford	MA	02746
e. City/Town	f. State	g. Zip Code

. Organization		
l. Mailing Address		
e. City/Town	f. State	g. Zip Code

b. Last Name

5. Project Location:

a. First Name

1000 South Rodney French Boulevard	New Bedford
a. Street Address	b. City/Town
002	002
c. Assessors Map/Plat Number	d. Parcel/Lot Number

Latitude and Longitude, if known:

d. Parcel/Lot Number

42d51m88s -70d89m17s

d. Latitude e. Longitude



## **WPA Form 5 – Order of Conditions**

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by	MassDEP:
SE049-087	1
MassDEP Fil	e #
eDEP Transa	action #
New Bedfo	ord
City/Town	

## A. General Information (cont.)

Bristol							
a. County				b. Certificate Nun	nber (i	f registered land)	
2941				253			
c. Book				d. Page			
Datas	6/1/2021			15/2021		6/16/2021	
Dates:	a. Date Notice of Inter	nt File	d b.	Date Public Hearing C	losed	c. Date of Issuance	
as need	Final Approved Plans and Other Documents (attach additional plan or document references as needed):						
	ber Pier - Stone Masc	nry l	Rehabilitati	on			
a. Plan Ti				5			
b. Prepar	Bond Inc.			Dennis Moran	maad	hu	
5/20/20				c. Signed and Sta	mped	Бу	
	evision Date			e. Scale			
f. Addition	nal Plan or Document Title					g. Date	
Findi	nae						
Followir provide the area	d in this application ar	bove nd pr	referenced resented at ed is signifi	d Notice of Intent a the public hearing cant to the followi	and b	pased on the information is Commission finds that iterests of the Wetlands	
	olic Water Supply b.			taining Shellfish	C.	☐ Prevention of Pollution	
☐ Priv	rate Water Supply e.	$\boxtimes$	Fisheries		f.	Protection of Wildlife Habitat	
☐ Gro	undwater Supply h.	$\boxtimes$	Storm Da	mage Prevention	i.		
This Co	mmission hereby finds	the p	oroject, as p	proposed, is: (chec	k one	e of the following boxes)	
proved s	subject to:						
		lands	s regulation	s. This Commissi	on o	h the performance rders that all work shall ove, the following	



## **WPA Form 5 – Order of Conditions**

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP:
SE049-0871
MassDEP File #

eDEP Transaction #
New Bedford
City/Town

## B. Findings (cont.)

Order.

De	nied because:
b.	the proposed work cannot be conditioned to meet the performance standards set forth in the wetland regulations. Therefore, work on this project may not go forward unless and until a new Notice of Intent is submitted which provides measures which are adequate to protect the interests of the Act, and a final Order of Conditions is issued. A description of the performance standards which the proposed work cannot meet is attached to this

C.	the information submitted by the applicant is not sufficient to describe the site, the work
	or the effect of the work on the interests identified in the Wetlands Protection Act.
	Therefore, work on this project may not go forward unless and until a revised Notice of
	Intent is submitted which provides sufficient information and includes measures which are
	adequate to protect the Act's interests, and a final Order of Conditions is issued. A
	description of the specific information which is lacking and why it is necessary is
	attached to this Order as per 310 CMR 10.05(6)(c).

3	☐ Buffer Zone Impacts: Shortest distance between limit of project	
0.	disturbance and the wetland resource area specified in 310 CMR 10.02(1)(a)	a. linear feet

## Inland Resource Area Impacts: Check all that apply below. (For Approvals Only)

Re	esource Area	Proposed Alteration	Permitted Alteration	Proposed Replacement	Permitted Replacement
4.	Bank	a. linear feet	b. linear feet	c. linear feet	d. linear feet
5.	☐ Bordering				
6.	Vegetated Wetland  Land Under	a. square feet	b. square feet	c. square feet	d. square feet
	Waterbodies and Waterways	a. square feet	b. square feet	c. square feet	d. square feet
		e. c/y dredged	f. c/y dredged		
7.	☐ Bordering Land Subject to Flooding	a. square feet	b. square feet	c. square feet	d. square feet
	Cubic Feet Flood Storage	e. cubic feet	f. cubic feet	g. cubic feet	h. cubic feet
8.	☐ Isolated Land Subject to Flooding	a. square feet	b. square feet		
	Cubic Feet Flood Storage	c. cubic feet	d. cubic feet	e. cubic feet	f. cubic feet
9.	☐ Riverfront Area	a. total sq. feet	b. total sq. feet		
	Sq ft within 100 ft	c. square feet	d. square feet	e. square feet	f. square feet
	Sq ft between 100- 200 ft	g. square feet	h. square feet	i. square feet	j. square feet



## **WPA Form 5 – Order of Conditions**

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP: SE049-0871 MassDEP File # eDEP Transaction # New Bedford City/Town

## B. Findings (cont.)

Coastal Resource Area Impacts: Check all that apply below. (For Approvals Only)

		Proposed Alteration	Permitted Alteration	Proposed Replacement	Permitted Replacement
10.	☐ Designated Port Areas	Indicate size u	ınder Land Unde	er the Ocean, be	low
11.	<b>—</b>	25	25		
	Ocean	a. square feet	b. square feet		
		3	3		
		c. c/y dredged	d. c/y dredged		
12.	☐ Barrier Beaches	Indicate size u below	ınder Coastal Be	eaches and/or Co	pastal Dunes
13.	☐ Coastal Beaches			cu yd	cu yd
13.	Coastal Beaches	a. square feet	b. square feet	c. nourishment	d. nourishment
14.	☐ Coastal Dunes			cu yd	cu yd
17.	Coastal Bulles	a. square feet	b. square feet	c. nourishment	d. nourishment
15.	Coastal Banks		V		
10.		a. linear feet	b. linear feet		
16.	☐ Rocky Intertidal				
	Shores	a. square feet	b. square feet		
17.	☐ Salt Marshes				
		a. square feet	b. square feet	c. square feet	d. square feet
18.	Land Under Salt				
	Ponds	a. square feet	b. square feet		
		o ob drodgod	d. c/y dredged		
	□	c. c/y dredged	a. c/y areagea		
19.	Land Containing	a equare feet	h aguara faat	a aguara faat	d aguara fact
	Shellfish	a. square feet	b. square feet	c. square feet	d. square feet
20.	☐ Fish Runs	Indicate size u	nder Coastal Ba	anks, Inland Bank	k, Land Under
		the Ocean, an	d/or inland Land	Under Waterboo	dies and
		Waterways, at	oove		
		a. c/y dredged	b. c/y dredged		
21.	□ Land Subject to	25	25		
۷١.	Coastal Storm	a. square feet	b. square feet		
	Flowage	a. oquaro root	b. oqualo loot		
	90				
	1				
22.	☐ Riverfront Area	a. total sq. feet	b. total sq. feet		
		a. total sq. root			
	Sq ft within 100 ft	c. square feet	d. square feet	e. square feet	f. square feet
	Sq ft between 100-	o. 545210 1001		o. oqualo 1000	1
	200 ft	g. square feet	h. square feet	i. square feet	j. square feet
					. ■ A CONTROL (CONTROL CONTROL CONTRO



## WPA Form 5 – Order of Conditions

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by	MassDEP
SE049-08	71
MassDEP F	ile #

eDEP Transaction #
New Bedford
City/Town

## B. Findings (cont.)

ĺ
,

23.	Restoration/Enhancement *:	
	a. square feet of BVW	b. square feet of salt marsh
24.	☐ Stream Crossing(s):	
	a. number of new stream crossings	b. number of replacement stream crossings

## C. General Conditions Under Massachusetts Wetlands Protection Act

## The following conditions are only applicable to Approved projects.

- 1. Failure to comply with all conditions stated herein, and with all related statutes and other regulatory measures, shall be deemed cause to revoke or modify this Order.
- amount here. 2. The Order does not grant any property rights or any exclusive privileges; it does not authorize any injury to private property or invasion of private rights.
  - 3. This Order does not relieve the permittee or any other person of the necessity of complying with all other applicable federal, state, or local statutes, ordinances, bylaws, or regulations.
  - 4. The work authorized hereunder shall be completed within three years from the date of this Order unless either of the following apply:
    - a. The work is a maintenance dredging project as provided for in the Act; or
    - b. The time for completion has been extended to a specified date more than three years, but less than five years, from the date of issuance. If this Order is intended to be valid for more than three years, the extension date and the special circumstances warranting the extended time period are set forth as a special condition in this Order.
    - c. If the work is for a Test Project, this Order of Conditions shall be valid for no more than one year.
  - 5. This Order may be extended by the issuing authority for one or more periods of up to three years each upon application to the issuing authority at least 30 days prior to the expiration date of the Order. An Order of Conditions for a Test Project may be extended for one additional year only upon written application by the applicant, subject to the provisions of 310 CMR 10.05(11)(f).
  - 6. If this Order constitutes an Amended Order of Conditions, this Amended Order of Conditions does not extend the issuance date of the original Final Order of Conditions and the Order will expire on 6/16/2024 unless extended in writing by the Department.
  - 7. Any fill used in connection with this project shall be clean fill. Any fill shall contain no trash, refuse, rubbish, or debris, including but not limited to lumber, bricks, plaster, wire, lath, paper, cardboard, pipe, tires, ashes, refrigerators, motor vehicles, or parts of any of the foregoing.



## WPA Form 5 – Order of Conditions

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP: SE049-0871 MassDEP File #

eDEP Transaction # New Bedford City/Town

## C. General Conditions Under Massachusetts Wetlands Protection Act

- 8. This Order is not final until all administrative appeal periods from this Order have elapsed, or if such an appeal has been taken, until all proceedings before the Department have been completed.
- 9. No work shall be undertaken until the Order has become final and then has been recorded in the Registry of Deeds or the Land Court for the district in which the land is located, within the chain of title of the affected property. In the case of recorded land, the Final Order shall also be noted in the Registry's Grantor Index under the name of the owner of the land upon which the proposed work is to be done. In the case of the registered land, the Final Order shall also be noted on the Land Court Certificate of Title of the owner of the land upon which the proposed work is done. The recording information shall be submitted to the Conservation Commission on the form at the end of this Order, which form must be stamped by the Registry of Deeds, prior to the commencement of work.
- A sign shall be displayed at the site not less then two square feet or more than three square feet in size bearing the words,

"Massachusetts Department of Environmental Protection" [or, "MassDEP"]

"File Number

SE049-0871 "

- 11. Where the Department of Environmental Protection is requested to issue a Superseding Order, the Conservation Commission shall be a party to all agency proceedings and hearings before MassDEP.
- 12. Upon completion of the work described herein, the applicant shall submit a Request for Certificate of Compliance (WPA Form 8A) to the Conservation Commission.
- 13. The work shall conform to the plans and special conditions referenced in this order.
- 14. Any change to the plans identified in Condition #13 above shall require the applicant to inquire of the Conservation Commission in writing whether the change is significant enough to require the filing of a new Notice of Intent.
- 15. The Agent or members of the Conservation Commission and the Department of Environmental Protection shall have the right to enter and inspect the area subject to this Order at reasonable hours to evaluate compliance with the conditions stated in this Order, and may require the submittal of any data deemed necessary by the Conservation Commission or Department for that evaluation.
- 16. This Order of Conditions shall apply to any successor in interest or successor in control of the property subject to this Order and to any contractor or other person performing work conditioned by this Order.



## **WPA Form 5 – Order of Conditions**

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP: SE049-0871 MassDEP File #

eDEP Transaction #
New Bedford
City/Town

## C. General Conditions Under Massachusetts Wetlands Protection Act (cont.)

- 17. Prior to the start of work, and if the project involves work adjacent to a Bordering Vegetated Wetland, the boundary of the wetland in the vicinity of the proposed work area shall be marked by wooden stakes or flagging. Once in place, the wetland boundary markers shall be maintained until a Certificate of Compliance has been issued by the Conservation Commission.
- 18. All sedimentation barriers shall be maintained in good repair until all disturbed areas have been fully stabilized with vegetation or other means. At no time shall sediments be deposited in a wetland or water body. During construction, the applicant or his/her designee shall inspect the erosion controls on a daily basis and shall remove accumulated sediments as needed. The applicant shall immediately control any erosion problems that occur at the site and shall also immediately notify the Conservation Commission, which reserves the right to require additional erosion and/or damage prevention controls it may deem necessary. Sedimentation barriers shall serve as the limit of work unless another limit of work line has been approved by this Order.

19.	The wo	rk associated with this Order (the "Project")
	(1)	is subject to the Massachusetts Stormwater Standards
	(2)	is NOT subject to the Massachusetts Stormwater Standards

## If the work is subject to the Stormwater Standards, then the project is subject to the following conditions:

- a) All work, including site preparation, land disturbance, construction and redevelopment, shall be implemented in accordance with the construction period pollution prevention and erosion and sedimentation control plan and, if applicable, the Stormwater Pollution Prevention Plan required by the National Pollution Discharge Elimination System Construction General Permit as required by Stormwater Condition 8. Construction period erosion, sedimentation and pollution control measures and best management practices (BMPs) shall remain in place until the site is fully stabilized.
- b) No stormwater runoff may be discharged to the post-construction stormwater BMPs unless and until a Registered Professional Engineer provides a Certification that:

  i. all construction period BMPs have been removed or will be removed by a date certain specified in the Certification. For any construction period BMPs intended to be converted to post construction operation for stormwater attenuation, recharge, and/or treatment, the conversion is allowed by the MassDEP Stormwater Handbook BMP specifications and that the BMP has been properly cleaned or prepared for post construction operation, including removal of all construction period sediment trapped in inlet and outlet control structures;

  ii. as-built final construction BMP plans are included, signed and stamped by a Registered Professional Engineer, certifying the site is fully stabilized;

  iii. any illicit discharges to the stormwater management system have been removed, as per

*iii.* any illicit discharges to the stormwater management system have been removed, as per the requirements of Stormwater Standard 10;



## **WPA Form 5 – Order of Conditions**

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP: SE049-0871 MassDEP File #

eDEP Transaction # New Bedford City/Town

## C. General Conditions Under Massachusetts Wetlands Protection Act (cont.)

iv. all post-construction stormwater BMPs are installed in accordance with the plans (including all planting plans) approved by the issuing authority, and have been inspected to ensure that they are not damaged and that they are in proper working condition;

- v. any vegetation associated with post-construction BMPs is suitably established to withstand erosion.
- c) The landowner is responsible for BMP maintenance until the issuing authority is notified that another party has legally assumed responsibility for BMP maintenance. Prior to requesting a Certificate of Compliance, or Partial Certificate of Compliance, the responsible party (defined in General Condition 18(e)) shall execute and submit to the issuing authority an Operation and Maintenance Compliance Statement ("O&M Statement) for the Stormwater BMPs identifying the party responsible for implementing the stormwater BMP Operation and Maintenance Plan ("O&M Plan") and certifying the following:
  - i.) the O&M Plan is complete and will be implemented upon receipt of the Certificate of Compliance, and
  - ii.) the future responsible parties shall be notified in writing of their ongoing legal responsibility to operate and maintain the stormwater management BMPs and implement the Stormwater Pollution Prevention Plan.
- d) Post-construction pollution prevention and source control shall be implemented in accordance with the long-term pollution prevention plan section of the approved Stormwater Report and, if applicable, the Stormwater Pollution Prevention Plan required by the National Pollution Discharge Elimination System Multi-Sector General Permit.
- e) Unless and until another party accepts responsibility, the landowner, or owner of any drainage easement, assumes responsibility for maintaining each BMP. To overcome this presumption, the landowner of the property must submit to the issuing authority a legally binding agreement of record, acceptable to the issuing authority, evidencing that another entity has accepted responsibility for maintaining the BMP, and that the proposed responsible party shall be treated as a permittee for purposes of implementing the requirements of Conditions 18(f) through 18(k) with respect to that BMP. Any failure of the proposed responsible party to implement the requirements of Conditions 18(f) through 18(k) with respect to that BMP shall be a violation of the Order of Conditions or Certificate of Compliance. In the case of stormwater BMPs that are serving more than one lot, the legally binding agreement shall also identify the lots that will be serviced by the stormwater BMPs. A plan and easement deed that grants the responsible party access to perform the required operation and maintenance must be submitted along with the legally binding agreement.
- f) The responsible party shall operate and maintain all stormwater BMPs in accordance with the design plans, the O&M Plan, and the requirements of the Massachusetts Stormwater Handbook.



## WPA Form 5 – Order of Conditions

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP: SE049-0871 MassDEP File #

eDEP Transaction # New Bedford City/Town

## C. General Conditions Under Massachusetts Wetlands Protection Act (cont.)

- g) The responsible party shall:
  - Maintain an operation and maintenance log for the last three (3) consecutive calendar years of inspections, repairs, maintenance and/or replacement of the stormwater management system or any part thereof, and disposal (for disposal the log shall indicate the type of material and the disposal location);
  - Make the maintenance log available to MassDEP and the Conservation Commission ("Commission") upon request; and
  - Allow members and agents of the MassDEP and the Commission to enter and
    inspect the site to evaluate and ensure that the responsible party is in compliance
    with the requirements for each BMP established in the O&M Plan approved by the
    issuing authority.
- h) All sediment or other contaminants removed from stormwater BMPs shall be disposed of in accordance with all applicable federal, state, and local laws and regulations.
- i) Illicit discharges to the stormwater management system as defined in 310 CMR 10.04 are prohibited.
- j) The stormwater management system approved in the Order of Conditions shall not be changed without the prior written approval of the issuing authority.
- k) Areas designated as qualifying pervious areas for the purpose of the Low Impact Site Design Credit (as defined in the MassDEP Stormwater Handbook, Volume 3, Chapter 1, Low Impact Development Site Design Credits) shall not be altered without the prior written approval of the issuing authority.
- Access for maintenance, repair, and/or replacement of BMPs shall not be withheld.
   Any fencing constructed around stormwater BMPs shall include access gates and shall be at least six inches above grade to allow for wildlife passage.

Special Conditions (if you need more space for additional conditions, please attach a text document):

## See Special Conditions 21 -48

20. For Test Projects subject to 310 CMR 10.05(11), the applicant shall also implement the monitoring plan and the restoration plan submitted with the Notice of Intent. If the conservation commission or Department determines that the Test Project threatens the public health, safety or the environment, the applicant shall implement the removal plan submitted with the Notice of Intent or modify the project as directed by the conservation commission or the Department.



## **WPA Form 5 – Order of Conditions**

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by Massl	DEP:
SE049-0871	
MassDEP File #	
-DED T	
eDEP Transaction	#
New Bedford	
City/Town	

## D. Findings Under Municipal Wetlands Bylaw or Ordinance

1.	Is a	municipal wetlands bylaw or ordinance applicable?   Ye	s 📙 No			
2.	The	New Bedford hereby finds Conservation Commission	s (check one that applies):			
	<ul> <li>a.  that the proposed work cannot be conditioned to meet the standards set municipal ordinance or bylaw, specifically:</li> </ul>					
		Municipal Ordinance or Bylaw	2. Citation			
	Therefore, work on this project may not go forward unless and until a revised Notice of Intent is submitted which provides measures which are adequate to meet these standards, and a final Order of Conditions is issued.					
b.  that the following additional conditions are necessary to comply with a n ordinance or bylaw:						
		Wetlands Ordinance  1. Municipal Ordinance or Bylaw	Sec. 15-101 thru 15-112			
3.	conditions and with the Notice of Intent referenced above. To the extent that the following conditions modify or differ from the plans, specifications, or other proposals submitted with the Notice of Intent, the conditions shall control.					
	The special conditions relating to municipal ordinance or bylaw are as follows (if you need more space for additional conditions, attach a text document):					
	MA DEP General Conditions 1 through 20 are Special Conditions pursuant to the City of New Bedford Wetlands Ordinance (Sec. 15-101 through 15-112). In additions, see attached Special Conditions 21 - 48.					



## WPA Form 5 – Order of Conditions

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP: SE049-0871

MassDEP File #

eDEP Transaction #
New Bedford

City/Town

## E. Signatures

This Order is valid for three years, unless otherwise specified as a special condition pursuant to General Conditions #4, from the date of issuance.

Please indicate the number of members who will sign this form. This Order must be signed by a majority of the Conservation Commission.

6/16/2021

1. Date of Issuance

4

2. Number of Signers

The Order must be mailed by certified mail (return receipt requested) or hand delivered to the applicant. A copy also must be mailed or hand delivered at the same time to the appropriate Department of Environmental Protection Regional Office, if not filing electronically, and the property owner, if different from applicant.

. //		
Signature Signature	Printed Name	
Signature	Printed Name	
Signature	Printed Name	
Signature	Printed Name	
Signature	Printed Name	
Signature	Printed Name	
by hand delivery on	by certified mail, return receipt requested, on 6/16/2021	
Date	Date	



## WPA Form 5 – Order of Conditions

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP: SE049-0871

MassDEP File #

eDEP Transaction #

New Bedford

City/Town

## F. Appeals

The applicant, the owner, any person aggrieved by this Order, any owner of land abutting the land subject to this Order, or any ten residents of the city or town in which such land is located, are hereby notified of their right to request the appropriate MassDEP Regional Office to issue a Superseding Order of Conditions. The request must be made by certified mail or hand delivery to the Department, with the appropriate filing fee and a completed Request for Departmental Action Fee Transmittal Form, as provided in 310 CMR 10.03(7) within ten business days from the date of issuance of this Order. A copy of the request shall at the same time be sent by certified mail or hand delivery to the Conservation Commission and to the applicant, if he/she is not the appellant.

Any appellants seeking to appeal the Department's Superseding Order associated with this appeal will be required to demonstrate prior participation in the review of this project. Previous participation in the permit proceeding means the submission of written information to the Conservation Commission prior to the close of the public hearing, requesting a Superseding Order, or providing written information to the Department prior to issuance of a Superseding Order.

The request shall state clearly and concisely the objections to the Order which is being appealed and how the Order does not contribute to the protection of the interests identified in the Massachusetts Wetlands Protection Act (M.G.L. c. 131, § 40), and is inconsistent with the wetlands regulations (310 CMR 10.00). To the extent that the Order is based on a municipal ordinance or bylaw, and not on the Massachusetts Wetlands Protection Act or regulations, the Department has no appellate jurisdiction.



## **WPA Form 5 – Order of Conditions**

Massachusetts Wetlands Protection Act M.G.L. c. 131, §40

Provided by MassDEP: SE049-0871

MassDEP File #

eDEP Transaction # New Bedford City/Town

## G. Recording Information

Prior to commencement of work, this Order of Conditions must be recorded in the Registry of Deeds or the Land Court for the district in which the land is located, within the chain of title of the affected property. In the case of recorded land, the Final Order shall also be noted in the Registry's Grantor Index under the name of the owner of the land subject to the Order. In the case of registered land, this Order shall also be noted on the Land Court Certificate of Title of the owner of the land subject to the Order of Conditions. The recording information on this page shall be submitted to the Conservation Commission listed below.

Conservation Commission		
Detach on dotted line, have stamped by the Regist Commission.		submit to the Conservation
To:		
Conservation Commission		
Please be advised that the Order of Conditions fo	r the Project at:	
Project Location	MassDEP File Number	
Has been recorded at the Registry of Deeds of:		
County	Book	Page
for: Property Owner		
and has been noted in the chain of title of the affe	cted property in:	
Book	Page	
In accordance with the Order of Conditions issued	i on:	
Date		
If recorded land, the instrument number identifying	g this transaction	is:
Instrument Number		
If registered land, the document number identifyin	g this transaction	is:
Document Number		
Signature of Applicant		



## CITY OF NEW BEDFORD JONATHAN F. MITCHELL, MAYOR


# FORT TABER PIER REHABILITATION PROJECT TIGHE&BOND NEW BEDFORD DEPARTMENT OF PUBLIC INFRASTRUCTURE

#### SE049-0871 SPECIAL CONDITIONS

- 21. No activity shall occur prior to obtaining all necessary and required permits, licenses and approvals; and until copies of the same have been furnished to the Conservation Commission.
- 22. Any design modifications, alterations, amendments, or additions shall be subject to the approval of the New Bedford Conservation Commission. Requests for any changes shall be made in writing and shall be accompanied by a revised plan.
- No modification to surface features, drainage or topography shall be permitted except as indicated by this Order of Conditions.
- 24. There shall be no construction other than that proposed by the Notice of Intent and included on the plans.
- 25. All resource areas not to be altered shall be kept clear of rubbish, debris, and construction material.
- 26. All excess material shall be removed from the site.
- 27. The owners shall notify the Conservation Commission of the work start date prior to its commencement so that regular inspections may be made.
- 28. The inspector and/or Commission members shall have the right to enter upon the land for the purpose of the inspection and/or the taking of pictures to determine and evaluate compliance with this Order.
- All facilities and equipment shall be continually maintained so as to comply with this Order of Conditions and M.G.L. Ch. 131 S40, the Wetlands Protection Act and Regulations 310 CMR 10.00 et seq.
- 30. Certain conditions such as maintenance or monitoring are on-going and are not to expire at the end of three years or with the issuance of a Certificate of Compliance.

- 31. This Order of Conditions shall apply to any successor in interest or successor in control.
- 32. Any changes required by any other board or authority may require a new filing with the Conservation Commission.
- 33. It is the responsibility of the applicant to complete the review required by agencies with jurisdiction over the activity that is subject to this Order of Conditions and procure all required permits or approvals before work commences. These reviews, permits, and approvals may include but are not limited to:
  - The Army Corps of Engineers
  - The MA Department of Environmental Protection
  - The MA Natural Heritage and Endangered Species Program
  - · Review by local Planning Boards, Zoning Boards, Board of Health and Building Inspector.
- 34. The Conservation Commission shall not be responsible or liable for the construction, operation, or maintenance of any part of this project and does not warrant the safety of same.
- 35. Any fill or construction materials shall be placed in upland areas.
- 36. In accordance with Condition number fourteen (14), no activity shall take place until the applicant has furnished written documentation that the plans on file with the Conservation Commission are consistent with permits and approvals of other City Boards.
- 37. Prior to any construction, an on-site inspection is to be held between the proposed contractor, the engineer, and the Conservation Commission Agent to go over the sequence of construction and all other restrictions and requirements as noted on the Order of Conditions. A written construction schedule is to be received at that time.
- Any changes in proposed drainage patterns shall require the written approval of the Conservation Commission.
- Notice of Intent, Order of Conditions and approved plans shall be retained on the site during construction and made available to all contractors.
- 40. All demolition and construction debris is to be disposed of in a legal upland location.
- 41. CCA, ACA or ACQ are the approved wood preservatives, with the exception of the tops of the timber piles which shall be treated with AWPA M4 (2% copper napthenate followed by coal-tar roofing cement) or approved equivalent.
- 42. Fuel shall not be stored on site.
- 43. A spill control kit including absorbent materials shall be on site at all times.
- 44. All hydraulic equipment shall have vegetable-based non-toxic, non-polluting and biodegradable hydraulic fluid.

- 45. An as-built plan shall be submitted upon completion of project and prior to issuance of a Certificate of Compliance.
- 46. All conditions are on going and do not expire until the issuance of a Certificate of Compliance.
- 47. Deploy and maintain impermeable turbidity curtain of sufficient length and vertical depth sufficiently seaward of work area. Curtain to remain in place until work is completed.
- 48. The discharge and/or cleanout of any concrete/ grout wash water to or excess cement to New Bedford Harbor is forbidden. All cleanouts shall be in a designated upland and away from any storm drains.



#### **SECTION 01110**

#### SUMMARY OF WORK

#### PART 1 GENERAL

#### 1.1 SUMMARY

#### A. Section Includes

1. Work of the Contract is shown and described in Drawings and Project Manual entitled:

Fort Taber Pier Stone Masonry Rehabilitation

Tighe & Bond, Inc. Westfield, Massachusetts

- 2. The Work includes the following major items:
  - a. Reinstallation of dislodged stones and backfilling with flowable concrete grout.

## B. Related Requirements

1. Section 00800 - Supplementary Conditions

#### 1.2 SUBMITTALS

- A. Informational Submittals
  - 1. Submit copies of permits or approvals required for the Work, prior to initiating the Work.

### 1.3 EXISTING DESCRIPTION

A. The pier has sustained localized damage to an area of the supporting wall that needs to be repaired. Existing stones can be restacked to rebuild the wall of the pier.

#### 1.4 PROJECT/SITE CONDITIONS

#### A. Permits

- 1. Obtain the permits and approvals listed below:
  - a. Permits and licenses of a temporary nature necessary to perform the Work.
  - b. Permits for disposal of construction wastes including disposal of cleared and grubbed materials.
  - c. Other permits or licenses required for the Contractor's operations or required elsewhere in the Contract Documents and not included herein.
- 2. Comply with the permits and approvals listed below:
  - a. City of New Bedford Conservation Commission Order of Conditions. A copy of the Order of Conditions is included in Section 00800.

- 3. Obtain required time extensions to permits obtained by the Contractor, if construction authorized by permits has not been completed by the expiration date noted on these permits.
- 4. Permits require that a representative of the permitting authority or the Owner be present on site during construction or given the opportunity to observe conditions prior to backfilling or otherwise proceeding with construction. Notify the Owner, Engineer, and the permitting authority prior to performing Work that is governed by the permit.
- 5. Submit copies of permits prior to performance of Work authorized by permits.

### B. Existing Conditions

- 1. Use of Premises and Off-site Work
  - a. The Work shall occur on the Owner's property and temporary easements obtained by the Owner within the limits of Work shown on the Drawings.
  - b. Land owned by the Owner is available for staging. Coordinate with City of New Bedford DPI for stanging location.
  - c. Obtain permits and approvals for use of any land and access thereto that is deemed necessary for the Work, where such land is not available for use by the Owner, including land for temporary construction facilities, access and egress, or for storage of materials. Confine apparatus and storage to such additional areas.
  - d. Obtain permits and written approvals from appropriate jurisdictional agencies for the use of premises not available for use by the Owner, including all offsite staging areas, borrow pits and waste areas. Submit copies of all permits and approvals to the Owner prior to using areas.
  - e. Provide for the disposal of waste materials off-site in accordance with all applicable laws.
  - f. Adhere to the limits of Work as indicated, to minimize obstruction to traffic and inconvenience to the Owner, general public, and residents in the vicinity of the Work, and to protect people and property. Keep fire hydrants on or adjacent to the Work accessible to fire fighting equipment at all times.
  - g. Make temporary provisions for the use of sidewalks and maintain functioning gutters, stormwater systems, drainage ditches, and culverts.
  - h. Maintain public access to businesses and residences including driveways and parking lots at all times during the Work.

#### PART 2 PRODUCTS

#### 2.1 MATERIALS FURNISHED BY OWNER

A. The Owner will not furnish any materials, labor or equipment under this Contract, however, existing stones that have dislodged from the pier shall be used for the repair.

#### PART 3 EXECUTION – NOT USED

**END OF SECTION** 

## Tighe&Bond

 $\hbox{\tt J:} \\ \hbox{\tt NN1011 New Bedford} \\ \hbox{\tt 007 Piers} \\ \hbox{\tt 01 - Fort Taber} \\ \hbox{\tt Specifications} \\ \hbox{\tt Fort Taber} \\ \hbox{\tt Div 1} \\ \hbox{\tt 101110.docx} \\ \hbox{\tt 101110.doc$ 

#### **SECTION 01140**

#### **WORK RESTRICTIONS**

#### PART 1 GENERAL

#### 1.1 SUMMARY

- A. Section Includes
  - 1. Work Schedule
  - 2. Construction Constraints
  - 3. Vehicle Access
  - 4. Available Work Area
  - 5. Site Usage Plan

## B. Related Requirements

1. Section 01310 - Coordination

#### 1.2 SUBMITTALS

A. Incorporate the requirements of this Section in the project schedule submitted under Section 01325.

#### 1.3 WORK SCHEDULE

- A. Conduct the Work during daylight hours on Monday through Friday, and within the time between 7:00 a.m. and 5:00 p.m. No work is to be done on Owner's holidays, Saturdays, Sundays or outside of the work hours described above. If required, work can occur outside these times with 48 hours prior written notice to the City and Engineer.
- B. If the Contractor would like to work outside the times listed above to better work the expected tide cycles the Contractor must provide prior authorization by the Owner.

#### PART 2 PRODUCTS – NOT USED

#### PART 3 EXECUTION

#### 3.1 CONSTRUCTION CONSTRAINTS

- A. The following are constraints for the Work. Incorporate these constraints into the schedule required to be submitted under Section 01325.
  - 1. Construction related to Fort Taber Pier must be completed within 120 days of Notice to Proceed.

### 3.2 VEHICLE AND EQUIPMENT ACCESS AND RESTRICTIONS

- A. Weight of equipment used during work shall be limited to 250 pounds per square foot within 5 feet of the pier wall.
- B. The contractor is responsible for any and all damage to the deck of the pier. The contractor shall use Terramats (rubber mats) and or dunnage to protect the pier deck from damage from equipment.

## 3.3 AVAILABLE WORK AREA

A. Limits of construction are defined on the Drawings. No work will be permitted to be performed outside these boundaries.

## 3.4 SITE USAGE PLAN

A. Locations of available staging areas will be coordinated with the City of New Bedford DPI.

## END OF SECTION

#### **SECTION 01290**

#### APPLICATION AND CERTIFICATE FOR PAYMENT

#### PART 1 GENERAL

#### 1.1 SUMMARY

- A. Section Includes
  - 1. Definition and description of measurement and payment to be used for the Work
  - 2. Payment procedures
  - 3. Payment requests for stored materials
- B. Related Requirements
  - 1. Section 01295 Schedule of Values

#### 1.2 GENERAL

- A. The following paragraphs describe payment procedures for the work to be done under the respective items in the Bid Form.
- B. Each lump sum and unit price will be deemed to include an amount considered by the Contractor to be adequate to cover the Contractor's overhead and profit for each separately identified item.
- C. Except as provided for in Section 01295, no separate measurement or payment will be made for Work called for in Division 0 or Division 1 of the Contract Specifications, unless specifically covered under the Bid items listed below. All costs associated with this Work will be considered incidental to the Contract Bid price.
- D. Division 2 through Division 4 Work will be measured and paid for at the Contractor's unit Bid price or lump sum Bid price as indicated on the Bid form. Those payable Work items, and related prices as Bid, will be the basis for all compensation to the Contractor for Work performed under this Contract. Work not specifically included as a Bid item, but which is required to properly and satisfactorily complete the Work is considered ancillary and incidental to the Bid item Work, and payment for such Work is considered to be included in the values as Bid for payable items. Compensation for all unit Bid price Work will be made based on the measured quantity of Work under the appropriate Bid items.

#### 1.3 LUMP SUM ITEMS

A. Each lump sum price stated in the Bid form shall constitute full compensation for all labor, equipment and materials necessary and required to complete the work specified under that particular item, and also all costs for doing related work as set forth in the Contract Documents or implied in carrying out their intent.

#### ITEM 2 - MOBILIZATION AND DEMOBILIZATION

#### 1. Measurement

a. There will be no measurement of quantities for lump sum items. Periodic partial payments for this Work, included under the Agreement, shall be based on the percent completion of each work item listed in the Schedule

N1101007/10/20/21

01290-1

**Application and Certificate** 

of Values provided under Section 01295 estimated by the Contractor and approved by the Engineer.

# 2. Payment

a. Payment of the lump sum Bid price will be paid in two equal installments. The first installment will occur at the time the first payment requisition is submitted after the Contractor has initiated full-time construction activity. Payment for the second installment will be included in the first payment request after Substantial Completion has been reached and all equipment has been removed from the Site. In no case will the total of both installments exceed 5 percent of the base Bid price.

## ITEM 3 - QUALITY CONTROL

#### 1. Measurement

a. There will be no measurement of quantities for lump sum items. Periodic partial payments for this Work, included under the Agreement, shall be based on the percent completion of each work item listed in the Schedule of Values provided under Section 01295 estimated by the Contractor and approved by the Engineer.

## 2. Payment

b. Payment of the lump sum covers all work necessary to furnish all labor, equipment, and materials to collect, cure, and test cylinders.

## ITEM 4 - DEMOLITION AND REMOVAL

## 1. Measurement

a. There will be no measurement of quantities for lump sum items. Periodic partial payments for this Work, included under the Agreement, shall be based on the percent completion of each work item listed in the Schedule of Values provided under Section 01295 estimated by the Contractor and approved by the Engineer.

## 2. Payment

a. Payment of the lump sum covers all work necessary to furnish, equipment and materials to complete the demolition and removal/dislodging of the granite blocks.

## ITEM 5 - GRANITE RECONSTRUCTION

## 3. Measurement

a. There will be no measurement of quantities for lump sum items. Periodic partial payments for this Work, included under the Agreement, shall be based on the percent completion of each work item listed in the Schedule of Values provided under Section 01295 estimated by the Contractor and approved by the Engineer.

## 4. Payment

a. Payment of the lump sum covers all work necessary to furnish all labor, equipment, and materials to set the granite blocks, additional granite

blocks, drill and grout J-hooks into granite stones. This work is inclusive of all mortar, epoxy, preparation of existing conditions, and all materials necessary to set the blocks.

## 1.4 UNIT PRICE ITEMS

- A. Each unit price stated in the Bid form shall constitute full compensation for all labor, equipment and materials necessary and required to complete the Work specified under that particular item, and also all costs for doing related work as set forth in the Contract Documents or implied in carrying out their intent.
- B. Payment of the unit price items will only be made for the actual quantity of Work performed in accordance with the Contract Documents.

## ITEM 6 - CONCRETE FILL

#### 1. Measurement

a. Measurement for concrete fill excavation will be on a cubic yard basis as measured in the field by the Engineer.

# 2. Payment

- a. Payment of the bid price for concrete fill will be full compensation for all of the material, and all labor, equipment and materials required for or incidental to the work including concrete fill, pumping, curing, testing, finishing, admixtures, etc.
- 3. Make formal submittal of request for payment by filling in the agreed data, by typewriter or electronically on EJCDC C-620, Contractor's Application for Payment, plus continuation sheet or sheets.
- 4. Sign and notarize the Application for Payment.
- 5. Submit the original of the Application for Payment, plus six identical copies of the continuation sheet or sheets, to the Engineer.
- 6. The Engineer will compare the formal submittal with the approved informal submittal and, if acceptable, will sign the Contractor's Application for Payment, and present the Application to the Owner.
- 7. Provide a signed and notarized Certificate for Stored Materials and proof of storage in a dry, watertight, heated and insured warehouse facility.

## 1.5 PAYMENT REQUESTS FOR STORED MATERIALS

- A. Requests for payment for stored materials shall be made in accordance with Section 00700 and shall be accompanied by the attached "Certificate for Stored Materials" form. Payment for stored materials shall not exceed the value actually paid by the Contractor for the stored materials as evidenced by the accompanying bill of sale, invoice, or other documentation.
- B. Partial payment requests for materials stored or so-called "engineering costs" by equipment manufacturers will not be allowed. All such costs shall be distributed proportionately among the various items of equipment/hardware to be furnished.

# Tighe&Bond

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION - NOT USED

# END OF SECTION

# CERTIFICATE FOR STORED MATERIALS

Tighe & Bond Project N	lo.
We,, request payment for materials and equipment not incorporated in the work included under our firm's contract we as listed below.	or ith
We hereby certify under penalty of perjury, that the materials not incorporated in twork have been delivered and are securely stored at the site or and that we have title to said materials free and clear of Liens, as evidenced by the attached bill of sale, invoice, or other documentation.	at
Liens, as evidenced by the attached bill of sale, invoice, or other documentation.	
We also certify that an inventory of said materials and/or equipment has been compil for the purposes of this monthly partial payment request. This list of materials and equipment, including unit prices for said material not incorporated in the work for whi payment is hereby requested, consisting of pages and dated is signed and attached hereto.	or ch
We acknowledge that payments made based on this request for materials and equipment not incorporated in the work does not relieve the contractor of its responsibility furnishing all materials and equipment required for the satisfactory completion of the projection to the contractual requirements.	for
We further certify that we can and will adequately protect said materials and equipment until they are incorporated in the work; that they meet the requirements of t specifications, and that they will be needed for incorporation in the work in the near future.	
IN WITNESS WHEREOF, we, the said	h-
IN WITNESS WHEREOF, we, the said ereunto set our hand and seal this day of, 20	
Contractor's Firm Name	
SIGNED, SEALED AND DELIVERED IN THE PRESENCE OF	
By	
Title	
Notary Public	
1.0mly 1 dolle	

# SCHEDULE OF STORED MATERIALS

Job No. Contract No. Contractor: Location:				Date Pay Est	imate
Item	Description	Supplier/Manufacturer	Quantity Stored and not Incorporated	Unit \$	Certified Value
Signature:	Contractor's Principa	Total A	amount Due for Stored Materi	als	
Title:					

EJCDC≣		Contractor's A	pplication for	r Payment No.		
Application DOCUMENTS COMMITTEE  To  Application Period: From (Contractor):				Application Date:		
		Period:				
		From (Contractor):		Via (Engineer):		
(Owner):						
Project:		Contract:				
Owner's Contract No.:	Owner's Contract No.: Contractor's Project No.:			Engineer's Project No.:		
	Application For Pay	nent				
	Change Order Sumn	nary				
Approved Change Orders	_	-	1. ORIGINAL CONT	RACT PRICE	. \$	
Number	Additions	Deductions	2. Net change by Char	nge Orders	. \$	
			3. Current Contract P	Price (Line 1 ± 2)	\$	
			4. TOTAL COMPLET	TED AND STORED TO DATE	•	
			(Column F on Progr	ress Estimate)	. \$	
			5. RETAINAGE:			
			a.	XWork Completed	. \$	
			b.	X Stored Material	. \$	
			c. Total	l Retainage (Line 5a + Line 5b)	. \$	
			6. AMOUNT ELIGIB	LE TO DATE (Line 4 - Line 5c)	. \$	
TOTALS			7. LESS PREVIOUS I	PAYMENTS (Line 6 from prior Application)	. \$	
NET CHANGE BY			8. AMOUNT DUE TH	HIS APPLICATION	. \$	
CHANGE ORDERS			9. BALANCE TO FIN	ISH, PLUS RETAINAGE		
			(Column G on Progr	ress Estimate + Line 5 above)	\$	
			<b>-</b>			
Contractor's Certification						
		owledge: (1) all previous progress payments	Payment of:	\$		
		ntract have been applied on account to		(Line 8 or other - attach explanation of the	e other amount)	
discharge Contractor's legitimate obligations incurred in connection with Work covered by prior Applications for Payment; (2) title of all Work, materials and equipment incorporated in said Work or						
		t will pass to Owner at time of payment	is recommended by:		_	
free and clear of all Liens, security interests and encumbrances (except such as are covered by a Bond acceptable to Owner indemnifying Owner against any such Liens, security interest or encumbrances); and (3) all Work covered by this Application for Payment is in accordance with the Contract Documents and is not defective.				(Engineer)	(Date)	
			Payment of:	\$		
				(Line 8 or other - attach explanation of the	e other amount)	
			is approved by:		<u>.                                      </u>	
				(Owner)	(Date)	
			4			
By:		Date:	Approved by:			

Funding Agency (if applicable)

(Date)

# **Progress Estimate - Lump Sum Work**

# **Contractor's Application**

For (Contract):			Application Number:					
Application Period:			Application Date:					
			Work Co	ompleted	Е	F		G
_	A	В	С	D	Materials Presently	Total Completed	%	Balance to Finish
Specification Section No.	Description	Scheduled Value (\$)	From Previous Application (C+D)	This Period	Stored (not in C or D)	and Stored to Date (C + D + E)	(F/B)	(B - F)
		-						•
						·		
	Totals							

## SCHEDULE OF VALUES

## PART 1 GENERAL

## 1.1 SUMMARY

- A. Section Includes
  - 1. Schedule of Values

## 1.2 SUBMITTALS

- A. Action Submittals
  - 1. Submit 3 copies of the Schedule of Values for approval within 10 days after the Effective Date of the Agreement.

## 1.3 SCHEDULE OF VALUES

- A. Schedule of Values shall be a detailed breakdown of the lump sum Work items showing values allocated to the various elements of the Work.
- B. The format of the Schedule of Values shall be a breakdown by Specification Section and content and shall be submitted on EJCDC C-620, Contractor's Application for Payment. The Engineer may require additional detailed documentation to support the values in the form of executed purchase orders, subcontracts, or other agreements.
- C. The Engineer will determine the level of breakdown and detail required. The breakdown shall include materials, installation, and start-up for equipment and controls where applicable. The final document will be the basis of payment requests for the duration of the Contract. No progress payment will be made until the Schedule of Values is approved by the Engineer.
- D. An unbalanced Schedule of Values providing overpayment on items of work performed first will not be accepted.
- PART 2 PRODUCTS NOT USED
- PART 3 EXECUTION NOT USED

#### **END OF SECTION**

 $\label{thm:linear} $$ \left( 0.07 \, Piers \ - Fort \, Taber \ Projects \ N\ 1011 \, New \, Bedford \ 0.07 \, Piers \ - Fort \, Taber \ Projects \ N\ 101295. docx \\ $\left( 0.07 \, Piers \ 1.01295. docx \, Piers \ 1.01295. docx \, Piers \ 1.01295. docx \\ $\left( 0.07 \, Piers \ 1.01295. docx \, Piers \ 1.01295. docx \, Piers \ 1.01295. docx \\ $\left( 0.07 \, Piers \ 1.01295. docx \, Piers \ 1.01295. docx \, Piers \ 1.01295. docx \\ $\left( 0.07 \, Piers \ 1.01295. docx \\ $\left( 0.07 \, Piers \ 1.01295. docx \\ $\left( 0.07 \, Piers \ 1.01295. docx \\ $\left( 0.07 \, Piers \ 1.01295. docx \, Piers \ 1.01$ 

## **COORDINATION**

## PART 1 GENERAL

## 1.1 SUMMARY

- A. Section Includes
  - 1. Project Management
  - 2. Coordination
  - 3. Project Meetings
- B. Related Requirements
  - 1. Section 01140 Work Restrictions
  - 2. Section 01325 Scheduling of Construction

## C. Related Work Not Included

 Operation of existing facilities will be performed by the Owner unless otherwise specified. The Owner will assist in arranging operation of any existing facilities or equipment required by the Contractor to connect to existing facilities, and the Contractor shall not operate existing valves or equipment. Only the Owner will operate Owner valves.

#### 1.2 SUBMITTALS

A. Incorporate the requirements of this Section, as well as Work which may impact the existing system operation, or the operations of any adjacent utility, in the project schedule submitted under Section 01325.

## B. Informational Submittals

- 1. Submit to the affected utility company, the Owner, and the Engineer, in writing, all requests for temporary shutdowns of facilities or interruption of operations. Submit requests at least 2 weeks prior to the beginning of the Work requiring shutdown or interruption. No shutdown shall occur without the approval of the utility company or the Owner.
- 2. At the pre-construction conference, supply to the Owner the cell phone number of a responsible person who may be contacted during off-hours for emergencies 24 hours a day, seven days a week.
- 3. Prepare a contact list of phone numbers, including cell phone numbers, and emails for all Project personnel and submit to the Engineer at the pre-construction conference. Include Contractor, Owner, Engineer, and New Bedford personnel including police, fire, and ambulance.

## 1.3 PROJECT MANAGEMENT

A. Retain a full-time Superintendent, satisfactory to the Owner and Engineer. The Superintendent shall not be changed except with the consent of the Owner and Engineer. The Superintendent shall be in full charge of the Work.

B. Complete the Work in a continuous uninterrupted operation. Use sufficient personnel and adequate equipment to complete the Work within the Contract Time.

## 1.4 COORDINATION

A. Perform all coordination necessary to complete the work as required.

#### 1.5 PROJECT MEETINGS

## A. Pre-Construction Conference

- 1. The Contractor shall be prepared to discuss the following subjects at the Pre-Construction Conference. Documentation for these items is required to be submitted within the time frames included in individual specification sections.
  - a. Project scheduling
  - b. Sequencing of critical path Work items
  - c. Shop Drawing procedures
  - d. Project changes and clarification procedures
  - e. Use of sites, access to Work areas, office and storage areas, security and temporary facilities
  - f. Contractor safety plan and representative
  - g. Progress payments and procedures
  - h. Required documentation
  - i. Project personnel contact list

## PART 2 PRODUCTS - NOT USED

#### PART 3 EXECUTION

#### 3.1 GENERAL

A. Notify DIGSAFE at 1-888-344-7233 at least 72 hours prior to any digging, trenching, rock removal, demolition, borings, backfill, grading, landscaping, or any other earth moving operations.

## 3.2 COORDINATION WITH THE OWNER'S OPERATIONS

- A. Notify the Owner and Engineer, in writing, a minimum of 1 week in advance of commencing Work on site.
- B. Notify the Owner and Engineer, in writing, a minimum of 1 week before commencing any work which may affect the Owner's operations.
- C. Perform all construction activities so as to avoid interference with operations of the facility and the work of others.

# 3.3 SEQUENCE OF CONSTRUCTION

A. Constructing the proposed improvements while maintaining existing operations will require a specific sequence of construction. The Contractor will be allowed reasonable flexibility in scheduling the construction activities. Provide a detailed construction schedule as required in Section 01325.

# END OF SECTION

 $\hbox{\tt J:} \\ \hbox{\tt NN1011 New Bedford} \\ \hbox{\tt 007 Piers} \\ \hbox{\tt 01 - Fort Taber} \\ \hbox{\tt Specifications} \\ \hbox{\tt Fort Taber} \\ \hbox{\tt Div 1} \\ \hbox{\tt 01310.docx} \\ \hbox{\tt NN1011 New Bedford} \\ \hbox{\tt NN1011 New Bedford}$ 

## CONSTRUCTION PHOTOGRAPHS

## PART 1 GENERAL

## 1.1 SUMMARY

#### A. Section Includes

1. Photographs taken at specified intervals before, during and after construction.

## 1.2 SUBMITTALS

#### A. Informational Submittals

1. Submit electronic files of each photograph on a CD or USB flash drive.

## PART 2 PRODUCTS

## 2.1 CONSTRUCTION PHOTOGRAPHS

A. Electronic files shall be in .jpg format.

#### PART 3 EXECUTION

## 3.1 PRE-CONSTRUCTION PHOTOGRAPHY

- A. Prior to the commencement of any Work under this Contract, take a minimum of 10 photographs. The photographs will serve as a record of the original conditions where construction activities will occur.
- B. The area to be photographed shall include, but not be limited to, the area within and adjacent to the proposed construction.
- C. Provide a minimum of 10 preconstruction photographs, or more as required to document the preconstruction condition of the Site and adjacent properties.

## 3.2 PROGRESS PHOTOGRAPHY

A. Take 10 construction photographs daily to depict the work completed each day.

## 3.3 POST-CONSTRUCTION PHOTOGRAPHY

A. Provide post construction photography after all Work has been completed at each location. The locations to be photographed and the number of photographs required shall be as specified in Paragraph 3.1 for the preconstruction photography.

## **END OF SECTION**

 $\hbox{\tt J:\N\N1011 New Bedford\007 Piers\01 - Fort\ Taber\Specifications\Fort\ Taber\Div\ 1\01320.docx} \\$ 

## SCHEDULING OF CONSTRUCTION

## PART 1 GENERAL

## 1.1 SUMMARY

- A. Section Includes
  - Milestones
  - 2. Progress Schedule
- B. Related Requirements
  - 1. Section 01140 Work Restrictions
  - 2. Section 01310 Coordination

#### 1.2 MILESTONES

- A. Milestone No. 1: The Contractor shall complete all Work on the pier shown on drawings no later than 120 days following the Notice to Proceed.
- B. If, in the opinion of the Owner, the progress of the Work is insufficient to achieve the scheduled completion of the milestone, the Contractor shall be required to take such measures as are necessary to achieve completion by the milestone date. Such measures may include, but shall not be limited to, employing additional equipment and personnel, working overtime, added shifts or any combination thereof, all at no additional cost to the Owner.

## 1.3 PROGRESS SCHEDULE.

- A. Graphically show the order and interdependence of activities, sequence of Work, how the start of a given activity depends on completion of preceding activities, and how completion of an activity may restrain the start of subsequent activities.
- B. The Work shall be planned by the Contractor and his Project field superintendent in coordination with all Subcontractors and Suppliers whose Work is shown on the Progress Schedule.
- C. Include, at a minimum, the following activities on the Progress Schedule:
  - 1. Project mobilization
  - 2. Submittal and approval of Shop Drawings
  - 3. Procurement of equipment and critical materials
  - 4. Installation of equipment and critical materials
  - 5. Fabrication of special equipment and material, and its installation and testing
  - 6. Final inspecting and testing
  - 7. Punchlist
  - 8. Final cleanup
  - 9. Other activities that may be critical to the Progress Schedule

- 10. All activities of the Owner and the Engineer which affect progress and/or affect required dates for completion of the Work
- 11. Milestone completion dates: 120 Days after the Notice to Proceed
- D. Take into consideration Shop Drawing submittal and approval time, the delivery times of equipment and materials, Subcontractors' Work, availability and abilities of workmen, weather conditions, any restrictions in operations at the Work site, and all other items that may affect completion of the Work within the Contract Time and specified milestones.
- E. The Progress Schedule shall reflect the requirements and constraints outlined in Section 01310, Coordination.
- F. The Progress Schedule shall reflect Work restrictions outlined in Section 01140.
- G. Show information in such detail that duration times of activities will range from one to 15 days. The selection and number of activities shall be subject to the approval of the Owner and Engineer.
- H. The Progress Schedule should show preceding and following event numbers for each activity, description of each activity, and activity duration in calendar days.
- I. Submit the Progress Schedule on maximum sheet size 30-inches high by the width required.

## 1.4 SUBMITTALS

#### A. Informational Submittals

- 1. Submit four prints of the preliminary Progress Schedule prepared in accordance with Article 2.05 of Section 00700 and the requirements of this section. Progress schedule must be submitted within 10 days after the Effective Date of the Agreement. Progress Schedule must be approved by the Owner and Engineer before the first progress payment will be made.
- 2. Revised analyses Within 10 days after receipt of the review comments, submit four prints of the Progress Schedule revised in accordance with those comments.
- 3. Periodic reports On the first progress meeting of each month, submit four prints of the updated Progress Schedule, as well as a report of construction activities in the prior month.
- 4. Before initiating the Work, submit an estimated monthly rate of Contractor payments for the project. If the payment schedule deviates from the original projection, submit a revised rate of expenditure schedule.

## PART 2 EXECUTION – NOT USED

## END OF SECTION

J:\N\N1011 New Bedford\007 Piers\01 - Fort Taber\Specifications\Fort Taber\Div 1\01325.docx

## SUBMITTAL PROCEDURES

## PART 1 GENERAL

## 1.1 SUMMARY

- A. Section Includes
  - 1. Action Submittals
  - 2. Informational Submittals

#### 1.2 DEFINITIONS

- A. Action Submittals includes written and graphic information submitted by Contractor that requires Engineer's approval.
- B. Informational Submittals includes information submitted by Contractor that does <u>not</u> require Engineer's approval. The Engineer will acknowledge receipt of such documents and provide comments when the submittals lack the detail required by the Contract Documents.

## 1.3 ACTION SUBMITTALS

## A. Shop Drawings

- 1. Shop Drawings as defined in the General Conditions, and as specified in individual work sections include, but are not necessarily limited to, custom-prepared data such as fabrication and erection/installation drawings, schedule information, piece part drawings, actual shop work manufacturing instructions, special wiring diagrams, coordination drawings, individual system or equipment inspection and test reports including performance curves and certification, as applicable to the Work.
- 2. Shop Drawings shall be of standardized sizes to enable the Owner to maintain a permanent record of the submissions. Approved standard size drawings shall be
  - a. 24 inches by 36 inches
  - b. 22 inches by 34 inches
  - c. 11 inches by 17 inches
  - d. 8.5 inches by 11 inches
- 3. Submit Shop Drawings at the proper time to prevent delays in delivery of materials. Coordinate submittals for related or interdependent equipment.
- 4. Advise the Engineer in writing of any deviations from the requirements of the Contract Documents.
- 5. Check all Shop Drawings regarding measurements, size of members, materials, and details to determine if they conform to the Contract Documents. Shop Drawings found to be inaccurate, not in compliance, or otherwise in error shall be returned to the Subcontractors or Suppliers for correction before submission to the Engineer. Drawings that are current shall be marked with the date, name, and approval stamp of the Contractor.

- 6. All details on Shop Drawings submitted for approval shall show clearly the relation of the various parts to the main members and lines of the structure, and where correct fabrication of the work depends upon field measurements, such measurements shall be made and noted on the Shop Drawings before being submitted for approval.
- 7. No material or equipment shall be purchased or fabricated until the required Shop Drawings have been submitted and approved. Materials and equipment and the work involved in their installation or incorporation into the Work shall then be as shown in and represented by the Shop Drawings.
- 8. Until the necessary approval has been given, do not proceed with any portion of the work, the design or details of which are dependent upon the design or details of work, materials, equipment or other features for which approval is required.
- 9. If submitted equipment requires modifications to the structures, piping, layout, or other details shown on the Drawings, details of the proposed modifications must also be submitted for approval. If such equipment and modifications are approved, perform all Work necessary to make such modifications at no additional cost to the Owner.
- B. Product Data: Product data as specified in individual Sections, include, but are not necessarily limited to, standard prepared data for manufactured products (catalog data), such as the manufacturer's product specification and installation instructions, availability of colors and patterns, manufacturer's printed statements of compliances and applicability, roughing-in diagrams and templates, catalog cuts, product photographs, standard wiring diagrams, printed performance curves and operational-range diagrams, production or quality control inspection and test reports and certifications, mill reports, product operating and maintenance instructions and recommended spare-parts listing, and printed product warranties, as applicable to the Work.
- C. Samples and color selection charts: Provide sample, when requested by individual Specification to establish conformance with the Specifications, and as necessary to define color, texture and pattern selections available.
- D. Schedule of Values: In accordance with Section 01295.

#### 1.4 INFORMATIONAL SUBMITTALS

- A. Schedule of Submittals
  - 1. Submit a preliminary Schedule of Submittals within 10 days of the Effective Date of the Agreement in accordance with Article 2.05 of Section 00700.
- B. Schedule of Manufacturers and Suppliers
  - 1. Submit a schedule of manufacturers and Suppliers within 7 days after Notice to Proceed including the names and addresses of the manufacturers and Suppliers of materials and equipment to be incorporated into the Work.
- C. Schedule of Major Products
  - 1. Submit a schedule of major products within 30 days after Notice to Proceed including a complete list of major products proposed for use, with specification section number, name of manufacturer, trade name, and model number of each product.

## D. Product Listing and Manufacturers Qualifications

1. For products specified only by reference standards, give manufacturer, trade name, model or catalog designation and reference standards. Specifically identify the products, the anticipated schedule for delivery and storage, and the estimated value thereof for materials which the Contractor intends to request approval for off-site storage.

# E. Certificates of Compliance

#### 1. General:

- a. Submit sworn certificates from the manufacturer or material supplier that the materials and fabrications provided under the Specification section conform with the Contract Documents.
- b. Certificates shall be signed by an officer of the manufacturer's corporation and witnessed by a Notary Public.
- 2. Welding: Submit in accordance with individual Specification sections.
- 3. Installer: Prepare written statements on manufacturer's letterhead certifying that installer complies with requirements as specified in individual Specification sections.
- 4. Material Test: Prepared by qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements.
- 5. Certificates of Successful Testing or Inspection: Submit when testing or inspection is required by Laws and Regulations or governing agency, or when specified in individual Specification sections.
- 6. Manufacturer's Certificate of Compliance: In accordance with individual Specification sections.

#### Procedures

# F. Coordination

- 1. Prepare and submit documentation in advance of fabrication and product manufacturer, so that the installation will not be delayed, other related work can be properly coordinated, and there is adequate time for review and resubmission, if required.
- 2. Provide no less than 30 days for review of submittals from the time received by the Engineer. For submittals of major equipment, that require more than 30 days to review, due to complexity and detail or those requiring review by multiple engineering disciplines, Engineer will notify Contractor of the circumstances and identify the anticipated date when the submittal will be returned.
- 3. Re-submittals will be subject to same review time.
- 4. No extension of time will be authorized due to failure to provide approvable submittals sufficiently in advance of the Work.
- G. Review Shop Drawings, product data, and samples prior to submission and verify and determine:

- 1. Field measurements
- 2. Conformance with the Contract Documents. Advise the Engineer in writing of any deviations from the requirements of the Contract Documents.
- 3. Delete or strike out information that is not applicable to the Work.
- H. Upload the electronic submittal files via Procore. Access to Procore will be provided by the Engineer. Files must be in .pdf format. The submittals will be returned in electronic .pdf format via Procore.
- I. Numbering: Submissions shall be accompanied by a transmittal form referencing the project name and applicable Specification section. Submittals shall be numbered sequentially, with the applicable Specification section and a hyphen preceding the number. (*e.g.* Submittal number 11330-01). Resubmittals shall bear the same transmittal number with a revision number commencing with "1" (*e.g.* Submittal number 11330-01-1).
- J. Provide a copy of the Submittal Certification Form (copy attached at the end of this section) which shall be attached to every copy of each submittal as required under Article 7.16 A.2 of Section 00700. Apply the Contractor's stamp and initials or signature certifying that the submission has been thoroughly reviewed for completeness, compliance with the Contract Documents, coordination with adjacent construction and dimensional compatibility. Items submitted without the stamp or that are incomplete will be returned by the Engineer for rework and resubmission.
- K. Provide a copy of the PE Certification Form (copy attached at the end of this section) which shall be attached to every copy of each submittal stamped by another Professional Engineer. Items submitted without the completed certification form will be returned by the Engineer for resubmission.
- L. Distribute copies of reviewed submittals along with the Engineer's transmittal to concerned parties with instructions to promptly report any inability to comply with the provisions or integrate the requirements with interfacing work.
- M. Partial and Incomplete Submittals
  - 1. Shop Drawings shall be submitted as a complete package by Specification section, unless otherwise reviewed and approved by the Engineer. It is the intent that all information, materials, and samples associated with each Specification section be included as a single submittal for the Engineer's review.
  - 2. Engineer will return entire submittals if preliminary review deems it incomplete including:
    - a. Missing or incomplete Submittal Certification Form
    - b. Insufficient number of copies
    - c. Missing content
  - 3. Partial submittals may be considered, at Engineer's option, only when necessary to expedite the Project.
  - 4. Partial submittals shall be clearly identified as such on the transmittal to identify missing components.

N. Submittals not required by the Specification will be returned without review or action code.

## O. Resubmission

- 1. Make corrections and modifications required by the Engineer and resubmit until approved.
- 2. Clearly identify changes made to submittals and indicate other changes that have been made other than those requested by the Engineer.
- 3. A maximum of two re-submissions of each shop drawing will be reviewed, checked and commented upon without charge to the Contractor (total of 3 submittals). Any additional submissions which are required by the Engineer to fulfill the stipulations of the Contract Documents will be charged to the Contractor as described in paragraph 7.16.E.2 of Section 00700.

## P. Distribution

1. Distribute approved Shop Drawings and approved product data to the Project Site and elsewhere as required to communicate the information to Suppliers, Subcontractors, and field personnel.

## 1.5 ENGINEER'S REVIEW

- A. The Engineer will review submittals for design, general methods of construction and detailing. The Engineer's review and approval of submittals shall not be construed as a complete check nor does it relieve the Contractor from responsibility for any departures or deviations from the requirements of the Contract Documents unless he has, in writing, called the Engineer's attention to such deviations at the time of submission. It will not extend to means, methods, technique, sequences, or procedures of construction (except where specifically and expressly called for by the Contract Documents) or to safety precautions or programs incident thereto.
- B. The Engineer's review of the submittals shall not relieve the Contractor from the responsibility for proper fitting of the Work, or the responsibility of furnishing any work required by the Contract Documents which may not be indicated on the submittals. The Contractor shall be solely responsible for any quantities shown on the submittals.
- C. If the Contractor considers any correction indicated on the submittals to constitute a change to the Contract Documents, the Contractor shall provide written notice to the Engineer at least 7 working days prior to release for manufacture.
- D. When the submittals have been completed to the satisfaction of the Engineer, the Contractor shall carry out the construction in accordance therewith and shall make no further changes therein except upon written instructions from the Engineer.
- E. Action submittals as defined in paragraph 1.2 will be reviewed and returned under one of the following codes:
  - 1. Approved (Action Code 1) is assigned when there are no notations or comments on the submittal. Equipment or materials may be released for manufacture, provided that it complies with requirements of the Contract Documents.
  - 2. Approved as Noted (Action Code 2) is assigned when there are notations or comments on the submittal, but the equipment or materials may still be released

- for manufacture. All notations and comments must be incorporated in the final product. Resubmission is not necessary.
- 3. Revise and Resubmit (Action Code 3) is assigned when there are notations and comments requiring a resubmittal of the package. Work cannot proceed until the submittal is revised and resubmitted for review.
- 4. Not Approved (Action Code 4) is assigned when the submittal contains non-specified items or does not meet the requirements of the Contract Documents. It may also be assigned when there is a significant amount of missing material required for the Engineer to perform a complete review. The entire package must be resubmitted, revised to bring the submittal into conformance. It may be necessary to resubmit using a different manufacturer/vendor to meet the requirements of the Contract Documents.
- F. Informational submittals as defined in paragraph 1.2 do not require approval by the Engineer. Such submittals will be returned under one of the following codes:
  - 1. Receipt Acknowledged (Action Code 5) is assigned when the submittal is provided for documentation purposes and is acknowledged as received. Comments may be noted using this action code.
  - 2. Revise and Resubmit (Action Code 6) is assigned when there are notations and comments requiring a resubmittal of the package.

PART 2 PRODUCTS – NOT USED

PART 3 EXECUTION – NOT USED

END OF SECTION

J:\N\N1011 New Bedford\007 Piers\01 - Fort Taber\Specifications\Fort Taber\Div 1\01330.docx

# SUBMITTAL CERTIFICATION FORM

PROJECT:			
ENGINEER:_		ENGINEER'S PROJECT NO.:	
CONTRACTO	R:	CONTRACTOR'S PROJECT	
NO.:			
TRANSMITT	AL NO:	SUBMITTAL NO.:	
	TON NO .	DRAWING NO.	
SPECIFICAT	ION NO.:	DRAWING NO:	
DESCRIPTIC	)N:		
MANUFACTL	JRER:		
certify that the requirement criteria, instead to the work related to the sequences, with the over the core of the work related to the sequences, with the over the core of the work over the core of the work related to the sequences, with the over the core of	the materials and/or equipments; that field measurements allation requirements, materified; that all materials would not been determined and we contractor's sole responsi	en reviewed by the undersigned and ment meets or exceeds the project s s, dimensions, quantities, specified perials, catalog numbers and related rith respect to intended use, fabricat and installation pertaining to the pereified; that review includes all informibility for means, methods, techniquation and safety; and item has been of	pecification erformance materials ion, rformance rmation les,
SUBMITTED	BY:	DATE:	
			-
	GENERAL CONTRACTOR'S	STAMP	
	GENERAL CONTRACTORS	STAPI	
l			J

# **PE CERTIFICATION FORM**

The undersigned hereby certifies that he/she Commonwealth of Massachusetts and that h	
	to design
(Name of C	ontractor)
(Insert PE Res	sponsibilities)
In accordance with Specification section	for the
(Name of	Project)
The undersigned further certifies that he conformance with all applicable local, state and, that his/her signature and PE stamp drawings used in, and resulting from, the de	and federal codes, rules and regulations; have been affixed to all calculations and
The undersigned hereby agrees to make all available to the	l original design drawings and calculations
(Insert Name	e of Owner)
or Owner's representative within seven days Owner.	s following written request therefor by the
PE Name	Contractor's Name
Signature	Signature
Title	Title
Address	Address

## **HEALTH & SAFETY PLAN**

## PART 1 GENERAL

## 1.1 SUMMARY

#### A. The Contractor shall:

- 1. Develop a site-specific Health and Safety Plan (HASP) specifically addressing the potential hazards that may be encountered at the work site. The HASP shall include the information described in this specification (as applicable) and meet all applicable OSHA requirements.
- 2. Furnish all labor, equipment, materials, and employee training for effective implementation of the HASP and worker health and safety protection of all Contractor personnel.
- 3. Furnish all labor, equipment, materials, and employee training to effectively complete any required air monitoring and/or decontamination.
- 4. Review the requirements and data provided for the project and supplement the HASP with any additional measures deemed necessary to fully comply with applicable regulatory requirements and to adequately protect personnel on the site.
- 5. Maintain a copy of the HASP at the worksite, accessible to employees working at the site.
- 6. Post the emergency response plan section of the HASP, inclusive of emergency alerting and response procedures and directions to the nearest hospital, in a visible location for all workers to see.

## B. Related Sections

1. 02220 – Demolition

## 1.2 SITE-SPECIFIC PROJECT CONDITIONS

A. The Contractor shall review and understand all existing information as it relates to potential exposure to subsurface site contaminants, environmental data and reports. Reference Section 00800 for copies of applicable environmental data.

## 1.3 REFERENCES

- A. OSHA 29 CFR Part 1910 (General Industry standards)
- B. OSHA 29 CFR Part 1926 (Construction Standards)

## 1.4 DEFINITIONS

A. Site Safety and Health Official (SSHO): The individual located at a job site who is responsible to the Contractor and has the authority and knowledge necessary to implement the HASP and verify compliance with applicable safety and health requirements.

#### 1.5 SUBMITTALS

- A. On-site Work shall not begin until the HASP has been submitted by the Contractor and accepted by the Owner/Engineer.
- B. Informational Submittals
  - 1. Submit the following within thirty (30) days after the Effective Date of the Agreement.
    - a. A site-specific HASP, including the information described in this Specification as applicable.
      - 1) The Engineer's review is only to determine if the HASP is consistent with the minimum requirements of this specification. Engineer has no control over contractor's health & safety and the means and methods of health & safety implementation. Engineer also does not perform health & safety monitoring of Contractor's Work.
      - 2) The review will not determine the adequacy of the HASP to address all potential hazards, as that remains the sole responsibility of the Contractor.
    - b. Documentation of qualifications and experience of the SSHO.
    - c. Applicable health and safety training records.

#### 1.6 CONTRACTOR'S RESPONSIBILITIES

- A. The Contractor is solely responsible for the health and safety of workers employed by the Contractor, any subcontractor, vendors/manufacturers, site visitors and anyone directly or indirectly employed by any of them.
- B. Provide a designated SSHO for the project.
- C. Pre-arrange emergency medical care services at a nearby hospital or medical clinic, including establishment of an emergency notification process and emergency routes of travel.
- D. Conduct pre-entry and weekly safety meetings with all site personnel, documenting attendance and topics covered.
- E. Develop and implement the site-specific HASP, inclusive of the elements in contained in this specification.

## 1.7 PERSONAL PROTECTIVE EQUIPMENT (PPE)

- A. All PPE must conform to the OSHA requirements, as indicated in the previous Reference Standards Section. Various PPE to be furnished by the Contractor under different levels of protection for their own personnel and subcontractor's personnel include, but are not limited to, the following:
  - 1. Level D Protection:
    - a. Gloves
    - b. Safety boots/shoes
    - c. Safety glasses

- d. Hearing protection (for high noise operations)
- e. Hard hat with optional face shield
- f. Life vest
- 2. Contractor is fully responsible for all PPE selection (including the various stages of protection), proper use, maintenance, and continuous monitoring.

## PART 2 EXECUTION

## 2.1 HEALTH AND SAFETY PLANNING AND IMPLEMENTATION

- A. Implement the HASP throughout the execution of all applicable work.
- B. The Contractor shall perform all monitoring as detailed in the HASP.
- C. Contractor(s) shall implement routine health and safety meetings and any follow-up supplemental briefings.
- D. Provide applicable health and safety training for all personnel who may come in contact with or be exposed to various dangerous, hazardous, or changing site conditions.
- E. Personnel who have not received applicable training and who are not equipped with the required PPE, shall not be permitted access to the site by the Contractor during the course of the work that may result in potential exposures to unsafe or hazardous site conditions.

## 2.2 INCIDENT REPORTING

- A. The Contractor shall comply with all accident and/or incident reporting requirements, including the following:
  - Should any unforeseen safety-related factor, hazard, or condition become evident during the course of the work, the Contractor must immediately take action to establish, maintain, and secure the site and working conditions. This shall be followed by immediate notice to the Owner and Engineer.
  - 2. If injury to any person on-site occurs, the Contractor shall immediately report the incident to the Owner and Engineer. Corrective actions shall be implemented.

#### END OF SECTION

J:\N\N1011 New Bedford\007 Piers\01 - Fort Taber\Specifications\Fort Taber\Div 1\01350.docx

# QUALITY CONTROL

#### 1.1 SUMMARY

- A. Section Includes
  - 1. Quality assurance and control of the Work
  - 2. Testing and inspection services
  - 3. Product test reports
  - 4. Manufacturer's field service
- B. Related Requirements
  - 1. Section 01451 Independent Testing Services
  - 2. Testing requirements are described in various Sections of the Project Manual.

## 1.2 SUBMITTALS

- A. Informational Submittals
  - 1. Product test reports

## 1.3 QUALITY ASSURANCE

- A. Monitor quality control over Suppliers, products, services, site conditions, and workmanship to produce Work of specified quality.
- B. Comply fully with manufacturer's instructions. Should these instructions conflict with the Specifications, request clarification from the Owner before proceeding.
- C. Comply with specified standards as a minimum quality for the Work except when more stringent tolerances, codes, or requirements indicate higher standards or more precise workmanship.

## 1.4 TESTING SERVICES FURNISHED BY CONTRACTOR

- A. Furnish all testing services required for materials and equipment proposed to be used in the Work, and quality control tests made in the field including:
  - 1. Concrete materials and mix designs
  - 2. Concrete in place
  - 3. Sieve analyses for all borrow materials used on the Project
  - 4. All other tests and engineering data as required in the Contract Documents.
- B. Testing agencies must meet the requirements of Section 01451.
- C. An independent commercial testing laboratory, with current Massachusetts certification, shall perform all tests that require the services of a laboratory to determine compliance with the Contract Documents. Independent testing laboratory requirements are defined under Section 01451.

- D. Secure and deliver the required number of samples to the laboratory as required by the Contract Documents.
- E. Notify Owner and Engineer of time, location and material being sampled.
- F. Schedule necessary testing laboratory services.
- G. Furnish written reports of each test within 48 hours of completion of testing.
- H. Notify the Engineer 48 hours prior to operations requiring inspections and laboratory testing services so the Engineer may witness testing. All failed test areas shall be reworked and re-tested until passing results are obtained.
- I. The Owner may hire its own independent testing laboratory for quality control tests made in the field or laboratory on materials and equipment during and after their incorporation in the Work. Cooperate with the Owner and independent testing laboratory and furnish samples of materials, design, mix, equipment, tools, storage, and assistance as requested.
- J. Re-work all failed test areas until passing results are obtained. All re-tests required as a result of the Contractor's failure to perform the work in accordance with the Contract Documents shall be at the Contractor's expense.

## 1.5 CODE COMPLIANCE TESTING

A. Provide inspections and tests required by codes or ordinances, or by a legally constituted authority having jurisdiction over the Work.

## 1.6 PRODUCT TEST REPORTS

A. Submit 2 copies of product test reports where required by the Contract Documents.

## 1.7 SUPPLIERS' FIELD SERVICE

A. Provide qualified field service and installation personnel from material and equipment Suppliers to observe site conditions, installation techniques, quality of workmanship, equipment start-up, adjustment, and performance test where required by the Contract Documents. Observations are to be reported and incorporated in the Work procedures.

## PART 2 PRODUCTS - NOT USED

## PART 3 EXECUTION - NOT USED

#### END OF SECTION

J:\N\N1011 New Bedford\007 Piers\01 - Fort Taber\Specifications\Fort Taber\Div 1\01450.docx

## INDEPENDENT TESTING SERVICES

## PART 1 GENERAL

## 1.1 SUMMARY

#### A. Section Includes

- 1. Independent testing services including geotechnical, concrete, grout and mortar, and welding inspection and testing
- 2. Testing laboratory services

## B. Related Requirements

- 1. Section 01450 Quality Control
- 2. Section 03300 Cast-in-Place Concrete

## 1.2 REFERENCES

#### A. General

1. ASTM E329 – Standard Specifications for Agencies Engaged in the Testing and/or Inspection of Materials used in Construction

# B. Soil Testing

1. American Association of State Highway and Transportation Officials (AASHTO)

# C. Concrete Testing

1. Cement and Concrete Reference Laboratory (CCRL)

## 1.3 SUBMITTALS

## A. Informational Submittals

- 1. Qualifications, experience, and certifications of each proposed testing service
- 2. Certificate of calibration for testing equipment
- 3. Inspection and test reports

## 1.4 QUALITY ASSURANCE

#### A. General

- 1. Comply with the requirements of Section 01450, Quality Control, for testing and inspection requirements.
- 2. Testing services shall have the following general qualifications:
  - a. Minimum five years as a firm with the type of testing specified.
  - b. Ability to provide timely field testing services to minimize the impact of the testing requirements on construction progress.

- c. Certification to perform the specified services in the state in which the Work is to be performed.
- 3. Testing services proposed by the Contractor shall be subject to review by the Owner and Engineer. Any testing firm not acceptable to the Owner or Engineer will be rejected.
- B. All testing agencies and laboratories must meet the requirements of ASTM E329.
- C. Testing company shall have been in business for a minimum of the last 5 years providing applicable testing services.
- D. Testing equipment shall be calibrated at maximum 12 month intervals by devices of accuracy traceable to National Bureau of Standards. Submit copy of certificate of calibration made by accredited calibration agency.
- E. Testing shall be in accordance with applicable codes and regulations referenced in individual Specification Sections, and with selected standards of the American Society for Testing and Materials.

## PART 2 PRODUCTS – NOT USED

## PART 3 EXECUTION

#### 3.1 TESTING SERVICES – GENERAL

- A. Provide testing services meeting the following:
  - 1. Provide qualified personnel promptly on notice.
  - 2. Perform inspections required by the Contract Documents. Sample and test materials and observe methods of construction to determine compliance with applicable standards and with the requirements of the Contract Documents.
  - 3. Take specimens and samples for testing, as required in individual Specification Sections. Provide all sampling equipment and deliver all specimens and Samples.
  - 4. Promptly notify the Owner and the Engineer of irregularities or deficiencies in the Work which are observed during performance of services.
  - 5. Promptly submit 2 copies of reports of inspections and tests to the Owner, and one copy to the Engineer including:
    - a. Date issued
    - b. Project title and number
    - c. Testing laboratory or agency name and address
    - d. Name and signature of inspector
    - e. Date of inspection or sampling
    - f. Record of temperature and weather
    - g. Date of test
    - h. Identification of product and Specification Section
    - i. Location of Project

- j. Type of inspection or test
- k. Results of tests and observations regarding compliance with Contract Documents
- B. Perform additional tests and services as required to assure compliance with the Contract Documents.
- C. Obtain Owner's approval of testing laboratory before performing testing services.
- D. Coordinate with testing laboratory.

## 3.2 CONCRETE TESTING

- A. Provide qualified independent field and laboratory testing service to perform the concrete testing required in Division 3 of the specifications.
- B. The concrete testing laboratory shall have been inspected by the CCRL within the past five years.
- C. The testing laboratory shall be licensed by the Commonwealth of Massachusetts.
- D. Field testing technicians shall have a Grade 1 concrete field technician license as issued by the American Concrete Institute (ACI).

## **END OF SECTION**

 $J:\N\1011$  New Bedford\007 Piers\01 - Fort Taber\Specifications\Fort Taber\Div 1\01451.docx

## TEMPORARY CONTROLS

## PART 1 GENERAL

## 1.1 SUMMARY

- A. Section Includes
  - 1. Sediment trapping devices

## 1.2 SUBMITTALS

- A. Informational Submittals
  - 1. Water Control Plan
  - 2. Sediment trapping devices

## PART 2 PRODUCTS

## 2.1 SEDIMENT TRAPPING DEVICES

- A. Dewatering bags shall be as manufactured by Dandy Dewatering Bag (Contact 800-591-2284) or approved equal and sized in accordance with the Contractor's Water Control Plan.
- B. Floating turbidity barriers shall be of sufficient size and strength for the intended work and shall be secured to prevent loss of containment. Turbidity barriers shall be as manufactured by Siltdam Containment Barriers as supplied by Brockton Equipment/Spilldam, Inc. (Contact 508-583-7850) or approved equal

## 2.2 EXECUTION

- A. The Contractor shall maintain hay bales, silt fence, silt socks, dewatering bags, and floating turbidity barriers in good condition and remove in their entirety upon completion of the work.
- B. The Contractor shall remove accumulated sediment trapped within the hay bales, silt fence, silt socks, and dewatering bags periodically and as directed by the Engineer.
- C. Floating turbidity barriers shall be deployed as required during the work. The barriers shall be of sufficient length and shall protect against escape of sediment during both ebb and flood tides. The Contractor shall familiarize itself with the current velocities and anchoring conditions at the waterfront.
- D. Perform work in accordance with City of New Bedford Conservation Commission Order of Conditions.

## **END OF SECTION**

J:\N\N1011 New Bedford\007 Piers\01 - Fort Taber\Specifications\Fort Taber\Div 1\01570.docx

# PRODUCT REQUIREMENTS

## PART 1 GENERAL

## 1.1 SUMMARY

- A. Section Includes
  - 1. Products and Materials
  - 2. Product Delivery Requirements
  - 3. Packaging, Handling and Storage Requirements
  - 4. Inspection of Offsite Work

## 1.2 QUALITY ASSURANCE

- A. Review all contract Drawings and Specifications with respect to specific system characteristics, applicability of materials and equipment for the intended purposes, sizes, orientation, and interface with other systems, both existing and proposed, and certify that the materials and equipment proposed will perform as specified prior to submitting shop drawings.
- B. Provide sworn certificates as to quality and quantity of materials where specified or requested by the Engineer.
- C. Obtain concurrence of the Engineer prior to processing, fabricating, or delivering material or equipment.

## 1.3 PRODUCTS AND MATERIALS

- A. Furnish products of qualified manufacturers suitable for intended use. Furnish products of each type by a single manufacturer unless specified otherwise.
- B. Use only new and first quality material in the Work. Material shall conform to the requirements of these Specifications and be approved by the Engineer. If, after trial, it is found that sources of supply that have been approved do not furnish a uniform product, or if the product from any source proves unacceptable at any time, the Contractor shall furnish approved materials from other approved sources.
- C. Immediately remove defective materials and equipment from the site, at no additional cost to the Owner. The Contractor may be required to furnish sworn certificates as to the quality and quantity of materials before materials are incorporated in the Work.
- D. Engineer has the right to approve the source of supply of all material prior to delivery.

# 1.4 PRODUCT DELIVERY REQUIREMENTS

- A. Transport and handle products in accordance with manufacturer's instructions.
- B. Promptly inspect shipments to ensure products comply with requirements, quantities are correct, and products are undamaged.
- C. Provide equipment and personnel to handle products by methods to prevent soiling, disfigurement, or damage.

- D. Progressively deliver materials and equipment to the Site so there will be neither delay in progress of the Work nor an accumulation of material that is not to be used within a reasonable time.
- E. Deliver products to the Site in their manufacturer's original container, with labels intact and legible.
  - 1. Maintain packaged materials with seals unbroken and labels intact until time of use.
  - 2. The Engineer may reject as non-complying such material and products that do not bear identification satisfactory to the Engineer as to the manufacturer, grade, quality, source, and other pertinent information.

## 1.5 PACKAGING, HANDLING AND STORAGE REQUIREMENTS


- A. Provide storage and handling of all materials and equipment required for the Work.
- B. Except as otherwise indicated in the Contract Documents, determine and comply with the manufacturer's recommendations on product storage, handling, and protection. Provide manufacturer's documentation on recommended storage procedures when requested by the Engineer.
- C. Properly store and protect all equipment immediately upon its arrival. All equipment shall be stored in a clean, dry, heated, secured, and insured indoor facility satisfactory to the Engineer. Equip drive motors with thermostatically controlled strip heaters. Outdoor storage with plastic, canvas, plywood or other cover will not be allowed except where specific approval for designated items not containing electrical components or bearings is obtained from the Engineer. This approval does not relieve the Contractor of responsibility for proper protection of materials.
- D. Familiarize workmen and subcontractors with hazards associated with materials, equipment, and chemicals specified herein and take all necessary safety precautions.
- E. Areas available on the construction site for storage of material and equipment shall be as shown on the Drawings or approved by the Owner.
- F. Materials and equipment to be incorporated in the Work shall be handled and stored by the manufacturer, fabricator, supplier, and Contractor before, during and after shipment in a manner to prevent warping, twisting, bending, breaking, chipping, rusting, and any injury, theft, or damage of any kind to the material or equipment.
- G. Protect finished surfaces including floor surfaces, stairs, joints, and soffits of passageways from damage until accepted by the Engineer.
- H. Promptly remove materials from the site of the Work which have become damaged or are unfit for the use intended or specified. The Contractor will not be compensated for the damaged materials or their removal costs.
- I. Handle, haul, and distribute all materials and all surplus materials on the different portions of the Work, as necessary or required. Provide suitable and adequate storage room for materials and equipment during the progress of the Work, and be responsible for the protection, loss of, or damage to materials and equipment furnished, until the final completion and acceptance of the Work.
- J. Storage and demurrage charges by transportation companies and vendors shall be borne by the Contractor.

- K. All materials and equipment to be incorporated in the Work shall be placed so as to not damage any part of the Work or existing facilities and so that free access can be had at all times to all parts of the Work and to all public utility installations in the vicinity of the Work. Keep materials and equipment neatly piled and compactly stored in such locations as will cause a minimum of inconvenience to the Owner.
- L. No material or equipment will be permitted to be stored in any of the Owner's facilities, unless otherwise approved by the Engineer.
- M. Do not store material or equipment in any wetland or environmentally sensitive area. Stockpile sites shall be level, devoid of mature stands of natural vegetation, and removed from drainage facilities and features, wetlands, and stream corridors.
- N. Contractor shall be fully responsible for loss or damage to stored materials and equipment.
- O. No item judged rusty, corroded or otherwise damaged during storage will be accepted. Any electrical or instrumentation item determined by the Engineer to be damaged shall be removed from the Site and replaced by a completely new item in first class condition. Items not properly stored will not be considered for any partial payment.
- P. Provide protective and preventive maintenance during storage consisting of manually exercising equipment where required, inspecting mechanical surfaces for signs of corrosion or other damage, lubricating, applying any coatings as recommended by the equipment manufacturer as necessary for its protection and other precautions as necessary to assure proper protection of equipment stored.
- Q. Treat ferrous surfaces not receiving finish coats of paint with rust preventive coating, and protect non-ferrous metal work and devices with suitable wrappings.

#### 1.6 INSPECTION OF OFFSITE WORK

- A. The Owner and Engineer will inspect Work performed away from the construction site during fabrication, manufacture, or testing, or before shipment. Give 1 weeks written notice regarding the place and time where such fabrication, manufacture, testing, or shipping will be done.
- PART 2 PRODUCTS NOT USED
- PART 3 EXECUTION NOT USED

## **END OF SECTION**



## DEMOLITION AND REMOVAL

## PART 1 GENERAL

## 1.1 SUMMARY

- A. Section Includes
  - 1. Demolition and removal of dislodged existing granite blocks.
- B. Related Sections
  - 1. Section 01320 Construction Photographs
  - 2. Section 01350 Health & Safety Plan

## 1.2 DEFINITIONS

- A. Demolish To tear down, segregate waste streams and lawfully recycle or dispose of all debris generated in the process including structure contents.
- B. Limit of Work Area delineated on Drawings that defines the extent of demolition work under the Contract.

## 1.3 SUBMITTALS

- A. Informational Submittals
  - 1. Methods of demolition and equipment proposed to demolish structures. This submittal should be sufficient to demonstrate a thorough understanding of the Work to be completed and the means that will be implemented to safely complete the demolition within the Contract Time without damage to surrounding structures or resources.
  - 2. Waste Management Plan to indicate the types of wastes to be generated and the proposed disposal or recycling locations. Include back-up disposal facilities.
  - 3. Copies of any authorizations and permits required to perform the Work, including disposal/recycling facility permits.
- B. The following records and disposal documentation must be maintained and kept current throughout the Project. These documents will be maintained in chronological order in a 3-ring binder with appropriate tabbed dividers. The binder will be reviewed for completeness at each progress meeting. Requests for periodic payments may be rejected, in whole or in part, if documentation is not current.
  - 1. Records of the amounts of waste generated, by waste type
  - 2. Evidence of lawful disposal or recycling of all wastes generated
  - 3. Documentation of underground structures and utilities
  - 4. Copies of any analytical results generated as a result of waste stream characterization

## 1.4 REGULATORY REQUIREMENTS

- A. Contractor is solely responsible for obtaining permits or approvals which may be required to perform the work of this section, including all costs, fees and taxes required or levied, except for the following permits that will be obtained by the Owner:
  - 1. Notice of Intent from Massachusetts Department of Environmental Protection.
- B. Notify and obtain such permits or approvals from agencies having jurisdiction over demolition prior to starting work.
- C. Complete, sign and submit a Notice of Intent to be covered under EPA's General Permit for Construction Activity.
- D. Comply with all applicable federal, state, and local environmental, safety and health requirements regarding the demolition of structures and other site features and recycling or disposal of demolition debris, as applicable.
- E. Conform to procedures identified in Section 01350 Health and Safety Plan if hazardous or contaminated materials are discovered.

#### PART 2 PRODUCTS – NOT USED

#### PART 3 EXECUTION

#### 3.1 PROJECT MANAGEMENT

- A. Provide a full-time Project Superintendent who shall serve as a direct communication among the Contractor, subcontractors, and the Owner.
- B. Require all subcontractors to provide a foreman or superintendent. That individual must be on site at all times that the subcontractor is working.

#### 3.2 EXAMINATION

- A. Verify site conditions before proceeding with demolition work. Field check the accuracy of the Drawings and inspect structures and utilities prior to start of work and notify the Engineer in writing, of any hazardous conditions and/or discrepancies. Primary structures and other site features are shown on the Drawings; other smaller structures, including, but not limited to, concrete walks and pads, miscellaneous signs, lamp posts, railings, and fencing may not be shown on the Drawings, but may exist within the Limit of Work and shall be demolished.
  - 1. Unknown Site Conditions The information provided on the Drawings and in the Specifications is believed accurate. Field verify all information. Bear full responsibility for obtaining all locations of underground structures, utilities and their connections. Maintain services to buildings outside the limits of work.

#### 3.3 PREPARATION

A. Remove and/or stabilize all overhead hazards, prior to commencing work near any pier. Where hazards cannot be stabilized, mark and control areas below hazards to prohibit access below the hazards. This shall be performed with caution tape, saw horses, safety fence or other types of barricades as determined by applicable safety codes. Similarly, all holes through the floors or weak sections of the floor shall either be covered or clearly marked to prohibit entry. Floor coverings shall be capable of supporting heavy equipment use.

#### 3.4 DEMOLITION

- A. Demolish the buildings, underground utilities and related appurtenances by methods that will not cause damage to surrounding structures, underground and overhead utilities, or other existing items and structures that are to remain in place.
- B. Promptly and properly manage all debris as the demolition progresses. Construct and/or prepare material staging/stockpile areas at locations approved by the Engineer.

#### C. Granite Blocks


- 1. Remove/dislodge granite blocks within the Limit of Work as indicated on the Drawings and/or Photographs.
- 2. Granite blocks intended to be reused in the re-stabilization of the site.
- 3. Barricade work area as necessary to protect workers and general public from falling debris.
- 4. Do not leave unstable structures unattended. Plan the workday so that all structures are stable at the end of each work day.

#### 3.5 SITE RESTORATION

- A. Prior to any backfilling, document the location of any structures that remain in place through construction photographs (Section 01320) and by obtaining swing ties to and elevations of any structures to be buried. Progress payments may be withheld if current documentation is not maintained.
- B. Restore stacked granite pier wall in accordance with Sections 04400 and 03310.

#### **END OF SECTION**

J:\N\N1011 New Bedford\007 Piers\01 - Fort Taber\Specifications\Fort Taber\Div 2\02220.docx



#### **SECTION 03200**

#### REINFORCING STEEL

#### PART 1 GENERAL

#### 1.1 WORK INCLUDED

A. Furnish and install reinforcement and associated items required for the cast-in-place concrete, complete.

#### 1.2 REFERENCES

- A. The latest editions of the following American Concrete Institute (ACI) publications shall be used as reference standards:
  - 1. ACI SP-66 ACI Detailing Manual
  - 2. ACI 301 Specifications for Structural Concrete for Buildings
  - 3. ACI 318 Reinforced Concrete
- B. The latest editions of the following American Society for Testing and Materials (ASTM) publications shall be used as reference standards:
  - 1. ASTM A497 Standard Specification for Steel Welded Wire Fabric, Deformed, for Concrete Reinforcement.
  - 2. ASTM A615 Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement.
  - 3. ASTM A775 Standard Specification for Epoxy-Coated Steel Reinforcing Bars.
  - 4. ASTM A934 Standard Specification for Epoxy-Coated Prefabricated Steel Reinforcing Bars.

#### 1.3 SUBMITTALS

- A. Submit the following:
  - 1. Mill test reports for each shipment of reinforcement. Identify reports with specific lots in shipments and submit prior to use of reinforcement in work.
  - 2. Chemical composition of reinforcing steel. Ladle analysis to identify percentage of carbon, phosphorous, manganese and sulfur present in steel.
  - 3. Shop and placement drawings to the Owner/Engineer for review prior to fabrication, which show:
    - a. All construction and expansion joints.
    - b. Reinforcement detailed in conformance with ACI SP-66.
    - c. Support bars and details of bar supports including type, size and spacing.
    - d. Marking for each reinforcement item.
  - 4. Coating applicator's notarized Certificate of Compliance that the coating for rebar meets the specified requirements.

# 1.4 PRODUCT HANDLING

#### A. Protection:

- 1. Use all means necessary to protect reinforcing steel before, during, and after installation and to protect the installed work and materials of all other trades.
- 2. Store in a manner to prevent excessive rusting and fouling with dirt, grease, and other bond-breaking coatings.
- 3. Use all necessary precautions to maintain identification after the bundles are broken.

# B. Replacements:

1. In the event of damage, immediately make all repairs and replacements necessary to the approval of the Owner/Engineer and at no additional cost to the Owner.

# PART 2 PRODUCTS

#### 2.1 REINFORCING STEEL

- A. All reinforcing steel shall be new, epoxy coated, free from rust, and comply with ASTM A-615, Grade 60.
- B. Where epoxy coated rebar is shown or specified, the rebar shall be coated in accordance with ASTM A775.
- C. Where epoxy coated rebar is shown or specified, repair damaged or cut ends with a touch-up field kit prior to pouring concrete.

#### 2.2 OTHER MATERIALS

A. All other materials not specifically described but required for a complete and proper installation of reinforcing steel, shall be as selected by the Contractor subject to the approval of the Owner/Engineer.

## PART 3 EXECUTION

#### 3.1 SURFACE CONDITIONS

#### A. Inspection:

- 1. Prior to installation of the work of this Section, carefully inspect the installed work of all other trades and verify that all such work is complete to the point where this installation may properly commence.
- 2. Verify that reinforcing steel may be installed in strict accordance with all pertinent codes and regulations, the approved Shop Drawings, and the original design.

# B. Discrepancies:

- 1. In the event of discrepancy, immediately notify the Owner/Engineer.
- 2. Do not proceed with installation in areas of discrepancy until all such discrepancies have been fully resolved.

#### 3.2 BENDING

#### A. General:

- 1. Fabricate all reinforcement in strict accordance with the approved Shop Drawings.
- 2. Do not use bars with kinks or bends not shown on the Drawings or on the approved Shop Drawings.
- 3. Do not bend or straighten steel in a manner that will damage the material

# B. Design:

1. All bends shall be in accordance with ACI 318. Bend all bars cold.

#### 3.3 PLACING

#### A. General:

1. Before start of concrete placement, accurately place all reinforcing steel, positively securing and supporting by concrete blocks, metal chairs or spaces, or by metal hangers.

# B. Splicing:

#### 1. Horizontal Bars:

- a. Place bars in horizontal members with minimum laps at splices sufficient to develop the strength of the bars in accordance with ACI 318.
- b. Bars may be wired together at laps except at points of support of the member, at which points preserve the clear space described above.
- c. Wherever possible, stagger the splices of adjacent bars.

# C. Other Splices:

1. Make only those other splices that are indicated on the approved Shop Drawings or specifically approved by the Owner/Engineer.

#### D. Dowels:

1. Place all required steel dowels and securely anchor them into position before the concrete is placed. Dowels placed into existing concrete shall be securely anchored with high strength epoxy as indicated on the Drawings. Drilling and cleaning of dowel holes shall be in accordance with manufacturer's recommendations.

#### E. Obstructions:

- 1. In the event conduits, piping, inserts, sleeves, or any other items interfere with placing reinforcement as indicated on the Drawings or as otherwise required, immediately consult the Engineer and obtain approval of new procedure before placing concrete.
- F. Use pre-cast concrete bar support blocks for foundation mats.

#### 3.4 MINIMUM COVER

A. Unless otherwise shown on the Drawings, provide the following minimum cover:

	Minimum Cover
Concrete cast against and permanently exposed to earth (e.g. footings)	3"
Stirrups, ties, and spirals	1 ½"
All other bars	2"

# 3.5 CLEANING REINFORCEMENT

A. Steel reinforcement, at the time concrete is placed around it, shall be free from rust scale, loose mill scale, oil, paint, and all other coatings which will destroy or reduce the bond between steel and concrete.

END OF SECTION

#### **SECTION 03310**

#### **CONCRETE**

#### PART 1 GENERAL

#### 1.1 WORK INCLUDED

A. The work covered under this Section includes, but is not limited to, the furnishing of all plant, labor, equipment, appliances and materials including all joint fillers and sealants, and performing all operations in connection worth providing cast-in-place concrete in accordance with these specifications and in close conformity with the lines and grades shown

# 1.2 QUALITY CONTROL

- A. As the work progresses, the Contractor shall be required to perform tests and/or engage a testing laboratory in order to confirm that the quality of the concrete will be in conformance with these Specifications. Concrete shall be sampled in accordance with Section 01450, QUALITY CONTROL.
- B. Compression test specimens will be made by the Contractor and cured according to ASTM C31. Six (6) specimens will be collected for each 10 cubic yard pour and for each date concrete is placed at a structure and one (1) sample tested at 7 days, three (3) samples tested at 28 days, and two (2) samples held in reserve.
- C. If the concrete is found to be substandard as a result of the initial testing, then any additional work for replacement or removal of the substandard concrete or retesting shall be at the Contractor's expense.

#### 1.3 SUBMITTALS

#### A. Submit the following:

- 1. Batch plant details giving the location, layout, capacity, and type of batch plant and the method of transporting concrete from the batch plant to the work location. The Contractor shall provide documentation that all requirements of local authorities and regulations have been met.
- 2. Notification to the Engineer of concrete deliveries, a minimum of 24 hours in advance of the scheduled delivery. Include within this notification, class and quantity of concrete, frequency of trucks, and ordered slump.
- 3. Description of methods for cold-weather and hot weather batching, mixing and delivery.
- 4. Concrete Mix Designs.
  - a. Submit concrete mix designs to the Engineer within a minimum of seven (7) calendar days prior to placement. Include a complete list of materials including admixtures, applicable reference specifications, and copies of test reports showing the mix has been successfully tested to produce the properties specified.
  - b. For each design mix, provide:

- 1) Certifications by the concrete supplier that ingredients conform to the specified requirements.
- 2) Certifications by the concrete supplier that design mix conforms to specified strength, unit weight, maximum size aggregate, air entrainment, slump and to be free of soluble chloride content.
- 3) Coarse aggregate gradation, specific gravity, and dry rodded unit weight.
- 4) Identify admixtures, and planned dosage rate.
- 5. Compression test results.

#### PART 2 PRODUCTS

# 2.1 CEMENT

A. Cement shall conform to ASTM C150, Type II. The tricalcium aluminate (C3A) content shall not be less than 4 percent to provide protection for the reinforcement and shall not be more than 10 percent to obtain concrete that is resistant to sulfate attack.

#### 2.2 FLY ASH

A. Fly ash shall comply with ASTM C 618, Type F; except that the maximum calcium oxide content shall be 8 percent, the maximum available alkalis shall be 1.5 percent, and the maximum allowable loss on ignition shall be 6 percent. Report the chemical analysis of the fly ash in accordance with ASTM C311. Evaluate and classify fly ash in accordance with ASTM D 5759. If Fly ash is utilized to improve the concrete properties, its content shall not exceed 20 percent by weight of the total cementitious material.

# 2.3 GRANULATED BLAST FURNACE SLAG

A. Slag shall be finely ground, hydraulic cement, produced from granulated blast furnace slag, a product of the iron making process. It shall conform to ASTM C 989-99 as manufactured by Lafarge Newcem or approved equal. If Slag is utilized to improve the concrete properties, its content shall not exceed 40 percent by weight of the total cementitious material.

# 2.4 MICROSILICA

A. Microsilica shall be Force 10,000 as manufactured by Grace Construction Products or approved equal. If Microsilica is utilized to improve the concrete properties, its content shall not exceed 10 percent by weight of the total cementitious material

#### 2.5 AGGREGATES

- A. Aggregates shall conform to ASTM C33, except as modified herein:
  - 1. The combined aggregates in the mixture (coarse, fine, and blending sizes) shall be well graded from coarse to the fine with not more than 18 percent nor less than 8 percent, unless otherwise permitted, of the combined aggregate retained on any individual sieve, with the exception that:
    - a. The No. 50 may have less than 8 percent retained;
    - b. Sieves finer than No. 50 shall have less than 8 percent retained; and

- c. The coarsest sieve may have less than 8 percent retained.
- d. Use blending sizes where necessary to provide a well graded combined aggregate. Reports of individual aggregates shall include standard concrete aggregate sieve sizes including 1-1/2", 1", 3/4", 1/2", 3/8", No. 4, No. 8, No. 16, No. 30, No. 50, and No. 100.
- B. Provide aggregates for exposed concrete from one source. Do not provide aggregates that react deleteriously with alkalies in cement. Refer to Appendix Paragraph entitled "TEST METHOD C227" of ASTM C33 for expansion limits. Provide aggregate containing no deleterious material properties as identified by ASTM C295.
- C. Aggregate, when subjected to five (5) cycles of the soundness test in accordance with ASTM C88, shall not have a loss greater than 10 percent when sodium sulfate is used.
- D. Where a size designation is indicated, the designation indicates the nominal maximum size of the coarse aggregate.
- E. Where historical data is used, provide aggregates from the same sources and having the same size ranges as those used in the concrete represented by historical data

#### 2.6 WATER

A. Water shall comply with the requirements of ASTM C 94 and the chloride and sulfate limits in accordance with ASTM D 512 and ASTM D 516. Mixing water shall not contain more than 500 parts per million of chlorides as Cl and not more than 100 parts per million of sulfates as SO4. Minimize the amount of water in the mix. Water shall be fresh, clean, and potable; free from injurious amounts of oils, acids, alkalis, salts, organic materials, or other substances deleterious to concrete.

### 2.7 CONCRETE

A. Concrete for this project shall be a high-performance mix conforming to Section 520 of the Standard Specifications and proportioned based on Class AAA of the Standard Specifications as shown in Table 1.

	Table 1							
Co	Concrete Proportioning							
Concrete Property	Seawalls/Piers	Other						
Minimum 28-Day Compressive Strength per AASHTO T23 (psi)	5,000							
Slump per AASHTO T119 (in) <sup>1</sup>	4 – 7 <sup>2</sup>							
Air Content per AASHTO T152 (%)	5.0 - 8.0							
Minimum Cementitious Content (lb/yd³)	705							
Maximum Cementitious Content (lb/yd³)	799							

Maximum Water/Cementitious Ratio by Mass	0.40	
Maximum Aggregate Size (in)	3/4	

#### Footnotes:

- <sup>1</sup> The slump range shall be measured at the point of discharge. The Contractor shall submit the target slump range for each mix design to the Engineer for approval.
- <sup>2</sup> Slump shall not exceed 4 inches for surfaces sloped greater than 4 percent. If additional workability is desired, the Contractor may propose to increase the maximum specified slump up to 6 inches if an AASHTO M 194 Type A Water Reducing Admixture is used, or up to 9 inches if an AASHTO M 194 Type F or G High Range Water Reducing Admixture is used. AASHTO M 194 Type F or G High Range Water Reducing Admixture is required when concrete is to be placed by pumping equipment. Admixtures shall be utilized in accordance with the manufacturers' recommended dosages.
- <sup>3</sup> The Contractor shall achieve the specified slump using an AASHTO M 194 Type A Water Reducing Admixture, or an AASHTO M 194 Type F or G High Range Water Reducing Admixture. AASHTO M 194 Type F or G High Range Water Reducing Admixture is required when concrete is to be placed by pumping equipment. Admixtures shall be utilized in accordance with the manufacturers' recommended dosages.

#### 2.8 PERFORMED JOINT FILLER

A. Preformed joint filler shall be extruded closed cell polyethylene foam as manufactured/supplied by Foamtech or approved equal.

#### 2.9 POLYURETHANE JOINT SEALANT

A. Polyurethane joint sealant shall be Sikaflex-1a as manufactured/supplied by Sika or approved equal.

#### 2.10 BONDING AGENTS

A. Bonding agent shall be SIKAFLEX-Armatec® 110 EpoCem®, as manufactured by SIKA or approved equal. Apply in accordance with the manufacturer's instructions.

# 2.11 NON-SHRINK GROUT

A. Non-Shrink Grout for grouting the vertical joints at the weep drains shall be Sika 212 and supplied/manufactured by Sika Corp. or approved equal.

#### 2.12 FAST SETTING MORTAR

A. Fast Setting Mortar for setting granite blocks shall be 5-Star Structural Concrete V/O, as manufactured/supplied by 5-Star Products, Inc. or approved equal. Apply in accordance with the manufacturer's instructions, and allow mortar to set a minimum of 24 hours prior to pouring the concrete backfill.

# 2.13 EPOXY GROUT

A. Epoxy grout for setting anchors or rebar shall be Hilti HIT-RE 500 V3 by Hilti America or approved equal. Apply in accordance with the manufacturer's instructions.

#### PART 3 EXECUTION

# 3.1 PREPARATION OF EQUIPMENT AND PLACE OF DEPOSIT

A. Before placement, all equipment for mixing and transporting the concrete shall be cleaned, and all debris and ice shall be removed from the places to be occupied by the concrete. Forms shall be thoroughly wetted (except in freezing weather) or oiled. The reinforcement shall be thoroughly cleaned of ice, dirt, rust scale or other deleterious coatings.

#### 3.2 PLACING CONCRETE

- A. Concrete shall be placed only when the Engineer is present unless otherwise approved.
- B. Concrete work shall be in accordance with ACI 318 Building Code Requirements for Reinforced Concrete, latest edition.
- C. Concrete shall be deposited as nearly as practicable in its final position to avoid segregation due to re-handling or flowing. The placing of concrete shall be carried on at such a rate that concrete is at all times plastic and flows readily. No concrete that has been contaminated by foreign material shall be used nor shall re-tempered concrete be used.
- D. Do not exceed a free vertical drop of 3 feet from the point of discharge.
- E. Concrete delivery trucks shall not have aluminum chutes. All chutes shall be round-bottomed.
- F. When placing is started, it shall be carried on as a continuous operation until placement is completed.
- G. All concrete shall be thoroughly consolidated during placement by vibration or other approved means. It shall be thoroughly worked around embedded fixtures and into the corners of the forms.

#### 3.3 VIBRATING CONCRETE

- A. Vibration of concrete shall comply with the requirements of ACI 301, ACI 309R, and ASTM A775 for epoxy-coated bar using vibrators with a minimum frequency of 9000 vibrations per minute (VPM). Use only high cycle or high frequency vibrators. Motor-in-head 60 cycle vibrators may not be used.
- B. For walls and deep beams, use a minimum of two vibrators with the first to melt down the mixture and the second to thoroughly consolidate the mass. Furnish a spare, working, vibrator on the job site whenever concrete is placed.
- C. Operate internal vibrators with the vibratory element submerged in the concrete. Do not use vibrators to transport the concrete in the forms.
- D. Place concrete in 18" maximum vertical lifts. Insert and withdraw vibrators approximately 18" apart. Penetrate at least 8" into the previously placed lift with the vibrator when more than one lift is required. Extract the vibrator using a series of up and down motions to drive the trapped air out of the concrete and from between the concrete and the forms.
- E. External vibrators shall be used on the exterior surface of the forms when internal vibrators do not provide adequate consolidation of the concrete.

- F. For slab construction, use vibrating screeds designed to consolidate the full depth of the concrete.
- G. Where beams and slabs intersect, use an internal vibrator to consolidate the beam.
- H. Do not vibrate concrete placed with anti-washout admixtures.
- I. Vibrators shall be equipped with rubber vibrator heads.

### 3.4 COLD WEATHER REQUIREMENTS

A. Proceed in accordance with ACI 306.1. Unless otherwise approved, the temperature of the mixed concrete shall be not less than 50° F and not more than 90° F at the time of placing it in the forms. Obtain approval prior to placing concrete when the ambient temperature is below 40° F or when concrete is likely to be subjected to freezing temperatures within 24 hours. Cover concrete and provide sufficient heat to maintain 60° F minimum for a minimum of 5 days after placing the concrete, and above 40° F for an additional 9 days. The temperature shall then be gradually lowered to that of the surrounding atmosphere.

# 3.5 HOT WEATHER REQUIREMENTS

A. Placement of concrete in hot weather shall be performed in accordance with ACI 305R. Maintain required concrete temperature using Figure 2.1.5, "EFFECT OF CONCRETE TEMPERATURES, RELATIVE HUMIDITY, AND WIND VELOCITY ON THE RATE OF EVAPORATION OF SURFACE MOISTURE FROM CONCRETE" in ACI 305R to prevent the evaporation rate from exceeding 0.2 pound of water per square foot of exposed concrete per hour. Cool ingredients before mixing or use other suitable means to control concrete temperature and prevent rapid drying of newly placed concrete. Shade the fresh concrete as soon as possible after placing. Start curing when the surface of the fresh concrete is sufficiently hard to permit curing without damage. Provide water hoses, pipes, spraying equipment, and water hauling equipment, where job site is remote to water source to maintain a moist concrete surface throughout the curing period. Provide burlap cover or other suitable permeable material with fog spray or continuous wetting of the concrete when weather conditions prevent the use of either liquid membrane curing compound or impervious sheets. For vertical surfaces, protect forms from direct sunlight and add water to top of structure once concrete is set.

# 3.6 FORMS

- A. Forms shall conform to shapes, lines and dimensions of the members as called for on the Drawings and shall be sufficiently tight to prevent leakage of concrete. They shall be properly braced or tied together so as to maintain position and shape.
- B. Forms shall be removed in such a manner as to ensure the complete safety of the structure. In no case shall supporting forms or shoring be removed until members have acquired sufficient strength to support their weight and imposed loads safely.

#### 3.7 JOINTS

- A. Construction Joints: Concrete shall be installed to the limits indicated with the use of construction joints as shown on the Drawings or as approved by the Engineer. Additional construction joints, other than those indicated on the Drawings, shall not be incorporated into the work without the approval of the Engineer.
- B. All concrete between consecutive joints shall be placed in a continuous operation.

- C. Thoroughly clean the surface of the concrete at construction joints and remove laitance prior to placing adjoining concrete.
- D. Apply a bonding agent to surface of hardened concrete in accordance with the manufacturer's requirements prior to placing adjoining concrete.

#### 3.8 CURING AND PROTECTION

- A. General: Protect freshly placed concrete from premature drying and excessive cold or hot temperatures.
- B. Formed Surfaces: Cure formed concrete surfaces, including underside of cap and other similar surfaces. If forms remain during curing period, continue curing for the remainder of the curing period.
- C. Unformed Surfaces: Begin curing immediately after finishing concrete. Cure all unformed surfaces.
- D. Evaporation Retarder: Apply evaporation retarder to uniformed concrete surfaces if hot, dry, or windy conditions cause moisture loss approaching 0.2 lb/sq. ft. x h before and during finishing operations. Apply according to manufacturer's written instructions after placing, screeding and bull floating or darbying concrete, but before float finishing.
- E. Cure concrete according to ACI 308.1, by one or a combination of the following methods.
  - 1. Moisture Curing: Keep surfaces continuously moist for not less than seven days.
  - 2. Moisture-Retaining-Cover Curing: Cover concrete surfaces with moisture-retaining cover for curing concrete, placed in widest practicable width, with sides and ends lapped at least 12 inches, and sealed by waterproof tape or adhesive. Cure for not less than seven days. Immediately repair any holes or tears during curing period using cover material and waterproof tape.
  - 3. Curing Compound: Apply uniformly in continuous operation by power spray or roller according to manufacturer's written instructions. Recoat areas subjected to heavy rainfall within three hours after initial application. Maintain continuity of coating and repair damage during curing period.

#### 3.9 EXPOSED EDGES

A. All exposed edge and reentrant corners not otherwise detailed on the Drawings shall have a minimum <sup>3</sup>/<sub>4</sub>" chamfer.

# 3.10 CONCRETE SURFACE REPAIRS


- A. Defective Concrete: Use patching mortar to repair and patch defective areas when approved by the Engineer. Remove and replace concrete that cannot be repaired and patched to the Engineer's satisfaction.
- B. Repairing Formed Surfaces: Repair and patch all voids at form ties and all surface defects including color and texture irregularities, cracks, spalls, air bubbles, honeycombs, rock pockets, fins and other projections on the surface, and stains and other discolorations that cannot be removed by cleaning.

- 1. Immediately after form removal, remove snap-tie cones, cut out honeycombs, rock pockets, and voids more than ½ inch (13mm) in any dimension in solid concrete, but not less than 1 inch (25mm) in depth. Make edges of cuts perpendicular to concrete surface. Clean, dampen with water, and brush-coat all holes and voids with bonding agent. Fill and compact with patching mortar before bonding agent has dried.
- 2. Repair defects on surfaces exposed to view by blending white Portland cement and standard Portland cement so that, when dry, patching mortar will match surrounding color. Patch a test area at inconspicuous locations to verify mixture and color match before proceeding with patching. Compact mortar in place and strike off slightly higher than surrounding surface.
- C. Patching Mortar: Mix dry-pack patching mortar, consisting of one-part Portland cement to two and one-half parts fine aggregate passing a No. 16 (1.18-mm) sieve, using only enough water for handling and placing.

#### 3.11 FINISH

- A. Concrete shall receive a smooth form finish as follows:
  - 1. Use form facing materials that will produce a smooth, hard, and uniform texture on the concrete.
  - 2. Arrange facing materials in an orderly, symmetrical manner, with a minimum number of seams.
  - 3. Limit form face deflection.
  - 4. Avoid the use of defective or damaged materials that will impair the concrete surface texture.
- B. The smooth form finish shall provide a neat and uniform appearance and provide a smooth and non-abrasive surface.
- C. Exposed concrete that will receive foot traffic will receive a non-skid broom finish.
- D. Exposed joints between granite blocks to receive tool finish joints to match existing joints between blocks.

END OF SECTION



#### **SECTION 04400**

#### STONE MASONRY

#### PART 1 GENERAL

#### 1.1 REFERENCES

- A. Refer to other divisions of these specifications, other sections in this division, and Drawings for related work, which may affect the work of this section.
- B. The Contract Documents indicate and show the limits of construction for this project. These specifications specify material and work requirements for this project. Both are complementary to each other, and both shall be followed to properly complete the work.

# 1.2 DESCRIPTION OF WORK

- A. Work Included: The Contractor shall provide all labor, materials, and equipment necessary to complete the Work of this Section, including but not limited to the following:
  - 1. Stone masonry work related to the repair of the pier as shown on the contract drawings.

#### 1.3 SUBMITTALS

- A. For any imported granite blocks, if required, that are not reused from the site the Contractor shall provide a sample of the proposed stone, including example cuts or splits that may be made in order to complete the work. The sample shall be a minimum of 1' x 1' x 2', and shall be delivered to the project site for approval by the Owner/Engineer.
- B. The Contractor shall provide a letter from the proposed stone quarry that will be supplying imported stone, certifying that it has the capacity and quantity of material to completely satisfy the project requirements.

#### 1.4 QUALITY ASSURANCE

- A. The Contractor shall provide a qualified stone mason to supervise the selection, fitting, working and placement of all stonework meeting these specifications and the intent of the project. If the Contractor is not experienced in stone masonry, it shall employ a stone mason to supervise stone placement and ensure quality stonework construction.
- B. The Contractor shall not switch sources of imported stone without submitting a new sample for written approval by the Owner/Engineer.

# 1.5 DELIVERY AND STORAGE

The Contractor shall provide a qualified stone mason to supervise the selection, fitting, working and placement of all stonework meeting these specifications and the intent of the project. If the Contractor is not experienced in stone masonry, it shall employ a stone mason to supervise stone placements.

#### PART 2 PRODUCTS

#### 2.1 MATERIALS

#### A. Stone

- 1. Existing stones on site shall be used for the reconstruction on the pier. If needed, the contractor shall import supplemental stones of similar size and shape to be used to repair the pier.
- 2. Exposed face of stones shall be of uniform dimensions.
- 3. Stones with cracks or soft seams shall be considered as separate blocks, assuming that frost action will eventually open the cracks. Rounded stones will not be accepted. Stones shall be dimensioned as shown on the Drawings and exposed faces shall be selected and placed to show the straightest, flattest face(s) free of defects to the extent possible.
- 4. Stones from the existing seawall that are reused shall be cleaned by pressure washing, including removal of seaweed/marine growth, in order to enhance bonding between the stones and concrete/mortar.

#### B. Mortar/Concrete

1. Refer Section 03310, CONCRETE.

#### PART 3 EXECUTION

- A. The wall construction shall be as indicated on the Drawings, with neat tight stone placement. Exposed stones shall be selected and placed to show the straightest, flattest face(s), and shall be free of defects to the greatest extent possible. Joints between stones shall not have gaps greater than 3".
- B. Unless otherwise noted, the vertical joints between stones shall be staggered at least 12 inches between adjacent courses to provide optimum interlocking. Unless otherwise shown, only stone shall be exposed along the face and top of the seawall footing and retaining wall concrete shall not be visible above mean lower low water or above the existing mudline. Stones shall not protrude more than 2" beyond adjacent stones at the joints and all working of exposed stone shall be by chipping (i.e., no exposed saw cut or grinder surfaces, or exposed drill holes over 3/4" diameter shall be visible).
- C. The Contractor shall make provisions to prevent concrete from seeping through the joints in the granite block facing during concrete pours.
- D. Stones shall be pressure washed with a minimum of a 5,000 psi pressure washer to remove marine growth prior to installation to allow for concrete to bond to stones.

Within two hours of placing concrete, the back side of the seawall stones shall be scrub-coated with a Portland cement/water slurry mixed to a pancake batter consistency. All stones shall be solidly placed and interlocked and any stone placement that allows a stone to rock or move by hand or foot pressure shall be reset. The Contractor shall be responsible for maintaining the stability of the stones by placing concrete in lifts and providing temporary shoring as required. Stones shall be adequately placed or braced to allow concrete consolidation using a vibrator. Concrete surfaces between lifts shall be kept rough and

# Tighe&Bond

irregular to ensure a high friction bonded surface between lifts. Joints to be finished as specified.

END OF SECTION



# THE COMMONWEALTH OF MASSACHUSETTS EXECUTIVE OFFICE OF LABOR AND WORKFORCE DEVELOPMENT DEPARTMENT OF LABOR STANDARDS

# **Prevailing Wage Rates**

As determined by the Director under the provisions of the Massachusetts General Laws, Chapter 149, Sections 26 to 27H

ROSALIN ACOSTA Secretary

MICHAEL FLANAGAN
Director

Lt. Governor

Awarding Authority: City of New Bedford

Contract Number: City/Town: NEW BEDFORD

Description of Work: The City of New Bedford is soliciting sealed bids for stone masonry work at Fort Taber Pier.

Job Location: 1000C S Rodney French Blvd., New Bedford, MA 02744

#### Information about Prevailing Wage Schedules for Awarding Authorities and Contractors

- The wage rates will remain in effect for the duration of the project, except in the case of multi-year public construction projects. For construction projects lasting longer than one year, awarding authorities must request an updated wage schedule no later than two weeks before the anniversary of the date the contract was executed by the awarding authority and the general contractor. For multi-year CM AT RISK projects, the awarding authority must request an annual update no later than two weeks before the anniversary date, determined as the earlier of: (a) the execution date of the GMP Amendment, or (b) the execution date of the first amendment to permit procurement of construction services. The annual update requirement is not applicable to 27F "rental of equipment" contracts. The updated wage schedule must be provided to all contractors, including general and sub-contractors, working on the construction project.
- This wage schedule applies only to the specific project referenced at the top of this page and uniquely identified by the "Wage Request Number" on all pages of this schedule.
- An Awarding Authority must request an updated wage schedule if it has not opened bids or selected a contractor within 90 days of the date of issuance of the wage schedule. For CM AT RISK projects (bid pursuant to G.L. c.149A), the earlier of: (a) the execution date of the GMP Amendment, or (b) the bid for the first construction scope of work must be within 90-days of the wage schedule issuance date.
- The wage schedule shall be incorporated in any advertisement or call for bids for the project as required by M.G.L. c. 149, § 27. The wage schedule shall be made a part of the contract awarded for the project. The wage schedule must be posted in a conspicuous place at the work site for the life of the project in accordance with M.G.L. c. 149 § 27. The wages listed on the wage schedule must be paid to employees performing construction work on the project whether they are employed by the prime contractor, a filed sub-bidder, or a sub-contractor.
- Apprentices working on the project are required to be registered with the Massachusetts Division of Apprentice Standards (DAS).
   Apprentices must keep their apprentice identification card on their persons during all work hours on the project. An apprentice registered with DAS may be paid the lower apprentice wage rate at the applicable step as provided on the prevailing wage schedule. Any apprentice not registered with DAS regardless of whether they are registered with another federal, state, local, or private agency must be paid the journeyworker's rate.
- Every contractor or subcontractor working on the construction project must submit weekly payroll reports and a Statement of Compliance directly to the awarding authority by mail or email and keep them on file for three years. Each weekly payroll report must contain: the employee's name, address, occupational classification, hours worked, and wages paid. Do not submit weekly payroll reports to DLS. For a sample payroll reporting form go to http://www.mass.gov/dols/pw.
- Contractors with questions about the wage rates or classifications included on the wage schedule have an affirmative obligation to inquire with DLS at (617) 626-6953.
- Contractors must obtain the wage schedules from awarding authorities. Failure of a contractor or subcontractor to pay the prevailing wage rates listed on the wage schedule to all employees who perform construction work on the project is a violation of the law and subjects the contractor or subcontractor to civil and criminal penalties.
- Employees not receiving the prevailing wage rate set forth on the wage schedule may file a complaint with the Fair Labor Division of the office of the Attorney General at (617) 727-3465.

**Issue Date:** 10/11/2022 **Wage Request Number:** 20221007-038

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
Construction						
(2 AXLE) DRIVER - EQUIPMENT TEAMSTERS JOINT COUNCIL NO. 10 ZONE B	12/01/2021	\$35.95	\$13.41	\$16.01	\$0.00	\$65.37
(3 AXLE) DRIVER - EQUIPMENT TEAMSTERS JOINT COUNCIL NO. 10 ZONE B	12/01/2021	\$36.02	\$13.41	\$16.01	\$0.00	\$65.44
(4 & 5 AXLE) DRIVER - EQUIPMENT TEAMSTERS JOINT COUNCIL NO. 10 ZONE B	12/01/2021	\$36.14	\$13.41	\$16.01	\$0.00	\$65.56
ADS/SUBMERSIBLE PILOT PILE DRIVER LOCAL 56 (ZONE 2)	08/01/2020	\$103.05	\$9.40	\$23.12	\$0.00	\$135.57
For apprentice rates see "Apprentice- PILE DRIVER"						
AIR TRACK OPERATOR	06/01/2022	\$37.06	\$9.10	\$16.64	\$0.00	\$62.80
LABORERS - ZONE 2	12/01/2022	\$37.91	\$9.10	\$16.64	\$0.00	\$63.65
	06/01/2023	\$38.81	\$9.10	\$16.64	\$0.00	\$64.55
	12/01/2023	\$39.71	\$9.10	\$16.64	\$0.00	\$65.45
For apprentice rates see "Apprentice- LABORER"						
AIR TRACK OPERATOR (HEAVY & HIGHWAY)  LABORERS - ZONE 2 (HEAVY & HIGHWAY)	12/01/2021	\$36.16	\$9.10	\$16.64	\$0.00	\$61.90
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)						
ASBESTOS WORKER (PIPES & TANKS) HEAT & FROST INSULATORS LOCAL 6 (SOUTHERN MASS)	12/01/2020	\$38.10	\$12.80	\$9.45	\$0.00	\$60.35
ASPHALT RAKER	06/01/2022	\$36.56	\$9.10	\$16.64	\$0.00	\$62.30
LABORERS - ZONE 2	12/01/2022	\$37.41	\$9.10	\$16.64	\$0.00	\$63.15
	06/01/2023	\$38.31	\$9.10	\$16.64	\$0.00	\$64.05
	12/01/2023	\$39.21	\$9.10	\$16.64	\$0.00	\$64.95
For apprentice rates see "Apprentice- LABORER"						
ASPHALT RAKER (HEAVY & HIGHWAY)  LABORERS - ZONE 2 (HEAVY & HIGHWAY)	12/01/2021	\$35.66	\$9.10	\$16.64	\$0.00	\$61.40
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)						
ASPHALT/CONCRETE/CRUSHER PLANT-ON SITE OPERATING ENGINEERS LOCAL 4	06/01/2022	\$52.38	\$14.25	\$16.05	\$0.00	\$82.68
OPERATING ENGINEERS LOCAL 4	12/01/2022	\$53.63	\$14.25	\$16.05	\$0.00	\$83.93
	06/01/2023	\$54.88	\$14.25	\$16.05	\$0.00	\$85.18
	12/01/2023	\$56.13	\$14.25	\$16.05	\$0.00	\$86.43
	06/01/2024	\$57.43	\$14.25	\$16.05	\$0.00	\$87.73
	12/01/2024	\$58.88	\$14.25	\$16.05	\$0.00	\$89.18
	06/01/2025	\$60.18	\$14.25	\$16.05	\$0.00	\$90.48
	12/01/2025	\$61.63	\$14.25	\$16.05	\$0.00	\$91.93
	06/01/2026	\$62.93	\$14.25	\$16.05	\$0.00	\$93.23
For apprentice rates see "Apprentice- OPERATING ENGINEERS"	12/01/2026	\$64.38	\$14.25	\$16.05	\$0.00	\$94.68

ue Date: 10/11/2022 Wage Request Number: 20221007-038 Page 2 of 3 Page 2 of 33

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
BACKHOE/FRONT-END LOADER	06/01/2022	\$52.38	\$14.25	\$16.05	\$0.00	\$82.68
OPERATING ENGINEERS LOCAL 4	12/01/2022	\$53.63	\$14.25	\$16.05	\$0.00	\$83.93
	06/01/2023	\$54.88	\$14.25	\$16.05	\$0.00	\$85.18
	12/01/2023	\$56.13	\$14.25	\$16.05	\$0.00	\$86.43
	06/01/2024	\$57.43	\$14.25	\$16.05	\$0.00	\$87.73
	12/01/2024	\$58.88	\$14.25	\$16.05	\$0.00	\$89.18
	06/01/2025	\$60.18	\$14.25	\$16.05	\$0.00	\$90.48
	12/01/2025	\$61.63	\$14.25	\$16.05	\$0.00	\$91.93
	06/01/2026	\$62.93	\$14.25	\$16.05	\$0.00	\$93.23
	12/01/2026	\$64.38	\$14.25	\$16.05	\$0.00	\$94.68
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
BARCO-TYPE JUMPING TAMPER	06/01/2022	\$36.56	\$9.10	\$16.64	\$0.00	\$62.30
LABORERS - ZONE 2	12/01/2022	\$37.41	\$9.10	\$16.64	\$0.00	\$63.15
	06/01/2023	\$38.31	\$9.10	\$16.64	\$0.00	\$64.05
	12/01/2023	\$39.21	\$9.10	\$16.64	\$0.00	\$64.95
For apprentice rates see "Apprentice- LABORER"						
BLOCK PAVER, RAMMER / CURB SETTER	06/01/2022	\$37.06	\$9.10	\$16.64	\$0.00	\$62.80
LABORERS - ZONE 2	12/01/2022	\$37.91	\$9.10	\$16.64	\$0.00	\$63.65
	06/01/2023	\$38.81	\$9.10	\$16.64	\$0.00	\$64.55
	12/01/2023	\$39.71	\$9.10	\$16.64	\$0.00	\$65.45
For apprentice rates see "Apprentice- LABORER"						
BLOCK PAVER, RAMMER / CURB SETTER (HEAVY & HIGHWAY)  LABORERS - ZONE 2 (HEAVY & HIGHWAY)	12/01/2021	\$36.16	\$9.10	\$16.64	\$0.00	\$61.90
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)  BOILER MAKER  BOILERMAKERS LOCAL 29	01/01/2020	\$46.10	\$7.07	\$17.98	\$0.00	\$71.15

Apprentice -	BOILERMAKER - Local 29
--------------	------------------------

Effect	ive Date -	01/01/2020				Supplemental	
Step	percent		Apprentice Base Wage	Health	Pension	Unemployment	Total Rate
1	65		\$29.97	\$7.07	\$11.69	\$0.00	\$48.73
2	65		\$29.97	\$7.07	\$11.69	\$0.00	\$48.73
3	70		\$32.27	\$7.07	\$12.59	\$0.00	\$51.93
4	75		\$34.58	\$7.07	\$13.49	\$0.00	\$55.14
5	80		\$36.88	\$7.07	\$14.38	\$0.00	\$58.33
6	85		\$39.19	\$7.07	\$15.29	\$0.00	\$61.55
7	90		\$41.49	\$7.07	\$16.18	\$0.00	\$64.74
8	95		\$43.80	\$7.07	\$17.09	\$0.00	\$67.96
Notes:	·						
Appre	entice to Jo	urneyworker Ratio:1:4					

 Issue Date:
 10/11/2022
 Wage Request Number:
 20221007-038
 Page 3 of 33

								Unemployment	
BRICK/STONE/ARTIFICIAL MASONRY (INCL. MASONRY			08/01/2022	2 \$59.15	\$11.49	\$22.34	\$0.00	\$92.98	
WATERPROOFING) BRICKLAYERS LOCAL 3 (NEW BEDFORD)				02/01/2023	3 \$60.35	\$11.49	\$22.34	\$0.00	\$94.18
	,	ĺ		08/01/2023	3 \$62.40	\$11.49	\$22.34	\$0.00	\$96.23
				02/01/2024	4 \$63.65	\$11.49	\$22.34	\$0.00	\$97.48
				08/01/2024	4 \$65.75	\$11.49	\$22.34	\$0.00	\$99.58
				02/01/2025	5 \$67.05	\$11.49	\$22.34	\$0.00	\$100.88
				08/01/2025	5 \$69.20	\$11.49	\$22.34	\$0.00	\$103.03
				02/01/2026	6 \$70.55	\$11.49	\$22.34	\$0.00	\$104.38
				08/01/2026	6 \$72.75	\$11.49	\$22.34	\$0.00	\$106.58
				02/01/2027	7 \$74.15	\$11.49	\$22.34	\$0.00	\$107.98
		ntice - <i>BR</i> ve Date -	ICK/PLASTER/CEMENT M 08/01/2022	ASON - Local 3 New Be	edford		Supplementa	1	
	Step	percent		Apprentice Base Wage	Health	Pension	Unemploymen		
	1	50		\$29.58	\$11.49	\$22.34	\$0.00	\$63.41	
	2	60		\$35.49	\$11.49	\$22.34	\$0.00	\$69.32	
	3	70		\$41.41	\$11.49	\$22.34	\$0.00	\$75.24	
	4	80		\$47.32	\$11.49	\$22.34	\$0.00		
	5	90		\$53.24	\$11.49	\$22.34	\$0.00		
		ve Date -	02/01/2023	Apprentice Base Wage	II 141-	Pension	Supplementa Unemploymen		
	Step 1	percent							
	2	50		\$30.18	\$11.49	\$22.34	\$0.00		
	3	60		\$36.21	\$11.49	\$22.34	\$0.00		
		70		\$42.25	\$11.49	\$22.34	\$0.00		
	4	80		\$48.28	\$11.49	\$22.34	\$0.00		
	5	90		\$54.32	\$11.49	\$22.34	\$0.00	\$88.15	
	Notes:								
	Appre	ntice to Jou	ırneyworker Ratio:1:5					'	
JLLDOZER. PERATING ENG			ER	06/01/2022	2 \$51.82	\$14.25	\$16.05	\$0.00	\$82.12
LIATING ENG	HIVLEKS L(	CAL 4		12/01/2022	2 \$53.05	\$14.25	\$16.05	\$0.00	\$83.35
				06/01/2023	3 \$54.29	\$14.25	\$16.05	\$0.00	\$84.59
				12/01/2023	3 \$55.53	\$14.25	\$16.05	\$0.00	\$85.83
				06/01/2024	4 \$56.81	\$14.25	\$16.05	\$0.00	\$87.11
				12/01/2024	4 \$58.25	\$14.25	\$16.05	\$0.00	\$88.55
				06/01/2025	5 \$59.53	\$14.25	\$16.05	\$0.00	\$89.83
				12/01/2025	5 \$60.97	\$14.25	\$16.05	\$0.00	\$91.27
				06/01/2026	6 \$62.25	\$14.25	\$16.05	\$0.00	\$92.55
				12/01/2026	6 \$63.69	\$14.25	\$16.05	\$0.00	\$93.99
	a rates see !	Apprentice- O	PERATING ENGINEERS"						
		INNING B	OTTOM MAN	12/01/2021	1 \$42.33	\$9.10	\$17.72	\$0.00	\$69.15

Wage Request Number:

20221007-038

Classification

**Issue Date:** 10/11/2022

Supplemental

Unemployment

Pension

Effective Date Base Wage Health

**Total Rate** 

Page 4 of 33

<i>ABORERS - FOU</i>		AND MARINE	12/01/2021	\$41.18	\$9.10	\$17.72	\$0.00	\$68.00
For apprentice	e rates see '	'Apprentice- LABORER"						
CAISSON & U		INNING TOP MAN AND MARINE	12/01/2021	\$41.18	\$9.10	\$17.72	\$0.00	\$68.00
For apprentice	e rates see '	'Apprentice- LABORER"						
		LL OPERATOR	06/01/2022	\$36.56	\$9.10	\$16.64	\$0.00	\$62.30
ABORERS - ZON	E 2		12/01/2022	\$37.41	\$9.10	\$16.64	\$0.00	\$63.15
			06/01/2023	\$38.31	\$9.10	\$16.64	\$0.00	\$64.05
			12/01/2023	\$39.21	\$9.10	\$16.64	\$0.00	\$64.95
**	e rates see '	'Apprentice- LABORER"						
CARPENTER Carpenters - 20	ONE 2 (Eas	tern Massachusetts)	09/01/2022		\$8.68	\$19.97	\$0.00	\$73.83
	, ,		03/01/2023	\$45.78	\$8.68	\$19.97	\$0.00	\$74.43
	Appre		ern MA					
	Step	ve Date - 09/01/2022 percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate	
	1	50	\$22.59	\$8.68	\$1.73	\$0.00	\$33.00	
	2	60	\$27.11	\$8.68	\$1.73	\$0.00	\$37.52	
	3	70	\$31.63	\$8.68	\$14.78	\$0.00	\$55.09	
	4	75	\$33.89	\$8.68	\$14.78	\$0.00	\$57.35	
	5	80	\$36.14	\$8.68	\$16.51	\$0.00	\$61.33	
	6	80	\$36.14	\$8.68	\$16.51	\$0.00	\$61.33	
	7	90	\$40.66	\$8.68	\$18.24	\$0.00	\$67.58	
	8	90	\$40.66	\$8.68	\$18.24	\$0.00	\$67.58	
		ve Date - 03/01/2023				Supplemental		
	Step	percent	Apprentice Base Wage	Health	Pension	Unemployment	Total Rate	
	1	50	\$22.89	\$8.68	\$1.73	\$0.00	\$33.30	
	2	60	\$27.47	\$8.68	\$1.73	\$0.00	\$37.88	
		70	¢22.05	\$8.68	\$14.78	\$0.00	\$55.51	
	3	70	\$32.05	ψ0.00				
	4	75	\$34.34	\$8.68	\$14.78	\$0.00	\$57.80	
	4 5	75 80	\$34.34 \$36.62		\$16.51	\$0.00 \$0.00	\$61.81	
	4 5 6	75 80 80	\$34.34 \$36.62 \$36.62	\$8.68			\$61.81 \$61.81	
	4 5 6 7	75 80 80 90	\$34.34 \$36.62	\$8.68 \$8.68	\$16.51	\$0.00	\$61.81	
	4 5 6	75 80 80	\$34.34 \$36.62 \$36.62	\$8.68 \$8.68 \$8.68	\$16.51 \$16.51	\$0.00 \$0.00	\$61.81 \$61.81	
	4 5 6 7	75 80 80 90 90	\$34.34 \$36.62 \$36.62 \$41.20 \$41.20	\$8.68 \$8.68 \$8.68 \$8.68	\$16.51 \$16.51 \$18.24	\$0.00 \$0.00 \$0.00	\$61.81 \$61.81 \$68.12	
	4 5 6 7 8 Notes:	75 80 80 90 90	\$34.34 \$36.62 \$36.62 \$41.20 \$41.20 	\$8.68 \$8.68 \$8.68 \$8.68	\$16.51 \$16.51 \$18.24	\$0.00 \$0.00 \$0.00	\$61.81 \$61.81 \$68.12	
	4 5 6 7 8 Notes:	75 80 80 90 90 90	\$34.34 \$36.62 \$36.62 \$41.20 \$41.20 	\$8.68 \$8.68 \$8.68 \$8.68	\$16.51 \$16.51 \$18.24	\$0.00 \$0.00 \$0.00	\$61.81 \$61.81 \$68.12	
CARPENTER	4 5 6 7 8 Notes: Appre	75 80 80 90 90 90 % Indentured After 10/1/17; 45/45/ Step 1&2 \$31.01/ 3&4 \$48.64/ 5&6 ntice to Journeyworker Ratio:1:5 FRAME	\$34.34 \$36.62 \$36.62 \$41.20 \$41.20 	\$8.68 \$8.68 \$8.68 \$8.68	\$16.51 \$16.51 \$18.24	\$0.00 \$0.00 \$0.00	\$61.81 \$61.81 \$68.12	

**Effective Date** 

12/01/2021

Base Wage

\$41.18

Health

\$9.10

Pension

\$17.72

Classification

CAISSON & UNDERPINNING LABORER

Supplemental

\$0.00

Unemployment

**Total Rate** 

\$68.00

**Issue Date:** 10/11/2022 **Wage Request Number:** 20221007-038 **Page 5 of 33** 

Pension

Apprentice -	CARPENTER (Wood Frame) - Zone 3
Effective Date	04/01/2022

Effecti	ive Date -	04/01/2022				Supplemental	
Step	percent		Apprentice Base Wage	Health	Pension	Unemployment	Total Rate
1	60		\$14.20	\$7.21	\$0.00	\$0.00	\$21.41
2	60		\$14.20	\$7.21	\$0.00	\$0.00	\$21.41
3	65		\$15.38	\$7.21	\$0.00	\$0.00	\$22.59
4	70		\$16.56	\$7.21	\$0.00	\$0.00	\$23.77
5	75		\$17.75	\$7.21	\$3.80	\$0.00	\$28.76
6	80		\$18.93	\$7.21	\$3.80	\$0.00	\$29.94
7	85		\$20.11	\$7.21	\$3.80	\$0.00	\$31.12
8	90		\$21.29	\$7.21	\$3.80	\$0.00	\$32.30
Effecti	ive Date -	04/01/2023				Supplemental	
Step	percent		Apprentice Base Wage	Health	Pension	Unemployment	Total Rate
1	60		\$14.50	\$7.21	\$0.00	\$0.00	\$21.71
2	60		\$14.50	\$7.21	\$0.00	\$0.00	\$21.71
3	65		\$15.70	\$7.21	\$0.00	\$0.00	\$22.91
4	70		\$16.91	\$7.21	\$0.00	\$0.00	\$24.12
5	75		\$18.12	\$7.21	\$3.80	\$0.00	\$29.13
6	80		\$19.33	\$7.21	\$3.80	\$0.00	\$30.34
7	85		\$20.54	\$7.21	\$3.80	\$0.00	\$31.55
8	90		\$21.74	\$7.21	\$3.80	\$0.00	\$32.75
Notes:							
			/45/55/55/70/70/80/80 5&6 \$27.57/ 7&8 \$29.94				
Appre	ntice to Jo	urneyworker Ratio:1	:5				
	PLASTER		01/01/2020	0 \$49.07	\$12.75	\$22.41	\$0.62 \$84.85

CEMENT MAS

BRICKLAYERS LOCAL 3 (NEW BEDFORD)

**Apprentice -** CEMENT MASONRY/PLASTERING - Eastern Mass (New Bedford)

Step	percent	Apprentice Base Wage	Health	Pension	Unemployment	Total Rate
l	50	\$24.54	\$12.75	\$15.41	\$0.00	\$52.70
2	60	\$29.44	\$12.75	\$17.41	\$0.62	\$60.22
3	65	\$31.90	\$12.75	\$18.41	\$0.62	\$63.68
4	70	\$34.35	\$12.75	\$19.41	\$0.62	\$67.13
5	75	\$36.80	\$12.75	\$20.41	\$0.62	\$70.58
6	80	\$39.26	\$12.75	\$21.41	\$0.62	\$74.04
7	90	\$44.16	\$12.75	\$22.41	\$0.62	\$79.94

Apprentice to Journeyworker Ratio:1:3

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
CHAIN SAW OPERATOR	06/01/2022	\$36.56	\$9.10	\$16.64	\$0.00	\$62.30
LABORERS - ZONE 2	12/01/2022	\$37.41	\$9.10	\$16.64	\$0.00	\$63.15
	06/01/2023	\$38.31	\$9.10	\$16.64	\$0.00	\$64.05
	12/01/2023	\$39.21	\$9.10	\$16.64	\$0.00	\$64.95
For apprentice rates see "Apprentice- LABORER"						
CLAM SHELLS/SLURRY BUCKETS/HEADING MACHINES OPERATING ENGINEERS LOCAL 4	06/01/2022	\$53.40	\$14.25	\$16.05	\$0.00	\$83.70
OF EKATING ENGINEERS LOCAL 4	12/01/2022	\$54.68	\$14.25	\$16.05	\$0.00	\$84.98
	06/01/2023	\$55.95	\$14.25	\$16.05	\$0.00	\$86.25
	12/01/2023	\$57.23	\$14.25	\$16.05	\$0.00	\$87.53
	06/01/2024	\$58.55	\$14.25	\$16.05	\$0.00	\$88.85
	12/01/2024	\$60.03	\$14.25	\$16.05	\$0.00	\$90.33
	06/01/2025	\$61.36	\$14.25	\$16.05	\$0.00	\$91.66
	12/01/2025	\$62.83	\$14.25	\$16.05	\$0.00	\$93.13
	06/01/2026	\$64.16	\$14.25	\$16.05	\$0.00	\$94.46
	12/01/2026	\$65.64	\$14.25	\$16.05	\$0.00	\$95.94
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
COMPRESSOR OPERATOR  OPERATING ENGINEERS LOCAL 4	06/01/2022	\$34.26	\$14.25	\$16.05	\$0.00	\$64.56
SI ERATING ENGINEERS LOCAL 4	12/01/2022	\$35.08	\$14.25	\$16.05	\$0.00	\$65.38
	06/01/2023	\$35.90	\$14.25	\$16.05	\$0.00	\$66.20
	12/01/2023	\$36.72	\$14.25	\$16.05	\$0.00	\$67.02
	06/01/2024	\$37.57	\$14.25	\$16.05	\$0.00	\$67.87
	12/01/2024	\$38.52	\$14.25	\$16.05	\$0.00	\$68.82
	06/01/2025	\$39.37	\$14.25	\$16.05	\$0.00	\$69.67
	12/01/2025	\$40.32	\$14.25	\$16.05	\$0.00	\$70.62
	06/01/2026	\$41.18	\$14.25	\$16.05	\$0.00	\$71.48
	12/01/2026	\$42.13	\$14.25	\$16.05	\$0.00	\$72.43
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
DELEADER (BRIDGE) PAINTERS LOCAL 35 - ZONE 2	07/01/2022	\$54.86	\$8.65	\$23.05	\$0.00	\$86.56
AINTERS DOCAL 33 - ZONE 2	01/01/2023	\$56.06	\$8.65	\$23.05	\$0.00	\$87.76
	07/01/2023	\$57.26	\$8.65	\$23.05	\$0.00	\$88.96
	01/01/2024	\$58.46	\$8.65	\$23.05	\$0.00	\$90.16
	07/01/2024	\$59.66	\$8.65	\$23.05	\$0.00	\$91.36
	01/01/2025	\$60.86	\$8.65	\$23.05	\$0.00	\$92.56

**Issue Date:** 10/11/2022 **Wage Request Number:** 20221007-038 **Page 7 of 33** 

Pension

**Total Rate** 

	Step	ive <b>Date</b> - 07/01/2022 percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate	
	1	50	\$27.43	\$8.65	\$0.00	\$0.00	\$36.08	
	2	55	\$30.17	\$8.65	\$6.27	\$0.00	\$45.09	
	3	60	\$32.92	\$8.65	\$6.84	\$0.00	\$48.41	
	4	65	\$35.66	\$8.65	\$7.41	\$0.00	\$51.72	
	5	70	\$38.40	\$8.65	\$19.63	\$0.00	\$66.68	
	6	75	\$41.15	\$8.65	\$20.20	\$0.00	\$70.00	
	7	80	\$43.89	\$8.65	\$20.77	\$0.00	\$73.31	
	8	90	\$49.37	\$8.65	\$21.91	\$0.00	\$79.93	
		ive Date - 01/01/2023				Supplemental		
	Step	percent	Apprentice Base Wage	Health	Pension	Unemployment	Total Rate	
	1	50	\$28.03	\$8.65	\$0.00	\$0.00	\$36.68	
	2	55	\$30.83	\$8.65	\$6.27	\$0.00	\$45.75	
	3	60	\$33.64	\$8.65	\$6.84	\$0.00	\$49.13	
	4	65	\$36.44	\$8.65	\$7.41	\$0.00	\$52.50	
	5	70	\$39.24	\$8.65	\$19.63	\$0.00	\$67.52	
	6	75	\$42.05	\$8.65	\$20.20	\$0.00	\$70.90	
	7	80	\$44.85	\$8.65	\$20.77	\$0.00	\$74.27	
	8	90	\$50.45	\$8.65	\$21.91	\$0.00	\$81.01	
	Notes:	Steps are 750 hrs.					<sub> </sub>	
	Appre	ntice to Journeyworker Ratio:1:1						
MO: ADZE			06/01/2022	\$42.33	\$9.10	\$17.57	\$0.00	\$69.00
ORERS - ZON	£ 2		12/01/2022	\$43.33	\$9.10	\$17.57	\$0.00	\$70.00
			06/01/2023	\$44.33	\$9.10	\$17.57	\$0.00	\$71.00
For apprentice	e rates see '	'Apprentice- LABORER"	12/01/2023	\$45.58	\$9.10	\$17.57	\$0.00	\$72.25
мо: васк	HOE/LO	DADER/HAMMER OPERATOR	06/01/2022	2 \$43.33	\$9.10	\$17.57	\$0.00	\$70.00
ORERS - ZON	E 2		12/01/2022			\$17.57	\$0.00	\$71.00
			06/01/2023			\$17.57	\$0.00	\$72.00
			12/01/2023			\$17.57	\$0.00	\$73.25
For apprentice	e rates see '	'Apprentice- LABORER"						
MO: BURN			06/01/2022	\$43.08	\$9.10	\$17.57	\$0.00	\$69.75
ALINO - ZUM	L 4		12/01/2022	\$44.08	\$9.10	\$17.57	\$0.00	\$70.75
			06/01/2023	\$45.08	\$9.10	\$17.57	\$0.00	\$71.75
			12/01/2023	\$46.33	\$9.10	\$17.57	\$0.00	\$73.00

DEMO: CONCRETE CUTTERSAWYER   6001/2022	Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1201/2022   \$44.33   \$9.10   \$17.57   \$0.00   \$71.00     6061/2023   \$46.58   \$9.10   \$17.57   \$0.00   \$72.00     For approntise rates see "Apprentise-LABORER"   \$0.001/2022   \$43.08   \$9.10   \$17.57   \$0.00   \$69.75     LABORERS - ZONE 2   \$2.01/2022   \$44.08   \$9.10   \$17.57   \$0.00   \$69.75     LABORERS - ZONE 2   \$2.01/2022   \$44.08   \$9.10   \$17.57   \$0.00   \$70.75     60.01/2023   \$45.08   \$9.10   \$17.57   \$0.00   \$70.75     60.01/2023   \$45.08   \$9.10   \$17.57   \$0.00   \$70.75     For apprentise rates see "Apprentise-LABORER"   \$1.001/2023   \$45.38   \$9.10   \$17.57   \$0.00   \$70.00     For apprentise rates see "Apprentise-LABORER"   \$6.01/2022   \$42.33   \$9.10   \$17.57   \$0.00   \$69.00     LABORERS - ZONE 2   \$1.001/2022   \$42.33   \$9.10   \$17.57   \$0.00   \$70.00     For apprentise rates see "Apprentise-LABORER"   \$1.001/2022   \$42.33   \$9.10   \$17.57   \$0.00   \$70.00     For apprentise rates see "Apprentise-LABORER"   \$1.001/2022   \$43.33   \$9.10   \$17.57   \$0.00   \$70.00     For apprentise rates see "Apprentise-LABORER"   \$1.001/2022   \$43.33   \$9.10   \$17.57   \$0.00   \$70.00     For apprentise rates see "Apprentise-LABORER"   \$1.001/2022   \$43.33   \$9.10   \$17.57   \$0.00   \$70.00     For apprentise rates see "Apprentise-LABORER"   \$1.001/2022   \$43.33   \$9.10   \$17.57   \$0.00   \$70.00     For apprentise rates see "Apprentise-LABORER"   \$1.001/2022   \$43.33   \$9.10   \$17.57   \$0.00   \$70.00     For apprentise rates see "Apprentise-LABORER"   \$1.001/2022   \$49.00   \$14.25   \$16.05   \$0.00   \$83.35     For apprentise rates see "Apprentise-PILE DRIVER"   \$1.001/2024   \$56.81   \$14.25   \$16.05   \$0.00   \$89.30     For apprentise rates see "Apprentise-PILE DRIVER"   \$1.001/2024   \$60.00   \$9.40   \$23.12   \$0.00   \$10.122     PUENT READER (EPFLUENT)   \$0.801/2020   \$49.00   \$9.40   \$23.12   \$0.00   \$10.122     PUENT READER (EPFLUENT)   \$0.801/2020   \$49.00   \$9.40   \$23.12   \$0.00   \$10.122     PUENT READER (EPFLUENT)   \$0.801/2020   \$49.00   \$9.40   \$23.12   \$0.00   \$10.0122     PUENT READER (EPFLUENT)		06/01/2022	\$43.33	\$9.10	\$17.57	\$0.00	\$70.00
Post apprentice rates see "Apprentice-LAHORER"   12/01/2022   S43.08   S9.10   S17.57   S0.00   S09.75	LABORERS - ZONE 2	12/01/2022	\$44.33	\$9.10	\$17.57	\$0.00	\$71.00
DEMO: JACKHAMMER OPERATOR   0601/2002   S43.08   S9.10   S17.57   S0.00   S69.75		06/01/2023	\$45.33	\$9.10	\$17.57	\$0.00	\$72.00
DEMO: JACKHAMMER OPERATOR   0601/2022   \$43.08   \$9.10   \$17.57   \$0.00   \$69.75		12/01/2023	\$46.58	\$9.10	\$17.57	\$0.00	\$73.25
LABORERS - ZONE 2   12.01/2022    \$44.08	For apprentice rates see "Apprentice- LABORER"						
\$\frac{1}{2}\(01\) \$\frac{1}{2		06/01/2022	\$43.08	\$9.10	\$17.57	\$0.00	\$69.75
Por apprentice rates see "Apprentice-LABORER"   12/01/202	LABORERS - ZONE 2	12/01/2022	\$44.08	\$9.10	\$17.57	\$0.00	\$70.75
DEMO: WRECKING LABORER		06/01/2023	\$45.08	\$9.10	\$17.57	\$0.00	\$71.75
DEMO: WRECKING LABORER		12/01/2023	\$46.33	\$9.10	\$17.57	\$0.00	\$73.00
1201/2022   \$43,33   \$9,10   \$17,57   \$0,00   \$70,00     6001/2023   \$44,33   \$9,10   \$17,57   \$0,00   \$70,00     For apprentice rates see "Apprentice-LABORER"   1201/2023   \$45,58   \$9,10   \$17,57   \$0,00   \$72,25     For apprentice rates see "Apprentice-LABORER"   1201/2022   \$51,82   \$14,25   \$16,05   \$0,00   \$82,12     OPERATING ENGINEERS LOCAL 4   1201/2022   \$53,05   \$14,25   \$16,05   \$0,00   \$83,35     1201/2023   \$55,53   \$14,25   \$16,05   \$0,00   \$84,59     1201/2024   \$55,81   \$14,25   \$16,05   \$0,00   \$88,35     1201/2024   \$55,81   \$14,25   \$16,05   \$0,00   \$88,33     1201/2024   \$55,81   \$14,25   \$16,05   \$0,00   \$88,33     1201/2024   \$55,81   \$14,25   \$16,05   \$0,00   \$88,35     1201/2024   \$55,81   \$14,25   \$16,05   \$0,00   \$88,35     1201/2024   \$55,85   \$14,25   \$16,05   \$0,00   \$88,35     1201/2025   \$59,53   \$14,25   \$16,05   \$0,00   \$89,83     1201/2025   \$59,53   \$14,25   \$16,05   \$0,00   \$89,83     1201/2025   \$60,97   \$14,25   \$16,05   \$0,00   \$89,83     1201/2026   \$63,69   \$14,25   \$16,05   \$0,00   \$89,83     1201/2026   \$63,69   \$14,25   \$16,05   \$0,00   \$89,83     1201/2026   \$63,69   \$14,25   \$16,05   \$0,00   \$93,99     For apprentice rates see "Apprentice-OPERATING ENGINEERS"   1201/2026   \$63,69   \$14,25   \$16,05   \$0,00   \$93,99     PUED RIVER LOCAL 56 (ZONE 2)   80,00   \$89,00   \$80,00   \$80,00   \$80,00   \$80,00     For apprentice rates see "Apprentice-PILE DRIVER"   100,00   \$80,00							
\$\frac{1201/2022}{60601/2023}\$\$\frac{4}{3}.33\$\$\$\frac{1}{3}.01\$\$\$\frac{1}{3}.17.57\$\$\$\frac{5}{3}.00\$\$\$\frac{5}{7}.00\$\$\$\frac{7}{3}.00\$\$\$\frac{1}{3}.00\$\$\$\frac{1}{3}.00\$\$\$\frac{1}{3}.20\$\$\frac{1}.20\$\$\frac{1}{3}.20\$\$\frac{1}.20\$\$\frac{1}{3}.20\$\$\frac{1}{3}.20\$\$\frac{1}.20\$\$\frac{1}{3}		06/01/2022	\$42.33	\$9.10	\$17.57	\$0.00	\$69.00
12/01/2023   345.58   59.10   \$17.57   \$0.00   \$72.25	LABORERS - ZONE 2	12/01/2022	\$43.33	\$9.10	\$17.57	\$0.00	\$70.00
Post apprentice rates see "Apprentice- LABORER"		06/01/2023	\$44.33	\$9.10	\$17.57	\$0.00	\$71.00
DIRECTIONAL DRILL MACHINE OPERATOR  OFFATING ENGINEERS LOCAL 4  12/01/2022 \$53.05 \$14.25 \$16.05 \$0.00 \$82.12  12/01/2022 \$53.05 \$14.25 \$16.05 \$0.00 \$83.35  06/01/2023 \$54.29 \$14.25 \$16.05 \$0.00 \$83.35  12/01/2023 \$55.53 \$14.25 \$16.05 \$0.00 \$884.59  12/01/2024 \$56.81 \$14.25 \$16.05 \$0.00 \$885.83  06/01/2024 \$56.81 \$14.25 \$16.05 \$0.00 \$887.11  12/01/2024 \$58.82 \$14.25 \$16.05 \$0.00 \$887.11  12/01/2024 \$58.82 \$14.25 \$16.05 \$0.00 \$887.11  12/01/2024 \$58.83 \$14.25 \$16.05 \$0.00 \$889.83  12/01/2025 \$69.97 \$14.25 \$16.05 \$0.00 \$889.83  12/01/2025 \$60.97 \$14.25 \$16.05 \$0.00 \$89.85  12/01/2026 \$62.25 \$14.25 \$16.05 \$0.00 \$89.25  12/01/2026 \$63.69 \$14.25 \$16.05 \$0.00 \$99.27  O6/01/2026 \$63.69 \$14.25 \$16.05 \$0.00 \$99.25  DIVER **  **PILE DRIVER LOCAL 56 (ZONE 2)**  **For apprentice rates see "Apprentice- PILE DRIVER"*  DIVER TENDER **  DIVER TENDER (EFFLUENT)**  PILE DRIVER LOCAL 56 (ZONE 2)**  For apprentice rates see "Apprentice- PILE DRIVER"*  DIVER TENDER (EFFLUENT)**  **PILE DRIVER LOCAL 56 (ZONE 2)**  **For apprentice rates see "Apprentice- PILE DRIVER"*  DIVER TENDER (EFFLUENT)**  **PILE DRIVER LOCAL 56 (ZONE 2)**  **For apprentice rates see "Apprentice- PILE DRIVER"*  DIVER TENDER (EFFLUENT)**  **PILE DRIVER LOCAL 56 (ZONE 2)**  **For apprentice rates see "Apprentice- PILE DRIVER"*  DIVER TENDER (EFFLUENT)**  **PILE DRIVER LOCAL 56 (ZONE 2)**  **For apprentice rates see "Apprentice- PILE DRIVER"*  DIVER TENDER (EFFLUENT)**  **PILE DRIVER LOCAL 56 (ZONE 2)**  **For apprentice rates see "Apprentice- PILE DRIVER"*  DIVER TENDER (EFFLUENT)**  **PILE DRIVER LOCAL 56 (ZONE 2)**  **For apprentice rates see "Apprentice- PILE DRIVER"*  DIVER TENDER (COLL 36 (ZONE 2))**  **For apprentice rates see "Apprentice- PILE DRIVER"*  DIVER TENDER (SOLUTE)**  **PILE DRIVER LOCAL 36 (ZONE 2)**  **For apprentice rates see "Apprentice- PILE DRIVER"*  DIVER TENDER (SOLUTE A)**  **ONO		12/01/2023	\$45.58	\$9.10	\$17.57	\$0.00	\$72.25
12/01/2022   \$33.05   \$14.25   \$16.05   \$0.00   \$83.35							
12/01/2022   \$33.05   \$14.25   \$16.05   \$0.00   \$83.35     06/01/2023   \$54.29   \$14.25   \$16.05   \$0.00   \$84.59     12/01/2023   \$55.53   \$14.25   \$16.05   \$0.00   \$88.58     12/01/2024   \$55.81   \$14.25   \$16.05   \$0.00   \$88.58     12/01/2024   \$58.25   \$14.25   \$16.05   \$0.00   \$88.51     12/01/2024   \$58.25   \$14.25   \$16.05   \$0.00   \$88.55     06/01/2025   \$59.53   \$14.25   \$16.05   \$0.00   \$88.55     12/01/2025   \$60.97   \$14.25   \$16.05   \$0.00   \$89.83     12/01/2026   \$62.25   \$14.25   \$16.05   \$0.00   \$91.27     06/01/2026   \$62.25   \$14.25   \$16.05   \$0.00   \$91.27     06/01/2026   \$63.69   \$14.25   \$16.05   \$0.00   \$92.55     12/01/2026   \$63.69   \$14.25   \$16.05   \$0.00   \$93.99     For apprentice rates see "Apprentice-OPERATING ENGINEERS"    DIVER PILE DRIVER LOCAL 56 (ZONE 2)		06/01/2022	\$51.82	\$14.25	\$16.05	\$0.00	\$82.12
12/01/2023   \$55.53   \$14.25   \$16.05   \$0.00   \$85.83     06/01/2024   \$56.81   \$14.25   \$16.05   \$0.00   \$87.11     12/01/2024   \$58.25   \$14.25   \$16.05   \$0.00   \$87.11     12/01/2024   \$58.25   \$14.25   \$16.05   \$0.00   \$88.55     06/01/2025   \$59.53   \$14.25   \$16.05   \$0.00   \$89.83     12/01/2025   \$60.97   \$14.25   \$16.05   \$0.00   \$91.27     06/01/2026   \$62.25   \$14.25   \$16.05   \$0.00   \$91.27     06/01/2026   \$63.69   \$14.25   \$16.05   \$0.00   \$92.55     12/01/2026   \$63.69   \$14.25   \$16.05   \$0.00   \$93.99     For apprentice rates see "Apprentice-PILE DRIVER"    DIVER   08/01/2020   \$68.70   \$9.40   \$23.12   \$0.00   \$101.22     For apprentice rates see "Apprentice-PILE DRIVER"    DIVER TENDER   08/01/2020   \$49.07   \$9.40   \$23.12   \$0.00   \$81.59     PILE DRIVER LOCAL 56 (ZONE 2)   \$0.00   \$106.12     For apprentice rates see "Apprentice-PILE DRIVER"    DIVER TENDER (EFFLUENT)   08/01/2020   \$73.60   \$9.40   \$23.12   \$0.00   \$106.12     PILE DRIVER LOCAL 56 (ZONE 2)   \$0.00   \$106.12     For apprentice rates see "Apprentice-PILE DRIVER"    DIVER SULURRY (EFFLUENT)   08/01/2020   \$73.60   \$9.40   \$23.12   \$0.00   \$106.12     PILE DRIVER LOCAL 56 (ZONE 2)   \$0.00   \$106.12     For apprentice rates see "Apprentice-PILE DRIVER"    DIVER SULURRY (EFFLUENT)   08/01/2020   \$103.05   \$9.40   \$23.12   \$0.00   \$135.57     PILE DRIVER LOCAL 56 (ZONE 2)   \$0.00   \$106.12     DRAWBRIDGE OPERATOR (Construction)   \$0.00	OF ENTITY ENGINEERS ESCAL 4	12/01/2022	\$53.05	\$14.25	\$16.05	\$0.00	\$83.35
06/01/2024   \$56.81   \$14.25   \$16.05   \$0.00   \$87.11     12/01/2024   \$58.25   \$14.25   \$16.05   \$0.00   \$88.55     06/01/2025   \$59.53   \$14.25   \$16.05   \$0.00   \$88.55     06/01/2025   \$59.53   \$14.25   \$16.05   \$0.00   \$89.83     12/01/2025   \$60.97   \$14.25   \$16.05   \$0.00   \$91.27     06/01/2026   \$62.25   \$14.25   \$16.05   \$0.00   \$92.55     12/01/2026   \$63.69   \$14.25   \$16.05   \$0.00   \$92.55     12/01/2026   \$63.69   \$14.25   \$16.05   \$0.00   \$93.99     For apprentice rates see "Apprentice-OPERATING ENGINEERS"   08/01/2020   \$68.70   \$9.40   \$23.12   \$0.00   \$101.22     PUED DRIVER LOCAL 56 (ZONE 2)   For apprentice rates see "Apprentice-PILE DRIVER"   08/01/2020   \$49.07   \$9.40   \$23.12   \$0.00   \$81.59     DIVER TENDER PILE DRIVER"   08/01/2020   \$73.60   \$9.40   \$23.12   \$0.00   \$106.12     PUED DRIVER LOCAL 56 (ZONE 2)   For apprentice rates see "Apprentice-PILE DRIVER"   08/01/2020   \$73.60   \$9.40   \$23.12   \$0.00   \$106.12     PUED DRIVER LOCAL 56 (ZONE 2)   For apprentice rates see "Apprentice-PILE DRIVER"   08/01/2020   \$73.60   \$9.40   \$23.12   \$0.00   \$105.12     PUED DRIVER LOCAL 56 (ZONE 2)   For apprentice rates see "Apprentice-PILE DRIVER"   08/01/2020   \$73.60   \$9.40   \$23.12   \$0.00   \$105.12     PUED DRIVER LOCAL 56 (ZONE 2)   For apprentice rates see "Apprentice-PILE DRIVER"   08/01/2020   \$103.05   \$9.40   \$23.12   \$0.00   \$135.57     PUED DRIVER LOCAL 56 (ZONE 2)   For apprentice rates see "Apprentice-PILE DRIVER"   08/01/2020   \$105.05   \$9.40   \$23.12   \$0.00   \$135.57     PUED DRIVER LOCAL 56 (ZONE 2)   For apprentice rates see "Apprentice-PILE DRIVER"   08/01/2020   \$105.05   \$9.40   \$23.12   \$0.00   \$135.57     PUED DRIVER LOCAL 56 (ZONE 2)   For apprentice rates see "Apprentice-PILE DRIVER"   08/01/2020   \$105.05   \$9.40   \$23.12   \$0.00   \$135.57     PUED DRIVER LOCAL 56 (ZONE 2)   For apprentice rates see "Apprentice-PILE DRIVER"   08/01/2020   \$105.05   \$9.40   \$23.12   \$0.00   \$135.57     PUED DRIVER LOCAL 56 (ZONE 2)   For apprentice rates see "Apprentice-PILE D		06/01/2023	\$54.29	\$14.25	\$16.05	\$0.00	\$84.59
12/01/2024   558.25   \$14.25   \$16.05   \$0.00   \$88.55     06/01/2025   \$59.53   \$14.25   \$16.05   \$0.00   \$89.83     12/01/2025   \$60.97   \$14.25   \$16.05   \$0.00   \$91.27     06/01/2026   \$62.25   \$14.25   \$16.05   \$0.00   \$92.55     12/01/2026   \$63.69   \$14.25   \$16.05   \$0.00   \$92.55     12/01/2026   \$63.69   \$14.25   \$16.05   \$0.00   \$93.99     For apprentice rates see "Apprentice- OPERATING ENGINEERS"   08/01/2020   \$68.70   \$9.40   \$23.12   \$0.00   \$101.22     DIVER TENDER   08/01/2020   \$49.07   \$9.40   \$23.12   \$0.00   \$81.59     PILE DRIVER LOCAL \$6 (ZONE 2)		12/01/2023	\$55.53	\$14.25	\$16.05	\$0.00	\$85.83
06/01/2025   \$59.53   \$14.25   \$16.05   \$0.00   \$89.83     12/01/2025   \$60.97   \$14.25   \$16.05   \$0.00   \$91.27     06/01/2026   \$62.25   \$14.25   \$16.05   \$0.00   \$92.55     12/01/2026   \$63.69   \$14.25   \$16.05   \$0.00   \$92.55     12/01/2026   \$63.69   \$14.25   \$16.05   \$0.00   \$93.99     For apprentice rates see "Apprentice- OPERATING ENGINEERS"     08/01/2020   \$68.70   \$9.40   \$23.12   \$0.00   \$101.22     For apprentice rates see "Apprentice- PILE DRIVER"   08/01/2020   \$49.07   \$9.40   \$23.12   \$0.00   \$81.59     DIVER TENDER PILE DRIVER (OCAL 56 (ZONE 2))   For apprentice rates see "Apprentice- PILE DRIVER"   08/01/2020   \$73.60   \$9.40   \$23.12   \$0.00   \$106.12     PILE DRIVER LOCAL 56 (ZONE 2)   For apprentice rates see "Apprentice- PILE DRIVER"   08/01/2020   \$73.60   \$9.40   \$23.12   \$0.00   \$106.12     PILE DRIVER LOCAL 56 (ZONE 2)   For apprentice rates see "Apprentice- PILE DRIVER"   08/01/2020   \$103.05   \$9.40   \$23.12   \$0.00   \$135.57     PILE DRIVER LOCAL 56 (ZONE 2)   For apprentice rates see "Apprentice- PILE DRIVER"   08/01/2020   \$26.77   \$6.67   \$3.93   \$0.16   \$37.53     DRAWBRIDGE OPERATOR (Construction)   07/01/2020   \$26.77   \$6.67   \$3.93   \$0.16   \$37.53     DRAWBRIDGE OPERATOR (Construction)   09/01/2022   \$46.35   \$11.50   \$16.18   \$0.00   \$74.03     ELECTRICIAN   09/01/2022   \$46.35   \$11.50   \$16.18   \$0.00   \$74.03     ELECTRICIANS LOCAL 223		06/01/2024	\$56.81	\$14.25	\$16.05	\$0.00	\$87.11
12/01/2025   \$60.97   \$14.25   \$16.05   \$0.00   \$91.27		12/01/2024	\$58.25	\$14.25	\$16.05	\$0.00	\$88.55
DIVER   12/01/2026   \$62.25   \$14.25   \$16.05   \$0.00   \$92.55     12/01/2026   \$63.69   \$14.25   \$16.05   \$0.00   \$93.99     For apprentice rates see "Apprentice-OPERATING ENGINEERS"   08/01/2020   \$68.70   \$9.40   \$23.12   \$0.00   \$101.22     For apprentice rates see "Apprentice-PILE DRIVER"   08/01/2020   \$49.07   \$9.40   \$23.12   \$0.00   \$81.59     DIVER TENDER   08/01/2020   \$49.07   \$9.40   \$23.12   \$0.00   \$81.59     For apprentice rates see "Apprentice-PILE DRIVER"   08/01/2020   \$73.60   \$9.40   \$23.12   \$0.00   \$106.12     PILE DRIVER LOCAL 56 (ZONE 2)   573.60   \$9.40   \$23.12   \$0.00   \$106.12     PILE DRIVER LOCAL 56 (ZONE 2)   573.60   \$9.40   \$23.12   \$0.00   \$105.12     For apprentice rates see "Apprentice-PILE DRIVER"   08/01/2020   \$73.60   \$9.40   \$23.12   \$0.00   \$105.57     PILE DRIVER LOCAL 56 (ZONE 2)   573.60   \$9.40   \$23.12   \$0.00   \$135.57     PILE DRIVER LOCAL 56 (ZONE 2)   573.60   \$9.40   \$23.12   \$0.00   \$135.57     PILE DRIVER LOCAL 56 (ZONE 2)   573.60   \$9.40   \$23.12   \$0.00   \$135.57     PILE DRIVER LOCAL 56 (ZONE 2)   573.60   \$9.40   \$23.12   \$0.00   \$135.57     PILE DRIVER LOCAL 56 (ZONE 2)   573.60   \$9.40   \$23.12   \$0.00   \$135.57     PILE DRIVER LOCAL 588   573.60   \$9.40   \$23.12   \$0.00   \$135.57     PILE DRIVER LOCAL 588   574.03   \$9.40   \$		06/01/2025	\$59.53	\$14.25	\$16.05	\$0.00	\$89.83
12/01/2026   \$63.69   \$14.25   \$16.05   \$0.00   \$93.99		12/01/2025	\$60.97	\$14.25	\$16.05	\$0.00	\$91.27
DIVER   08/01/2020   \$68.70   \$9.40   \$23.12   \$0.00   \$101.22		06/01/2026	\$62.25	\$14.25	\$16.05	\$0.00	\$92.55
DIVER   08/01/2020   \$68.70   \$9.40   \$23.12   \$0.00   \$101.22		12/01/2026	\$63.69	\$14.25	\$16.05	\$0.00	\$93.99
### PILE DRIVER LOCAL 56 (ZONE 2) For apprentice rates see "Apprentice-PILE DRIVER"  DIVER TENDER ### PILE DRIVER LOCAL 56 (ZONE 2) For apprentice rates see "Apprentice-PILE DRIVER"  DIVER TENDER (EFFLUENT) ### PILE DRIVER LOCAL 56 (ZONE 2) For apprentice rates see "Apprentice-PILE DRIVER"  DIVER/SLURRY (EFFLUENT) ### DRIVER LOCAL 56 (ZONE 2) For apprentice rates see "Apprentice-PILE DRIVER"  DIVER/SLURRY (EFFLUENT) ### DRIVER LOCAL 56 (ZONE 2) For apprentice rates see "Apprentice-PILE DRIVER"  DRAWBRIDGE OPERATOR (Construction) ### DRAWBRIDGE OPERATOR (Cons	For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
For apprentice rates see "Apprentice- PILE DRIVER"  DIVER TENDER  PILE DRIVER LOCAL 56 (ZONE 2)  For apprentice rates see "Apprentice- PILE DRIVER"  DIVER TENDER (EFFLUENT)  PILE DRIVER LOCAL 56 (ZONE 2)  For apprentice rates see "Apprentice- PILE DRIVER"  DIVER/SLURRY (EFFLUENT)  PILE DRIVER (SFFLUENT)  PILE DRIVER (CONE 2)  For apprentice rates see "Apprentice- PILE DRIVER"  DRAWBRIDGE OPERATOR (Construction)  DRAWBRIDGE - SEIU LOCAL 888  ELECTRICIAN  09/01/2022 \$46.35 \$11.50 \$16.18 \$0.00 \$74.03 \$10.00 \$1		08/01/2020	\$68.70	\$9.40	\$23.12	\$0.00	\$101.22
DIVER TENDER   98/01/2020   \$49.07   \$9.40   \$23.12   \$0.00   \$81.59							
### PILE DRIVER LOCAL 56 (ZONE 2)  For apprentice rates see "Apprentice- PILE DRIVER"  DIVER TENDER (EFFLUENT)  PILE DRIVER LOCAL 56 (ZONE 2)  For apprentice rates see "Apprentice- PILE DRIVER"  DIVER/SLURRY (EFFLUENT)  PILE DRIVER LOCAL 56 (ZONE 2)  For apprentice rates see "Apprentice- PILE DRIVER"  DRAWBRIDGE OPERATOR (Construction)  DRAWBRIDGE - SEIU LOCAL 888  ELECTRICIAN  ELECTRICIAN  ELECTRICIANS LOCAL 223  **9.40**  \$23.12**  \$0.00**  \$106.12  \$0.00**  \$135.57  \$6.67** \$3.93**  \$0.16**  \$37.53  \$17.53  \$16.18**  \$0.00**  \$74.03		00/01/2020	Φ40.07	ФО 40	¢22.12	<b>60.00</b>	Φ01.50
DIVER TENDER (EFFLUENT)  PILE DRIVER LOCAL 56 (ZONE 2)  For apprentice rates see "Apprentice- PILE DRIVER"  DIVER/SLURRY (EFFLUENT)  PILE DRIVER LOCAL 56 (ZONE 2)  For apprentice rates see "Apprentice- PILE DRIVER"  DRAWBRIDGE OPERATOR (Construction)  DRAWBRIDGE - SEIU LOCAL 888  DRAWBRIDGE - SEIU LOCAL 888  DRAWBRIDGE OPERATOR (Construction)  DRAWBRIDGE OPERATOR (Construction)  DRAWBRIDGE - SEIU LOCAL 888  DRAWBRIDGE OPERATOR (Construction)  DRAWBRIDGE - SEIU LOCAL 888		08/01/2020	\$49.07	\$9.40	\$23.12	\$0.00	\$81.59
### PILE DRIVER LOCAL 56 (ZONE 2)  For apprentice rates see "Apprentice- PILE DRIVER"  DIVER/SLURRY (EFFLUENT)  PILE DRIVER LOCAL 56 (ZONE 2)  For apprentice rates see "Apprentice- PILE DRIVER"  DRAWBRIDGE OPERATOR (Construction)  DRAWBRIDGE - SEIU LOCAL 888  ELECTRICIAN  ELECTRICIAN  ELECTRICIANS LOCAL 223  ##################################	For apprentice rates see "Apprentice- PILE DRIVER"						
DIVER/SLURRY (EFFLUENT)  PILE DRIVER LOCAL 56 (ZONE 2)  For apprentice rates see "Apprentice- PILE DRIVER"  DRAWBRIDGE OPERATOR (Construction)  DRAWBRIDGE - SEIU LOCAL 888  ELECTRICIAN  ELECTRICIAN  ELECTRICIANS LOCAL 223  08/01/2020 \$103.05 \$9.40 \$23.12 \$0.00 \$135.57  \$0.00 \$135.57  \$0.00 \$135.57  \$0.00 \$135.57  \$0.00 \$135.57  \$0.00 \$135.57		08/01/2020	\$73.60	\$9.40	\$23.12	\$0.00	\$106.12
### PILE DRIVER LOCAL 56 (ZONE 2)  For apprentice rates see "Apprentice- PILE DRIVER"  DRAWBRIDGE OPERATOR (Construction)  DRAWBRIDGE - SEIU LOCAL 888  ELECTRICIAN  ELECTRICIAN  60/01/2020  \$103.03  \$103.03  \$37.53  \$37.53  \$37.53	For apprentice rates see "Apprentice- PILE DRIVER"						
DRAWBRIDGE OPERATOR (Construction)  DRAWBRIDGE - SEIU LOCAL 888  ELECTRICIAN  ELECTRICIANS LOCAL 223  07/01/2020 \$26.77 \$6.67 \$3.93 \$0.16 \$37.53  \$74.03	,	08/01/2020	\$103.05	\$9.40	\$23.12	\$0.00	\$135.57
DRAWBRIDGE - SEIU LOCAL 888       \$37.33         ELECTRICIAN       09/01/2022       \$46.35       \$11.50       \$16.18       \$0.00       \$74.03         ELECTRICIANS LOCAL 223	For apprentice rates see "Apprentice- PILE DRIVER"						
ELECTRICIANS LOCAL 223	,	07/01/2020	\$26.77	\$6.67	\$3.93	\$0.16	\$37.53
ELECTRICIANS LOCAL 223	ELECTRICIAN	09/01/2022	\$46.35	\$11.50	\$16.18	\$0.00	\$74.03
	ELECTRICIANS LOCAL 223	09/01/2023	\$47.87	\$11.75	\$16.86	\$0.00	\$76.48

Issue Date: 10/11/2022 Wage Request Number: 20221007-038 Page 9 of 3.

Supplemental Unemployment

Pension

**Total Rate** 

	Step	ve Date - percent		Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate	
	1	40		\$18.54	\$11.50	\$0.56	\$0.00	\$30.60	
	2	45		\$20.86	\$11.50	\$0.63	\$0.00	\$32.99	
	3	50		\$23.18	\$11.50	\$0.70	\$0.00	\$35.38	
	4	55		\$25.49	\$11.50	\$7.35	\$0.00	\$44.34	
	5	60		\$27.81	\$11.50	\$7.86	\$0.00	\$47.17	
	6	65		\$30.13	\$11.50	\$8.37	\$0.00	\$50.00	
	7	70		\$32.45	\$11.50	\$8.89	\$0.00	\$52.84	
	8	75		\$34.76	\$11.50	\$9.40	\$0.00	\$55.66	
		ve Date -	09/01/2023	America Pasa Wasa	Haalth	Danaian	Supplemental Unemployment	Total Rate	
	Step 1	percent		Apprentice Base Wage		Pension			
	2	40		\$19.15	\$11.75	\$0.57	\$0.00	\$31.47	
		45		\$21.54	\$11.75	\$0.65	\$0.00	\$33.94	
	3	50		\$23.94	\$11.75	\$0.72	\$0.00	\$36.41	
	4	55		\$26.33	\$11.75	\$7.79	\$0.00	\$45.87	
	5	60		\$28.72	\$11.75	\$8.31	\$0.00	\$48.78	
	6	65		\$31.12	\$11.75	\$8.65	\$0.00	\$51.52	
	7	70		\$33.51	\$11.75	\$9.38	\$0.00	\$54.64	
	8	75		\$35.90	\$11.75	\$9.90	\$0.00	\$57.55	
į	Notes:								
								į	
	Apprei	ntice to Jo	urneyworker Ratio:2:3***						
ATOR CO				01/01/202	2 \$65.	62 \$16.03	\$20.21	\$0.00	\$10

Effectiv	ve Date -	01/01/2022				Supplemental		
Step	percent	Арр	prentice Base Wage	Health	Pension	Unemployment	Total Rate	
1	50		\$32.81	\$16.03	\$0.00	\$0.00	\$48.84	
2	55		\$36.09	\$16.03	\$20.21	\$0.00	\$72.33	
3	65		\$42.65	\$16.03	\$20.21	\$0.00	\$78.89	
4	70		\$45.93	\$16.03	\$20.21	\$0.00	\$82.17	
5	80		\$52.50	\$16.03	\$20.21	\$0.00	\$88.74	
Notes:	Steps 1-2 a	are 6 mos.; Steps 3-5 are 1 year					-	
Apprei	ntice to Jou	rneyworker Ratio:1:1						

ELEVATOR CONSTRUCTOR HELPER	01/01/2022	\$45.93	\$16.03	\$20.21	\$0.00	\$82.17
ELEVATOR CONSTRUCTORS LOCAL 4						

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rat
For apprentice rates see "Apprentice - ELEVATOR CONSTRUCTOR"					Chempioyment	
FENCE & GUARD RAIL ERECTOR (HEAVY & HIGHWAY)  LABORERS - ZONE 2 (HEAVY & HIGHWAY)	12/01/2021	\$35.66	\$9.10	\$16.64	\$0.00	\$61.40
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)						
FIELD ENG.INST.PERSON-BLDG,SITE,HVY/HWY  OPERATING ENGINEERS LOCAL 4	05/01/2022	\$47.18	\$14.00	\$16.05	\$0.00	\$77.23
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
FIELD ENG.PARTY CHIEF-BLDG,SITE,HVY/HWY OPERATING ENGINEERS LOCAL 4	05/01/2022	\$48.72	\$14.00	\$16.05	\$0.00	\$78.77
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
FIELD ENG.ROD PERSON-BLDG,SITE,HVY/HWY OPERATING ENGINEERS LOCAL 4	05/01/2022	\$23.33	\$14.00	\$16.05	\$0.00	\$53.38
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
FIRE ALARM INSTALLER ELECTRICIANS LOCAL 223	09/01/2020	\$43.66	\$10.90	\$14.66	\$0.00	\$69.22
For apprentice rates see "Apprentice- ELECTRICIAN"						
FIRE ALARM REPAIR / MAINTENANCE / COMMISSIONING ELECTRICIANS	09/01/2020	\$36.86	\$10.90	\$12.45	\$0.00	\$60.21
LOCAL 223 For apprentice rates see "Apprentice- TELECOMMUNICATIONS TECHNICIAN"						
FIREMAN (ASST. ENGINEER)	06/01/2022	\$42.53	\$14.25	\$16.05	\$0.00	\$72.83
OPERATING ENGINEERS LOCAL 4	12/01/2022	\$43.54	\$14.25	\$16.05	\$0.00	\$73.84
	06/01/2023	\$44.56	\$14.25	\$16.05	\$0.00	\$74.86
	12/01/2023	\$45.57	\$14.25	\$16.05	\$0.00	\$75.87
	06/01/2024	\$46.63	\$14.25	\$16.05	\$0.00	\$76.93
	12/01/2024	\$47.81	\$14.25	\$16.05	\$0.00	\$78.11
	06/01/2025	\$48.87	\$14.25	\$16.05	\$0.00	\$79.17
	12/01/2025	\$50.04	\$14.25	\$16.05	\$0.00	\$80.34
	06/01/2026	\$51.10	\$14.25	\$16.05	\$0.00	\$81.40
	12/01/2026	\$52.28	\$14.25	\$16.05	\$0.00	\$82.58
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
FLAGGER & SIGNALER (HEAVY & HIGHWAY) LABORERS - ZONE 2 (HEAVY & HIGHWAY)	12/01/2021	\$24.50	\$9.10	\$16.64	\$0.00	\$50.24
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)						
FLOORCOVERER FLOORCOVERERS LOCAL 2168 ZONE I	03/01/2022	\$49.93	\$8.68	\$20.27	\$0.00	\$78.88

 Issue Date:
 10/11/2022
 Wage Request Number:
 20221007-038
 Page 11 of 33

Apprentice -	FLOORCOVERER - Local 2168 Zone I
--------------	----------------------------------

Effective Date - 0	3/01/2022			Supplemental		
Step percent	Apprentice Base Wage	Health	Pension	Unemployment	Total Rate	
1 50	\$24.97	\$8.68	\$1.79	\$0.00	\$35.44	
2 55	\$27.46	\$8.68	\$1.79	\$0.00	\$37.93	
3 60	\$29.96	\$8.68	\$14.90	\$0.00	\$53.54	
4 65	\$32.45	\$8.68	\$14.90	\$0.00	\$56.03	
5 70	\$34.95	\$8.68	\$16.69	\$0.00	\$60.32	
6 75	\$37.45	\$8.68	\$16.69	\$0.00	\$62.82	
7 80	\$39.94	\$8.68	\$18.48	\$0.00	\$67.10	
8 85	\$42.44	\$8.68	\$18.48	\$0.00	\$69.60	
	/17; 45/45/55/55/70/70/80/80 (1500hr Steps) 2.94/ 3&4 \$39.66/ 5&6 \$60.32/ 7&8 \$67.10					
FORK LIFT/CHERRY PICKER	<u> </u>	2 \$52.38	¢14.25	\$16.05	\$0.00	\$82.68
OPERATING ENGINEERS LOCAL 4	06/01/2022 12/01/2022		\$14.25 \$14.25	\$16.05	\$0.00	\$83.93
	06/01/2023		\$14.25 \$14.25	\$16.05	\$0.00	\$85.18
	12/01/2023		\$14.25	\$16.05	\$0.00	\$86.43
	06/01/202		\$14.25 \$14.25	\$16.05	\$0.00	\$87.73
	12/01/2024		\$14.25	\$16.05	\$0.00	\$89.18
	06/01/2025		\$14.25	\$16.05	\$0.00	\$90.48
	12/01/2025		\$14.25	\$16.05	\$0.00	\$91.93
	06/01/2026		\$14.25	\$16.05	\$0.00	\$93.23
	12/01/2026		\$14.25	\$16.05	\$0.00	\$94.68
For apprentice rates see "Apprentice- OPE			4-11-2			47
GENERATOR/LIGHTING PLANT/F	IEATERS 06/01/2022	2 \$34.26	\$14.25	\$16.05	\$0.00	\$64.56
OPERATING ENGINEERS LOCAL 4	12/01/2022	2 \$35.08	\$14.25	\$16.05	\$0.00	\$65.38
	06/01/2023	\$35.90	\$14.25	\$16.05	\$0.00	\$66.20
	12/01/2023	3 \$36.72	\$14.25	\$16.05	\$0.00	\$67.02
	06/01/2024	\$37.57	\$14.25	\$16.05	\$0.00	\$67.87
	12/01/2024	\$38.52	\$14.25	\$16.05	\$0.00	\$68.82
	06/01/2025	\$39.37	\$14.25	\$16.05	\$0.00	\$69.67
	12/01/2025	\$40.32	\$14.25	\$16.05	\$0.00	\$70.62
	06/01/2026	\$41.18	\$14.25	\$16.05	\$0.00	\$71.48
	12/01/2026	\$42.13	\$14.25	\$16.05	\$0.00	\$72.43
For apprentice rates see "Apprentice- OPE	DDIED DIED IN INCOME					
GLAZIER (GLASS PLANK/AIR BA SYSTEMS)	RRIER/INTERIOR 06/01/2020	\$39.18	\$10.80	\$10.45	\$0.00	\$60.43

GLAZIERS LOCAL 1333

**Issue Date:** 10/11/2022 20221007-038 Page 12 of 33

Pension

Apprentice -	GLAZIER - Local 1333
Effective Date	06/01/2020

Liiccu	ve Date -	06/01/2020				Supplemental	
Step	percent		Apprentice Base Wage	Health	Pension	Unemployment	Total Rate
1	50		\$19.59	\$10.80	\$1.80	\$0.00	\$32.19
2	56		\$22.04	\$10.80	\$1.80	\$0.00	\$34.64
3	63		\$24.49	\$10.80	\$2.45	\$0.00	\$37.74
4	69		\$26.94	\$10.80	\$2.45	\$0.00	\$40.19
5	75		\$29.39	\$10.80	\$3.15	\$0.00	\$43.34
6	81		\$31.83	\$10.80	\$3.15	\$0.00	\$45.78
7	88		\$34.28	\$10.80	\$10.45	\$0.00	\$55.53
8	94		\$36.73	\$10.80	\$10.45	\$0.00	\$57.98

Apprentice to Journeyworker Ratio:1:3
---------------------------------------

HOISTING ENGINEER/CRANES/GRADALLS	06/01/2022	\$52.38	\$14.25	\$16.05	\$0.00	\$82.68
OPERATING ENGINEERS LOCAL 4	12/01/2022	\$53.63	\$14.25	\$16.05	\$0.00	\$83.93
	06/01/2023	\$54.88	\$14.25	\$16.05	\$0.00	\$85.18
	12/01/2023	\$56.13	\$14.25	\$16.05	\$0.00	\$86.43
	06/01/2024	\$57.43	\$14.25	\$16.05	\$0.00	\$87.73
	12/01/2024	\$58.88	\$14.25	\$16.05	\$0.00	\$89.18
	06/01/2025	\$60.18	\$14.25	\$16.05	\$0.00	\$90.48
	12/01/2025	\$61.63	\$14.25	\$16.05	\$0.00	\$91.93
	06/01/2026	\$62.93	\$14.25	\$16.05	\$0.00	\$93.23
	12/01/2026	\$64.38	\$14.25	\$16.05	\$0.00	\$94.68

Wage Request Number: 20221007-038 **Issue Date:** 10/11/2022 Page 13 of 33 **Apprentice -** OPERATING ENGINEERS - Local 4

Pension

**Total Rate** 

1   55		Step percer		Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate	
Page		1 55		\$28.81	\$14.00	\$0.00	\$0.00	\$42.81	
3   65   \$34.05   \$14.00   \$16.05   \$0.00   \$64.10     4   70   \$36.67   \$14.00   \$16.05   \$0.00   \$66.72     5   75   \$39.29   \$14.00   \$16.05   \$0.00   \$66.72     6   80   \$44.90   \$14.00   \$16.05   \$0.00   \$71.95     7   85   \$44.52   \$14.00   \$16.05   \$0.00   \$71.95     8   90   \$47.14   \$14.00   \$16.05   \$0.00   \$77.19      Effective Date - 12/01/2022   \$47.14   \$14.00   \$16.05   \$0.00   \$77.19      Effective Date - 12/01/2022   \$49.00   \$16.05   \$0.00   \$60.00		2 60							
Signature   Sign		3 65							
S		4 70		\$36.67	\$14.00	\$16.05	\$0.00	\$66.72	
Receivable   Rec		5 75							
Part		6 80							
Refrective   Date   12/01/2022   Supplemental   Pension   Supplemental   Date   Pension   Supplemental   Pension   University   Pension   P		7 85							
Step   percent   Apprentice Base Wage   Health   Pension   Unemployment   Total Rate		8 90							
Step		Effective Date	- 12/01/2022				Supplemental		
2 60 \$32.18 \$14.25 \$16.05 \$0.00 \$62.48 3 65 \$34.86 \$14.25 \$16.05 \$0.00 \$65.16 4 70 \$37.54 \$14.25 \$16.05 \$0.00 \$65.16 4 70 \$37.54 \$14.25 \$16.05 \$0.00 \$67.84 5 75 \$40.22 \$14.25 \$16.05 \$0.00 \$70.52 6 80 \$42.90 \$14.25 \$16.05 \$0.00 \$73.20 7 85 \$45.59 \$14.25 \$16.05 \$0.00 \$73.20 Notes:    Notes:		Step percer	nt	Apprentice Base Wage	Health	Pension		Total Rate	
\$\frac{3}{4} \ 70 \ \$33.86 \ \$14.25 \ \$16.05 \ \$0.00 \ \$65.16 \ 4 \ 70 \ \$37.54 \ \$14.25 \ \$16.05 \ \$0.00 \ \$67.84 \ 5 \ 75 \ \$40.22 \ \$14.25 \ \$16.05 \ \$0.00 \ \$67.84 \ 5 \ 75 \ \$40.22 \ \$14.25 \ \$16.05 \ \$0.00 \ \$70.52 \ 6 \ 80 \ \$42.90 \ \$14.25 \ \$16.05 \ \$0.00 \ \$73.20 \ 7 \ 85 \ \$45.59 \ \$14.25 \ \$16.05 \ \$0.00 \ \$75.89 \ 8 \ 90 \ \$48.27 \ \$14.25 \ \$16.05 \ \$0.00 \ \$78.57 \ \end{align*}    Notes:		1 55		\$29.50	\$14.25	\$0.00	\$0.00	\$43.75	
4 70 \$37.54 \$14.25 \$16.05 \$0.00 \$67.84 \$5 75 \$40.22 \$14.25 \$16.05 \$0.00 \$70.52 \$6 80 \$42.90 \$14.25 \$16.05 \$0.00 \$70.52 \$6 80 \$42.90 \$14.25 \$16.05 \$0.00 \$73.20 \$73.20 \$7 85 \$40.22 \$14.25 \$16.05 \$0.00 \$73.20 \$75.89 \$8 90 \$48.27 \$14.25 \$16.05 \$0.00 \$75.89 \$71.80 \$90 \$48.27 \$14.25 \$16.05 \$0.00 \$78.57 \$85 \$90 \$48.27 \$14.25 \$16.05 \$0.00 \$78.57 \$85 \$90 \$48.27 \$14.25 \$16.05 \$0.00 \$78.57 \$85 \$90 \$48.27 \$14.25 \$16.05 \$0.00 \$78.57 \$85 \$90 \$48.27 \$14.25 \$16.05 \$0.00 \$78.57 \$85 \$90 \$48.27 \$14.25 \$16.05 \$0.00 \$78.57 \$85 \$90 \$48.27 \$14.25 \$16.05 \$0.00 \$78.57 \$85 \$90 \$90 \$71.80 \$90 \$90 \$90 \$90 \$90 \$90 \$90 \$90 \$90 \$9		2 60		\$32.18	\$14.25	\$16.05	\$0.00	\$62.48	
Section   Sect		3 65		\$34.86	\$14.25	\$16.05	\$0.00	\$65.16	
Notes:		4 70		\$37.54	\$14.25	\$16.05	\$0.00	\$67.84	
Notes:		5 75		\$40.22	\$14.25	\$16.05	\$0.00	\$70.52	
Notes:		6 80		\$42.90	\$14.25	\$16.05	\$0.00	\$73.20	
Notes:		7 85		\$45.59	\$14.25	\$16.05	\$0.00	\$75.89	
Apprentice to Journeyworker Ratio:1:6  VAC (DUCTWORK) EETMETAL WORKERS LOCAL 17 - B  For apprentice rates see "Apprentice- SHEET METAL WORKER"  VAC (ELECTRICAL CONTROLS) O9/01/2020 S43.66 S10.90 S14.66 S0.00 S69.2  ECTRICIANS LOCAL 223 For apprentice rates see "Apprentice- ELECTRICIAN"  VAC (TESTING AND BALANCING - AIR) EETMETAL WORKERS LOCAL 17 - B For apprentice rates see "Apprentice- SHEET METAL WORKER"  VAC (TESTING AND BALANCING - WATER) UAGE OF A PIPEFITTER LOCAL 51 For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC UMBERS & PIPEFITTERS LOCAL 51 For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC UMBERS & PIPEFITTERS LOCAL 51 For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC UMBERS & PIPEFITTERS LOCAL 51 For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VDRAULIC DRILLS O6/01/2022 S37.06 S9.10 S16.64 S0.00 S62.8 O6/01/2023 S38.81 S9.10 S16.64 S0.00 S63.6 O6/01/2023 S38.81 S9.10 S16.64 S0.00 S65.4		8 90		\$48.27	\$14.25	\$16.05	\$0.00	\$78.57	
AC (DUCTWORK)		Notes:							
VAC (DUCTWORK)  IEETMETAL WORKERS LOCAL 17 - B  For apprentice rates see "Apprentice- SHEET METAL WORKER"  VAC (ELECTRICAL CONTROLS)  ECTRICIANS LOCAL 223  For apprentice rates see "Apprentice- ELECTRICIAN"  VAC (TESTING AND BALANCING - AIR)  For apprentice rates see "Apprentice- SHEET METAL WORKER"  VAC (TESTING AND BALANCING - WATER)  For apprentice rates see "Apprentice- SHEET METAL WORKER"  VAC (TESTING AND BALANCING - WATER)  VAC (TESTING AND BALANCING - WATER)  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR ADDRESS & PIPEFITTER SUCAL 51  FOR ADDRESS &		ļ							
For apprentice rates see "Apprentice- ELECTRICIAN"  VAC (ELECTRICAL CONTROLS)  ECTRICIANS LOCAL 223  For apprentice rates see "Apprentice- ELECTRICIAN"  VAC (TESTING AND BALANCING - AIR)  For apprentice rates see "Apprentice- SHEET METAL WORKER"  VAC (TESTING AND BALANCING - WATER)  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC (TESTING AND BALANCING - WATER)  WAC MECHANIC  WAC (TESTING AND BALANCING - WATER)  WAC MECHANIC  WAC MECHANIC  WAC MECHANIC  WAC MECHANIC  WAC MECHANIC  WAC MECHANIC  WAS A PIPEFITTER' or "PLUMBER/PIPEFITTER"  VAC MECHANIC  WAC MECH		Apprentice to	Journeyworker Ratio:1:6						
VAC (ELECTRICAL CONTROLS)  ### CFOR apprentice rates see "Apprentice- ELECTRICIAN"  VAC (TESTING AND BALANCING - AIR)  #### AIR PROPERTITERS LOCAL 17 - B  For apprentice rates see "Apprentice- SHEET METAL WORKER"  VAC (TESTING AND BALANCING - WATER)  ### VAC (MECHANIC  ### UMBERS & PIPEFITTERS LOCAL 51  ### For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  ### VAC MECHANIC  ### UMBERS & PIPEFITTERS LOCAL 51  ### For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  ### VAC MECHANIC  #			В	04/01/2022	2 \$38.91	\$13.65	\$17.15	\$2.09	\$71.80
For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR ap	For apprentice 1	rates see "Apprentic	e- SHEET METAL WORKER"						
VAC (TESTING AND BALANCING - AIR)  For apprentice rates see "Apprentice- SHEET METAL WORKER"  VAC (TESTING AND BALANCING - WATER)  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  FOR apprentice rates see "Apprentice- PIPEFITTER"  VAC MECHANIC  OR ASSOCIATE AS SA	*		ROLS)	09/01/2020	\$43.66	\$10.90	\$14.66	\$0.00	\$69.22
For apprentice rates see "Apprentice- SHEET METAL WORKER"  VAC (TESTING AND BALANCING -WATER)  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VDRAULIC DRILLS  BORRES - ZONE 2  12/01/2022 \$37.06 \$9.10 \$16.64 \$0.00 \$62.8  06/01/2023 \$38.81 \$9.10 \$16.64 \$0.00 \$63.6  12/01/2023 \$38.81 \$9.10 \$16.64 \$0.00 \$64.5  12/01/2023 \$39.71 \$9.10 \$16.64 \$0.00 \$65.4	For apprentice i	rates see "Apprentic	e- ELECTRICIAN"						
VAC (TESTING AND BALANCING -WATER)  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  YDRAULIC DRILLS  BORERS - ZONE 2  12/01/2022  \$37.06  \$9.10  \$16.64  \$0.00  \$62.8  66/01/2022  \$37.91  \$9.10  \$16.64  \$0.00  \$63.6  66/01/2023  \$38.81  \$9.10  \$16.64  \$0.00  \$64.5  12/01/2023  \$39.71  \$9.10  \$16.64  \$0.00  \$65.4	,		*	04/01/2022	2 \$38.91	\$13.65	\$17.15	\$2.09	\$71.80
### For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  WAC MECHANIC ### UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  #### YDRAULIC DRILLS ### 10.15 #19.95 #0.00 #76.5  ### BORERS - ZONE 2 #12/01/2022 #37.06 #9.10 #16.64 #0.00 #63.6  ### 06/01/2023 #38.81 #9.10 #16.64 #0.00 #64.5  ### 12/01/2023 #39.71 #9.10 #16.64 #0.00 #64.5	For apprentice 1	rates see "Apprentic	e- SHEET METAL WORKER"						
WAC MECHANIC  UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  VDRAULIC DRILLS  BORERS - ZONE 2  12/01/2022 \$37.06 \$9.10 \$16.64 \$0.00 \$62.8  12/01/2022 \$37.91 \$9.10 \$16.64 \$0.00 \$63.6  06/01/2023 \$38.81 \$9.10 \$16.64 \$0.00 \$64.5  12/01/2023 \$39.71 \$9.10 \$16.64 \$0.00 \$65.4				08/30/202	1 \$46.49	\$10.15	\$19.95	\$0.00	\$76.59
### UMBERS & PIPEFITTERS LOCAL 51  For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"  **YDRAULIC DRILLS** **BORERS - ZONE 2**  12/01/2022** \$37.06** \$9.10** \$16.64** \$0.00** \$62.8**  12/01/2023** \$38.81** \$9.10** \$16.64** \$0.00** \$64.5**  12/01/2023** \$39.71** \$9.10** \$16.64** \$0.00** \$64.5**	For apprentice 1	rates see "Apprentic	e- PIPEFITTER" or "PLUMBER/PIPE	FITTER"					
YDRAULIC DRILLS BORERS - ZONE 2  12/01/2022 \$37.06 \$9.10 \$16.64 \$0.00 \$62.8  12/01/2022 \$37.91 \$9.10 \$16.64 \$0.00 \$63.6  06/01/2023 \$38.81 \$9.10 \$16.64 \$0.00 \$64.5  12/01/2023 \$39.71 \$9.10 \$16.64 \$0.00 \$65.4			51	08/30/202	1 \$46.49	\$10.15	\$19.95	\$0.00	\$76.59
BORERS - ZONE 2 12/01/2022 \$37.00 \$7.10 \$16.64 \$0.00 \$63.6 06/01/2023 \$38.81 \$9.10 \$16.64 \$0.00 \$64.5 12/01/2023 \$39.71 \$9.10 \$16.64 \$0.00 \$65.4	For apprentice i	rates see "Apprentic	e- PIPEFITTER" or "PLUMBER/PIPE	FITTER"					
12/01/2022 \$37.91 \$9.10 \$16.64 \$0.00 \$63.6 06/01/2023 \$38.81 \$9.10 \$16.64 \$0.00 \$64.5 12/01/2023 \$39.71 \$9.10 \$16.64 \$0.00 \$65.4				06/01/2022	2 \$37.06	\$9.10	\$16.64	\$0.00	\$62.80
12/01/2023 \$39.71 \$9.10 \$16.64 \$0.00 \$65.4	dukeks - ZUNE	2		12/01/2022	2 \$37.91	\$9.10	\$16.64	\$0.00	\$63.65
				06/01/2023	3 \$38.81	\$9.10	\$16.64	\$0.00	\$64.55
······································	For apprentice i	rates see "Apprentic	e- LABORER"	12/01/2023	3 \$39.71	\$9.10	\$16.64	\$0.00	\$65.45

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
HYDRAULIC DRILLS (HEAVY & HIGHWAY)  LABORERS - ZONE 2 (HEAVY & HIGHWAY)	12/01/2021	\$36.16	\$9.10	\$16.64	\$0.00	\$61.90
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)						
INSULATOR (PIPES & TANKS) HEAT & FROST INSULATORS LOCAL 6 (SOUTHERN MASS)	09/01/2022	\$48.95	\$13.80	\$17.14	\$0.00	\$79.89

• •	ntice - ASBESTOS INSULATOR	? (Pipes & Tanks) - Local 6 Soi	ıthern MA			
	ve Date - 09/01/2022	Apprentice Base Wage	Uaalth	Pension	Supplemental Unemployment	Total Rate
Step	percent	Apprentice base wage	пеанн	rension	Onemployment	Total Nate
1	50	\$24.48	\$13.80	\$12.42	\$0.00	\$50.70
2	60	\$29.37	\$13.80	\$13.36	\$0.00	\$56.53
3	70	\$34.27	\$13.80	\$14.31	\$0.00	\$62.38
4	80	\$39.16	\$13.80	\$15.25	\$0.00	\$68.21

Steps are 1 year

Apprentice to Journeyworker Ratio:1:4

Notes:

IRONWORKER/WELDER 03/16/2021 \$42.46 \$7.70 \$17.10 \$0.00 \$67.26

Appre	ntice - IRONWOR	KER - Local 3/				
Effect	ive Date - 03/16/2	2021				Supplemental
Step	percent		Apprentice Base Wage	Health	Pension	Unemployment
1	70		\$29.72	\$7.70	\$17.10	\$0.00
2	75		\$31.85	\$7.70	\$17.10	\$0.00

1	70	\$29.72	\$7.70	\$17.10	\$0.00	\$54.52
2	75	\$31.85	\$7.70	\$17.10	\$0.00	\$56.65
3	80	\$33.97	\$7.70	\$17.10	\$0.00	\$58.77
4	85	\$36.09	\$7.70	\$17.10	\$0.00	\$60.89
5	90	\$38.21	\$7.70	\$17.10	\$0.00	\$63.01
6	95	\$40.34	\$7.70	\$17.10	\$0.00	\$65.14

Total Rate

Notes:	 	 	 

r r						
JACKHAMMER & PAVING BREAKER OPERATOR	06/01/2022	\$36.56	\$9.10	\$16.64	\$0.00	\$62.30
LABORERS - ZONE 2	12/01/2022	\$37.41	\$9.10	\$16.64	\$0.00	\$63.15
	06/01/2023	\$38.31	\$9.10	\$16.64	\$0.00	\$64.05
	12/01/2023	\$39.21	\$9.10	\$16.64	\$0.00	\$64.95
For apprentice rates see "Apprentice- LABORER"						
LABORER	06/01/2022	\$36.31	\$9.10	\$16.64	\$0.00	\$62.05
LABORERS - ZONE 2	12/01/2022	\$37.16	\$9.10	\$16.64	\$0.00	\$62.90
	06/01/2023	\$38.06	\$9.10	\$16.64	\$0.00	\$63.80
	12/01/2023	\$38.96	\$9.10	\$16.64	\$0.00	\$64.70

**Issue Date:** 10/11/2022 **Wage Request Number:** 20221007-038 **Page 15 of 33** 

**Total Rate** 

For apprentice rates see "Apprentice- LABORER"

	Effecti					Supplemental		
-	Step	percent	Apprentice Base Wage	Health	Pension	Unemployment	Total Rate	
	1	60	\$21.79	\$9.10	\$16.64	\$0.00	\$47.53	
	2	70	\$25.42	\$9.10	\$16.64	\$0.00	\$51.16	
	3	80	\$29.05	\$9.10	\$16.64	\$0.00	\$54.79	
	4	90	\$32.68	\$9.10	\$16.64	\$0.00	\$58.42	
1	Effecti	ve Date - 12/01/2022				Supplemental		
;	Step	percent	Apprentice Base Wage	Health	Pension	Unemployment	Total Rate	
	1	60	\$22.30	\$9.10	\$16.64	\$0.00	\$48.04	
	2	70	\$26.01	\$9.10	\$16.64	\$0.00	\$51.75	
	3	80	\$29.73	\$9.10	\$16.64	\$0.00	\$55.47	
	4	90	\$33.44	\$9.10	\$16.64	\$0.00	\$59.18	
_  1	Notes:							
[								
BORER (HEA		ntice to Journeyworker Ratio:1:5						
ORERS - ZONE 2	2 (HEAV)	√ & HIGHWAY)	12/01/2021	\$35.41	\$9.10			
1	Appren	v & HIGHWAY) ntice - LABORER (Heavy & Highw ve Date - 12/01/2021				Sunnlemental		
, 1	Appren	ntice - LABORER (Heavy & Highw			Pension	Supplemental Unemployment	Total Rate	
<i>I</i> ]	Apprer Effectiv	atice - <i>LABORER (Heavy &amp; Highw</i> we <b>Date</b> - 12/01/2021	ay) - Zone 2				Total Rate \$46.99	
2 1 3	Apprer Effectiv	ntice - LABORER (Heavy & Highw we Date - 12/01/2021 percent	ay) - Zone 2  Apprentice Base Wage	Health	Pension	Unemployment		
1 1 :	Apprer Effective Step	ntice - LABORER (Heavy & Highw we Date - 12/01/2021 percent	ay) - Zone 2  Apprentice Base Wage \$21.25	Health \$9.10	Pension \$16.64	Unemployment \$0.00	\$46.99	
1 1 :	Apprer Effective Step 1	ntice - LABORER (Heavy & Highwave Date - 12/01/2021 percent 60 70	Apprentice Base Wage \$21.25 \$24.79	Health \$9.10 \$9.10	Pension \$16.64 \$16.64	\$0.00 \$0.00	\$46.99 \$50.53	
2 1 3 -	Apprer Effectiv Step 1 2 3	ntice - LABORER (Heavy & Highwore Date - 12/01/2021 percent 60 70 80	Apprentice Base Wage \$21.25 \$24.79 \$28.33	Health \$9.10 \$9.10 \$9.10	Pension \$16.64 \$16.64 \$16.64	\$0.00 \$0.00 \$0.00	\$46.99 \$50.53 \$54.07	
2 1 3 -	Appren Effective Step 1 2 3 4	ntice - LABORER (Heavy & Highwore Date - 12/01/2021 percent 60 70 80	Apprentice Base Wage \$21.25 \$24.79 \$28.33	Health \$9.10 \$9.10 \$9.10	Pension \$16.64 \$16.64 \$16.64	\$0.00 \$0.00 \$0.00	\$46.99 \$50.53 \$54.07	
	Apprer Effective Step 1 2 3 4 Notes:	percent  60  70  80  90  ntice to Journeyworker Ratio:1:5	Apprentice Base Wage \$21.25 \$24.79 \$28.33	Health \$9.10 \$9.10 \$9.10	Pension \$16.64 \$16.64 \$16.64	\$0.00 \$0.00 \$0.00	\$46.99 \$50.53 \$54.07	
BORER: CAR	Apprer Effective Step 1 2 3 4 Notes: Apprer	percent  60  70  80  90  ntice to Journeyworker Ratio:1:5	Apprentice Base Wage \$21.25 \$24.79 \$28.33	Health \$9.10 \$9.10 \$9.10 \$9.10	Pension \$16.64 \$16.64 \$16.64	\$0.00 \$0.00 \$0.00	\$46.99 \$50.53 \$54.07	\$62.05
-    -                   	Apprer Effective Step 1 2 3 4 Notes: Apprer	percent  60  70  80  90  ntice to Journeyworker Ratio:1:5	Apprentice Base Wage \$21.25 \$24.79 \$28.33 \$31.87	Health \$9.10 \$9.10 \$9.10 \$9.10 \$9.36	Pension \$16.64 \$16.64 \$16.64 \$19.10	\$0.00 \$0.00 \$0.00 \$0.00	\$46.99 \$50.53 \$54.07 \$57.61	\$62.05 \$62.90
BORER: CAF	Apprer Effective Step 1 2 3 4 Notes: Apprer	percent  60  70  80  90  ntice to Journeyworker Ratio:1:5	Apprentice Base Wage \$21.25 \$24.79 \$28.33 \$31.87	Health \$9.10 \$9.10 \$9.10 \$9.10 \$9.10 \$9.10	Pension \$16.64 \$16.64 \$16.64 \$19.10	\$0.00 \$0.00 \$0.00 \$0.00 \$16.64	\$46.99 \$50.53 \$54.07 \$57.61	\$62.90
BORER: CAF	Apprer Effective Step 1 2 3 4 Notes: Apprer	percent  60  70  80  90  — — — — — — — — — — — — — — — — — — —	Apprentice Base Wage \$21.25 \$24.79 \$28.33 \$31.87	Health \$9.10 \$9.10 \$9.10 \$9.10 \$9.10 \$9.10 \$9.10 \$36.31 \$37.16 \$38.06	Pension \$16.64 \$16.64 \$16.64 \$16.64 \$9.10 \$9.10	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00	\$46.99 \$50.53 \$54.07 \$57.61	
BORER: CAF	Apprer Effective Step 1 2 3 4 Notes: Apprer RPENT 2	ntice - LABORER (Heavy & Highwaye Date - 12/01/2021 percent 60 70 80 90	Apprentice Base Wage \$21.25 \$24.79 \$28.33 \$31.87	Health \$9.10 \$9.10 \$9.10 \$9.10 \$9.10 \$9.10 \$9.10 \$36.31 \$37.16 \$38.06 \$38.96	Pension \$16.64 \$16.64 \$16.64 \$19.10 \$9.10 \$9.10 \$9.10	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$16.64 \$16.64 \$16.64	\$46.99 \$50.53 \$54.07 \$57.61 \$0.00 \$0.00 \$0.00 \$0.00	\$62.90 \$63.80 \$64.70
BORER: CAF For apprentice ra BORER: CEM	Apprer Effective Step 1 2 3 4 Notes: Apprer RPENT 2	percent  60  70  80  90  — — — — — — — — — — — — — — — — — — —	Apprentice Base Wage \$21.25 \$24.79 \$28.33 \$31.87	Health \$9.10 \$9.10 \$9.10 \$9.10 \$9.10 \$36.31 \$37.16 \$38.06 \$38.96	Pension \$16.64 \$16.64 \$16.64 \$16.64 \$9.10 \$9.10	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$16.64 \$16.64 \$16.64 \$16.64	\$46.99 \$50.53 \$54.07 \$57.61   \$0.00 \$0.00 \$0.00	\$62.90 \$63.80 \$64.70 \$62.05
BORER: CAF For apprentice ra BORER: CEM	Apprer Effective Step 1 2 3 4 Notes: Apprer RPENT 2	ntice - LABORER (Heavy & Highwaye Date - 12/01/2021 percent 60 70 80 90	Apprentice Base Wage \$21.25 \$24.79 \$28.33 \$31.87	Health \$9.10 \$9.10 \$9.10 \$9.10 \$9.10 \$36.31 \$37.16 \$38.06 \$38.96	Pension \$16.64 \$16.64 \$16.64 \$19.10 \$9.10 \$9.10 \$9.10	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$16.64 \$16.64 \$16.64	\$46.99 \$50.53 \$54.07 \$57.61 \$0.00 \$0.00 \$0.00 \$0.00	\$62.90 \$63.80 \$64.70
BORER: CAF	Apprer Effective Step 1 2 3 4 Notes: Apprer RPENT 2	ntice - LABORER (Heavy & Highwaye Date - 12/01/2021 percent 60 70 80 90	Apprentice Base Wage \$21.25 \$24.79 \$28.33 \$31.87	Health \$9.10 \$9.10 \$9.10 \$9.10 \$9.10 \$36.31 \$37.16 \$38.96 \$38.96	Pension \$16.64 \$16.64 \$16.64 \$16.64 \$9.10 \$9.10 \$9.10 \$9.10	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$16.64 \$16.64 \$16.64 \$16.64	\$46.99 \$50.53 \$54.07 \$57.61 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00	\$62.90 \$63.80 \$64.70 \$62.03

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
LABORER: HAZARDOUS WASTE/ASBESTOS REMOVER	06/01/2022	\$36.40	\$9.10	\$16.70	\$0.00	\$62.20
LABORERS - ZONE 2	12/01/2022	\$37.25	\$9.10	\$16.70	\$0.00	\$63.05
	06/01/2023	\$38.15	\$9.10	\$16.70	\$0.00	\$63.95
	12/01/2023	\$39.05	\$9.10	\$16.70	\$0.00	\$64.85
For apprentice rates see "Apprentice- LABORER"						
LABORER: MASON TENDER LABORERS - ZONE 2	06/01/2022	\$36.56	\$9.10	\$16.64	\$0.00	\$62.30
ELDOIGHO ZONE Z	12/01/2022	\$37.41	\$9.10	\$16.64	\$0.00	\$63.15
	06/01/2023	\$38.31	\$9.10	\$16.64	\$0.00	\$64.05
B	12/01/2023	\$39.21	\$9.10	\$16.64	\$0.00	\$64.95
For apprentice rates see "Apprentice- LABORER"  LABORER: MASON TENDER (HEAVY & HIGHWAY)	12/01/2021	\$35.66	\$9.10	\$16.64	\$0.00	\$61.40
LABORERS - ZONE 2 (HEAVY & HIGHWAY)						
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)						
LABORER: MULTI-TRADE TENDER LABORERS - ZONE 2	06/01/2022	\$36.31	\$9.10	\$16.64	\$0.00	\$62.05
ABOIGNO - ZOIL Z	12/01/2022	\$37.16	\$9.10	\$16.64	\$0.00	\$62.90
	06/01/2023	\$38.06	\$9.10	\$16.64	\$0.00	\$63.80
	12/01/2023	\$38.96	\$9.10	\$16.64	\$0.00	\$64.70
For apprentice rates see "Apprentice- LABORER"						
LABORER: TREE REMOVER  ABORERS - ZONE 2	06/01/2022	\$36.31	\$9.10	\$16.64	\$0.00	\$62.05
	12/01/2022	\$37.16	\$9.10	\$16.64	\$0.00	\$62.90
	06/01/2023	\$38.06	\$9.10	\$16.64	\$0.00	\$63.80
	12/01/2023	\$38.96	\$9.10	\$16.64	\$0.00	\$64.70
This classification applies to the removal of standing trees, and the trimming and r clearance incidental to construction. For apprentice rates see "Apprentice-LABO		ibs when related	to public work	s construction	or site	
LASER BEAM OPERATOR	06/01/2022	\$36.56	\$9.10	\$16.64	\$0.00	\$62.30
ABORERS - ZONE 2	12/01/2022	\$37.41	\$9.10	\$16.64	\$0.00	\$63.15
	06/01/2023	\$38.31	\$9.10	\$16.64	\$0.00	\$64.05
	12/01/2023	\$39.21	\$9.10	\$16.64	\$0.00	\$64.95
For apprentice rates see "Apprentice- LABORER"		*	**			*
LASER BEAM OPERATOR (HEAVY & HIGHWAY)  LABORERS - ZONE 2 (HEAVY & HIGHWAY)	12/01/2021	\$35.66	\$9.10	\$16.64	\$0.00	\$61.40
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)						
MARBLE & TILE FINISHERS	08/01/2022	\$45.29	\$11.49	\$20.37	\$0.00	\$77.15
BRICKLAYERS LOCAL 3 - MARBLE & TILE	02/01/2023	\$46.25	\$11.49	\$20.37	\$0.00	\$78.11
	08/01/2023	\$47.89	\$11.49	\$20.37	\$0.00	\$79.75
	02/01/2024	\$48.89	\$11.49	\$20.37	\$0.00	\$80.75
	08/01/2024	\$50.57	\$11.49	\$20.37	\$0.00	\$82.43
	02/01/2025	\$51.61	\$11.49	\$20.37	\$0.00	\$83.47
	08/01/2025	\$53.33	\$11.49	\$20.37	\$0.00	\$85.19
	02/01/2026	\$54.41	\$11.49	\$20.37	\$0.00	\$86.27
	08/01/2026	\$56.17	\$11.49	\$20.37	\$0.00	\$88.03
	02/01/2027	\$50.17 \$57.29	\$11.49	\$20.37	\$0.00	\$89.15
	02/01/202/	\$31.29	\$11.49	φ20.3/	φυ.υ <del>υ</del>	\$07.13

 Issue Date:
 10/11/2022
 Wage Request Number:
 20221007-038
 Page 17 of 33

Pension

\$22.31

\$22.31

\$11.49

\$11.49

\$0.00

\$0.00

\$106.57

\$107.97

Effective Date - 08/01/2022         Supplemental Supplemental Pension         Supplemental Unemployment         Total Rate Pension         Supplemental Pension         Supplemental Pension         Total Rate Pension         Supplemental Pension         Total Rate Pension         Supplemental Pension         Supplemental Pension         Supplemental Pe	:
2 60 \$27.17 \$11.49 \$20.37 \$0.00 \$59.03	
3 70 \$31.70 \$11.49 \$20.37 \$0.00 \$63.56	
4 80 \$36.23 \$11.49 \$20.37 \$0.00 \$68.09	
5 90 \$40.76 \$11.49 \$20.37 \$0.00 \$72.62	
Effective Date - 02/01/2023  Supplemental	
Step percent Apprentice Base Wage Health Pension Unemployment Total Rate	
1 50 \$23.13 \$11.49 \$20.37 \$0.00 \$54.99	
2 60 \$27.75 \$11.49 \$20.37 \$0.00 \$59.61	
3 70 \$32.38 \$11.49 \$20.37 \$0.00 \$64.24	
4 80 \$37.00 \$11.49 \$20.37 \$0.00 \$68.86	
5 90 \$41.63 \$11.49 \$20.37 \$0.00 \$73.49	
Notes:	
i de la companya de	
Apprentice to Journeyworker Ratio:1:3	
MARBLE MASONS, TILELAYERS & TERRAZZO MECH 08/01/2022 \$59.17 \$11.49 \$22.31 \$0.00	\$92.97
BRICKLAYERS LOCAL 3 - MARBLE & TILE 02/01/2023 \$60.37 \$11.49 \$22.31 \$0.00	\$94.17
08/01/2023 \$62.42 \$11.49 \$22.31 \$0.00	\$96.22
02/01/2024 \$63.67 \$11.49 \$22.31 \$0.00	\$97.47
08/01/2024 \$65.77 \$11.49 \$22.31 \$0.00	\$99.57
02/01/2025 \$67.07 \$11.49 \$22.31 \$0.00	\$100.87
08/01/2025 \$69.22 \$11.49 \$22.31 \$0.00	\$103.02
02/01/2026 \$70.57 \$11.49 \$22.31 \$0.00	\$104.37

08/01/2026

02/01/2027

\$72.77

\$74.17

**Issue Date:** 10/11/2022 Wage Request Number: 20221007-038 Page 18 of 33

**Total Rate** 

Apprentice - MARBLE-TILE-TERRAZZO MECHANIC - Local 3 Marble & Tile

Pension

**Effective Date -**08/01/2022 Supplemental Apprentice Base Wage Health Total Rate Step percent Pension Unemployment 1 50 \$29.59 \$11.49 \$22.31 \$0.00 \$63.39 2 60 \$35.50 \$11.49 \$22.31 \$0.00 \$69.30 3 70 \$41.42 \$11.49 \$22.31 \$0.00 \$75.22 4 80 \$47.34 \$11.49 \$22.31 \$0.00 \$81.14 5 90 \$53.25 \$11.49 \$22.31 \$0.00 \$87.05 **Effective Date -**02/01/2023 Supplemental Unemployment Total Rate Step percent Apprentice Base Wage Health Pension 1 50 \$30.19 \$22.31 \$63.99 \$11.49 \$0.00 2 60 \$22.31 \$0.00 \$70.02 \$36.22 \$11.49 3 70 \$42.26 \$11.49 \$22.31 \$0.00 \$76.06 4 80 \$48.30 \$22.31 \$0.00 \$11.49 \$82.10 5 90 \$54.33 \$11.49 \$22.31 \$0.00 \$88.13 Notes: Apprentice to Journeyworker Ratio:1:5 MECH. SWEEPER OPERATOR (ON CONST. SITES) 06/01/2022 \$16.05 \$0.00 \$82.12 \$51.82 \$14.25 OPERATING ENGINEERS LOCAL 4 \$0.00 12/01/2022 \$53.05 \$14.25 \$16.05 \$83.35 \$16.05 \$0.00 06/01/2023 \$54.29 \$14.25 \$84.59 12/01/2023 \$16.05 \$0.00 \$55.53 \$14.25 \$85.83 \$16.05 \$0.00 06/01/2024 \$56.81 \$14.25 \$87.11 12/01/2024 \$16.05 \$0.00 \$58.25 \$14.25 \$88.55 06/01/2025 \$59.53 \$14.25 \$16.05 \$0.00 \$89.83 \$60.97 \$14.25 12/01/2025 \$16.05 \$0.00 \$91.27 \$16.05 \$0.00 06/01/2026 \$62.25 \$14.25 \$92.55 \$16.05 \$0.00 12/01/2026 \$63.69 \$14.25 \$93.99 For apprentice rates see "Apprentice- OPERATING ENGINEERS" MECHANICS MAINTENANCE \$14.25 \$16.05 \$0.00 06/01/2022 \$51.82 \$82.12 OPERATING ENGINEERS LOCAL 4 12/01/2022 \$53.05 \$14.25 \$16.05 \$0.00 \$83.35 06/01/2023 \$54.29 \$14.25 \$16.05 \$0.00 \$84.59 \$16.05 12/01/2023 \$55.53 \$14.25 \$0.00 \$85.83 06/01/2024 \$56.81 \$14.25 \$16.05 \$0.00 \$87.11 \$16.05 \$0.00 12/01/2024 \$88.55 \$58.25 \$14.25 \$0.00 \$16.05 06/01/2025 \$59.53 \$14.25 \$89.83 \$16.05 \$0.00 12/01/2025 \$60.97 \$14.25 \$91.27 06/01/2026 \$62.25 \$14.25 \$16.05 \$0.00 \$92.55 12/01/2026 \$63.69 \$14.25 \$16.05 \$0.00 \$93.99 For apprentice rates see "Apprentice- OPERATING ENGINEERS" MILLWRIGHT (Zone 2) 01/03/2022 \$40.67 \$8.58 \$21.57 \$0.00 \$70.82 MILLWRIGHTS LOCAL 1121 - Zone 2 \$21.57 01/02/2023 \$41.92 \$8.58 \$0.00 \$72.07

**Total Rate** 

	Step	ive <b>Date</b> - 01/03/2022 percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate	
	1	55	\$22.37	\$8.58	\$5.72	\$0.00	\$36.67	
	2	65	\$26.44	\$8.58	\$17.93	\$0.00	\$52.95	
	3	75	\$30.50	\$8.58	\$18.98	\$0.00	\$58.06	
	4	85	\$34.57	\$8.58	\$20.01	\$0.00	\$63.16	
	Effecti	ive Date - 01/02/2023				Supplemental		
	Step	percent	Apprentice Base Wage	Health	Pension	Unemployment	Total Rate	
	1	55	\$23.06	\$8.58	\$5.72	\$0.00	\$37.36	
	2	65	\$27.25	\$8.58	\$17.93	\$0.00	\$53.76	
	3	75	\$31.44	\$8.58	\$18.98	\$0.00	\$59.00	
	4	85	\$35.63	\$8.58	\$20.01	\$0.00	\$64.22	
		Step 1&2 Appr. indentured after 1/6 but do receive annuity. (Step 1 \$5.0 Steps are 2,000 hours						
	Appre	ntice to Journeyworker Ratio:1:4						
MORTAR MIX ABORERS - ZON			06/01/2022	\$36.56	\$9.10	\$16.64	\$0.00	\$62.30
ADORERS - ZON	E 2		12/01/2022	\$37.41	\$9.10	\$16.64	\$0.00	\$63.15
			06/01/2023	\$38.31	\$9.10	\$16.64	\$0.00	\$64.05
For apprentice	e rates see '	'Apprentice- LABORER"	12/01/2023	\$39.21	\$9.10	\$16.64	\$0.00	\$64.95
		N TRUCK CRANES,GRADALLS)	06/01/2022	\$23.80	\$14.25	\$16.05	\$0.00	\$54.10
PERATING ENG	INEEKS LO	JCAL 4	12/01/2022	\$24.37	\$14.25	\$16.05	\$0.00	\$54.67
			06/01/2023	\$24.94	\$14.25	\$16.05	\$0.00	\$55.24
			12/01/2023	\$25.51	\$14.25	\$16.05	\$0.00	\$55.81
			06/01/2024	\$26.11	\$14.25	\$16.05	\$0.00	\$56.41
			12/01/2024	\$26.77	\$14.25	\$16.05	\$0.00	\$57.07
			06/01/2025	\$27.37	\$14.25	\$16.05	\$0.00	\$57.67
				\$28.03	\$14.25	\$16.05	\$0.00	\$58.33
			12/01/2025	Ψ20.03				Φ.σ.O. O.O.
			12/01/2025 06/01/2026		\$14.25	\$16.05	\$0.00	\$58.92
Ran average.	o motos	Agreement OPED ATING ENGINEERS		\$28.62		\$16.05 \$16.05	\$0.00 \$0.00	
		'Apprentice- OPERATING ENGINEERS"  NES GRADALLS)	06/01/2026 12/01/2026	\$28.62 \$29.29	\$14.25	\$16.05	\$0.00	\$58.92 \$59.59
ILER (TRUC	CK CRA	NES, GRADALLS)	06/01/2026 12/01/2026 06/01/2022	\$28.62 \$29.29 \$28.88	\$14.25 \$14.25	\$16.05 \$16.05	\$0.00 \$0.00	\$59.59 \$59.18
ILER (TRUC	CK CRA	NES, GRADALLS)	06/01/2026 12/01/2026 06/01/2022 12/01/2022	\$28.62 \$29.29 \$28.88 \$29.57	\$14.25 \$14.25 \$14.25	\$16.05 \$16.05 \$16.05	\$0.00 \$0.00 \$0.00	\$59.59 \$59.18 \$59.87
ILER (TRUC	CK CRA	NES, GRADALLS)	06/01/2026 12/01/2026 06/01/2022 12/01/2022 06/01/2023	\$28.62 \$29.29 \$28.88 \$29.57 \$30.27	\$14.25 \$14.25 \$14.25 \$14.25	\$16.05 \$16.05 \$16.05 \$16.05	\$0.00 \$0.00 \$0.00 \$0.00	\$59.59 \$59.18 \$59.87 \$60.57
ILER (TRUC	CK CRA	NES, GRADALLS)	06/01/2026 12/01/2026 06/01/2022 12/01/2022 06/01/2023 12/01/2023	\$28.62 \$29.29 \$28.88 \$29.57 \$30.27 \$30.96	\$14.25 \$14.25 \$14.25 \$14.25 \$14.25	\$16.05 \$16.05 \$16.05 \$16.05 \$16.05	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00	\$59.59 \$59.18 \$59.87 \$60.57 \$61.26
ILER (TRUC	CK CRA	NES, GRADALLS)	06/01/2026 12/01/2026 06/01/2022 12/01/2023 06/01/2023 06/01/2024	\$28.62 \$29.29 \$28.88 \$29.57 \$30.27 \$30.96 \$31.68	\$14.25 \$14.25 \$14.25 \$14.25 \$14.25 \$14.25	\$16.05 \$16.05 \$16.05 \$16.05 \$16.05	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00	\$59.59 \$59.18 \$59.87 \$60.57 \$61.26 \$61.98
ILER (TRUC	CK CRA	NES, GRADALLS)	06/01/2026 12/01/2026 06/01/2022 12/01/2022 06/01/2023 12/01/2023 06/01/2024	\$28.62 \$29.29 \$28.88 \$29.57 \$30.27 \$30.96 \$31.68 \$32.48	\$14.25 \$14.25 \$14.25 \$14.25 \$14.25 \$14.25	\$16.05 \$16.05 \$16.05 \$16.05 \$16.05 \$16.05	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00	\$59.59 \$59.18 \$59.87 \$60.57 \$61.26 \$61.98 \$62.78
ILER (TRUC	CK CRA	NES, GRADALLS)	06/01/2026 12/01/2026 06/01/2022 12/01/2022 06/01/2023 12/01/2024 12/01/2024 06/01/2025	\$28.62 \$29.29 \$28.88 \$29.57 \$30.27 \$30.96 \$31.68 \$32.48 \$33.20	\$14.25 \$14.25 \$14.25 \$14.25 \$14.25 \$14.25 \$14.25	\$16.05 \$16.05 \$16.05 \$16.05 \$16.05 \$16.05 \$16.05	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00	\$59.59 \$59.18 \$59.87 \$60.57 \$61.26 \$61.98 \$62.78 \$63.50
	CK CRA	NES, GRADALLS)	06/01/2026 12/01/2026 06/01/2022 12/01/2022 06/01/2023 12/01/2023 06/01/2024	\$28.62 \$29.29 \$28.88 \$29.57 \$30.27 \$30.96 \$31.68 \$32.48 \$33.20 \$34.00	\$14.25 \$14.25 \$14.25 \$14.25 \$14.25 \$14.25 \$14.25 \$14.25	\$16.05 \$16.05 \$16.05 \$16.05 \$16.05 \$16.05	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00	\$59.59 \$59.18 \$59.87 \$60.57 \$61.26 \$61.98 \$62.78

Classification  For apprentice rates see "Apprentice- OPERATING ENGINEERS"	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
OTHER POWER DRIVEN EQUIPMENT - CLASS II	06/01/2022	\$51.82	\$14.25	\$16.05	\$0.00	\$82.12
OPERATING ENGINEERS LOCAL 4	12/01/2022	\$53.05	\$14.25	\$16.05	\$0.00	\$83.35
	06/01/2023	\$54.29	\$14.25	\$16.05	\$0.00	\$84.59
	12/01/2023	\$55.53	\$14.25	\$16.05	\$0.00	\$85.83
	06/01/2024	\$56.81	\$14.25	\$16.05	\$0.00	\$87.11
	12/01/2024	\$58.25	\$14.25	\$16.05	\$0.00	\$88.55
	06/01/2025	\$59.53	\$14.25	\$16.05	\$0.00	\$89.83
	12/01/2025	\$60.97	\$14.25	\$16.05	\$0.00	\$91.27
	06/01/2026	\$62.25	\$14.25	\$16.05	\$0.00	\$92.55
	12/01/2026	\$63.69	\$14.25	\$16.05	\$0.00	\$93.99
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
PAINTER (BRIDGES/TANKS)	07/01/2022	\$54.86	\$8.65	\$23.05	\$0.00	\$86.56
PAINTERS LOCAL 35 - ZONE 2	01/01/2023	\$56.06	\$8.65	\$23.05	\$0.00	\$87.76
	07/01/2023	\$57.26	\$8.65	\$23.05	\$0.00	\$88.96
	01/01/2024	\$58.46	\$8.65	\$23.05	\$0.00	\$90.16
	07/01/2024	\$59.66	\$8.65	\$23.05	\$0.00	\$91.36
	01/01/2025	\$60.86	\$8.65	\$23.05	\$0.00	\$92.56

**Apprentice -** *PAINTER Local 35 - BRIDGES/TANKS* 

Liice	ive Date -	07/01/2022				Supplemental	
Step	percent		Apprentice Base Wage	Health	Pension	Unemployment	Total Rate
1	50		\$27.43	\$8.65	\$0.00	\$0.00	\$36.08
2	55		\$30.17	\$8.65	\$6.27	\$0.00	\$45.09
3	60		\$32.92	\$8.65	\$6.84	\$0.00	\$48.41
4	65		\$35.66	\$8.65	\$7.41	\$0.00	\$51.72
5	70		\$38.40	\$8.65	\$19.63	\$0.00	\$66.68
6	75		\$41.15	\$8.65	\$20.20	\$0.00	\$70.00
7	80		\$43.89	\$8.65	\$20.77	\$0.00	\$73.31
8	90		\$49.37	\$8.65	\$21.91	\$0.00	\$79.93
Effect	ive Date -	01/01/2023				Supplemental	
Effect Step	percent	01/01/2023	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
Step		01/01/2023	Apprentice Base Wage \$28.03	Health \$8.65	Pension \$0.00	1.1	Total Rate \$36.68
Step 1	percent	01/01/2023				Unemployment	
Step 1 2	percent 50	01/01/2023	\$28.03	\$8.65	\$0.00	Unemployment \$0.00	\$36.68
Step	50 55	01/01/2023	\$28.03 \$30.83	\$8.65 \$8.65	\$0.00 \$6.27	\$0.00 \$0.00	\$36.68 \$45.75
Step 1 2 3 4	50 55 60	01/01/2023	\$28.03 \$30.83 \$33.64	\$8.65 \$8.65 \$8.65	\$0.00 \$6.27 \$6.84	\$0.00 \$0.00 \$0.00	\$36.68 \$45.75 \$49.13
Step  1 2 3	50 55 60 65	01/01/2023	\$28.03 \$30.83 \$33.64 \$36.44	\$8.65 \$8.65 \$8.65 \$8.65	\$0.00 \$6.27 \$6.84 \$7.41	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00	\$36.68 \$45.75 \$49.13 \$52.50
Step 1 2 3 4 5 5	50 55 60 65 70	01/01/2023	\$28.03 \$30.83 \$33.64 \$36.44 \$39.24	\$8.65 \$8.65 \$8.65 \$8.65 \$8.65	\$0.00 \$6.27 \$6.84 \$7.41 \$19.63	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00	\$36.68 \$45.75 \$49.13 \$52.50 \$67.52

Apprentice to Journeyworker Ratio:1:1

 Issue Date:
 10/11/2022
 Wage Request Number:
 20221007-038
 Page 21 of 33

Classification		Effective Date   1		Base Wage	e Health	lealth Pension	Supplemental Unemployment	Total Rate	
		SANDBLAST, NEW) *		07/01/2022	\$45.76	\$8.65	\$23.05	\$0.00	\$77.46
		rfaces to be painted are new consused. PAINTERS LOCAL 35 - ZONE		01/01/2023	\$46.96	\$8.65	\$23.05	\$0.00	\$78.66
Ew paint rate	Shall be	used.PAINTERS LOCAL 33 - ZONE	2	07/01/2023	\$48.16	\$8.65	\$23.05	\$0.00	\$79.86
				01/01/2024	\$49.36	\$8.65	\$23.05	\$0.00	\$81.06
				07/01/2024	\$50.56	\$8.65	\$23.05	\$0.00	\$82.26
				01/01/2025	\$51.76	\$8.65	\$23.05	\$0.00	\$83.46
	Annre	ntice - PAINTER Local 35 Zo	one 2 - Spray/Sand	dhlast - New					
		ive Date - 07/01/2022	= ~p, ~				Supplementa	1	
	Step	percent	Apprent	tice Base Wage	Health	Pension	Unemploymen		
	1	50		\$22.88	\$8.65	\$0.00	\$0.00	\$31.53	
	2	55		\$25.17	\$8.65	\$6.27	\$0.00		
	3	60		\$27.46	\$8.65	\$6.84	\$0.00		
	4	65		\$29.74	\$8.65	\$7.41	\$0.00		
	5	70		\$32.03	\$8.65	\$19.63	\$0.00	\$60.31	
	6	75		\$34.32	\$8.65	\$20.20	\$0.00		
	7	80		\$36.61	\$8.65	\$20.77	\$0.00	\$66.03	
	8	90		\$41.18	\$8.65	\$21.91	\$0.00	\$71.74	
		ive Date - 01/01/2023					Supplementa		
	Step	percent	Apprent	tice Base Wage	Health	Pension	Unemploymen	t Total Rate	
	1	50		\$23.48	\$8.65	\$0.00	\$0.00	\$32.13	
	2	55		\$25.83	\$8.65	\$6.27	\$0.00	\$40.75	
	3	60		\$28.18	\$8.65	\$6.84	\$0.00	\$43.67	
	4	65		\$30.52	\$8.65	\$7.41	\$0.00	\$46.58	
	5	70		\$32.87	\$8.65	\$19.63	\$0.00	\$61.15	
	6	75		\$35.22	\$8.65	\$20.20	\$0.00	\$64.07	
	7	80		\$37.57	\$8.65	\$20.77	\$0.00	\$66.99	
	8	90		\$42.26	\$8.65	\$21.91	\$0.00	\$72.82	
	Notes:								
		Steps are 750 hrs.							
	Appre	ntice to Journeyworker Ratio	:1:1						
INTER (SPR		SANDBLAST, REPAINT)		07/01/2022	\$43.82	\$8.65	\$23.05	\$0.00	\$75.52
IVIERS LOCAL .	ss - ZONE	5 Z		01/01/2023	\$45.02	\$8.65	\$23.05	\$0.00	\$76.72
				07/01/2023	\$46.22	\$8.65	\$23.05	\$0.00	\$77.92
				01/01/2024	\$47.42	\$8.65	\$23.05	\$0.00	\$79.12
				07/01/2024	\$48.62	\$8.65	\$23.05	\$0.00	\$80.32

Supplemental

**Total Rate** 

**Issue Date:** 10/11/2022 **Wage Request Number:** 20221007-038 **Page 22 of 33** 

Ste	rective Date -	07/01/2022	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate	
1	50		\$21.91	\$8.65	\$0.00	\$0.00	\$30.56	
2	55		\$24.10	\$8.65	\$6.27	\$0.00	\$39.02	
3	60		\$26.29	\$8.65	\$6.84	\$0.00	\$41.78	
4	65		\$28.48	\$8.65	\$7.41	\$0.00	\$44.54	
5	70		\$30.67	\$8.65	\$19.63	\$0.00	\$58.95	
6	75		\$32.87	\$8.65	\$20.20	\$0.00	\$61.72	
7	80		\$35.06	\$8.65	\$20.77	\$0.00	\$64.48	
8	90		\$39.44	\$8.65	\$21.91	\$0.00	\$70.00	
Eff	ective Date -	01/01/2023				Supplemental		
Ste	p percent		Apprentice Base Wage	Health	Pension	Unemployment	Total Rate	
1	50		\$22.51	\$8.65	\$0.00	\$0.00	\$31.16	
2	55		\$24.76	\$8.65	\$6.27	\$0.00	\$39.68	
3	60		\$27.01	\$8.65	\$6.84	\$0.00	\$42.50	
4	65		\$29.26	\$8.65	\$7.41	\$0.00	\$45.32	
5	70		\$31.51	\$8.65	\$19.63	\$0.00	\$59.79	
6	75		\$33.77	\$8.65	\$20.20	\$0.00	\$62.62	
7	80		\$36.02	\$8.65	\$20.77	\$0.00	\$65.44	
8	90		\$40.52	\$8.65	\$21.91	\$0.00	\$71.08	
No	 tes:							
·	Steps are	750 hrs.					i	
Ap	prentice to Jo	ourneyworker Ratio:1:1						
	(BRUSH, NE		07/01/2022	2 \$44.3	6 \$8.65	\$23.05	\$0.00	\$76.0
		painted are new construction TERS LOCAL 35 - ZONE 2	01/01/2023	3 \$45.5	6 \$8.65	\$23.05	\$0.00	\$77.2
in rate silai	i oc uscu.PAIN	IERS LOCAL 33 - ZONE 2	07/01/2023	\$46.7	6 \$8.65	\$23.05	\$0.00	\$78.4
			01/01/2024	\$47.9	6 \$8.65	\$23.05	\$0.00	\$79.6

**Issue Date:** 10/11/2022 **Wage Request Number:** 20221007-038 Page 23 of 33

07/01/2024

01/01/2025

\$49.16

\$50.36

\$8.65

\$8.65

\$23.05

\$23.05

\$0.00

\$0.00

\$80.86

\$82.06

Pension

**Total Rate** 

Effect	tive Date - 07/01/2022				Supplemental		
Step	percent	Apprentice Base Wage	Health	Pension	Unemployment	Total R	ate
1	50	\$22.18	\$8.65	\$0.00	\$0.00	\$30	.83
2	55	\$24.40	\$8.65	\$6.27	\$0.00	\$39	.32
3	60	\$26.62	\$8.65	\$6.84	\$0.00	\$42	.11
4	65	\$28.83	\$8.65	\$7.41	\$0.00	\$44	.89
5	70	\$31.05	\$8.65	\$19.63	\$0.00	\$59	.33
6	75	\$33.27	\$8.65	\$20.20	\$0.00	\$62	.12
7	80	\$35.49	\$8.65	\$20.77	\$0.00	\$64	.91
8	90	\$39.92	\$8.65	\$21.91	\$0.00	\$70	.48
Effect	tive Date - 01/01/2023				Supplemental		
Step	percent	Apprentice Base Wage	Health	Pension	Unemployment	Total R	.ate
1	50	\$22.78	\$8.65	\$0.00	\$0.00	\$31	.43
2	55	\$25.06	\$8.65	\$6.27	\$0.00	\$39	.98
3	60	\$27.34	\$8.65	\$6.84	\$0.00	\$42	.83
4	65	\$29.61	\$8.65	\$7.41	\$0.00	\$45	.67
5	70	\$31.89	\$8.65	\$19.63	\$0.00	\$60	.17
6	75	\$34.17	\$8.65	\$20.20	\$0.00	\$63	.02
7	80	\$36.45	\$8.65	\$20.77	\$0.00	\$65	.87
8	90	\$41.00	\$8.65	\$21.91	\$0.00	\$71	.56
Notes	<u> </u>						
i	Steps are 750 hrs.						
Appr	entice to Journeyworker R	atio:1:1					_
ER / TAPER (B	RUSH, REPAINT)	07/01/2022	\$42.42	\$8.65	\$23.05	\$0.00	\$74.1
RS LOCAL 35 - ZON	TE 2	01/01/2023		\$8.65	\$23.05	\$0.00	\$75.3
		07/01/2023		\$8.65	\$23.05	\$0.00	\$76.5
		01/01/2024		\$8.65	\$23.05	\$0.00	\$77.7
		07/01/2024		\$8.65	\$23.05	\$0.00	\$78.9
		01/01/2025		\$8.65	\$23.05	\$0.00	\$80.1

**Issue Date:** 10/11/2022 Wage Request Number: 20221007-038 Page 24 of 33

**Total Rate** 

Pension

50		Health	Pension	Unemployment	Total Rate	•
	\$21.21	\$8.65	\$0.00	\$0.00	\$29.86	<u> </u>
55	\$23.33	\$8.65	\$6.27	\$0.00	\$38.25	5
60	\$25.45	\$8.65	\$6.84	\$0.00	\$40.94	ļ
65	\$27.57	\$8.65	\$7.41	\$0.00	\$43.63	3
70	\$29.69	\$8.65	\$19.63	\$0.00	\$57.97	7
75	\$31.82	\$8.65	\$20.20	\$0.00	\$60.67	7
80	\$33.94	\$8.65	\$20.77	\$0.00	\$63.36	ó
90	\$38.18	\$8.65	\$21.91	\$0.00	\$68.74	ļ
	Annrentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate	<b>.</b>
*						
90	\$39.26	\$8.65	\$21.91	\$0.00		
Steps are 750 hrs.						
ntice to Journeyworker Ratio:1:1						
Y & HIGHWAY)	12/01/2021	\$35.41	\$9.10	\$16.64	\$0.00	\$61.15
	12/01/2021	\$35.78	\$13.41	\$16.01	\$0.00	\$65.20
NE 2)	AND 08/01/2020	\$46.11	\$9.40	\$23.12	\$0.00	\$78.63
	70 75 80 90  ve Date - 01/01/2023 percent 50 55 60 65 70 75 80 90  Steps are 750 hrs.  ntice to Journeyworker Ratio:1:1 ARKINGS (HEAVY/HIGHWAY) Y& HIGHWAY) Apprentice- LABORER (Heavy and Highway) CAPPRIL NO. 10 ZONE B	70 \$29.69 75 \$31.82 80 \$33.94 90 \$38.18   Ve Date - 01/01/2023 percent Apprentice Base Wage  50 \$21.81 55 \$23.99 60 \$26.17 65 \$28.35 70 \$30.53 75 \$32.72 80 \$34.90 90 \$39.26   Steps are 750 hrs.  Intice to Journeyworker Ratio:1:1  ARKINGS (HEAVY/HIGHWAY) Ye HIGHWAY) Papprentice- LABORER (Heavy and Highway)  UCKS DRIVER IL NO. 10 ZONE B  NSTRUCTOR (UNDERPINNING AND 08/01/2020)  DNE 2) Apprentice- PILE DRIVER"	70 \$29.69 \$8.65 75 \$31.82 \$8.65 80 \$33.94 \$8.65 90 \$38.18 \$8.65   ve Date - 01/01/2023  percent Apprentice Base Wage Health  50 \$21.81 \$8.65 55 \$23.99 \$8.65 60 \$26.17 \$8.65 65 \$28.35 \$8.65 70 \$30.53 \$8.65 70 \$30.53 \$8.65 75 \$32.72 \$8.65 80 \$34.90 \$8.65 80 \$34.90 \$8.65 90 \$39.26 \$8.65  Steps are 750 hrs.  Intice to Journeyworker Ratio:1:1  ARKINGS (HEAVY/HIGHWAY) \$2.01/2021 \$35.41  APPRICATE TO A B B B B B B B B B B B B B B B B B B	\$29.69	To   S29.69   S8.65   S19.63   S0.00	Total Rate   Section   S

**Issue Date:** 10/11/2022 Page 25 of 33

\$0.00

\$0.00

\$0.00

\$64.05

\$64.95

\$61.40

\$16.64

\$16.64

\$16.64

**Total Rate** 

	ffective Date - tep percent	08/01/2020	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate	
1	0		\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	
No	(Same as	ce wages shall be no less than s set in Zone 1) /2\$61.96/3\$66.87/4\$69.32/5\$		\$76.68				
$A_{J}$	pprentice to J	ourneyworker Ratio:1:5						
IPELAYER			06/01/2022	\$36.56	\$9.10	\$16.64	\$0.00	\$62.30
ABORERS - ZONE 2			12/01/2022	\$37.41	\$9.10	\$16.64	\$0.00	\$63.15
			06/01/2023	\$38.31	\$9.10	\$16.64	\$0.00	\$64.05
_			12/01/2023	\$39.21	\$9.10	\$16.64	\$0.00	\$64.95
For apprentice rates								
PELAYER (HEA BORERS - ZONE 2 (I			12/01/2021	\$35.66	\$9.10	\$16.64	\$0.00	\$61.40
For apprentice rate	es see "Apprentice-	LABORER (Heavy and Highway)						
UMBER & PIPI	EFITTER		08/30/2021	\$46.49	\$10.15	\$19.95	\$0.00	\$76.59
$\mathbf{A_{I}}$	pprentice - P	PLUMBER/PIPEFITTER - Lo	ocal 51					
Ef	ffective Date -	PLUMBER/PIPEFITTER - La 08/30/2021		Health	Pension	Supplemental Unemployment	Total Rate	
Ef	ffective Date - tep percent		Apprentice Base Wage		Pension \$2.50	Unemployment	Total Rate	
Ef St	ffective Date - tep percent 40		Apprentice Base Wage	\$10.15	\$2.50	Unemployment \$0.00	\$31.25	
E1 St	ffective Date - tep percent 40 50		Apprentice Base Wage			Unemployment	\$31.25 \$35.90	
Ef St 2	ffective Date - tep percent 40 50 60		Apprentice Base Wage \$18.60 \$23.25	\$10.15 \$10.15	\$2.50 \$2.50	\$0.00 \$0.00	\$31.25	
Ef St 1 2 3	### description of the image of		Apprentice Base Wage \$18.60 \$23.25 \$27.89	\$10.15 \$10.15 \$10.15	\$2.50 \$2.50 \$8.80	\$0.00 \$0.00 \$0.00	\$31.25 \$35.90 \$46.84	
Ef St 1 2 3 4 5	### doi: 10.1016/j.cm.		\$18.60 \$23.25 \$27.89 \$32.54	\$10.15 \$10.15 \$10.15 \$10.15	\$2.50 \$2.50 \$8.80 \$14.08	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00	\$31.25 \$35.90 \$46.84 \$56.77	
Et St 1 2 3 4 5 5	### description		\$18.60 \$23.25 \$27.89 \$32.54 \$37.19	\$10.15 \$10.15 \$10.15 \$10.15	\$2.50 \$2.50 \$8.80 \$14.08	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00	\$31.25 \$35.90 \$46.84 \$56.77	
Ef St 1 2 3 3 4 5 No.	ffective Date - tep percent		\$18.60 \$23.25 \$27.89 \$32.54 \$37.19	\$10.15 \$10.15 \$10.15 \$10.15	\$2.50 \$2.50 \$8.80 \$14.08	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00	\$31.25 \$35.90 \$46.84 \$56.77	
Eff  St  1  2  3  4  5  NO  NEUMATIC CON	tep percent  40  50  60  70  80  otes: Steps 20  NTROLS (TEM	08/30/2021 000hrs. Prior 9/1/05; 40/40/45 ourneyworker Ratio:1:3	\$18.60 \$23.25 \$27.89 \$32.54 \$37.19	\$10.15 \$10.15 \$10.15 \$10.15 \$10.15	\$2.50 \$2.50 \$8.80 \$14.08	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00	\$31.25 \$35.90 \$46.84 \$56.77	\$76.59
St  St  1  2  3  4  5  No  Neumatic con  Jumbers & Pipefit	tep percent  40  50  60  70  80  otes: Steps 20  NTROLS (TEM	08/30/2021 000hrs. Prior 9/1/05; 40/40/45 ourneyworker Ratio:1:3	Apprentice Base Wage \$18.60 \$23.25 \$27.89 \$32.54 \$37.19	\$10.15 \$10.15 \$10.15 \$10.15 \$10.15	\$2.50 \$2.50 \$8.80 \$14.08 \$17.60	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00	\$31.25 \$35.90 \$46.84 \$56.77 \$64.94	
St  St  1  2  3  4  5  No  Neumatic con	tep percent  40  50  60  70  80  otes: Steps 20  NTROLS (TEN TTERS LOCAL 51  es see "Apprentice-	08/30/2021 000hrs. Prior 9/1/05; 40/40/45 ourneyworker Ratio:1:3 MP.) PIPEFITTER" or "PLUMBER/PIPE	Apprentice Base Wage \$18.60 \$23.25 \$27.89 \$32.54 \$37.19	\$10.15 \$10.15 \$10.15 \$10.15 \$10.15 \$46.49	\$2.50 \$2.50 \$8.80 \$14.08 \$17.60	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00	\$31.25 \$35.90 \$46.84 \$56.77 \$64.94	

HIGHWAY)

LABORERS - ZONE 2 (HEAVY & HIGHWAY)

 $\frac{ \mbox{For apprentice rates see "Apprentice- LABORER"} }{\mbox{PNEUMATIC DRILL/TOOL OPERATOR (HEAVY \& } }$ 

For apprentice rates see "Apprentice- LABORER (Heavy and Highway)

06/01/2023

12/01/2023

12/01/2021

\$38.31

\$39.21

\$35.66

\$9.10

\$9.10

\$9.10

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
POWDERMAN & BLASTER	06/01/2022	\$37.31	\$9.10	\$16.64	\$0.00	\$63.05
LABORERS - ZONE 2	12/01/2022	\$38.16	\$9.10	\$16.64	\$0.00	\$63.90
	06/01/2023	\$39.06	\$9.10	\$16.64	\$0.00	\$64.80
	12/01/2023	\$39.96	\$9.10	\$16.64	\$0.00	\$65.70
For apprentice rates see "Apprentice- LABORER"						
POWDERMAN & BLASTER (HEAVY & HIGHWAY)  LABORERS - ZONE 2 (HEAVY & HIGHWAY)	12/01/2021	\$36.41	\$9.10	\$16.64	\$0.00	\$62.15
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)						
POWER SHOVEL/DERRICK/TRENCHING MACHINE	06/01/2022	\$52.38	\$14.25	\$16.05	\$0.00	\$82.68
OPERATING ENGINEERS LOCAL 4	12/01/2022	\$53.63	\$14.25	\$16.05	\$0.00	\$83.93
	06/01/2023	\$54.88	\$14.25	\$16.05	\$0.00	\$85.18
	12/01/2023	\$56.13	\$14.25	\$16.05	\$0.00	\$86.43
	06/01/2024	\$57.43	\$14.25	\$16.05	\$0.00	\$87.73
	12/01/2024	\$58.88	\$14.25	\$16.05	\$0.00	\$89.18
	06/01/2025	\$60.18	\$14.25	\$16.05	\$0.00	\$90.48
	12/01/2025	\$61.63	\$14.25	\$16.05	\$0.00	\$91.93
	06/01/2026	\$62.93	\$14.25	\$16.05	\$0.00	\$93.23
For apprentice rates see "Apprentice- OPERATING ENGINEERS"	12/01/2026	\$64.38	\$14.25	\$16.05	\$0.00	\$94.68
PUMP OPERATOR (CONCRETE)	06/01/2022	\$52.38	\$14.25	\$16.05	\$0.00	\$82.68
OPERATING ENGINEERS LOCAL 4	12/01/2022	\$53.63	\$14.25	\$16.05	\$0.00	\$83.93
	06/01/2023	\$54.88	\$14.25	\$16.05	\$0.00	\$85.18
	12/01/2023	\$56.13	\$14.25	\$16.05	\$0.00	\$86.43
	06/01/2024	\$57.43	\$14.25	\$16.05	\$0.00	\$87.73
	12/01/2024	\$58.88	\$14.25	\$16.05	\$0.00	\$89.18
	06/01/2025	\$60.18	\$14.25	\$16.05	\$0.00	\$90.48
	12/01/2025	\$61.63	\$14.25	\$16.05	\$0.00	\$91.93
	06/01/2026	\$62.93	\$14.25	\$16.05	\$0.00	\$93.23
	12/01/2026	\$64.38	\$14.25	\$16.05	\$0.00	\$94.68
For apprentice rates see "Apprentice- OPERATING ENGINEERS"	12/01/2020	<b>ФО4.3</b> 6	\$14.23	\$10.03	ψ0.00	\$24.00
PUMP OPERATOR (DEWATERING, OTHER)	06/01/2022	\$34.26	\$14.25	\$16.05	\$0.00	\$64.56
OPERATING ENGINEERS LOCAL 4	12/01/2022	\$35.08	\$14.25	\$16.05	\$0.00	\$65.38
	06/01/2023	\$35.90	\$14.25	\$16.05	\$0.00	\$66.20
	12/01/2023	\$36.72	\$14.25	\$16.05	\$0.00	\$67.02
	06/01/2024	\$37.57	\$14.25	\$16.05	\$0.00	\$67.87
	12/01/2024	\$38.52	\$14.25	\$16.05	\$0.00	\$68.82
	06/01/2025	\$39.37	\$14.25	\$16.05	\$0.00	\$69.67
	12/01/2025	\$40.32	\$14.25	\$16.05	\$0.00	\$70.62
	06/01/2026	\$41.18	\$14.25	\$16.05	\$0.00	\$71.48
	12/01/2026	\$42.13	\$14.25	\$16.05	\$0.00	\$72.43
For apprentice rates see "Apprentice- OPERATING ENGINEERS"			J- 1. <b>-2</b>			

**Issue Date:** 10/11/2022 Wage Request Number: 20221007-038

Page 27 of 33

Classification	<b>Effective Date</b>	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
READY-MIX CONCRETE DRIVER	01/01/2022	\$25.75	\$9.76	\$4.00	\$0.00	\$39.51
TEAMSTERS 170 - Dauphinais (Bellingham)	12/01/2022	\$26.40	\$10.26	\$4.75	\$0.00	\$41.41
	01/01/2023	\$26.40	\$10.26	\$4.75	\$0.00	\$41.41
	12/01/2023	\$27.00	\$10.76	\$5.45	\$0.00	\$43.21
	01/01/2024	\$27.00	\$10.76	\$5.45	\$0.00	\$43.21
	12/01/2024	\$27.60	\$11.26	\$6.15	\$0.00	\$45.01
	01/01/2025	\$27.60	\$11.26	\$6.15	\$0.00	\$45.01
RECLAIMERS	06/01/2022	\$51.82	\$14.25	\$16.05	\$0.00	\$82.12
OPERATING ENGINEERS LOCAL 4	12/01/2022	\$53.05	\$14.25	\$16.05	\$0.00	\$83.35
	06/01/2023	\$54.29	\$14.25	\$16.05	\$0.00	\$84.59
	12/01/2023	\$55.53	\$14.25	\$16.05	\$0.00	\$85.83
	06/01/2024	\$56.81	\$14.25	\$16.05	\$0.00	\$87.11
	12/01/2024	\$58.25	\$14.25	\$16.05	\$0.00	\$88.55
	06/01/2025	\$59.53	\$14.25	\$16.05	\$0.00	\$89.83
	12/01/2025	\$60.97	\$14.25	\$16.05	\$0.00	\$91.27
	06/01/2026	\$62.25	\$14.25	\$16.05	\$0.00	\$92.55
	12/01/2026	\$63.69	\$14.25	\$16.05	\$0.00	\$93.99
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
RIDE-ON MOTORIZED BUGGY OPERATOR  LABORERS - ZONE 2	06/01/2022	\$36.56	\$9.10	\$16.64	\$0.00	\$62.30
2000	12/01/2022	\$37.41	\$9.10	\$16.64	\$0.00	\$63.15
	06/01/2023	\$38.31	\$9.10	\$16.64	\$0.00	\$64.05
Formation and an all Amendian LADORERS	12/01/2023	\$39.21	\$9.10	\$16.64	\$0.00	\$64.95
For apprentice rates see "Apprentice- LABORER"					***	
ROLLER/SPREADER/MULCHING MACHINE  OPERATING ENGINEERS LOCAL 4	06/01/2022	\$51.82	\$14.25	\$16.05	\$0.00	\$82.12
	12/01/2022	\$53.05	\$14.25	\$16.05	\$0.00	\$83.35
	06/01/2023	\$54.29	\$14.25	\$16.05	\$0.00	\$84.59
	12/01/2023	\$55.53	\$14.25	\$16.05	\$0.00	\$85.83
	06/01/2024	\$56.81	\$14.25	\$16.05	\$0.00	\$87.11
	12/01/2024	\$58.25	\$14.25	\$16.05	\$0.00	\$88.55
	06/01/2025	\$59.53	\$14.25	\$16.05	\$0.00	\$89.83
	12/01/2025	\$60.97	\$14.25	\$16.05	\$0.00	\$91.27
	06/01/2026	\$62.25	\$14.25	\$16.05	\$0.00	\$92.55
	12/01/2026	\$63.69	\$14.25	\$16.05	\$0.00	\$93.99
For apprentice rates see "Apprentice- OPERATING ENGINEERS"  ROOFER (Inc.Roofer Waterproofing &Roofer Damproofg)	02/01/2022	\$47.03	\$12.28	\$19.45	\$0.00	\$78.76

 Issue Date:
 10/11/2022
 Wage Request Number:
 20221007-038
 Page 28 of 33

Appre	ntice - ROOFER - Local	33					
Effecti Step	ive Date - 02/01/2022 percent	Apprentice Base Wage	Haalth	Pension	Supplemental Unemployment	Total Rate	a
1 Step	50	11 0					
2	60	\$23.52 \$28.22	\$12.28 \$12.28	\$5.21 \$19.45	\$0.00 \$0.00	\$41.01 \$59.95	
3	65	\$30.57	\$12.28	\$19.45	\$0.00	\$62.30	
4	75	\$35.27	\$12.28	\$19.45	\$0.00	\$67.00	
5	85	\$39.98	\$12.28	\$19.45	\$0.00	\$71.7	l
Notes:	** 1:5, 2:6-10, the 1:10; I Step 1 is 2000 hrs.; Step: (Hot Pitch Mechanics' re						
Appre	ntice to Journeyworker F	Ratio:**					
ROOFER SLATE / TIL ROOFERS LOCAL 33	E / PRECAST CONCRET	TE 02/01/2022	\$47.28	\$12.28	\$19.45	\$0.00	\$79.01
For apprentice rates see	'Apprentice- ROOFER"						
SHEETMETAL WORK SHEETMETAL WORKERS LO		04/01/2022	\$37.41	\$13.95	\$17.85	\$2.08	\$71.29

Et: Ste	fective Date - 04/01 ep percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate	
1	40	\$14.96	\$13.95	\$4.10	\$1.02	\$34.03	
2	45	\$16.83	\$13.95	\$4.61	\$1.09	\$36.48	
3	50	\$18.71	\$13.95	\$11.26	\$1.35	\$45.27	
4	55	\$20.58	\$13.95	\$11.26	\$1.41	\$47.20	
5	60	\$22.45	\$13.95	\$14.60	\$1.53	\$52.53	
6	65	\$24.32	\$13.95	\$14.88	\$1.59	\$54.74	
7	70	\$26.19	\$13.95	\$15.16	\$1.66	\$56.96	
8	75	\$28.06	\$13.95	\$15.44	\$1.72	\$59.17	
9	80	\$29.93	\$13.95	\$15.72	\$1.79	\$61.39	
10	85	\$31.80	\$13.95	\$15.57	\$1.85	\$63.17	
No							
Ar	prentice to Journeyw	orker Ratio:1:3					
	RTH MOVING EQUI Uncil no. 10 zone b	P < 35 TONS 12/01/202	1 \$36.24	\$13.41	\$16.01	\$0.00	\$65.66
	RTH MOVING EQUI	P > 35 TONS 12/01/202	1 \$36.53	\$13.41	\$16.01	\$0.00	\$65.93

**Issue Date:** 10/11/2022 Wage Request Number: 20221007-038 Page 29 of 33

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
SPRINKLER FITTER	10/01/2022	\$59.00	\$10.44	\$22.60	\$0.00	\$92.04
SPRINKLER FITTERS LOCAL 550 - (Section B) Zone 2	03/01/2023	\$60.53	\$10.44	\$22.60	\$0.00	\$93.57
	10/01/2023	\$62.11	\$10.44	\$22.60	\$0.00	\$95.15
	03/01/2024	\$63.73	\$10.44	\$22.60	\$0.00	\$96.77
	10/01/2024	\$65.35	\$10.44	\$22.60	\$0.00	\$98.39
	03/01/2025	\$66.97	\$10.44	\$22.60	\$0.00	\$100.01

**Apprentice** - SPRINKLER FITTER - Local 550 (Section B) Zone 2

Effective Date - 10/01/2022

Enecu	ve Date -	10/01/2022				Supplemental	
Step	percent		Apprentice Base Wage	Health	Pension	Unemployment	Total Rate
1	35		\$20.65	\$10.44	\$9.10	\$0.00	\$40.19
2	40		\$23.60	\$10.44	\$9.10	\$0.00	\$43.14
3	45		\$26.55	\$10.44	\$9.10	\$0.00	\$46.09
4	50		\$29.50	\$10.44	\$9.10	\$0.00	\$49.04
5	55		\$32.45	\$10.44	\$9.10	\$0.00	\$51.99
6	60		\$35.40	\$10.44	\$11.10	\$0.00	\$56.94
7	65		\$38.35	\$10.44	\$11.10	\$0.00	\$59.89
8	70		\$41.30	\$10.44	\$11.10	\$0.00	\$62.84
9	75		\$44.25	\$10.44	\$11.10	\$0.00	\$65.79
10	80		\$47.20	\$10.44	\$11.10	\$0.00	\$68.74
Effecti	ve Date -	03/01/2023				Supplemental	
Step	percent		Apprentice Base Wage	Health	Pension	Unemployment	Total Rate
1	35		\$21.19	\$10.44	\$9.10	\$0.00	\$40.73
			\$24.21	\$10.44	\$9.10	\$0.00	\$43.75
2	40		Ψ24.21				
2	40 45		\$27.24	\$10.44	\$9.10	\$0.00	\$46.78
				\$10.44 \$10.44	\$9.10 \$9.10		\$46.78 \$49.81
3	45		\$27.24			\$0.00	
3 4	45 50		\$27.24 \$30.27	\$10.44	\$9.10	\$0.00 \$0.00	\$49.81
3 4 5	45 50 55		\$27.24 \$30.27 \$33.29	\$10.44 \$10.44	\$9.10 \$9.10	\$0.00 \$0.00 \$0.00	\$49.81 \$52.83
3 4 5 6	45 50 55 60		\$27.24 \$30.27 \$33.29 \$36.32	\$10.44 \$10.44 \$10.44	\$9.10 \$9.10 \$11.10	\$0.00 \$0.00 \$0.00 \$0.00	\$49.81 \$52.83 \$57.86
3 4 5 6 7	45 50 55 60 65		\$27.24 \$30.27 \$33.29 \$36.32 \$39.34	\$10.44 \$10.44 \$10.44 \$10.44	\$9.10 \$9.10 \$11.10	\$0.00 \$0.00 \$0.00 \$0.00	\$49.81 \$52.83 \$57.86 \$60.88

Apprentice to Journeyworker Ratio:1:3

**Issue Date:** 10/11/2022 **Wage Request Number:** 20221007-038 **Page 30 of 33** 

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rat
STEAM BOILER OPERATOR	06/01/2022	\$51.82	\$14.25	\$16.05	\$0.00	\$82.12
OPERATING ENGINEERS LOCAL 4	12/01/2022	\$53.05	\$14.25	\$16.05	\$0.00	\$83.35
	06/01/2023	\$54.29	\$14.25	\$16.05	\$0.00	\$84.59
	12/01/2023	\$55.53	\$14.25	\$16.05	\$0.00	\$85.83
	06/01/2024	\$56.81	\$14.25	\$16.05	\$0.00	\$87.11
	12/01/2024	\$58.25	\$14.25	\$16.05	\$0.00	\$88.55
	06/01/2025	\$59.53	\$14.25	\$16.05	\$0.00	\$89.83
	12/01/2025	\$60.97	\$14.25	\$16.05	\$0.00	\$91.27
	06/01/2026	\$62.25	\$14.25	\$16.05	\$0.00	\$92.55
	12/01/2026	\$63.69	\$14.25	\$16.05	\$0.00	\$93.99
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
TAMPERS, SELF-PROPELLED OR TRACTOR DRAWN OPERATING ENGINEERS LOCAL 4	06/01/2022	\$51.82	\$14.25	\$16.05	\$0.00	\$82.12
SI EKITING ENGINEERS LOCAL 7	12/01/2022	\$53.05	\$14.25	\$16.05	\$0.00	\$83.35
	06/01/2023	\$54.29	\$14.25	\$16.05	\$0.00	\$84.59
	12/01/2023	\$55.53	\$14.25	\$16.05	\$0.00	\$85.83
	06/01/2024	\$56.81	\$14.25	\$16.05	\$0.00	\$87.11
	12/01/2024	\$58.25	\$14.25	\$16.05	\$0.00	\$88.55
	06/01/2025	\$59.53	\$14.25	\$16.05	\$0.00	\$89.83
	12/01/2025	\$60.97	\$14.25	\$16.05	\$0.00	\$91.27
	06/01/2026	\$62.25	\$14.25	\$16.05	\$0.00	\$92.55
For apprentice rates see "Apprentice- OPERATING ENGINEERS"	12/01/2026	\$63.69	\$14.25	\$16.05	\$0.00	\$93.99
TELECOMMUNICATION TECHNICIAN	00/01/2022	#20.1 <i>C</i>	¢11.25	¢12.21	00.00	¢(2.72
ELECTRICIANS LOCAL 223	09/01/2022	\$38.16	\$11.25	\$13.31	\$0.00	\$62.72
	09/01/2023	\$39.40	\$11.50	\$13.91	\$0.00	\$64.81
	09/01/2024	\$40.69	\$11.75	\$14.53	\$0.00	\$66.97

**Effective Date -** 09/01/2022

	Effecti	ve Date - 09/01/2022				Supplemental		
	Step	percent	Apprentice Base Wage	Health	Pension	Unemployment	To	tal Rate
	1	0	\$0.00	\$0.00	\$0.00	\$0.00		\$0.00
i	Notes:	See Electrician Apprentice Wages	3					
		Telecom Apprentice Wages shall	be the same as the Electrician	Apprentice '	Wages			
	Appre	ntice to Journeyworker Ratio:2:	3***					
TERRAZZO FINISHERS		08/01/2022	2 \$58.09	9 \$11.49	\$22.34	\$0.00	\$91.92	
BRICKLAYERS LOCA	'AL 3 - M	ARBLE & TILE	02/01/2023	3 \$59.29	9 \$11.49	\$22.34	\$0.00	\$93.12
			08/01/202	3 \$61.34	4 \$11.49	\$22.34	\$0.00	\$95.17
			02/01/2024	4 \$62.59	9 \$11.49	\$22.34	\$0.00	\$96.42
			08/01/2024	4 \$64.69	9 \$11.49	\$22.34	\$0.00	\$98.52
			02/01/202	5 \$65.99	9 \$11.49	\$22.34	\$0.00	\$99.82
			08/01/202	5 \$68.14	4 \$11.49	\$22.34	\$0.00	\$101.97
			02/01/2020	5 \$69.49	9 \$11.49	\$22.34	\$0.00	\$103.32
			08/01/2020	5 \$71.69	9 \$11.49	\$22.34	\$0.00	\$105.52
			02/01/202	7 \$73.09	9 \$11.49	\$22.34	\$0.00	\$106.92

**Issue Date:** 10/11/2022 Wage Request Number: 20221007-038 Page 31 of 33

Pension

**Total Rate** 

1	Appren	tice - TE	ERRAZZO FINISHER - Loc	al 3 Marble & Tile					
]	Effectiv	e Date -	08/01/2022				Supplemental		
_	Step	percent		Apprentice Base Wage	Health	Pension	Unemployment	Total Rate	:
	1	50		\$29.05	\$11.49	\$22.34	\$0.00	\$62.88	
	2	60		\$34.85	\$11.49	\$22.34	\$0.00	\$68.68	
	3	70		\$40.66	\$11.49	\$22.34	\$0.00	\$74.49	1
	4	80		\$46.47	\$11.49	\$22.34	\$0.00	\$80.30	ı
	5	90		\$52.28	\$11.49	\$22.34	\$0.00	\$86.11	
		e Date -	02/01/2023				Supplemental		
-	Step	percent		Apprentice Base Wage	Health	Pension	Unemployment	Total Rate	:
	1	50		\$29.65	\$11.49	\$22.34	\$0.00	\$63.48	
	2	60		\$35.57	\$11.49	\$22.34	\$0.00	\$69.40	ı
	3	70		\$41.50	\$11.49	\$22.34	\$0.00	\$75.33	
	4	80		\$47.43	\$11.49	\$22.34	\$0.00	\$81.26	
	5	90		\$53.36	\$11.49	\$22.34	\$0.00	\$87.19	
-	Notes:								
İ									
l-	Appren	tice to Jo	urneyworker Ratio:1:3						
TEST BORING I	DATION A	IND MARINI		12/01/202	1 \$42.58	\$9.10	\$17.72	\$0.00	\$69.40
For apprentice ra									
TEST BORING I Laborers - Founi				12/01/202	1 \$41.30	\$9.10	\$17.72	\$0.00	\$68.12
For apprentice ra	ates see "A	Apprentice- I	LABORER"						
TEST BORING I Laborers - found			E	12/01/202	1 \$41.18	\$9.10	\$17.72	\$0.00	\$68.00
For apprentice ra	ates see "/	Apprentice- I	ABORER"						
TRACTORS/POI OPERATING ENGINA			I GENERATORS	06/01/2022	2 \$51.82	\$14.25	\$16.05	\$0.00	\$82.12
OI EKATING ENGIN	EEKS LO	CAL 4		12/01/2022	2 \$53.05	\$14.25	\$16.05	\$0.00	\$83.35
				06/01/2023	3 \$54.29	\$14.25	\$16.05	\$0.00	\$84.59
				12/01/2023	3 \$55.53	\$14.25	\$16.05	\$0.00	\$85.83
				06/01/2024	4 \$56.81	\$14.25	\$16.05	\$0.00	\$87.11
				12/01/2024	4 \$58.25	\$14.25	\$16.05	\$0.00	\$88.55
				06/01/2023	5 \$59.53	\$14.25	\$16.05	\$0.00	\$89.83
				12/01/2023	5 \$60.97	\$14.25	\$16.05	\$0.00	\$91.27
				06/01/2020	6 \$62.25	\$14.25	\$16.05	\$0.00	\$92.55
For apprentice ra	ates see "/	Apprentice- (	OPERATING ENGINEERS"	12/01/2020	6 \$63.69	\$14.25	\$16.05	\$0.00	\$93.99
	EART	H MOVIN	IG EQUIPMENT	12/01/202	1 \$36.82	\$13.41	\$16.01	\$0.00	\$66.24
TUNNEL WORK			D AIR	12/01/202	1 \$53.41	\$9.10	\$18.17	\$0.00	\$80.68
For apprentice ra			.ABORER"						

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
TUNNEL WORK - COMPRESSED AIR (HAZ. WASTE) LABORERS (COMPRESSED AIR)	12/01/2021	\$55.41	\$9.10	\$18.17	\$0.00	\$82.68
For apprentice rates see "Apprentice- LABORER"						
TUNNEL WORK - FREE AIR LABORERS (FREE AIR TUNNEL)	12/01/2021	\$45.48	\$9.10	\$18.17	\$0.00	\$72.75
For apprentice rates see "Apprentice- LABORER"						
TUNNEL WORK - FREE AIR (HAZ. WASTE) LABORERS (FREE AIR TUNNEL)	12/01/2021	\$47.48	\$9.10	\$18.17	\$0.00	\$74.75
For apprentice rates see "Apprentice- LABORER"						
VAC-HAUL TEAMSTERS JOINT COUNCIL NO. 10 ZONE B	12/01/2021	\$36.24	\$13.41	\$16.01	\$0.00	\$65.66
WAGON DRILL OPERATOR	06/01/2022	\$36.56	\$9.10	\$16.64	\$0.00	\$62.30
LABORERS - ZONE 2	12/01/2022	\$37.41	\$9.10	\$16.64	\$0.00	\$63.15
	06/01/2023	\$38.31	\$9.10	\$16.64	\$0.00	\$64.05
	12/01/2023	\$39.21	\$9.10	\$16.64	\$0.00	\$64.95
For apprentice rates see "Apprentice- LABORER"						
WAGON DRILL OPERATOR (HEAVY & HIGHWAY)  LABORERS - ZONE 2 (HEAVY & HIGHWAY)	12/01/2021	\$35.66	\$9.10	\$16.64	\$0.00	\$61.40
For apprentice rates see "Apprentice- LABORER (Heavy and Highway)						
WASTE WATER PUMP OPERATOR	06/01/2022	\$52.38	\$14.25	\$16.05	\$0.00	\$82.68
OPERATING ENGINEERS LOCAL 4	12/01/2022	\$53.63	\$14.25	\$16.05	\$0.00	\$83.93
	06/01/2023	\$54.88	\$14.25	\$16.05	\$0.00	\$85.18
	12/01/2023	\$56.13	\$14.25	\$16.05	\$0.00	\$86.43
	06/01/2024	\$57.43	\$14.25	\$16.05	\$0.00	\$87.73
	12/01/2024	\$58.88	\$14.25	\$16.05	\$0.00	\$89.18
	06/01/2025	\$60.18	\$14.25	\$16.05	\$0.00	\$90.48
	12/01/2025	\$61.63	\$14.25	\$16.05	\$0.00	\$91.93
	06/01/2026	\$62.93	\$14.25	\$16.05	\$0.00	\$93.23
For apprentice rates see "Apprentice- OPERATING ENGINEERS"	12/01/2026	\$64.38	\$14.25	\$16.05	\$0.00	\$94.68
WATER METER INSTALLER PLUMBERS & PIPEFITTERS LOCAL 51	08/30/2021	\$46.49	\$10.15	\$19.95	\$0.00	\$76.59

Additional Apprentice Information:

Minimum wage rates for apprentices employed on public works projects are listed above as a percentage of the pre-determined hourly wage rate established by the Commissioner under the provisions of the M.G.L. c. 149, ss. 26-27D. Apprentice ratios are established by the Division of Apprenticeship Training pursuant to M.G.L. c. 23, ss. 11E-11L.

All apprentices must be registered with the Division of Apprenticeship Training in accordance with M.G.L. c. 23, ss. 11E-11L.

All steps are six months (1000 hours.)

Ratios are expressed in allowable number of apprentices to journeymen or fraction thereof, unless otherwise specified.

- \*\* Multiple ratios are listed in the comment field.
- \*\*\* APP to JM; 1:1, 2:2, 2:3, 3:4, 4:4, 4:5, 4:6, 5:7, 6:7, 6:8, 6:9, 7:10, 8:10, 8:11, 8:12, 9:13, 10:13, 10:14, etc.

For apprentice rates see "Apprentice- PLUMBER/PIPEFITTER" or "PLUMBER/GASFITTER"

\*\*\*\* APP to JM; 1:1, 1:2, 2:3, 2:4, 3:5, 4:6, 4:7, 5:8, 6:9, 6:10, 7:11, 8:12, 8:13, 9:14, 10:15, 10:16, etc.

**Issue Date:** 10/11/2022 **Wage Request Number:** 20221007-038 **Page 33 of 33**