



GOULOFF - JORDAN SURVEYING AND DESIGN, INC.


1133 BROADWAY FORT WAYNE, IN 46802
PH (260) 424-5362 FAX (260) 424-4916

BOUNDARY RETRACEMENT SURVEY



Lot 5 - Plat 1, Centivre Park Addition
2703 N. Clinton Street, Fort Wayne, IN 46805

LEGEND

- (m) MEASURED
- (r) RECORDED
- (c) CALCULATED
- (p) PLATTED INFORMATION



SCALE: 1"=40'



(A) 2 Story Framed Residence

Flood Note:

By graphic plotting only and subject to map scale uncertainties, the real estate described and depicted hereon appears to lie in Zone "X" (NOT considered a special flood hazard area) on FIRM Map Number 18003C0282G, dated August 3, 2009 for Allen County, Indiana.

For the exclusive use of: Slagle / new owner

Date: February 15, 2017

Job No.: 20170025

SHEET 1 OF 2



**GOULOFF - JORDAN
SURVEYING AND DESIGN, INC.**

1133 BROADWAY FORT WAYNE, IN 46802
PH (260) 424-5362 FAX (260) 424-4916

SURVEYOR'S REPORT

Lot 5 - Plat 1, Centivre Park Addition
2703 N. Clinton Street, Fort Wayne, IN 46805

LEGAL DESCRIPTION - Doc. # 205062946

REAL ESTATE IN ALLEN COUNTY, STATE OF INDIANA, MORE PARTICULARLY AS FOLLOWS, TO WIT:

LOT NUMBERED 5 OF PLAT 1 OF CENTILIVRE PARK ADDITION TO THE CITY OF FORT WAYNE THE PLAT OF WHICH IS RECORDED IN PLAT BOOK 8, PAGE 51, IN THE OFFICE OF THE RECORDER OF ALLEN COUNTY, INDIANA, EXCEPT THAT PART OF SAID LOT 5 PARTICULARLY DESCRIBED AS FOLLOWS: BEGINNING AT THE NORTHEAST CORNER OF SAID LOT; THENCE SOUTH 1 DEGREE 40 MINUTES 00 SECONDS WEST 59.00 FEET ALONG THE EAST LINE OF SAID LOT TO THE SOUTHEAST CORNER OF SAID LOT; THENCE SOUTH 88 DEGREES 32 MINUTES 40 SECONDS WEST 12.52 FEET ALONG THE SOUTH LINE OF SAID LOT; THENCE NORTH 1 DEGREE 40 MINUTES 00 SECONDS EAST 59.00 FEET TO THE NORTH LINE OF SAID LOT; THENCE NORTH 88 DEGREES 32 MINUTES 40 SECONDS EAST 12.52 FEET ALONG SAID NORTH LINE TO THE POINT OF BEGINNING AND CONTAINING 738 SQUARE FEET MORE OR LESS. SUBJECT TO ALL RESTRICTIONS, LIMITATIONS AND EASEMENTS OF RECORD.

SURVEYOR'S REPORT

This report and the accompanying survey plat have been prepared in accordance with Title 865, Article 1, Rule 12, Sec 1-29 and all amendments thereto of the Indiana Administrative Code, which establishes the minimum standards for the practice of land surveying.

Monuments set are 5/8 inch round by 24 inch long steel rebars with yellow plastic caps stamped "GOU LS29500017", and set flush with the ground surface.

Monuments found are noted with an above (x.x) or below (-x.x) ground surface dimension.

This purpose for this survey is to "retrace" the boundary of the real estate described hereon.

THEORY OF LOCATION:

The lines and corners for this survey were established as depicted on the survey drawing and per information shown on the plat of Plat 1, Centivre Park Addition and Document Number 205062946 as found in the Office of the Recorder of Allen County, Indiana.

The uncertainty in the lines and corners found or established by this survey are as follows:

(A) Availability and condition of reference monuments:

Monuments found are described and depicted on the survey drawing.

Uncertainty created by the location of the monuments found or set on the subject property due to variations in reference monuments (monuments found on the subject property and on adjacent properties) is the difference between "measured" and "platted" or "recorded" angular or distance measurements as depicted on the survey drawing.

The maximum uncertainty for this survey is 1.41 feet.

(B) Occupation or possession lines:

No uncertainty was created by visible occupation or possession lines.

(C) Clarity or ambiguity of the record description and or adjoiner's descriptions:

No uncertainty was created by the above mentioned documents.

(D) This survey falls under the classification of a "Suburban" survey. The acceptable relative positional precision (random errors in measurements) = 0.13 feet (40 millimeters) plus 100 parts per million as specified in Section 7 of said Rule 12.

SURVEYOR'S CERTIFICATION

This survey was performed by, or under the responsible direction of the undersigned registered land surveyor and to the best of said registered land surveyor's knowledge and belief, said survey was executed according to the applicable survey requirements of 865 IAC-1-12-1 thru 29.

Field work for this survey was performed on February 14, 2017.

DATED THIS 15th DAY OF FEBRUARY, 2017.

Timothy C. Gouloff, R.L.S. 29500017

Job No.: 20170025

