

INDEX	EQUIPMENT	LOCATION / TAG	QTY	DESCRIPTION
1	DSTATCOM MAIN & AUX ENCLOSURE	Main (Lead) Container	1	Enclosure: L=13.7m, W=2.4m, H=2.9m Weight=21,338kg
2		AUX Container	1	Enclosure: L=13.7m, W=2.4m, H=2.9m Weight=24,494kg
3	DSTATCOM INVERTER	Main Container	6	1.25MVAR Inverter
4		AUX Container	8	1.25MVAR Inverter
5	TRANSFORMER (PADMOUNT)	35PT1	1	2.5MVA - 34.5kV/480V - Delta/WYE - Oil Filled
6		35PT2	1	2.5MVA - 34.5kV/480V - Delta/WYE - Oil Filled
7		35PT3	1	2.5MVA - 34.5kV/480V - Delta/WYE - Oil Filled
8		35PT4	1	2.5MVA - 34.5kV/480V - Delta/WYE - Oil Filled
9		35PT5	1	2.5MVA - 34.5kV/480V - Delta/WYE - Oil Filled
10		35PT6	1	2.5MVA - 34.5kV/480V - Delta/WYE - Oil Filled
11		35PT7	1	2.5MVA - 34.5kV/480V - Delta/WYE - Oil Filled
12	SSD RELAYS	Main (Lead) Container	3	SEL-751A - SSD Protection Relays
13	COOLING FAN	1.25MVA INVERTER	14	480VAC, 5HP Impeller Cooling Fans (with integral Motor)
14	REACTOR		14	Reactor - 30.5uH
15	BREAKER		14	480VAC Square D Circuit Breaker
16	POWER CABLE	TRANSFORMER / VISTA SWGR	100m	35kV, 1C, 500MCM, AL, 1/3 CN, 100% TR-XLPE