


# HOW TO START THE F.W. SALT SYSTEM



## FILL HOT TUB & START UP

Attach the pre-filter to your garden hose and begin filling through filter area. Once there is 6" of water in the tub, add the entire bottle of MetalGon. Stop filling once the water level meets the bottom of the pillows, and then power up the tub.

## SHOCK HOT TUB

Ensure tub temperature is set as preferred.  
Activate Jets on High.  
Add approximately 1 tablespoon of granular chlorine (based on gallons of the hot tub).  
After 10 minutes, test water. (ideal range 5-10ppm residual chlorine)




## USE YOUR TUB!

Explore each seat, how to use the jets and find your favorite setting!  
This means playing with the jets and air valve functions, and getting to know your spa controls and lights.

## SANITIZE AFTER EACH USE

Add 1-2 teaspoons of granular chlorine per adult after each use, always adding chlorine to filter well while jets are running on high for a minimum of 10 minutes (or the Clean Cycle)



## TEST FOR SANITIZER



Use FreshWater test strips, and follow the instructions. Test for Free Chlorine (FCL). Target: 3-5ppm  
If FCL isn't in the target range of 3-5 ppm, repeat dose of granular chlorine and retest.  
NOTE: Do not turn on salt system for first week. After tub activity, use granular chlorine to sanitize.

## BALANCE WATER

Use test strips to test for Alkalinity (target 80-120) and pH (target 7.2-7.8).  
First adjust Alkalinity to proper range using Spa Up or Spa Down, keeping in mind that it takes 24 hours for levels to adjust.  
After Alkalinity is in range, repeat for pH.




- **SANITIZING AND TESTING ARE KEY TO HAPPY TUBBING!**

VISIT US AT [ALASKASPA.COM](http://ALASKASPA.COM)

or give us a call at 563-3848 and we're happy to help!

# HOW TO START THE F.W. SALT SYSTEM



## DAY 7: ADD VANISHING ACT

Remove pillow from bag and rinse in sink before adding to the hot tub. (**IMPORTANT:** See owners manual for correct required placement to remove calcium.)

After 24 hours, Test for Calcium Hardness.

If CH is <100ppm remove vanishing act pillow and dispose. IF CH level is still high, verify vanishing act pillow position, run for 1 more day, then remove & dispose.

## DAY 8: ADD SALT

With CH levels < 100ppm, you can now add salt.

Activate jets on high, and refer to salt system owners manual to verify amount of salt to be added.

Add 1 cup of salt into the filter well at a time, using 1/2 cup less than owners manual suggests. After 5 mins from adding the final cup, test with salt test strips and on top side control to verify salt levels.



## DAY 8: TURN ON SYSTEM

After verifying salt levels, turn on the Fresh Water Salt System and set to output level 10. Refer to owners manual to clarify how to access the salt system menu.

Continue to use granular chlorine after each use as you did in first week as it can take 36-72 hours for the FW Salt system to produce chlorine residuals on its own.




## DAY 9: TEST BEFORE USE

Test for Free Chlorine before using tub.

If FCL is 3-5ppm, discontinue using granular chlorine as the salt system is now producing chlorine residual.

If FCL is less than 3-5ppm, leave output at 10 and add granular chlorine after each use.



## DAYS 10-12: TEST BEFORE USE

If on Day 9, your FCL was under 3-5 ppm, continue testing each day BEFORE using your tub.

(If your FCL was in the target range, disregard this step.)



## ENJOY FRESHWATER

Stop using granular when your FCL tests at 3-5ppm with the FreshWater salt system on.

Your checkup light will flash on Day 10 (and every 10 days after that). Reconfirm FCL levels every 10 days. We suggest setting reminders in your calendar. Please see owners manual for full details.



LOVE IT! PLEASE TELL YOUR FRIENDS. NEED HELP-JUST ASK!

VISIT US AT [ALASKASPA.COM](http://ALASKASPA.COM)

or give us a call at 563-3848